



# Kivy Documentation

*Release 1.10.1.dev0*

[www.kivy.org](http://www.kivy.org)



---

# Contents

---

<b>I User's Guide</b>	<b>3</b>
1 Installation	5
2 Philosophy	27
3 Contributing	29
4 FAQ	45
5 Contact Us	49
<b>II Programming Guide</b>	<b>51</b>
6 Kivy Basics	53
7 Controlling the environment	59
8 Configure Kivy	63
9 Architectural Overview	65
10 Events and Properties	71
11 Input management	81
12 Widgets	89
13 Graphics	109
14 Kv language	113
15 Integrating with other Frameworks	123
16 Packaging your application	127
17 Package licensing	147

<b>III Tutorials</b>	<b>151</b>
18 Pong Game Tutorial	153
19 A Simple Paint App	165
20 Crash Course	175
<b>IV API Reference</b>	<b>177</b>
21 Kivy framework	179
22 Adapters	273
23 Core Abstraction	283
24 Kivy module for binary dependencies.	315
25 Effects	317
26 Garden	321
27 Graphics	323
28 Input management	397
29 Kivy Language	417
30 External libraries	437
31 Modules	441
32 Network support	453
33 Storage	457
34 Tools	463
35 Widgets	467
<b>V Appendix</b>	<b>677</b>
36 License	679
Python Module Index	681

Welcome to Kivy's documentation. Kivy is an open source software library for the rapid development of applications equipped with novel user interfaces, such as multi-touch apps.

We recommend that you get started with *Getting Started*. Then head over to the *Programming Guide*. We also have [Create an application](#) if you are impatient.

You are probably wondering why you should be interested in using Kivy. There is a document outlining our [Philosophy](#) that we encourage you to read, and a detailed [Architectural Overview](#).

If you want to contribute to Kivy, make sure to read [Contributing](#). If your concern isn't addressed in the documentation, feel free to [Contact Us](#).



# Part I

# USER'S GUIDE

This part of the documentation explains the basic ideas behind Kivy's design and why you'd want to use it. It goes on with a discussion of the architecture and shows you how to create stunning applications in a short time using the framework.



# Installation

---

We try not to reinvent the wheel, but to bring something innovative to the market. As a consequence, we're focused on our own code and use pre-existing, high quality third-party libraries where possible.

To support the full, rich set of features that Kivy offers, several other libraries are required. If you do not use a specific feature (e.g. video playback), you don't need the corresponding dependency.

That said, there is one dependency that Kivy **does** require: [Cython](#).

In addition, you need a [Python](#) 2.x ( $2.7 \leq x < 3.0$ ) or 3.x ( $3.3 \leq x$ ) interpreter. If you want to enable features like windowing (i.e. open a Window), audio/video playback or spelling correction, additional dependencies must be available. For these, we recommend [SDL2](#), [Gstreamer 1.x](#) and [PyEnchant](#) respectively.

Other optional libraries (mutually independent) are:

- [OpenCV 2.0](#) – Camera input,
- [Pillow](#) – Image and text display,
- [PyEnchant](#) – Spelling correction.

That said, **DON'T PANIC!**

We don't expect you to install all those things on your own. Instead, we have created nice portable packages that you can use directly, and they already contain the necessary packages for your platform. We just want you to know that there are alternatives to the defaults and give you an overview of the things Kivy uses internally.

## 1.1 Dependencies

Here are listed dependencies required for Kivy to run and have/had issues in specific versions that broke our core functionality and Kivy either doesn't compile or can throw errors:

### 1.1.1 Cython

Kivy 1.10.1.dev0 **requires at least Cython version 0.23**, and has been tested through 0.27.3. Later versions may work, but as they have not been tested there is no guarantee. **The following versions of Cython have known issues and cannot be used with Kivy: 0.27, 0.27.2**

#### Known issues

- 0.27 -> Kivy Cython declaration bug in 1.10.0 causes failing compilation

#### Unsupported

- 0.27 - 0.27.2 -> Kivy doesn't compile on Python 3.4 with **MinGWPy** because of a used unexported symbol during the compilation. For more details see [this issue](#).

## 1.2 Stable Version

The latest stable version can be found on Kivy's website at <http://kivy.org/#download>. Please refer to the installation instructions for your specific platform:

### 1.2.1 Installation on Windows

Beginning with 1.9.1 we provide binary **wheels** for Kivy and all its dependencies to be used with an existing Python installation. See [Installation](#).

We also provide nightly wheels generated using Kivy **master**. See [Nightly wheel installation](#). See also [Upgrading from a previous Kivy dist](#). If installing kivy to an **alternate location** and not to site-packages, please see [Installing Kivy to an alternate location](#).

---

**Note:** For Python < 3.5 we use the MinGW compiler. However, for Python 3.5+ on Windows we currently only support the MSVC compiler because of the following Python [issue 4709](#) about MinGW. Generally this should make no difference when using precompiled wheels.

---

To use Kivy you need **Python**. Multiple versions of Python can be installed side by side, but Kivy needs to be installed for each Python version that you want to use Kivy.

#### Installation

Now that python is installed, open the **Command line** and make sure python is available by typing `python --version`. Then, do the following to install.

1. Ensure you have the latest pip and wheel:

```
python -m pip install --upgrade pip wheel setuptools
```

2. Install the dependencies (skip gstreamer (~120MB) if not needed, see [Kivy's dependencies](#)):

```
python -m pip install docutils pygments pypiwin32 kivy.deps.sdl2 kivy.deps.  
→glew  
python -m pip install kivy.deps.gstreamer
```

---

**Note:** If you encounter a *MemoryError* while installing, add after `pip install` an option `-no-cache-dir`.

For Python 3.5 only we additionally offer angle which can be used instead of glew and can be installed with:

```
python -m pip install kivy.deps.angle
```

3. Install kivy:

```
python -m pip install kivy
```

4. (Optionally) Install the kivy examples:

```
python -m pip install kivy_examples
```

The examples are installed in the share directory under the root directory where python is installed.

That's it. You should now be able to `import kivy` in python or run a basic example if you installed the kivy examples:

```
python share\kivy-examples\demo\showcase\main.py
```

---

**Note:** If you encounter any **permission denied** errors, try opening the **Command prompt as administrator** and trying again.

What are wheels, pip and wheel

In Python, packages such as Kivy can be installed with the python package manager, `pip`. Some packages such as Kivy require additional steps, such as compilation, when installing using the Kivy source code with pip. Wheels (with a `.whl` extension) are pre-built distributions of a package that has already been compiled and do not require additional steps to install.

When hosted on `pypi` one installs a wheel using `pip`, e.g. `python -m pip install kivy`. When downloading and installing a wheel directly, `python -m pip install wheel_file_name` is used, such as:

```
python -m pip install C:\Kivy-1.9.1.dev-cp27-none-win_amd64.whl
```

Nightly wheel installation

**Warning:** Using the latest development version can be risky and you might encounter issues during development. If you encounter any bugs, please report them.

Snapshot wheels of current Kivy master are created on every commit to the *master* branch of kivy repository. They can be found [here](#). To use them, instead of doing `python -m pip install kivy` we'll install one of these wheels as follows.

- [Python 2.7, 32bit](#)
- [Python 3.4, 32bit](#)
- [Python 3.5, 32bit](#)

- Python 3.6, 32bit
- Python 2.7, 64bit
- Python 3.4, 64bit
- Python 3.5, 64bit
- Python 3.6, 64bit

1. Perform steps 1 and 2 of the above Installation section.
2. Download the appropriate wheel for your system.
3. Install it with `python -m pip install wheel-name` where `wheel-name` is the name of the renamed file and add deps to the `PATH`.

Kivy examples are separated from the core because of their size. The examples can be installed separately on both Python 2 and 3 with this single wheel:

- Kivy examples

### Kivy's dependencies

We offer wheels for Kivy and its dependencies separately so only desired dependencies need be installed. The dependencies are offered as optional sub-packages of `kivy.deps`, e.g. `kivy.deps.sdl2`.

Currently on Windows, we provide the following dependency wheels:

- `gstreamer` for audio and video
- `glew` and/or `angle (3.5 only)` for OpenGL
- `sdl2` for control and/or OpenGL.

One can select which of these to use for OpenGL use using the `KIVY_GL_BACKEND` environment variable by setting it to `glew` (the default), `angle`, or `sdl2`. `angle` is currently in an experimental phase as a substitute for `glew` on Python 3.5 only.

`gstreamer` is an optional dependency which only needs to be installed if video display or audio is desired. `ffpyplayer` is an alternate dependency for audio or video.

### Command line

Know your command line. To execute any of the `pip` or `wheel` commands, one needs a command line tool with `python` on the path. The default command line on Windows is [Command Prompt](#), and the quickest way to open it is to press `Win+R` on your keyboard, type `cmd` in the window that opens, and then press enter.

Alternate linux style command shells that we recommend is [Git for Windows](#) which offers a bash command line as well as `git`. Note, `CMD` can still be used even if `bash` is installed.

Walking the path! To add your `python` to the path, simply open your command line and then use the `cd` command to change the current directory to where `python` is installed, e.g. `cd C:\Python27`. Alternatively if you only have one `python` version installed, permanently add the `python` directory to the path for `cmd` or `bash`.

### Use development Kivy

**Warning:** Using the latest development version can be risky and you might encounter issues during development. If you encounter any bugs, please report them.

To compile and install kivy using the kivy [source code](#) or to use kivy with git rather than a wheel there are some additional steps:

1. Both the `python` and the `Python\Scripts` directories **must** be on the path. They must be on the path every time you recompile kivy.
2. Ensure you have the latest pip and wheel with:

```
python -m pip install --upgrade pip wheel setuptools
```

3. Get the compiler. For Python < 3.5 we use mingwpy as follows.

- (a) Create the `python\Lib\distutils\distutils.cfg` file and add the two lines:

```
[build]
compiler = mingw32
```

- (b) Install MinGW with:

```
python -m pip install -i https://pypi.anaconda.org/carlkl/simple mingwpy
```

For Python 3.5 we use the MSVC compiler. For 3.5, [Visual Studio 2015](#) is required, which is available for free. Just download and install it and you'll be good to go.

Visual Studio is very big so you can also use the smaller, [Visual C Build Tools instead](#).

4. Set the environment variables. On windows do:

```
set USE SDL2=1
set USE GSTREAMER=1
```

In bash do:

```
export USE SDL2=1
export USE GSTREAMER=1
```

These variables must be set everytime you recompile kivy.

5. Install the other dependencies as well as their dev versions (you can skip gstreamer and gstreamer\_dev if you aren't going to use video/audio):

```
python -m pip install cython docutils pygments pypiwin32 kivy.deps.sdl2 \
kivy.deps.glew kivy.deps.gstreamer kivy.deps.glew_dev kivy.deps.sdl2_dev \
kivy.deps.gstreamer_dev
```

6. If you downloaded or cloned kivy to an alternate location and don't want to install it to site-packages read the next section.
7. Finally compile and install kivy with `pip install filename`, where `filename` can be a url such as <https://github.com/kivy/kivy/archive/master.zip> for kivy master, or the full path to a local copy of a kivy.

## Compile Kivy

1. Start installation of Kivy cloned from GitHub:

```
python -m pip install kivy\.
```

If the compilation succeeds without any error, Kivy should be good to go. You can test it with running a basic example:

```
python share\kivy-examples\demo\showcase\main.py
```

## Installing Kivy to an alternate location

In development Kivy is often installed to an alternate location and then installed with:

```
python -m pip install -e location
```

That allows Kivy to remain in its original location while being available to python, which is useful for tracking changes you make in Kivy for example directly with Git.

To achieve using Kivy in an alternate location extra tweaking is required. Due to this [issue](#) wheel and pip install the dependency wheels to `python\Lib\site-packages\kivy`. So they need to be moved to your actual kivy installation from site-packages.

After installing the kivy dependencies and downloading or cloning kivy to your favorite location, do the following:

1. Move the contents of `python\Lib\site-packages\kivy\deps` to `your-path\kivy\deps` where `your-path` is the path where your kivy is located.
2. Remove the `python\Lib\site-packages\kivy` directory altogether.
3. From `python\Lib\site-packages` move all `kivy.deps.*.dist-info` directories to `your-path` right next to kivy.

Now you can safely compile kivy in its current location with one of these commands:

```
> make  
> mingw32-make  
> python -m pip install -e .  
> python setup.py build_ext --inplace
```

If kivy fails to be imported, you probably didn't delete all the `*.dist-info` folders and and the `kivy` or `kivy.deps*` folders from site-packages.

## Making Python available anywhere

There are two methods for launching python on your `*.py` files.

### Double-click method

If you only have one Python installed, you can associate all `*.py` files with your python, if it isn't already, and then run it by double clicking. Or you can only do it once if you want to be able to choose each time:

1. Right click on the Python file (.py file extension) of the application you want to launch
2. From the context menu that appears, select *Open With*
3. Browse your hard disk drive and find the file `python.exe` that you want to use. Select it.
4. Select "Always open the file with..." if you don't want to repeat this procedure every time you double click a .py file.
5. You are done. Open the file.

## Send-to method

You can launch a .py file with our Python using the Send-to menu:

1. Browse to the `python.exe` file you want to use. Right click on it and copy it.
2. Open Windows explorer (File explorer in Windows 8), and go to the address 'shell:sendto'. You should get the special Windows directory `SendTo`
3. Paste the previously copied `python.exe` file as a shortcut.
4. Rename it to `python <python-version>`. E.g. `python27-x64`

You can now execute your application by right clicking on the .py file -> "Send To" -> "python <python-version>".

## Upgrading from a previous Kivy dist

To install the new wheels to a previous Kivy distribution all the files and folders, except for the python folder should be deleted from the distribution. This python folder will then be treated as a normal system installed python and all the steps described in [Installation](#) can then be continued.

### 1.2.2 Installation on OS X

---

**Note:** This guide describes multiple ways for setting up Kivy. Installing with Homebrew and pip is recommended for general use.

---

#### Using Homebrew with pip

You can install Kivy with Homebrew and pip using the following steps:

1. Install the requirements using `homebrew`:

```
$ brew install pkg-config sdl2 sdl2_image sdl2_ttf sdl2_mixer  
→ gstreamer
```

2. Install Cython and Kivy using pip:

```
$ pip install Cython==0.26.1  
$ pip install kivy
```

- To install the development version, use this in the second step:

```
$ pip install https://github.com/kivy/kivy/archive/master.zip
```

#### Using MacPorts with pip

---

**Note:** You will have to manually install gstreamer support if you wish to support video playback in your Kivy App. The latest port documents show the following [py-gst-python port](#).

---

You can install Kivy with Macports and pip using the following steps:

1. Install `Macports`

2. Install and set Python 3.4 as the default:

```
$ port install python34  
$ port select --set python python34
```

3. Install and set pip as the default:

```
$ port install pip-34  
$ port select --set pip pip-34
```

4. Install the requirements using Macports:

```
$ port install libsdl2 libsdl2_image libsdl2_ttf libsdl2_mixer
```

5. Install Cython and Kivy using pip:

```
$ pip install Cython==0.26.1  
$ pip install kivy
```

- To install the development version, use this in the second step:

```
$ pip install https://github.com/kivy/kivy/archive/master.zip
```

## Using The Kivy.app

---

**Note:** Kivy.app is not available for download at the moment. For details, see [this](#) issue.

---

---

**Note:** This method has only been tested on OS X 10.7 and above (64-bit). For versions prior to 10.7 or 10.7 32-bit, you have to install the components yourself. We suggest using [homebrew](#) to do that.

---

For OS X 10.7 and later, we provide packages with all dependencies bundled in a virtual environment, including a Python 3 interpreter for Kivy3.app. These bundles are primarily used for rapid prototyping, and currently serve as containers for packaging Kivy apps with Buildozer.

To install Kivy, you must:

1. Navigate to the latest Kivy release at <https://kivy.org/downloads/> and download *Kivy-\*-osx-python\*.7z*.
2. Extract it using an archive program like [Keka](#).
3. Copy the Kivy2.app or Kivy3.app as Kivy.app to /Applications. Paste the following line in the terminal:

```
$ sudo mv Kivy2.app /Applications/Kivy.app
```

4. Create a symlink named *kivy* to easily launch apps with kivy venv:

```
$ ln -s /Applications/Kivy.app/Contents/Resources/script /usr/local/bin/kivy
```

5. Examples and all the normal kivy tools are present in the Kivy.app/Contents/Resources/kivy directory.

You should now have a *kivy* script that you can use to launch your kivy app from the terminal.

You can just drag and drop your main.py to run your app too.

## Installing modules

The Kivy SDK on OS X uses its own virtual env that is activated when you run your app using the *kivy* command. To install any module you need to install the module like so:

```
$ kivy -m pip install <modulename>
```

Where are the modules/files installed?

Inside the portable venv within the app at:

```
Kivy.app/Contents/Resources/venv/
```

If you install a module that installs a binary for example like kivy-garden. That binary will be only available from the venv above, as in after you do:

```
kivy -m pip install kivy-garden
```

The garden lib will be only available when you activate this env:

```
source /Applications/Kivy.app/Contents/Resources/venv/bin/activate
garden install mapview
deactivate
```

To install binary files

Just copy the binary to the /Applications/Kivy.app/Contents/Resources/venv/bin/ directory.

To include other frameworks

Kivy.app comes with SDL2 and Gstreamer frameworks provided. To include frameworks other than the ones provided do the following:

```
git clone http://github.com/tito/osxrelocator
export PYTHONPATH=~/path/to/osxrelocator
cd /Applications/Kivy.app
python -m osxrelocator -r . /Library/Frameworks/<Framework_name>.framework/ \
@executable_path/../Frameworks/<Framework_name>.framework/
```

Do not forget to replace <Framework\_name> with your framework. This tool *osxrelocator* essentially changes the path for the libs in the framework such that they are relative to the executable within the .app, making the Framework portable with the .app.

Start any Kivy Application

You can run any Kivy application by simply dragging the application's main file onto the Kivy.app icon. Just try this with any python file in the examples folder.

Start from the Command Line

If you want to use Kivy from the command line, double-click the **Make Symlinks** script after you have dragged the Kivy.app into the Applications folder. To test if it worked:

1. Open Terminal.app and enter:

```
$ kivy
```

You should get a Python prompt.

2. In there, type:

```
>>> import kivy
```

If it just goes to the next line without errors, it worked.

3. Running any Kivy application from the command line is now simply a matter of executing a command like the following:

```
$ kivy yourapplication.py
```

### 1.2.3 Installation on Linux

#### Using software packages

For installing distribution relative packages .deb/.rpm/...

#### Ubuntu / Kubuntu / Xubuntu / Lubuntu (Saucy and above)

1. Add one of the PPAs as you prefer

**stable builds** \$ sudo add-apt-repository ppa:kivy-team/kivy

**nightly builds** \$ sudo add-apt-repository ppa:kivy-team/kivy-daily

2. Update your package list using your package manager \$ sudo apt-get update

3. Install Kivy

**Python2 - python-kivy** \$ sudo apt-get install python-kivy

**Python3 - python3-kivy** \$ sudo apt-get install python3-kivy

**optionally the examples - kivy-examples** \$ sudo apt-get install python-kivy-examples

#### Debian (Jessie or newer)

1. Add one of the PPAs to your sources.list in apt manually or via Synaptic

**stable builds** deb <http://ppa.launchpad.net/kivy-team/kivy/ubuntu> xenial main

**daily builds** deb <http://ppa.launchpad.net/kivy-team/kivy-daily/ubuntu> xenial main

**Notice:** Wheezy is not supported - You'll need to upgrade to Jessie at least!

2. Add the GPG key to your apt keyring by executing

as user:

```
sudo apt-key adv --keyserver keyserver.ubuntu.com --recv-keys  
A863D2D6
```

as root:

```
apt-key adv --keyserver keyserver.ubuntu.com --recv-keys  
A863D2D6
```

3. Refresh your package list and install **python-kivy** and/or **python3-kivy** and optionally the examples found in **kivy-examples**

## Linux Mint

1. Find out on which Ubuntu release your installation is based on, using this [overview](#).
2. Continue as described for Ubuntu above, depending on which version your installation is based on.

## Bodhi Linux

1. Find out which version of the distribution you are running and use the table below to find out on which Ubuntu LTS it is based.

**Bodhi 1** Ubuntu 10.04 LTS aka Lucid (No packages, just manual install)

**Bodhi 2** Ubuntu 12.04 LTS aka Precise

**Bodhi 3** Ubuntu 14.04 LTS aka Trusty

**Bodhi 4** Ubuntu 16.04 LTS aka Xenial

2. Continue as described for Ubuntu above, depending on which version your installation is based on.

## OpenSuSE

1. To install kivy go to <http://software.opensuse.org/package/python-Kivy> and use the "1 Click Install" for your openSUSE version. You might need to make the latest kivy version appear in the list by clicking on "Show unstable packages". We prefer to use packages by " devel:languages:python".
2. If you would like access to the examples, please select **python-Kivy-examples** in the upcoming installation wizard.

## Gentoo

1. There is a kivy ebuild (kivy stable version)

```
emerge Kivy
```

2. available USE-flags are:

*cairo: Standard flag, let kivy use cairo graphical libraries. camera: Install libraries needed to support camera. doc: Standard flag, will make you build the documentation locally. examples: Standard flag, will give you kivy examples programs. garden: Install garden tool to manage user maintained widgets. gstreamer: Standard flag, kivy will be able to use audio/video streaming libraries. spell: Standard flag, provide enchant to use spelling in kivy apps.*

## Other

For other distros, we recommend installing via pip as shown below.

### 1.2.4 Installation in a Virtual Environment

Common dependencies

Cython

Different versions of Kivy have only been tested up to a certain Cython version. It may or may not work with a later version.

Kivy	Cython
1.8	0.20.2
1.9	0.21.2
1.9.1	0.23
1.10.1	0.25

Dependencies with SDL2

Ubuntu example

In the following command use “python” and “python-dev” for Python 2, or “python3” and “python3-dev” for Python 3.

```
# Install necessary system packages
sudo apt-get install -y \
    python-pip \
    build-essential \
    git \
    python \
    python-dev \
    ffmpeg \
    libsdl2-dev \
    libsdl2-image-dev \
    libsdl2-mixer-dev \
    libsdl2-ttf-dev \
    libportmidi-dev \
    libswscale-dev \
    libavformat-dev \
    libavcodec-dev \
    zlib1g-dev

# Install gstreamer for audio, video (optional)
sudo apt-get install -y \
    libgstreamer1.0 \
    gstreamer1.0-plugins-base \
    gstreamer1.0-plugins-good
```

**Note:** Depending on your Linux version, you may receive error messages related to the “ffmpeg” package. In this scenario, use “libav-tools” in place of “ffmpeg” (above), or use a PPA (as shown below):

```

- sudo add-apt-repository ppa:mc3man/trusty-media
- sudo apt-get update
- sudo apt-get install ffmpeg

```

## Installation

```

# Make sure Pip, Virtualenv and Setuptools are updated
sudo pip install --upgrade pip virtualenv setuptools

# Then create a virtualenv named "kivyinstall" by either:

# 1. using the default interpreter
virtualenv --no-site-packages kivyinstall

# or 2. using a specific interpreter
# (this will use the interpreter in /usr/bin/python2.7)
virtualenv --no-site-packages -p /usr/bin/python2.7 kivyinstall

# Enter the virtualenv
.kivyinstall/bin/activate

# Use correct Cython version here
pip install Cython==0.27.3

# Install stable version of Kivy into the virtualenv
pip install kivy
# For the development version of Kivy, use the following command instead
# pip install git+https://github.com/kivy/kivy.git@master

```

Dependencies with legacy PyGame

## Ubuntu example

```

# Install necessary system packages
sudo apt-get install -y \
    python-pip \
    build-essential \
    mercurial \
    git \
    python \
    python-dev \
    ffmpeg \
    libsdl-image1.2-dev \
    libsdl-mixer1.2-dev \
    libsdl-ttf2.0-dev \
    libsmpeg-dev \
    libsdl1.2-dev \
    libportmidi-dev \
    libswscale-dev \
    libavformat-dev \
    libavcodec-dev \
    zlib1g-dev

```

## Fedora

```
$ sudo yum install \
  make \
  mercurial \
  automake \
  gcc \
  gcc-c++ \
  SDL_ttf-devel \
  SDL_mixer-devel \
  khrplatform-devel \
  mesa-libGLES \
  mesa-libGLES-devel \
  gstreamer-plugins-good \
  gstreamer \
  gstreamer-python \
  mtdev-devel \
  python-devel \
  python-pip
```

## OpenSuse

```
$ sudo zypper install \
  python-distutils-extra \
  python-gstreamer-0_10 \
  python-enchant \
  gstreamer-0_10-plugins-good \
  python-devel \
  Mesa-devel \
  python-pip
$ sudo zypper install -t pattern devel_C_C++
```

## Installation

```
# Make sure Pip, Virtualenv and Setuptools are updated
sudo pip install --upgrade pip virtualenv setuptools

# Then create a virtualenv named "kivyinstall" by either:

# 1. using the default interpreter
virtualenv --no-site-packages kivyinstall

# or 2. using a specific interpreter
# (this will use the interpreter in /usr/bin/python2.7)
virtualenv --no-site-packages -p /usr/bin/python2.7 kivyinstall

# Enter the virtualenv
.kivyinstall/bin/activate

pip install numpy

pip install Cython==0.27.3

# If you want to install pygame backend instead of sdl2
```

```
# you can install pygame using command below and enforce using
# export USE SDL2=0. If kivy's setup can't find sdl2 libs it will
# automatically set this value to 0 then try to build using pygame.
pip install hg+http://bitbucket.org/pygame/pygame
```

```
# Install stable version of Kivy into the virtualenv
pip install kivy
# For the development version of Kivy, use the following command instead
pip install git+https://github.com/kivy/kivy.git@master
```

## Install additional Virtualenv packages

```
# Install development version of buildozer into the virtualenv
pip install git+https://github.com/kivy/buildozer.git@master

# Install development version of plyer into the virtualenv
pip install git+https://github.com/kivy/plyer.git@master

# Install a couple of dependencies for KivyCatalog
pip install -U pygments docutils
```

## Start from the Command Line

We ship some examples that are ready-to-run. However, these examples are packaged inside the package. This means you must first know where easy\_install has installed your current kivy package, and then go to the examples directory:

```
$ python -c "import pkg_resources; print(pkg_resources.resource_filename('kivy', './share/kivy-examples'))"
```

And you should have a path similar to:

```
/usr/local/lib/python2.6/dist-packages/Kivy-1.0.4_beta-py2.6-linux-x86_64.egg/
→share/kivy-examples/
```

Then you can go to the example directory, and run it:

```
# launch touchtracer
$ cd <path to kivy-examples>
$ cd demo/touchtracer
$ python main.py

# launch pictures
$ cd <path to kivy-examples>
$ cd demo/pictures
$ python main.py
```

If you are familiar with Unix and symbolic links, you can create a link directly in your home directory for easier access. For example:

1. Get the example path from the command line above
2. Paste into your console:

```
$ ln -s <path to kivy-examples> ~/
```

3. Then, you can access to kivy-examples directly in your home directory:

```
$ cd ~/kivy-examples
```

If you wish to start your Kivy programs as scripts (by typing `./main.py`) or by double-clicking them, you will want to define the correct version of Python by linking to it. Something like:

```
$ sudo ln -s /usr/bin/python2.7 /usr/bin/kivy
```

Or, if you are running Kivy inside a virtualenv, link to the Python interpreter for it, like:

```
$ sudo ln -s /home/your_username/Envs/kivy/bin/python2.7 /usr/bin/kivy
```

Then, inside each main.py, add a new first line:

```
#!/usr/bin/kivy
```

NOTE: Beware of Python files stored with Windows-style line endings (CR-LF). Linux will not ignore the <CR> and will try to use it as part of the file name. This makes confusing error messages. Convert to Unix line endings.

#### Device permissions

When your app starts, Kivy uses `Mtdev` to scan for available multi-touch devices to use for input. Access to these devices is typically restricted to users or group with the appropriate permissions.

If you do not have access to these devices, Kivy will log an error or warning specifying these devices, normally something like:

```
Permission denied: '/dev/input/eventX'
```

In order to use these devices, you need to grant the user or group permission. This can be done via:

```
$ sudo chmod u+r /dev/input/eventX
```

for the user or:

```
$ sudo chmod g+r /dev/input/eventX
```

for the group. These permissions will only be effective for the duration of your current session. A more permanent solution is to add the user to a group that has these permissions. For example, in Ubuntu, you can add the user to the 'input' group:

```
$ sudo adduser $USER input
```

Note that you need to log out then back in again for these permissions to be applied.

#### 1.2.5 Installation on Android

Kivy is a Python framework, and simply installing it on an Android device the same way as on a desktop machine will do nothing. However, you can compile a Kivy application to a standard Android APK that will run just like a normal java app on (more or less) any device.

We provide several different tools to help you run code on an Android device, covered fully in the [Android packaging documentation](#). These include creating a fully standalone APK that may be released

on an Android store, as well as the ability to run your Kivy apps without a compilation step using our pre-prepared Kivy Launcher app.

### 1.2.6 Installation on Raspberry Pi

You can install Kivy manually, or you can download and boot KivyPie on the Raspberry Pi. Both options are described below.

#### Manual installation (On Raspbian Jessie/Stretch)

1. Install the dependencies:

```
sudo apt-get update
sudo apt-get install libsdl2-dev libsdl2-image-dev libsdl2-mixer-dev libsdl2-
    ↪ttf-dev \
    pkg-config libgl1-mesa-dev libgles2-mesa-dev \
    python-setuptools libgstreamer1.0-dev git-core \
    gstreamer1.0-plugins-{bad,base,good,ugly} \
    gstreamer1.0-{omx,alsa} python-dev libmtdev-dev \
    xclip xsel
```

2. Install a new enough version of Cython:

```
sudo pip install -U Cython==0.27.3
```

3. Install Kivy globally on your system:

```
sudo pip install git+https://github.com/kivy/kivy.git@master
```

4. Or build and use kivy inplace (best for development):

```
git clone https://github.com/kivy/kivy
cd kivy

make
echo "export PYTHONPATH=$(pwd):$PYTHONPATH" >> ~/.profile
source ~/.profile
```

---

**Note:** On versions of kivy prior to 1.10.1, Mesa library naming changes can result in “Unable to find any valuable Window provider” errors. If you experience this issue, please upgrade or consult [ticket #5360](#).

---

#### Manual installation (On Raspbian Wheezy)

1. Add APT sources for Gstreamer 1.0 in */etc/apt/sources.list*:

```
deb http://vontaene.de/raspbian-updates/ . main
```

2. Add APT key for vontaene.de:

```
gpg --recv-keys 0C667A3E
gpg -a --export 0C667A3E | sudo apt-key add -
```

3. Install the dependencies:

```
sudo apt-get update
sudo apt-get install libsdl2-dev libsdl2-image-dev libsdl2-mixer-dev libsdl2-
    -ttf-dev \
    pkg-config libgl1-mesa-dev libgles2-mesa-dev \
    python-setuptools libgstreamer1.0-dev git-core \
    gstreamer1.0-plugins-{bad,base,good,ugly} \
    gstreamer1.0-{omx,alsa} python-dev
```

4. Install pip from source:

```
wget https://raw.github.com/pypa/pip/master/contrib/get-pip.py
sudo python get-pip.py
```

5. Install Cython from sources (debian packages are outdated):

```
sudo pip install Cython==0.26.1
```

6. Install Kivy globally on your system:

```
sudo pip install git+https://github.com/kivy/kivy.git@master
```

7. Or build and use kivy inplace (best for development):

```
git clone https://github.com/kivy/kivy
cd kivy

make
echo "export PYTHONPATH=$(pwd):$PYTHONPATH" >> ~/.profile
source ~/.profile
```

## KivyPie distribution

KivyPie is a compact and lightweight Raspbian based distribution that comes with Kivy installed and ready to run. It is the result of applying the manual installation steps described above, with a few more extra tools. You can download the image from <http://kivypie.mitako.eu/kivy-download.html> and boot it on a Raspberry PI.

## Running the demo

Go to your *kivy/examples* folder, you'll have tons of demo you could try.

You could start the showcase:

```
cd kivy/examples/demo/showcase
python main.py
```

3d monkey demo is also fun too see:

```
cd kivy/examples/3Drendering
python main.py
```

## Change the default screen to use

You can set an environment variable named *KIVY\_BCM\_DISPMANX\_ID* in order to change the display used to run Kivy. For example, to force the display to be HDMI, use:

```
KIVY_BCM_DISPMANX_ID=2 python main.py
```

Check [Controlling the environment](#) to see all the possible values.

Using Official RPi touch display

If you are using the official Raspberry Pi touch display, you need to configure Kivy to use it as an input source. To do this, edit the file `~/.kivy/config.ini` and go to the `[input]` section. Add this:

```
mouse = mouse
mtdev_%(name)s = probesysfs,provider=mtdev
hid_%(name)s = probesysfs,provider=hidinput
```

For more information about configuring Kivy, see [Configure Kivy](#)

Where to go ?

We made few games using GPIO / physical input we got during Pycon 2013: a button and a tilt. Check-out the <https://github.com/kivy/piki>. You will need to adapt the GPIO pin in the code.

A video to see what we were doing with it: <http://www.youtube.com/watch?v=NVM09gaX6pQ>

## 1.3 Development Version

The development version is for developers and testers. Note that when running a development version, you're running potentially broken code at your own risk. To use the development version, you will first need to install the dependencies. Thereafter, you will need to set up Kivy on your computer in a way that allows for easy development. For that, please see our [Contributing](#) document.

### 1.3.1 Installing Dependencies

To install Kivy's dependencies, follow the guide below for your platform. You might also need these packages for the RST and lexing components:

```
$ sudo pip install pygments docutils
```

Ubuntu

For Ubuntu 12.04 and above (tested to 14.04), simply enter the following command that will install all necessary packages:

```
$ sudo apt-get install python-setuptools python-pygame python-opengl \
python-gst0.10 python-enchant gstreamer0.10-plugins-good python-dev \
build-essential libgl1-mesa-dev-lts-quantal libgles2-mesa-dev-lts-quantal \
python-pip
```

For Ubuntu 15.04 and versions older than 12.04, this one should work:

```
$ sudo apt-get install python-setuptools python-pygame python-opengl \
python-gst0.10 python-enchant gstreamer0.10-plugins-good python-dev \
build-essential libgl1-mesa-dev libgles2-mesa-dev zlib1g-dev python-pip
```

For Ubuntu 16.04:

```
$ sudo apt-get install python-setuptools python-pygame python-opengl \
  python-gst0.10 python-enchant gstreamer0.10-plugins-good python-dev \
  build-essential python-pip libgl1-mesa-dev libgles2-mesa-dev zlib1g-dev
```

For Ubuntu 17.10:

```
$ sudo apt-get install python-setuptools python-pygame python-opengl \
  python-enchant python-dev build-essential python-pip libgl1-mesa-dev \
  libgles2-mesa-dev zlib1g-dev
```

Kivy requires a recent version of Cython, so it's better to use the latest supported version from pypi:

```
$ sudo pip install --upgrade Cython==0.27.3
```

OS X

Without using brew you can install the dependencies for kivy by manually pasting the following commands in a terminal:

```
curl -O -L https://www.libsdl.org/release/SDL2-2.0.4.dmg
curl -O -L https://www.libsdl.org/projects/SDL_image/release/SDL2_image-2.0.1.dmg
curl -O -L https://www.libsdl.org/projects/SDL_mixer/release/SDL2_mixer-2.0.1.dmg
curl -O -L https://www.libsdl.org/projects/SDL_ttf/release/SDL2_ttf-2.0.13.dmg
curl -O -L http://gstreamer.freedesktop.org/data/pkg/osx/1.7.1/gstreamer-1.0-1.7.1-
  ↪x86_64.pkg
curl -O -L http://gstreamer.freedesktop.org/data/pkg/osx/1.7.1/gstreamer-1.0-devel-
  ↪1.7.1-x86_64.pkg
hdiutil attach SDL2-2.0.4.dmg
sudo cp -a /Volumes/SDL2/SDL2.framework /Library/Frameworks/
```

This should ask you for your root password, provide it and then paste the following lines in your terminal:

```
hdiutil attach SDL2_image-2.0.1.dmg
sudo cp -a /Volumes/SDL2_image/SDL2_image.framework /Library/Frameworks/
hdiutil attach SDL2_ttf-2.0.13.dmg
sudo cp -a /Volumes/SDL2_ttf/SDL2_ttf.framework /Library/Frameworks/
hdiutil attach SDL2_mixer-2.0.1.dmg
sudo cp -a /Volumes/SDL2_mixer/SDL2_mixer.framework /Library/Frameworks/
sudo installer -package gstreamer-1.0-1.7.1-x86_64.pkg -target /
sudo installer -package gstreamer-1.0-devel-1.7.1-x86_64.pkg -target /
pip install --upgrade --user cython pillow
```

Now that you have all the dependencies for kivy, you need to make sure you have the command line tools installed:

```
xcode-select --install
```

Go to an appropriate dir like:

```
mkdir ~/code
cd ~/code
```

You can now install kivy itself:

```
git clone http://github.com/kivy/kivy
cd kivy
make
```

This should compile kivy, to make it accessible in your python env just point your PYTHONPATH to this dir:

```
export PYTHONPATH=~/code/kivy:$PYTHONPATH
```

To check if kivy is installed, type the following command in your terminal:

```
python -c "import kivy"
```

It should give you an output similar to the following:

```
$ python -c "import kivy"
[INFO    ] [Logger      ] Record log in /Users/quanon/.kivy/logs/kivy_15-12-31_21.
          ↴txt
[INFO    ] [Screen       ] Apply screen settings for Motorola Droid 2
[INFO    ] [Screen       ] size=480x854 dpi=240 density=1.5 orientation=portrait
[INFO    ] [Kivy         ] v1.9.1-stable
[INFO    ] [Python        ] v2.7.10 (default, Oct 23 2015, 18:05:06)
[GCC 4.2.1 Compatible Apple LLVM 7.0.0 (clang-700.0.59.5)]
```

## OSX HomeBrew

If you prefer to use homebrew: install the requirements using [homebrew](#):

```
$ brew install sdl2 sdl2_image sdl2_ttf sdl2_mixer gstreamer
```

## Windows

See [Use development Kivy](#).

### 1.3.2 Installing Kivy for Development

Now that you've installed all the required dependencies, it's time to download and compile a development version of Kivy:

Download Kivy from GitHub:

```
$ git clone git://github.com/kivy/kivy.git
$ cd kivy
```

Compile:

```
$ python setup.py build_ext --inplace -f
```

If you have the `make` command available, you can also use the following shortcut to compile (does the same as the last command):

```
$ make
```

**Warning:** By default, versions 2.7 to 2.7.2 of Python use the gcc compiler which ships with earlier versions of XCode. As of version 4.2, only the clang compiler is shipped with XCode by default. This means that if you build using XCode 4.2 or above, you need to ensure you have at least Python 2.7.3 installed, but preferably the latest version (2.7.5 at the time of writing).

If you want to modify the Kivy code itself, set up the [PYTHONPATH environment variable](#) to point at your clone. This way you don't have to install (`setup.py install`) after every tiny modification. Python will instead import Kivy from your clone.

Alternatively, if you don't want to make any changes to Kivy itself, you can also run (as admin, e.g. with sudo):

```
$ python setup.py install
```

If you want to contribute code (patches, new features) to the Kivy codebase, please read [Contributing](#).

### 1.3.3 Running the test suite

To help detect issues and behaviour changes in Kivy, a set of unittests are provided. A good thing to do is to run them just after your Kivy installation, and every time you intend to push a change. If you think something was broken in Kivy, perhaps a test will show this. (If not, it might be a good time to write one.)

Kivy tests are based on nosetests, which you can install from your package manager or using pip:

```
$ pip install nose
```

To run the test suite, do:

```
$ make test
```

### 1.3.4 Uninstalling Kivy

If you are mixing multiple Kivy installations, you might be confused about where each Kivy version is located. Please note that you might need to follow these steps multiple times if you have multiple Kivy versions installed in the Python library path. To find your current installed version, you can use the command line:

```
$ python -c 'import kivy; print(kivy.__path__)'
```

Then, remove that directory recursively.

If you have installed Kivy with easy\_install on linux, the directory may contain a "egg" directory. Remove that as well:

```
$ python -c 'import kivy; print(kivy.__path__)'
['/usr/local/lib/python2.7/dist-packages/Kivy-1.0.7-py2.7-linux-x86_64.egg/kivy']
$ sudo rm -rf /usr/local/lib/python2.7/dist-packages/Kivy-1.0.7-py2.7-linux-x86_64.
    ↴egg
```

If you have installed with apt-get, do:

```
$ sudo apt-get remove --purge python-kivy
```

# Philosophy

---

In case you are wondering what Kivy is all about and what sets it apart from other solutions, this document is for you.

## 2.1 Why bother?

Why would you want to use Kivy? After all, there are many great toolkits (or frameworks, or platforms) available out there – for free. You have Qt and Flash, to name just two good choices for application development. Many of these numerous solutions already support Multi-Touch, so what is it that makes Kivy special and worth using?

### 2.1.1 Fresh

Kivy is made for today and tomorrow. Novel input methods such as Multi-Touch have become increasingly important. We created Kivy from scratch, specifically for this kind of interaction. That means we were able to rethink many things in terms of human computer interaction, whereas older (not to mean ‘outdated’, rather ‘well-established’) toolkits carry their legacy, which is often a burden. We’re not trying to force this new approach to using a computer into the corset of existing models (say single-pointer mouse interaction). We want to let it flourish and let you explore the possibilities. *This* is what really sets Kivy apart.

### 2.1.2 Fast

Kivy is fast. This applies to both *application development* and *application execution* speeds. We have optimized Kivy in many ways. We implement time-critical functionality on the *C level* to leverage the power of existing compilers. More importantly, we also use *intelligent algorithms* to minimize costly operations. We also use the *GPU* wherever it makes sense in our context. The computational power of today’s graphics cards surpasses that of today’s CPUs by far for some tasks and algorithms, especially drawing. That’s why we try to let the GPU do as much of the work as possible, thus increasing performance considerably.

### 2.1.3 Flexible

Kivy is flexible. This means it can be run on *a variety of different devices*, including Android powered smartphones and tablets. We support *all major operating systems* (Windows, Linux, OS X). Being flexible also means that Kivy's fast-paced development allows it to *adapt to new technologies quickly*. More than once have we added support for new external devices and software protocols, sometimes even before they were released. Lastly, Kivy is also flexible in that it is possible to use it in combination with a great number of different third-party solutions. For example, on Windows we support WM\_TOUCH, which means that any device that has Windows 7 Pen & Touch drivers will *just work* with Kivy. On OS X you can use Apple's Multi-Touch capable devices, such as trackpads and mice. On Linux, you can use HID kernel input events. In addition to that, we support TUIO (Tangible User Interface Objects) and a number of other input sources.

### 2.1.4 Focused

Kivy is focused. You can write a simple application with a few lines of code. Kivy programs are created using the *Python* programming language, which is incredibly versatile and powerful, yet easy to use. In addition, we created our own description language, the *Kivy Language*, for creating sophisticated user interfaces. This language allows you to set up, connect and arrange your application elements quickly. We feel that allowing you to focus on the essence of your application is more important than forcing you to fiddle with compiler settings. We took that burden off your shoulders.

### 2.1.5 Funded

Kivy is actively developed by professionals in their field. Kivy is a community-influenced, professionally developed and commercially backed solution. Some of our core developers develop Kivy for a living. Kivy is here to stay. It's not a small, vanishing student project.

### 2.1.6 Free

Kivy is free to use. You don't have to pay for it. You don't even have to pay for it if you're making money out of selling an application that uses Kivy.

# Contributing

---

There are many ways in which you can contribute to Kivy. Code patches are just one thing amongst others that you can submit to help the project. We also welcome feedback, bug reports, feature requests, documentation improvements, advertisement & advocating, testing, graphics contributions and many other ideas. Just talk to us if you want to help, and we will help you help us.

## 3.1 Code of Conduct

In the interest of fostering an open and welcoming community, we as contributors and maintainers need to ensure participation in our project and our sister projects is a harassment-free and positive experience for everyone.

As such, it is vital that all interaction is conducted in a manner conveying respect, open-mindedness and gratitude. For a more comprehensive discussion of these guidelines, please refer to the [Contributor Covenant](#). This document provides an accurate description of what is expected of you, both as a core developer or a first time contributor.

## 3.2 Feedback

This is by far the easiest way to contribute something. If you're using Kivy for your own project, don't hesitate sharing. It doesn't have to be a high-class enterprise app, obviously. It's just incredibly motivating to know that people use the things you develop and what it enables them to do. If you have something that you would like to tell us, please don't hesitate. Screenshots and videos are also very welcome! We're also interested in the problems you had when getting started. Please feel encouraged to report any obstacles you encountered such as missing documentation, misleading directions or similar. We are perfectionists, so even if it's just a typo, let us know.

### 3.3 Reporting an Issue

If you found anything wrong, a crash, segfault, missing documentation, invalid spelling or just weird examples, please take 2 minutes to report the issue.

1. Move your logging level to debug by editing `<user_directory>/kivy/config.ini`:

```
[kivy]
log_level = debug
```

2. Execute your code again, and copy/paste the complete output to <http://gist.github.com/>, including the log from Kivy and the python backtrace.
3. Open <https://github.com/kivy/kivy/issues/>
4. Set the title of your issue
5. Explain exactly what to do to reproduce the issue and paste the link of the output posted on <http://gist.github.com/>
6. Validate the issue and you're done!

If you are feeling up to it, you can also try to resolve the bug, and contribute by sending us the patch :) Read the next section to find out how to do this.

### 3.4 Code Contributions

Code contributions (patches, new features) are the most obvious way to help with the project's development. Since this is so common we ask you to follow our workflow to most efficiently work with us. Adhering to our workflow ensures that your contribution won't be forgotten or lost. Also, your name will always be associated with the change you made, which basically means eternal fame in our code history (you can opt-out if you don't want that).

#### 3.4.1 Coding style

- If you haven't done it yet, read the [PEP8](#) about coding style in python.
- Activate the pep8 check on git commits like this:

```
make hook
```

This will pass the code added to the git staging zone (about to be committed) through a pep8 checker program when you do a commit, and ensure that you didn't introduce pep8 errors. If you did, the commit will be rejected: please correct the errors and try again.

#### 3.4.2 Performance

- take care of performance issues: read [Python performance tips](#)
- cpu intensive parts of Kivy are written in cython: if you are doing a lot of computation, consider using it too.

### 3.4.3 Git & GitHub

We use git as our version control system for our code base. If you have never used git or a similar DVCS (or even any VCS) before, we strongly suggest you take a look at the great documentation that is available for git online. The [Git Community Book](#) or the [Git Videos](#) are both great ways to learn git. Trust us when we say that git is a great tool. It may seem daunting at first, but after a while you'll (hopefully) love it as much as we do. Teaching you git, however, is well beyond the scope of this document.

Also, we use [GitHub](#) to host our code. In the following we will assume that you have a (free) GitHub account. While this part is optional, it allows for a tight integration between your patches and our upstream code base. If you don't want to use GitHub, we assume you know what you are doing anyway.

### 3.4.4 Code Workflow

So here is the initial setup to begin with our workflow (you only need to do this once to install Kivy). Basically you follow the installation instructions from [Installing Kivy for Development](#), but you don't clone our repository, you fork it. Here are the steps:

1. Log in to GitHub
2. Create a fork of the [Kivy repository](#) by clicking the *fork* button.
3. Clone your fork of our repository to your computer. Your fork will have the git remote name 'origin' and you will be on branch 'master':

```
git clone https://github.com/username/kivy.git
```

4. Compile and set up PYTHONPATH or install (see [Installing Kivy for Development](#)).
5. Install our pre-commit hook that ensures your code doesn't violate our styleguide by executing *make hook* from the root directory of your clone. This will run our styleguide check whenever you do a commit, and if there are violations in the parts that you changed, your commit will be aborted. Fix & retry.
6. Add the kivy repo as a remote source:

```
git remote add kivy https://github.com/kivy/kivy.git
```

Now, whenever you want to create a patch, you follow the following steps:

1. See if there is a ticket in our bug tracker for the fix or feature and announce that you'll be working on it if it doesn't yet have an assignee.
2. Create a new, appropriately named branch in your local repository for that specific feature or bugfix. (Keeping a new branch per feature makes sure we can easily pull in your changes without pulling any other stuff that is not supposed to be pulled.):

```
git checkout -b new_feature
```

3. Modify the code to do what you want (e.g. fix it).
4. Test the code. Try to do this even for small fixes. You never know whether you have introduced some weird bug without testing.
5. Do one or more minimal, atomic commits per fix or per feature. Minimal/Atomic means *keep the commit clean*. Don't commit other stuff that doesn't logically belong to this fix or feature. This is **not** about creating one commit per line changed. Use `git add -p` if necessary.

6. Give each commit an appropriate commit message, so that others who are not familiar with the matter get a good idea of what you changed.
7. Once you are satisfied with your changes, pull our upstream repository and merge it with your local repository. We can pull your stuff, but since you know exactly what's changed, you should do the merge:

```
git pull kivy master
```

8. Push your local branch into your remote repository on GitHub:

```
git push origin new_feature
```

9. Send a *Pull Request* with a description of what you changed via the button in the GitHub interface of your repository. (This is why we forked initially. Your repository is linked against ours.)

**Warning:** If you change parts of the code base that require compilation, you will have to recompile in order for your changes to take effect. The `make` command will do that for you (see the `Makefile` if you want to know what it does). If you need to clean your current directory from compiled files, execute `make clean`. If you want to get rid of **all** files that are not under version control, run `make distclean` (**Caution:** If your changes are not under version control, this command will delete them!)

Now we will receive your pull request. We will check whether your changes are clean and make sense (if you talked to us before doing all of this we will have told you whether it makes sense or not). If so, we will pull them and you will get instant karma. Congratulations, you're a hero!

## 3.5 Documentation Contributions

Documentation contributions generally follow the same workflow as code contributions, but are just a bit more lax.

1. Following the instructions above,
  - (a) Fork the repository.
  - (b) Clone your fork to your computer.
  - (c) Setup `kivy` repo as a remote source.
2. Install `python-sphinx`. (See `docs/README` for assistance.)
3. Use [ReStructuredText Markup](#) to make changes to the HTML documentation in `docs/sources`.

To submit a documentation update, use the following steps:

1. Create a new, appropriately named branch in your local repository:

```
git checkout -b my_docs_update
```

2. Modify the documentation with your correction or improvement.
3. Re-generate the HTML pages, and review your update:

```
make html
```

4. Give each commit an appropriate commit message, so that others who are not familiar with the matter get a good idea of what you changed.

5. Keep each commit focused on a single related theme. Don't commit other stuff that doesn't logically belong to this update.
6. Push to your remote repository on GitHub:

```
git push
```

7. Send a *Pull Request* with a description of what you changed via the button in the GitHub interface of your repository.

We don't ask you to go through all the hassle just to correct a single typo, but for more complex contributions, please follow the suggested workflow.

### 3.5.1 Docstrings

Every module/class/method/function needs a docstring, so use the following keywords when relevant:

- ... `versionadded::` to mark the version in which the feature was added.
- ... `versionchanged::` to mark the version in which the behaviour of the feature was changed.
- ... `note::` to add additional info about how to use the feature or related feature.
- ... `warning::` to indicate a potential issue the user might run into using the feature.

Examples:

```
def my_new_feature(self, arg):
    """
    New feature is awesome

    ... versionadded:: 1.1.4

    ... note:: This new feature will likely blow your mind

    ... warning:: Please take a seat before trying this feature
    """
```

Will result in:

`def my_new_feature(self, arg):` New feature is awesome

New in version 1.1.4.

---

**Note:** This new feature will likely blow your mind

---

**Warning:** Please take a seat before trying this feature

When referring to other parts of the api use:

- `:mod:`~kivy.module`` to refer to a module
- `:class:`~kivy.module.Class`` to refer to a class
- `:meth:`~kivy.module.Class.method`` to refer to a method
- `:doc:`api-kivy.module`` to refer to the documentation of a module (same for a class and a method)

Obviously replacing *module Class* and *method* with their real name, and using using ‘.’ to separate modules referring to imbricated modules, e.g:

```
:mod:`~kivy.uix.floatlayout`  
:class:`~kivy.uix.floatlayout.FloatLayout`  
:meth:`~kivy.core.window.WindowBase.toggle_fullscreen`  
:doc:`/api-kivy.core.window`
```

Will result in:

*floatlayout FloatLayout toggleFullscreen() Window*

*:doc:* and *:mod:* are essentially the same, except for an anchor in the url which makes *:doc:* preferred for the cleaner url.

To build your documentation, run:

```
make html
```

If you updated your kivy install, and have some trouble compiling docs, run:

```
make clean force html
```

The docs will be generated in `docs/build/html`. For more information on docstring formatting, please refer to the official [Sphinx Documentation](#).

## 3.6 Unit tests contributions

For the testing team, we have the document [Unit tests](#) that explains how Kivy unit tests work and how you can create your own. Use the same approach as the *Code Workflow* to submit new tests.

### 3.6.1 Unit tests

Tests are located in the *kivy/tests* folder. If you find a bug in Kivy, a good thing to do can be to write a minimal case showing the issue and to ask core devs if the behaviour shown is intended or a real bug. If you write your code as a [unittest](#), it will prevent the bug from coming back unnoticed in the future, and will make Kivy a better, stronger project. Writing a unittest may be a really good way to get familiar with Kivy while doing something useful.

Unit tests are separated into two cases:

- Non graphical unit tests: these are standard unit tests that can run in a console
- Graphical unit tests: these need a GL context, and if requested, work via image comparison

To be able to run unit tests, you need to install nose (<http://code.google.com/p/python-nose/>), and coverage (<http://nedbatchelder.com/code/coverage/>). You can use `easy_install` for that:

```
sudo easy_install nose coverage
```

Then, in the kivy directory:

```
make test
```

How it works

All the tests are located in *kivy/tests*, and the filename starts with *test\_<name>.py*. Nose will automatically gather all the files and classes inside this folder, and use them to generate test cases.

To write a test, create a file that respects the previous naming, then start with this template:

```
import unittest

class XXXTestCase(unittest.TestCase):

    def setUp(self):
        # import class and prepare everything here.
        pass

    def test_YYY(self):
        # place your test case here
        a = 1
        self.assertEqual(a, 1)
```

Replace XXX with an appropriate name that covers your tests cases, then replace 'YYY' with the name of your test. If you have any doubts, check how the other tests have been written.

Then, to execute them, just run:

```
make test
```

If you want to execute that file only, you can run:

```
nosetests kivy/tests/test_your testcase.py
```

or include this simple `unittest.main()` call at the end of the file and run the test with `python test_your testcase.py`:

```
if __name__ == '__main__':
    unittest.main()
```

## Graphical unit tests

While simple unit tests are fine and useful to keep things granular, in certain cases we need to test Kivy after the GL Window is created to interact with the graphics, widgets and to test more advanced stuff such as widget, modules, various cases of input and interaction with everything that becomes available only after the Window is created and Kivy properly initialized.

These tests are executed the same way like the ordinary unit tests i.e. either with `nosetests` or via `unittest.main()`.

Here are two similar examples with different approaches of running the app. In the first one you are setting up the required stuff manually and the `tearDown()` of the `GraphicUnitTest` may only attempt to clean it after you:

```
from kivy.tests.common import GraphicUnitTest

class MyTestCase(GraphicUnitTest):

    def test_runtouchapp(self):
        # non-integrated approach
        from kivy.app import runTouchApp
        from kivy.uix.button import Button

        button = Button()
        runTouchApp(button)

        # get your Window instance safely
```

```

from kivy.base import EventLoop
EventLoop.ensure_window()
window = EventLoop.window

# your asserts
self.assertEqual(window.children[0], button)
self.assertEqual(
    window.children[0].height,
    window.height
)

```

In the second test case both `setUp()` and `tearDown()` work together with `GraphicUnitTest.render()`. This is the basic setup it does automatically:

- Window is sized to 320 x 240 px
- Only the default Config is used during the test, it's restricted with the `KIVY_USE_DEFAULTCONFIG` environment variable
- Any input (mouse/touch/...) is *removed* and if you need to test it, either mock it or manually add it
- Window's canvas is cleared before displaying any widget tree

**Warning:** Do NOT use absolute numbers in your tests to preserve the functionality across the all resolutions. Instead, use e.g. relative position or size and multiply it by the `Window.size` in your test.

```

from kivy.tests.common import GraphicUnitTest, UnitTestTouch

class MyTestCase(GraphicUnitTest):

    def test_render(self):
        from kivy.uix.button import Button

        # with GraphicUnitTest.render() you basically do this:
        # runTouchApp(Button()) + some setup before
        button = Button()
        self.render(button)

        # get your Window instance safely
        from kivy.base import EventLoop
        EventLoop.ensure_window()
        window = EventLoop.window

        touch = UnitTestTouch(
            *[s / 2.0 for s in window.size]
        )

        # bind something to test the touch with
        button.bind(
            on_release=lambda instance: setattr(
                instance, 'test_released', True
            )
        )

        # then let's touch the Window's center
        touch.touch_down()
        touch.touch_up()
        self.assertTrue(button.test_released)

```

```
if __name__ == '__main__':
    import unittest
    unittest.main()
```

---

**Note:** Make sure you check the source of `kivy.tests.common` before writing comprehensive test cases.

---

## GL unit tests

GL unit test are more difficult. You must know that even if OpenGL is a standard, the output/rendering is not. It depends on your GPU and the driver used. For these tests, the goal is to save the output of the rendering at frame X, and compare it to a reference image.

Currently, images are generated at 320x240 pixels, in *png* format.

---

**Note:** Currently, image comparison is done per-pixel. This means the reference image that you generate will only be correct for your GPU/driver. If somebody can implement image comparison with “delta” support, patches are welcome :)

---

To execute GL unit tests, you need to create a directory:

```
mkdir kivy/tests/results
KIVY_UNITTEST_SCREENSHOTS=1 make test
```

The results directory will contain all the reference images and the generated images. After the first execution, if the results directory is empty, no comparison will be done. It will use the generated images as reference. After the second execution, all the images will be compared to the reference images.

A html file is available to show the comparison before/after the test, and a snippet of the associated unit test. It will be generated at:

`kivy/tests/build/index.html`

---

**Note:** The build directory is cleaned after each call to `make test`. If you don’t want that, just use `nosetests` command.

---

## Writing GL Unit tests

The idea is to create a root widget, as you would do in `build()`, or in `kivy.base.runTouchApp()`. You’ll give that root widget to a rendering function which will capture the output in X frames.

Here is an example:

```
from kivy.tests.common import GraphicUnitTest

class VertexInstructionTestCase(GraphicUnitTest):

    def test_ellipse(self):
        from kivy.uix.widget import Widget
        from kivy.graphics import Ellipse, Color
        r = self.render
```

```

# create a root widget
wid = Widget()

# put some graphics instruction on it
with wid.canvas:
    Color(1, 1, 1)
    self.e = Ellipse(pos=(100, 100), size=(200, 100))

# render, and capture it directly
r(wid)

# as alternative, you can capture in 2 frames:
r(wid, 2)

# or in 10 frames
r(wid, 10)

```

Each call to `self.render` (or `r` in our example) will generate an image named as follows:

`<classname>_<funcname>-<r-call-count>.png`

`r-call-count` represents the number of times that `self.render` is called inside the test function.

The reference images are named:

`ref_<classname>_<funcname>-<r-call-count>.png`

You can easily replace the reference image with a new one if you wish.

## Coverage reports

Coverage is based on the execution of previous tests. Statistics on code coverage are automatically calculated during execution. You can generate an html report of the coverage with the command:

`make cover`

Then, open `kivy/htmlcov/index.html` with your favorite web browser.

## 3.7 GSOC

### 3.7.1 Google Summer of Code - 2017

#### Introduction

Kivy is a cross-platform, business friendly, GPU accelerated open source Python library for rapid development of applications that make use of innovative user interfaces, such as multi-touch apps.

The Kivy Organization oversees several major projects:

- The [Kivy](#) GUI Library
- The [Python-For-Android](#) compilation tool.
- The [Kivy-iOS](#) compilation tool.
- The [PyJNIus](#) library for interfacing with Java from Python.

- The [PyOBJus](#) library for interfacing with Objective-C from Python.
- The [Plyer](#) platform-independent Python wrapper for platform dependent APIs.
- [Buildozer](#) - A generic Python packager for Android, iOS, and desktop.
- [KivEnt](#) - A 2d Game Engine that provides optimized methods of handling large amounts of dynamic visual data.
- [Kivy Designer](#) - A graphical GUI designer for Kivy built in Kivy.

Altogether, these projects allow the user to create applications for every major operating system that make use of any native APIs present. Our goal is to enable development of Python applications that run everywhere off the same codebase and make use of platform dependent APIs and features that users of specific operating systems have come to expect.

Depending on which project you choose you may need to know Cython, OpenGL ES2, Java, Objective-C, or C in addition to Python. We make heavy use of Cython and OpenGL for computational and graphics performance where it matters, and the other languages are typically involved in accessing OS or provider level APIs.

We are hoping to participate in Google Summer of Code 2017. This page showcases some ideas for GSoC projects and corresponding guidelines for students contributing to the Kivy Framework.

## Requirements

It is assumed that the incoming student meets some basic requirements as highlighted here:

- Intermediate level familiarity with Python.
- Comfortable with git and github (Kivy and its sister projects are all managed on github) If you have never used github before you may be interested in this [tutorial](#).
- Comfortable with event driven programming.
- Has suitable tools/environment for Kivy or the sister project you are going to work on. For example to be able to work on PyOBJus you would need access to an iOS device, OS X with Xcode and a developer license, to work on PyJNIus you would need an Android device, and to work on plyer you would need access to hardware for both platforms.

Additional desired skills may be listed with specific projects.

Familiarize yourself with the [contribution guide](#) We can help you get up to speed, however students demonstrating ability in advance will be given preference.

## How to get started

For Kivy, the easiest way is to follow the installation instructions for the development version for your specific platform:

<http://kivy.org/docs/installation/installation.html#development-version>

For the rest it's usually sufficient to install the relevant project from git and add it to your PYTHONPATH.

e.g. for PyJNIus:

```
git clone http://github.com/kivy/pyjnius
export PYTHONPATH=/path/to/pyjnius:$PYTHONPATH
```

## Project Ideas

Here are some prospective ideas sourced from the Kivy development team, if none of these projects interest you come talk to us in #kivy-dev about a project idea of your own.

### Beginner Projects

These projects should be suitable for anyone with a college level familiarity with Python and require little knowledge of platform specifics.

### Intermediate Projects

These projects may involve cursory level knowledge of several OS level details, some OpenGL interaction, or other topics that may be a bit out of the wheelhouse of the average Pythonista.

#### Plyer:

**Description:** Plyer is a platform-independent Python API to use features commonly found on the desktop and mobile platforms supported by Kivy. The idea is to provide a stable API to the user for accessing features of their desktop or mobile device.

The student would replace some *java* code currently in the p4a project to a more appropriate place in Plyer. In addition, the student would work on improving access to platform specific features through Plyer, including accessibility, Bluetooth Low Energy, accessing and editing contacts, sharing, NFC, in-app browser, Wi-Fi (enable, disable, access to Wi-Fi services (Wi-Fi direct, network accessibility, current IP info on network etc.), Camera capture (video), camera display, Google Play integration, launch phone call interface, sms interface, geolocation, interaction with notifications, internationalization (I18N), and all the missing platform implementations from existing features.

Under the hood you'll use PyJNIus on Android, PyOBJus on OS X and iOS, ctypes on Windows, and native APIs on Linux. This probably would also include improving PyOBJus and PyJNIus to handle interfaces that they can't right now.

#### References:

- <https://github.com/kivy/plyer>
- <https://github.com/kivy/pyjnius>
- <https://github.com/kivy/pyobjus>
- <https://github.com/kivy/python-for-android>
- <https://github.com/kivy/kivy-ios>

**Expected outcome:** A successful outcome would include moving the Java/PyOBJus code from p4a/kivy-ios to plyer and implementing some or all of the new facades to be decided with the student.

- **Mentors:** Akshay Arora
- **Requirements:** Access to Linux, Windows, OS X, iOS device, Android device.
- **Task level:** Intermediate
- **Desired Skills:** Familiarity with PyJNIus, PyOBJus.

### Font Reshaping and Font Fallback Support

**Description:** Currently Kivy does not support reshaping for alphabets such as Arabic, Persian, Thai, or Devanagari. The solution is to integrate a text shaping and layout engine (Pango and Harfbuzz). You would need to ensure that Pango and Harfbuzz can be compiled on every platform, and integrate it as a core text provider.

The second part of the same project would involve font fallback support. If a particular character/glyph is missing, currently we show a [] box. The solution for this would involve either using an OS API if available or maintaining a hashtable for the default fonts on each OS which can be used for glyph fallback.

#### References:

- <http://www.pango.org>
- <https://www.freedesktop.org/wiki/Software/HarfBuzz/>
- <https://github.com/kivy/kivy/tree/master/kivy/core/text>

**Expected outcome:** Font fallback and text reshaping support in Kivy, compilation recipes for Python-For-Android and packaging on desktop platforms.

- **Mentors:** Akshay Arora, Jacob Kovac, Matthew Einhorn
- **Requirements:** Access to a desktop OS and ideally at least one mobile platform
- **Task level:** Intermediate
- **Desired Skills:** Familiarity with text rendering, Pango, HarfBuzz and Kivy's provider abstraction.

## Advanced Projects

These projects may involve very in-depth knowledge of Kivy's existing internals, the hairy details of cross-platform compilation, or other fairly advanced topics. If you are comfortable with the internals of Python, working with C code, and using Cython to build your own C extensions these projects may appeal to you.

### Kivent: Chipmunk 7 Integration

**Description:** Kivent is a modular entity-component based game engine built on top of Kivy. Kivent provides a highly performant approach to building games in Python that avoids some of the worst overhead of Python using specialized Cython constructs.

At the moment, Kivent internally makes use of the cymunk library (<https://github.com/tito/cymunk>) for physics simulation and collision detection. Cymunk is based on Chipmunk2d 6.x, recently Chipmunk 7 has released and brought many previously premium features into the core library. In addition to the API changes present in the newest Chipmunk, the Kivent - Cymunk bridging does not make most efficient use of the Kivent API for handling C level objects and data. The student will be responsible for creating a new wrapper over Chipmunk2d 7 that better matches Kivent's approach to handling game data.

#### References:

- <http://chipmunk-physics.net/>
- <https://github.com/kivy/kivent>

**Expected Outcome:** A successful outcome involves a new kivent\_tiled module being released for the Kivent game engine.

- **Mentors:** Jacob Kovac
- **Requirements:** Access to at least one Kivy platform.

- **Task level:** Advanced
- **Desired Skills:** Familiarity with Cython, Python, and game dev related math concepts.

### KV Compiler: A compiler for the KV language

**Description:** The KV language is a fundamental component of Kivy. The KV language allows one to describe a GUI; from the creation of a Widget tree to the actions that should be taken in response value changes and events. In effect it is a concise way to create rule bindings using the Kivy properties and events. Internally, python code that reflects these rules are created and bound to the properties and events. Currently, these bindings are not at all optimized because upon each widget creation all of these rules are re-evaluated and bound. This process can be significantly optimized by pre-compiling the kv code, especially the bindings. A compiler would also allow us to update and fix some of the long-standing kv language issues.

Work on a kv-compiler has already progressed quite far, in fact a PR in the pre-alpha stage, is currently open. However, it is out of sync with the current codebase due to some unrelated kv changes in the meantime. Also, that PR would require a significant re-write to make things more modular, self-contained, and extensible. So there is much work still to be done on it.

Theming has also been a prepatual issue in Kivy, a KV compiler may help implement bindings that facilitate theming.

### References:

- <https://kivy.org/docs/guide/lang.html>
- <https://github.com/kivy/kivy/pull/3456>
- <https://github.com/kivy/kivy/wiki/KEP001:-Instantiate-things-other-than-widgets-from-kv>
- <https://github.com/kivy/kivy/issues/691>
- <https://github.com/kivy/kivy/issues/2727>

**Expected Outcome:** A successful outcome would be a compiler which compiles kv code into python code. The compiler should be modular and extensible so that we can continue to improve the kv language. The compiler should have the common debug/optimization options. The compiled code should also be human readable so issues could be traced back to the original kv code. The compiler should also be a drop in replacement for the current KV runtime compiler, and would require extensive testing.

- **Mentors:** Matthew Einhorn
- **Requirements:** Access to at least one Kivy platform.
- **Task level:** Advanced
- **Desired Skills:** Familiarity with Cython, Python, and Kivy. Familiarity with typical computer science concepts and data structures is also desired.

### How to Contact devs

All communication must happen via public channels, private emails and IRC messages are discouraged.

Ask your questions on the Kivy Users forum <https://groups.google.com/group/kivy-users> or send a mail at [kivy-users@googlegroups.com](mailto:kivy-users@googlegroups.com)

Make sure to join the kivy-dev user group too: <https://groups.google.com/forum/#!forum/kivy-dev>.

You can also try to contact us on IRC (online chat), to get the IRC handles of the devs mentioned above visit <https://kivy.org/#aboutus>.

Make sure to read the [IRC rules](#) before connecting. [Connect to webchat](#).

Most of our developers are located in Europe, India, and North America so keep in mind typical waking hours for these areas.

## How to be a good student

If you want to participate as a student and want to maximize your chances of being accepted, start talking to us today and try fixing some smaller problems to get used to our workflow. If we know you can work well with us, you will have much better chances of being selected.

Here's a checklist:

- Make sure to read through the website and at least skim the documentation.
- Look at the source code.
- Read our contribution guidelines.
- Make a contribution! Kivy would like to see how you engage with the development process. Take a look at the issue tracker for a Kivy project that interests you and submit a Pull Request. It can be a simple bug or a documentation change. We are looking to get a feel for how you work, not evaluating your capabilities. Don't worry about trying to pick something to impress us.
- Pick an idea that you think is interesting from the ideas list or come up with your own idea.
- Do some research **yourself**. GSoC is about give and take, not just one sided interaction. It is about you trying to achieve agreed upon goals with our support. The main driving force in this should be, obviously, yourself. Many students pop up and ask what they should do. You should base that decision on your interests and your skills. Show us you're serious about it and take the initiative.
- Write a draft [proposal](#) about what you want to do. Include what you understand the current state of the project to be, what you would like to improve, how, etc.
- Discuss that proposal with us in a timely manner. Get feedback.
- Be patient! Especially on IRC. We will try to get to you if we're available. If not, send an email and just wait. Most questions are already answered in the docs or somewhere else and can be found with some research. Your questions should reflect that you've actually thought through what you're asking and done some rudimentary research.
- Most of all don't forget to have fun and interact with the community. The community is as big a part of Open Source as the code itself.

## What to expect if you are chosen

- All students should join the #kivy and the #kivy-dev irc channels daily, this is how the development team communicates both internally and with the users.
- You and your mentors will agree on two week milestones for the duration of the summer.
- Development will occur in your fork of the master branch of Kivy, we expect you to submit at least one PR a week from your branch into a branch reserved for you in the primary repo. This will be your forum for reporting progress as well as documenting any struggles you may have encountered.
- Missing 2 weekly PR or 2 milestones will result in your failure unless there have been extenuating circumstances. If something comes up, please inform your mentors as soon as possible. If a milestone seems out of reach we will work with you to reevaluate the goals.
- Your changes will be merged into master once the project has been completed and we have thoroughly tested on every platform that is relevant.



# FAQ

---

There are a number of questions that repeatedly need to be answered. The following document tries to answer some of them.

## 4.1 Technical FAQ

### 4.1.1 Fatal Python error: (pygame parachute) Segmentation Fault

Most of time, this issue is due to the usage of old graphics drivers. Install the latest graphics driver available for your graphics card, and it should be ok.

If not, this means you have probably triggered some OpenGL code without an available OpenGL context. If you are loading images, atlases, using graphics instructions, you must spawn a Window first:

```
# method 1 (preferred)
from kivy.base import EventLoop
EventLoop.ensure_window()

# method 2
from kivy.core.window import Window
```

If not, please report a detailed issue on github by following the instructions in the [Reporting an Issue](#) section of the [Contributing](#) documentation. This is very important for us because that kind of error can be very hard to debug. Give us all the information you can give about your environment and execution.

### 4.1.2 undefined symbol: glGenerateMipmap

Your graphics card or its drivers might be too old. Update your graphics drivers to the latest available version and retry.

### 4.1.3 ImportError: No module named event

If you use Kivy from our development version, you must compile it before using it. In the kivy directory, do:

```
make force
```

## 4.2 Android FAQ

### 4.2.1 could not extract public data

This error message can occur under various circumstances. Ensure that:

- you have a phone with an sdcard
- you are not currently in “USB Mass Storage” mode
- you have permissions to write to the sdcard

In the case of the “USB Mass Storage” mode error, and if you don’t want to keep unplugging the device, set the usb option to Power.

### 4.2.2 Crash on touch interaction on Android 2.3.x

There have been reports of crashes on Adreno 200/205 based devices. Apps otherwise run fine but crash when interacted with/through the screen.

These reports also mentioned the issue being resolved when moving to an ICS or higher ROM.

### 4.2.3 Is it possible to have a kiosk app on android 3.0 ?

Thomas Hansen have wrote a detailed answer on the kivy-users mailing list:

[https://groups.google.com/d/msg/kivy-users/QKoCekAR1c0/yV-85Y\\_iAw0J](https://groups.google.com/d/msg/kivy-users/QKoCekAR1c0/yV-85Y_iAw0J)

Basically, you need to root the device, remove the SystemUI package, add some lines to the xml configuration, and you’re done.

### 4.2.4 What’s the difference between python-for-android from Kivy and SL4A?

Despite having the same name, Kivy’s python-for-android is not related to the python-for-android project from SL4A, Py4A, or android-python27. They are distinctly different projects with different goals. You may be able to use Py4A with Kivy, but no code or effort has been made to do so. The Kivy team feels that our python-for-android is the best solution for us going forward, and attempts to integrate with and support Py4A is not a good use of our time.

## 4.3 Project FAQ

### 4.3.1 Why do you use Python? Isn’t it slow?

Let us try to give a thorough answer; please bear with us.

Python is a very agile language that allows you to do many things in a (by comparison) short time. For many development scenarios, we strongly prefer writing our application quickly in a high-level language such as Python, testing it, then optionally optimizing it.

But what about speed? If you compare execution speeds of implementations for a certain set of algorithms (esp. number crunching) you will find that Python is a lot slower than say, C++. Now you may be even more convinced that it's not a good idea in our case to use Python. Drawing sophisticated graphics (and we are not talking about your grandmother's OpenGL here) is computationally quite expensive and given that we often want to do that for rich user experiences, that would be a fair argument. **But**, in virtually every case your application ends up spending most of the time (by far) executing the same part of the code. In Kivy, for example, these parts are event dispatching and graphics drawing. Now Python allows you to do something to make these parts much faster.

By using Cython, you can compile your code down to the C level, and from there your usual C compiler optimizes things. This is a pretty pain free process and if you add some hints to your code, the result becomes even faster. We are talking about a speed up in performance by a factor of anything between 1x and up to more than 1000x (greatly depends on your code). In Kivy, we did this for you and implemented the portions of our code, where efficiency really is critical, on the C level.

For graphics drawing, we also leverage today's GPUs which are, for some tasks such as graphics rasterization, much more efficient than a CPU. Kivy does as much as is reasonable on the GPU to maximize performance. If you use our Canvas API to do the drawing, there is even a compiler that we invented which optimizes your drawing code automatically. If you keep your drawing mostly on the GPU, much of your program's execution speed is not determined by the programming language used, but by the graphics hardware you throw at it.

We believe that these (and other) optimizations that Kivy does for you already make most applications fast enough by far. Often you will even want to limit the speed of the application in order not to waste resources. But even if this is not sufficient, you still have the option of using Cython for your own code to *greatly* speed it up.

Trust us when we say that we have given this very careful thought. We have performed many different benchmarks and come up with some clever optimizations to make your application run smoothly.

### 4.3.2 Does Kivy support Python 3.x?

Yes! As of version 1.8.0 Kivy supports both Python >= 2.7 and Python >= 3.3 with the same codebase. Python 3 is also now supported by python-for-android.

However, be aware that while Kivy will run in Python 3.3+, our iOS build tools still require Python 2.7.

### 4.3.3 How is Kivy related to PyMT?

Our developers are professionals and are pretty savvy in their area of expertise. However, before Kivy came around there was (and still is) a project named PyMT that was led by our core developers. We learned a great deal from that project during the time that we developed it. In the more than two years of research and development we found many interesting ways to improve the design of our framework. We have performed numerous benchmarks and as it turns out, to achieve the great speed and flexibility that Kivy has, we had to rewrite quite a big portion of the codebase, making this a backwards-incompatible but future-proof decision. Most notable are the performance increases, which are just incredible. Kivy starts and operates just so much faster, due to these heavy optimizations. We also had the opportunity to work with businesses and associations using PyMT. We were able to test our product on a large diversity of setups and made PyMT work on all of them. Writing a system such as Kivy or PyMT is one thing. Making it work under all these different conditions is another. We have a good background here, and brought our knowledge to Kivy.

Furthermore, since some of our core developers decided to drop their full-time jobs and turn to this project completely, it was decided that a more professional foundation had to be laid. Kivy is that

foundation. It is supposed to be a stable and professional product. Technically, Kivy is not really a successor to PyMT because there is no easy migration path between them. However, the goal is the same: Producing high-quality applications for novel user interfaces. This is why we encourage everyone to base new projects on Kivy instead of PyMT. Active development of PyMT has stalled. Maintenance patches are still accepted.

#### 4.3.4 Do you accept patches?

Yes, we love patches. In order to ensure a smooth integration of your precious changes however, please make sure to read our contribution guidelines. Obviously we don't accept every patch. Your patch has to be consistent with our styleguide and, more importantly, make sense. It does make sense to talk to us before you come up with bigger changes, especially new features.

#### 4.3.5 Does the Kivy project participate in Google's Summer of Code ?

Potential students ask whether we participate in GSoC. The clear answer is: Indeed. :-)

If you want to participate as a student and want to maximize your chances of being accepted, start talking to us today and try fixing some smaller (or larger, if you can ;-) problems to get used to our workflow. If we know you can work well with us, that'd be a big plus.

Here's a checklist:

- Make sure to read through the website and at least skim the documentation.
- Look at the source code.
- Read our contribution guidelines.
- Pick an idea that you think is interesting from the ideas list (see link above) or come up with your own idea.
- Do some research **yourself**. GSoC is not about us teaching you something and you getting paid for that. It is about you trying to achieve agreed upon goals by yourself with our support. The main driving force in this should be, obviously, yourself. Many students come up and ask what they should do. Well, we don't know because we know neither your interests nor your skills. Show us you're serious about it and take initiative.
- Write a draft proposal about what you want to do. Include what you understand the current state is (very roughly), what you would like to improve and how, etc.
- Discuss that proposal with us in a timely manner. Get feedback.
- Be patient! Especially on IRC. We will try to get to you if we're available. If not, send an email and just wait. Most questions are already answered in the docs or somewhere else and can be found with some research. If your questions don't reflect that you've actually thought through what you're asking, it might not be well received.

Good luck! :-)

# Contact Us

---

You can contact us in several different ways:

## 5.1 Issue Tracker

If you have found an issue with the code or have a feature request, please see our [issue tracker](#). If there is no issue yet that matches your inquiry, feel free to create a new one. Please make sure you receive the mails that github sends if we comment on the issue in case we need more information. For bugs, please provide all the information necessary, like the operating system you're using, the [full error message](#) or any other logs, a description of what you did to trigger the bug and what the actual bug was, as well as anything else that might be of interest. Obviously, we can only help if you tell us precisely what the actual problem is.

## 5.2 Mail

For users of our framework, there is a mailing list for support inquiries on the [kivy-users Google Group](#). Use this list if you have issues with your Kivy-based app. We also have a mailing list for matters that deal with development of the actual Kivy framework code on the [kivy-dev Google Group](#).

## 5.3 IRC

### #Kivy on irc.freenode.net

IRC is great for real-time communication, but please make sure to **wait** after you asked your question. If you just join, ask and quit we have **no way** of knowing who you were and where we're supposed to send our answer. Also, keep in mind we're mostly based in Europe, so take into account any timezone issues. If you're unlucky more than once, try the mailing list.

If you don't have an IRC client, you can also use [Freenode's web chat](#), but please, don't close the browser window too soon. Just enter **#kivy** in the channels field.

Please read our [Community Guidelines](#) before asking for help on the mailing list or IRC channel.

Part II

## PROGRAMMING GUIDE



# Kivy Basics

---

## 6.1 Installation of the Kivy environment

Kivy depends on many Python libraries, such as pygame, gstreamer, PIL, Cairo, and more. They are not all required, but depending on the platform you're working on, they can be a pain to install. For Windows and MacOS X, we provide a portable package that you can just unzip and use.

- *Installation on Windows*
- *Installation on OS X*
- *Installation on Linux*

If you want to install everything yourself, ensure that you have at least [Cython](#) and [Pygame](#). A typical pip installation looks like this:

```
pip install cython  
pip install hg+http://bitbucket.org/pygame/pygame  
pip install kivy
```

The [development version](#) can be installed with git:

```
git clone https://github.com/kivy/kivy  
make
```

## 6.2 Create an application

Creating a kivy application is as simple as:

- sub-classing the [App](#) class
- implementing its [build\(\)](#) method so it returns a [Widget](#) instance (the root of your widget tree)
- instantiating this class, and calling its [run\(\)](#) method.

Here is an example of a minimal application:

```
import kivy
kivy.require('1.0.6') # replace with your current kivy version !

from kivy.app import App
from kivy.uix.label import Label


class MyApp(App):


    def build(self):
        return Label(text='Hello world')

if __name__ == '__main__':
    MyApp().run()
```

You can save this to a text file, *main.py* for example, and run it.

## 6.3 Kivy App Life Cycle

First off, let's get familiar with the Kivy app life cycle.



As you can see above, for all intents and purposes, our entry point into our App is the `run()` method, and in our case that is “`MyApp().run()`”. We will get back to this, but let's start from the third line:

```
from kivy.app import App
```

It's required that the base Class of your App inherits from the *App* class. It's present in the `kivy_installation_dir/kivy/app.py`.

---

**Note:** Go ahead and open up that file if you want to delve deeper into what the Kivy App class does. We encourage you to open the code and read through it. Kivy is based on Python and uses Sphinx for documentation, so the documentation for each class is in the actual file.

---

Similarly on line 2:

```
from kivy.uix.label import Label
```

One important thing to note here is the way packages/classes are laid out. The `uix` module is the section that holds the user interface elements like layouts and widgets.

Moving on to line 5:

```
class MyApp(App):
```

This is where we are *defining* the Base Class of our Kivy App. You should only ever need to change the name of your app `MyApp` in this line.

Further on to line 7:

```
def build(self):
```

As highlighted by the image above, show casing the *Kivy App Life Cycle*, this is the function where you should initialize and return your *Root Widget*. This is what we do on line 8:

```
return Label(text='Hello world')
```

Here we initialize a Label with text 'Hello World' and return its instance. This Label will be the Root Widget of this App.

---

**Note:** Python uses indentation to denote code blocks, therefore take note that in the code provided above, at line 9 the class and function definition ends.

---

Now on to the portion that will make our app run at line 11 and 12:

```
if __name__ == '__main__':
    MyApp().run()
```

Here the class `MyApp` is initialized and its `run()` method called. This initializes and starts our Kivy application.

## 6.4 Running the application

To run the application, follow the instructions for your operating system:

**Linux** Follow the instructions for [running a Kivy application on Linux](#):

```
$ python main.py
```

**Windows** Follow the instructions for [running a Kivy application on Windows](#):


```
$ python main.py  
# or  
C:\appdir>kivy.bat main.py
```

**Mac OS X** Follow the instructions for *running a Kivy application on OS X*:

```
$ kivy main.py
```

**Android** Your application needs some complementary files to be able to run on Android.  
See [Create a package for Android](#) for further reference.

A window should open, showing a single Label (with the Text 'Hello World') that covers the entire window's area. That's all there is to it.



## 6.5 Customize the application

Lets extend this application a bit, say a simple UserName/Password page.

```
from kivy.app import App  
from kivy.uix.gridlayout import GridLayout  
from kivy.uix.label import Label  
from kivy.uix.textinput import TextInput  
  
class LoginScreen(GridLayout):  
  
    def __init__(self, **kwargs):  
        super(LoginScreen, self).__init__(**kwargs)  
        self.cols = 2  
        self.add_widget(Label(text='User Name'))  
        self.username = TextInput(multiline=False)
```

```

    self.add_widget(self.username)
    self.add_widget(Label(text='password'))
    self.password = TextInput(password=True, multiline=False)
    self.add_widget(self.password)

class MyApp(App):

    def build(self):
        return LoginScreen()

if __name__ == '__main__':
    MyApp().run()

```

At line 2 we import a `GridLayout`:

```
from kivy.uix.gridlayout import GridLayout
```

This class is used as a Base for our Root Widget (`LoginScreen`) defined at line 9:

```
class LoginScreen(GridLayout):
```

At line 12 in the class `LoginScreen`, we override the method `__init__()` so as to add widgets and to define their behavior:

```
def __init__(self, **kwargs):
    super(LoginScreen, self).__init__(**kwargs)
```

One should not forget to call `super` in order to implement the functionality of the original class being overloaded. Also note that it is good practice not to omit the `**kwargs` while calling `super`, as they are sometimes used internally.

Moving on to Line 15 and beyond:

```

self.cols = 2
self.add_widget(Label(text='User Name'))
self.username = TextInput(multiline=False)
self.add_widget(self.username)
self.add_widget(Label(text='password'))
self.password = TextInput(password=True, multiline=False)
self.add_widget(self.password)

```

We ask the `GridLayout` to manage its children in two columns and add a `Label` and a `TextInput` for the username and password.

Running the above code will give you a window that should look like this:



Try re-sizing the window and you will see that the widgets on screen adjust themselves according to the size of the window without you having to do anything. This is because widgets use size hinting by default.

The code above doesn't handle the input from the user, does no validation or anything else. We will delve deeper into this and **Widget** size and positioning in the coming sections.

# Controlling the environment

---

Many environment variables are available to control the initialization and behavior of Kivy.

For example, in order to restrict text rendering to the PIL implementation:

```
$ KIVY_TEXT=pil python main.py
```

Environment variables should be set before importing kivy:

```
import os
os.environ['KIVY_TEXT'] = 'pil'
import kivy
```

## 7.1 Path control

New in version 1.0.7.

You can control the default directories where config files, modules and kivy data are located.

**KIVY\_DATA\_DIR** Location of the Kivy data, defaults to *<kivy path>/data*

**KIVY\_MODULES\_DIR** Location of the Kivy modules, defaults to *<kivy path>/modules*

**KIVY\_HOME** Location of the Kivy home. This directory is used for local configuration, and must be in a writable location.

**Defaults to:**

- Desktop: *<user home>/.kivy*
- Android: *<android app path>/.kivy*
- iOS: *<user home>/Documents/.kivy*

New in version 1.9.0.

**KIVY SDL2 PATH** If set, the SDL2 libraries and headers from this path are used when compiling kivy instead of the ones installed system-wide. To use the same libraries while running a kivy app, this path must be added at the start of the PATH environment variable.

New in version 1.9.0.

**Warning:** This path is required for the compilation of Kivy. It is not required for program execution.

## 7.2 Configuration

**KIVY USE DEFAULTCONFIG** If this name is found in environ, Kivy will not read the user config file.

**KIVY NO CONFIG** If set, no configuration file will be read or written to. This also applies to the user configuration directory.

**KIVY NO FILELOG** If set, logs will not print to a file

**KIVY NO CONSOLELOG** If set, logs will not print to the console

**KIVY NO ARGS** If set, the argument passed in command line will not be parsed and used by Kivy. Ie, you can safely make a script or an app with your own arguments without requiring the – delimiter:

```
import os
os.environ["KIVY_NO_ARGS"] = "1"
import kivy
```

New in version 1.9.0.

## 7.3 Restrict core to specific implementation

**kivy.core** try to select the best implementation available for your platform. For testing or custom installation, you might want to restrict the selector to a specific implementation.

**KIVY WINDOW** Implementation to use for creating the Window

Values: sdl2, pygame, x11, egl\_rpi

**KIVY TEXT** Implementation to use for rendering text

Values: sdl2, pil, pygame, sdlttf

**KIVY VIDEO** Implementation to use for rendering video

Values: gstplayer, ffpyleplayer, ffmpeg, null

**KIVY AUDIO** Implementation to use for playing audio

Values: sdl2, gstplayer, ffpyleplayer, pygame, avplayer

**KIVY IMAGE** Implementation to use for reading image

Values: sdl2, pil, pygame, imageio, tex, dds, gif

**KIVY CAMERA** Implementation to use for reading camera

Values: avfoundation, android, opencv

**KIVY\_SPELLING** Implementation to use for spelling

Values: enchant, osxappkit

**KIVY\_CLIPBOARD** Implementation to use for clipboard management

Values: sdl2, pygame, dummy, android

## 7.4 Metrics

**KIVY\_DPI** If set, the value will be used for `Metrics.dpi`.

New in version 1.4.0.

**KIVY\_METRICS\_DENSITY** If set, the value will be used for `Metrics.density`.

New in version 1.5.0.

**KIVY\_METRICS\_FONTSIZE**

If set, the value will be used for `Metrics.fontsize`.

New in version 1.5.0.

## 7.5 Graphics

**KIVY\_GL\_BACKEND** The OpenGL backend to use. See [cgl](#).

**KIVY\_GL\_DEBUG** Whether to log OpenGL calls. See [cgl](#).

**KIVY\_GRAPHICS** Whether to use OpenGL ES2. See [cgl](#).

**KIVY\_GLES\_LIMITS** Whether the GLES2 restrictions are enforced (the default, or if set to 1). If set to false, Kivy will not be truly GLES2 compatible.

Following is a list of the potential incompatibilities that result when set to true.

Mesh indices	If true, the number of indices in a mesh is limited to 65535
Texture blit	When blitting to a texture, the data (color and buffer) format must be the same format as the one used at the texture creation. On desktop, the conversion of different color is correctly handled by the driver, while on Android, most of devices fail to do it. Ref: <a href="https://github.com/kivy/kivy/issues/1600">https://github.com/kivy/kivy/issues/1600</a>

New in version 1.8.1.

**KIVY BCM DISPMANX\_ID** Change the default Raspberry Pi display to use. The list of available value is accessible in `vc_dispmanx_types.h`. Default value is 0:

- 0: `DISPMANX_ID_MAIN_LCD`
- 1: `DISPMANX_ID_AUX_LCD`
- 2: `DISPMANX_ID_HDMI`
- 3: `DISPMANX_ID_SDTV`
- 4: `DISPMANX_ID_FORCE_LCD`
- 5: `DISPMANX_ID_FORCE_TV`
- 6: `DISPMANX_ID_FORCE_OTHER`

**KIVY\_BCM\_DISPMANX\_LAYER** Change the default Raspberry Pi dispmanx layer. Default value is 0.

New in version 1.10.1.

# Configure Kivy

---

The configuration file for kivy is named *config.ini*, and adheres to the **standard INI** format.

## 8.1 Locating the configuration file

The location of the configuration file is controlled by the environment variable *KIVY\_HOME*:

```
<KIVY_HOME>/config.ini
```

On desktop, this defaults to:

```
<HOME_DIRECTORY>/ .kivy/config.ini
```

Therefore, if your user is named “tito”, the file will be here:

- Windows: C:\Users\tito\.kivy\config.ini
- OS X: /Users/tito/.kivy/config.ini
- Linux: /home/tito/.kivy/config.ini

On Android, this defaults to:

```
<ANDROID_APP_PATH>/ .kivy/config.ini
```

If your app is named “org.kivy.launcher”, the file will be here:

```
/data/data/org.kivy.launcher/files/.kivy/config.ini
```

On iOS, this defaults to:

```
<HOME_DIRECTORY>/Documents/.kivy/config.ini
```

## 8.2 Local configuration

Sometimes it's desired to change configuration only for certain applications or during testing of a separate part of Kivy for example input providers. To create a separate configuration file you can simply use these commands:

```
from kivy.config import Config  
  
Config.read(<file>)  
# set config  
Config.write()
```

When a local configuration of single `.ini` file isn't enough, e.g. when you want to have separate environment for `garden`, kivy logs and other things, you'll need to change the the `KIVY_HOME` environment variable in your application to get desired result:

```
import os  
os.environ['KIVY_HOME'] = <folder>
```

or before each run of the application change it manually in the console:

1. Windows:

```
set KIVY_HOME=<folder>
```

2. Linux & OSX:

```
export KIVY_HOME=<folder>
```

After the change of `KIVY_HOME`, the folder will behave exactly the same as the default `.kivy/` folder mentioned above.

## 8.3 Understanding config tokens

All the configuration tokens are explained in the `kivy.config` module.

# Architectural Overview


---

We would like to take a moment to explain how we designed Kivy from a software engineering point of view. This is key to understanding how everything works together. If you just look at the code, chances are you will get a rough idea already, but since this approach certainly is daunting for most users, this section explains the basic ideas of the implementation in more detail. You can skip this section and refer to it later, but we suggest at least skimming it for a rough overview.

Kivy consists of several building blocks that we will explain shortly. Here is a graphical summary of the architecture:



# Kivy Architecture



## 9.1 Core Providers and Input Providers

One idea that is key to understanding Kivy's internals is that of modularity and abstraction. We try to abstract basic tasks such as opening a window, displaying images and text, playing audio, getting images from a camera, spelling correction and so on. We call these *core* tasks. This makes the API both easy to use and easy to extend. Most importantly, it allows us to use – what we call – specific providers for the respective scenarios in which your app is being run. For example, on OSX, Linux and Windows, there are different native APIs for the different core tasks. A piece of code that uses one of these specific APIs to talk to the operating system on one side and to Kivy on the other (acting as an intermediate communication layer) is what we call a *core provider*. The advantage of using specialized core providers for each platform is that we can fully leverage the functionality exposed by the operating system and act as efficiently as possible. It also gives users a choice. Furthermore, by using libraries that are shipped with any one platform, we effectively reduce the size of the Kivy distribution and make packaging easier. This also makes it easier to port Kivy to other platforms. The Android port benefited greatly from this.

We follow the same concept with input handling. An *input provider* is a piece of code that adds support for a specific input device, such as Apple's trackpads, TUIO or a mouse emulator. If you need to add support for a new input device, you can simply provide a new class that reads your input data from your device and transforms them into Kivy basic events.

## 9.2 Graphics

Kivy's graphics API is our abstraction of OpenGL. On the lowest level, Kivy issues hardware-accelerated drawing commands using OpenGL. Writing OpenGL code however can be a bit confusing, especially to newcomers. That's why we provide the graphics API that lets you draw things using simple metaphors that do not exist as such in OpenGL (e.g. Canvas, Rectangle, etc.).

All of our widgets themselves use this graphics API, which is implemented on the C level for performance reasons.

Another advantage of the graphics API is its ability to automatically optimize the drawing commands that your code issues. This is especially helpful if you're not an expert at tuning OpenGL. This makes your drawing code more efficient in many cases.

You can, of course, still use raw OpenGL commands if you prefer. The version we target is OpenGL 2.0 ES (GLES2) on all devices, so if you want to stay cross-platform compatible, we advise you to only use the GLES2 functions.

## 9.3 Core

The code in the core package provides commonly used features, such as:

**Clock** You can use the clock to schedule timer events. Both one-shot timers and periodic timers are supported.

**Cache** If you need to cache something that you use often, you can use our class for that instead of writing your own.

**Gesture Detection** We ship a simple gesture recognizer that you can use to detect various kinds of strokes, such as circles or rectangles. You can train it to detect your own strokes.

**Kivy Language** The kivy language is used to easily and efficiently describe user interfaces.

**Properties** These are not the normal properties that you may know from python. They are our own property classes that link your widget code with the user interface description.

## 9.4 UIX (Widgets & Layouts)

The UIX module contains commonly used widgets and layouts that you can reuse to quickly create a user interface.

**Widgets** Widgets are user interface elements that you add to your program to provide some kind of functionality. They may or may not be visible. Examples would be a file browser, buttons, sliders, lists and so on. Widgets receive MotionEvents.

**Layouts** You use layouts to arrange widgets. It is of course possible to calculate your widgets' positions yourself, but often it is more convenient to use one of our ready made layouts. Examples would be Grid Layouts or Box Layouts. You can also nest layouts.

## 9.5 Modules

If you've ever used a modern web browser and customized it with some add-ons then you already know the basic idea behind our module classes. Modules can be used to inject functionality into Kivy programs, even if the original author did not include it.

An example would be a module that always shows the FPS of the current application and some graph depicting the FPS over time.

You can also write your own modules.

## 9.6 Input Events (Touches)

Kivy abstracts different input types and sources such as touches, mice, TUIO or similar. What all of these input types have in common is that you can associate a 2D onscreen-position with any individual input event. (There are other input devices such as accelerometers where you cannot easily find a 2D position for e.g. a tilt of your device. This kind of input is handled separately. In the following we describe the former types.)

All of these input types are represented by instances of the Touch() class. (Note that this does not only refer to finger touches, but all the other input types as well. We just called it *Touch* for the sake of simplicity. Think of it of something that *touches* the user interface or your screen.) A touch instance, or object, can be in one of three states. When a touch enters one of these states, your program is informed that the event occurred. The three states a touch can be in are:

**Down** A touch is down only once, at the very moment where it first appears.

**Move** A touch can be in this state for a potentially unlimited time. A touch does not have to be in this state during its lifetime. A ‘Move’ happens whenever the 2D position of a touch changes.

**Up** A touch goes up at most once, or never. In practice you will almost always receive an up event because nobody is going to hold a finger on the screen for all eternity, but it is not guaranteed. If you know the input sources your users will be using, you will know whether or not you can rely on this state being entered.

## 9.7 Widgets and Event Dispatching

The term *widget* is often used in GUI programming contexts to describe some part of the program that the user interacts with. In Kivy, a widget is an object that receives input events. It does not necessarily have to have a visible representation on the screen. All widgets are arranged in a *widget tree* (which is a tree data structure as known from computer science classes): One widget can have any number of child widgets or none. There is exactly one *root widget* at the top of the tree that has no parent widget, and all other widgets are directly or indirectly children of this widget (which is why it’s called the root).

When new input data is available, Kivy sends out one event per touch. The root widget of the widget tree first receives the event. Depending on the state of the touch, the on\_touch\_down, on\_touch\_move or on\_touch\_up event is dispatched (with the touch as the argument) to the root widget, which results in the root widget’s corresponding on\_touch\_down, on\_touch\_move or on\_touch\_up event handler being called.

Each widget (this includes the root widget) in the tree can choose to either digest or pass the event on. If an event handler returns True, it means that the event has been digested and handled properly. No further processing will happen with that event. Otherwise, the event handler passes the widget on to its own children by calling its superclass’s implementation of the respective event handler. This goes all the way up to the base Widget class, which – in its touch event handlers – does nothing but pass the touches to its children:

```
# This is analogous for move/up:  
def on_touch_down(self, touch):  
    for child in self.children[:]:
```

```
if child.dispatch('on_touch_down', touch):
    return True
```

This really is much easier than it first seems. An example of how this can be used to create nice applications quickly will be given in the following section.


Often times you will want to restrict the *area* on the screen that a widget watches for touches. You can use a widget's `collide_point()` method to achieve this. You simply pass it the touch's position and it returns True if the touch is within the 'watched area' or False otherwise. By default, this checks the rectangular region on the screen that's described by the widget's pos (for position; x & y) and size (width & height), but you can override this behaviour in your own class.



# Events and Properties

Events are an important part of Kivy programming. That may not be surprising to those with GUI development experience, but it's an important concept for newcomers. Once you understand how events work and how to bind to them, you will see them everywhere in Kivy. They make it easy to build whatever behavior you want into Kivy.

The following illustration shows how events are handled in the Kivy framework.



## 10.1 Introduction to the Event Dispatcher

One of the most important base classes of the framework is the `EventDispatcher` class. This class allows you to register event types, and to dispatch them to interested parties (usually other event dispatchers). The `Widget`, `Animation` and `Clock` classes are examples of event dispatchers.

`EventDispatcher` objects depend on the main loop to generate and handle events.

## 10.2 Main loop

As outlined in the illustration above, Kivy has a *main loop*. This loop is running during all of the application's lifetime and only quits when exiting the application.

Inside the loop, at every iteration, events are generated from user input, hardware sensors or a couple of other sources, and frames are rendered to the display.

Your application will specify callbacks (more on this later), which are called by the main loop. If a callback takes too long or doesn't quit at all, the main loop is broken and your app doesn't work properly anymore.

In Kivy applications, you have to avoid long/infinite loops or sleeping. For example the following code does both:

```
while True:  
    animate_something()  
    time.sleep(.10)
```

When you run this, the program will never exit your loop, preventing Kivy from doing all of the other things that need doing. As a result, all you'll see is a black window which you won't be able to interact with. Instead, you need to "schedule" your `animate_something()` function to be called repeatedly.

### 10.2.1 Scheduling a repetitive event

You can call a function or a method every X times per second using `schedule_interval()`. Here is an example of calling a function named `my_callback` 30 times per second:

```
def my_callback(dt):  
    print 'My callback is called', dt  
event = Clock.schedule_interval(my_callback, 1 / 30.)
```

You have multiple ways of unscheduling a previously scheduled event. One, is to use `cancel()` or `unschedule()`:

```
event.cancel()
```

or:

```
Clock.unschedule(event)
```

Alternatively, you can return False in your callback, and your event will be automatically unscheduled:

```
count = 0  
def my_callback(dt):  
    global count  
    count += 1  
    if count == 10:  
        print 'Last call of my callback, bye bye !'
```

```

    return False
    print 'My callback is called'
Clock.schedule_interval(my_callback, 1 / 30.)

```

### 10.2.2 Scheduling a one-time event

Using `schedule_once()`, you can call a function “later”, like in the next frame, or in X seconds:

```

def my_callback(dt):
    print 'My callback is called !'
Clock.schedule_once(my_callback, 1)

```

This will call `my_callback` in one second. The second argument is the amount of time to wait before calling the function, in seconds. However, you can achieve some other results with special values for the second argument:

- If X is greater than 0, the callback will be called in X seconds
- If X is 0, the callback will be called after the next frame
- If X is -1, the callback will be called before the next frame

The -1 is mostly used when you are already in a scheduled event, and if you want to schedule a call BEFORE the next frame is happening.

A second method for repeating a function call is to first schedule a callback once with `schedule_once()`, and a second call to this function inside the callback itself:

```

def my_callback(dt):
    print 'My callback is called !'
    Clock.schedule_once(my_callback, 1)
Clock.schedule_once(my_callback, 1)

```

While the main loop will try to keep to the schedule as requested, there is some uncertainty as to when exactly a scheduled callback will be called. Sometimes another callback or some other task in the application will take longer than anticipated and thus the timing can be a little off.

In the latter solution to the repetitive callback problem, the next iteration will be called at least one second after the last iteration ends. With `schedule_interval()` however, the callback is called every second.

### 10.2.3 Trigger events

Sometimes you may want to schedule a function to be called only once for the next frame, preventing duplicate calls. You might be tempted to achieve that like so:

```

# First, schedule once.
event = Clock.schedule_once(my_callback, 0)

# Then, in another place you will have to unschedule first
# to avoid duplicate call. Then you can schedule again.
Clock.unschedule(event)
event = Clock.schedule_once(my_callback, 0)

```

This way of programming a trigger is expensive, since you'll always call `unschedule`, even if the event has already completed. In addition, a new event is created every time. Use a trigger instead:

```
trigger = Clock.create_trigger(my_callback)
# later
trigger()
```

Each time you call trigger(), it will schedule a single call of your callback. If it was already scheduled, it will not be rescheduled.

## 10.3 Widget events

A widget has 2 default types of events:

- Property event: if your widget changes its position or size, an event is fired.
- Widget-defined event: e.g. an event will be fired for a Button when it's pressed or released.

For a discussion on how widget touch events managed and propagated, please refer to the [Widget touch event bubbling](#) section.

## 10.4 Creating custom events

To create an event dispatcher with custom events, you need to register the name of the event in the class and then create a method of the same name.

See the following example:

```
class MyEventDispatcher(EventDispatcher):
    def __init__(self, **kwargs):
        self.register_event_type('on_test')
        super(MyEventDispatcher, self).__init__(**kwargs)

    def do_something(self, value):
        # when do_something is called, the 'on_test' event will be
        # dispatched with the value
        self.dispatch('on_test', value)

    def on_test(self, *args):
        print "I am dispatched", args
```

## 10.5 Attaching callbacks

To use events, you have to bind callbacks to them. When the event is dispatched, your callbacks will be called with the parameters relevant to that specific event.

A callback can be any python callable, but you need to ensure it accepts the arguments that the event emits. For this, it's usually safest to accept the `*args` argument, which will catch all arguments in the `args` list.

Example:

```
def my_callback(value, *args):
    print "Hello, I got an event!", args

ev = MyEventDispatcher()
```

```
ev.bind(on_test=my_callback)
ev.do_something('test')
```

Please refer to the `kivy.event.EventDispatcher.bind()` method documentation for more examples on how to attach callbacks.

## 10.6 Introduction to Properties

Properties are an awesome way to define events and bind to them. Essentially, they produce events such that when an attribute of your object changes, all properties that reference that attribute are automatically updated.

There are different kinds of properties to describe the type of data you want to handle.

- `StringProperty`
- `NumericProperty`
- `BoundedNumericProperty`
- `ObjectProperty`
- `DictProperty`
- `ListProperty`
- `OptionProperty`
- `AliasProperty`
- `BooleanProperty`
- `ReferenceListProperty`

## 10.7 Declaration of a Property

To declare properties, you must declare them at the class level. The class will then do the work to instantiate the real attributes when your object is created. These properties are not attributes: they are mechanisms for creating events based on your attributes:

```
class MyWidget(Widget):
    text = StringProperty('')
```

When overriding `__init__`, always accept `**kwargs` and use `super()` to call the parent's `__init__` method, passing in your class instance:

```
def __init__(self, **kwargs):
    super(MyWidget, self).__init__(**kwargs)
```

## 10.8 Dispatching a Property event

Kivy properties, by default, provide an `on_<property_name>` event. This event is called when the value of the property is changed.

---

**Note:** If the new value for the property is equal to the current value, then the `on_<property_name>` event will not be called.

---

For example, consider the following code:

```
1 class CustomBtn(Widget):
2
3     pressed = ListProperty([0, 0])
4
5     def on_touch_down(self, touch):
6         if self.collide_point(*touch.pos):
7             self.pressed = touch.pos
8             return True
9     return super(CustomBtn, self).on_touch_down(touch)
10
11    def on_pressed(self, instance, pos):
12        print ('pressed at {pos}'.format(pos=pos))
```

In the code above at line 3:

```
pressed = ListProperty([0, 0])
```

We define the `pressed` Property of type `ListProperty`, giving it a default value of `[0, 0]`. From this point forward, the `on_pressed` event will be called whenever the value of this property is changed.

At Line 5:

```
def on_touch_down(self, touch):
    if self.collide_point(*touch.pos):
        self.pressed = touch.pos
        return True
    return super(CustomBtn, self).on_touch_down(touch)
```

We override the `on_touch_down()` method of the `Widget` class. Here, we check for collision of the `touch` with our widget.

If the touch falls inside of our widget, we change the value of `pressed` to `touch.pos` and return `True`, indicating that we have consumed the touch and don't want it to propagate any further.

Finally, if the touch falls outside our widget, we call the original event using `super(...)` and return the result. This allows the touch event propagation to continue as it would normally have occurred.

Finally on line 11:

```
def on_pressed(self, instance, pos):
    print ('pressed at {pos}'.format(pos=pos))
```

We define an `on_pressed` function that will be called by the property whenever the property value is changed.

---

**Note:** This `on_<prop_name>` event is called within the class where the property is defined. To monitor/observe any change to a property outside of the class where it's defined, you should bind to the property as shown below.

---

### Binding to the property

How to monitor changes to a property when all you have access to is a widget instance? You *bind* to the property:

```
your_widget_instance.bind(property_name=function_name)
```

For example, consider the following code:

```
1 class RootWidget(BoxLayout):
2
3     def __init__(self, **kwargs):
4         super(RootWidget, self).__init__(**kwargs)
5         self.add_widget(Button(text='btn 1'))
6         cb = CustomBtn()
7         cb.bind(pressed=self.btn_pressed)
8         self.add_widget(cb)
9         self.add_widget(Button(text='btn 2'))
10
11     def btn_pressed(self, instance, pos):
12         print ('pos: printed from root widget: {pos}'.format(pos=pos))
```

If you run the code as is, you will notice two print statements in the console. One from the *on\_pressed* event that is called inside the *CustomBtn* class and another from the *btn\_pressed* function that we bind to the property change.

The reason that both functions are called is simple. Binding doesn't mean overriding. Having both of these functions is redundant and you should generally only use one of the methods of listening/reacting to property changes.

You should also take note of the parameters that are passed to the *on<property\_name>* event or the function bound to the property.

```
def btn_pressed(self, instance, pos):
```

The first parameter is *self*, which is the instance of the class where this function is defined. You can use an in-line function as follows:

```
1 cb = CustomBtn()
2
3 def _local_func(instance, pos):
4     print ('pos: printed from root widget: {pos}'.format(pos=pos))
5
6 cb.bind(pressed=_local_func)
7 self.add_widget(cb)
```

The first parameter would be the *instance* of the class the property is defined.

The second parameter would be the *value*, which is the new value of the property.

Here is the complete example, derived from the snippets above, that you can use to copy and paste into an editor to experiment.

```
1 from kivy.app import App
2 from kivy.uix.widget import Widget
3 from kivy.uix.button import Button
4 from kivy.uix.boxlayout import BoxLayout
5 from kivy.properties import ListProperty
6
7 class RootWidget(BoxLayout):
8
9     def __init__(self, **kwargs):
10         super(RootWidget, self).__init__(**kwargs)
11         self.add_widget(Button(text='btn 1'))
12         cb = CustomBtn()
```

```

13     cb.bind(pressed=self.btn_pressed)
14     self.add_widget(cb)
15     self.add_widget(Button(text='btn 2'))
16
17     def btn_pressed(self, instance, pos):
18         print ('pos: printed from root widget: {pos}'.format(pos=pos))
19
20 class CustomBtn(Widget):
21
22     pressed = ListProperty([0, 0])
23
24     def on_touch_down(self, touch):
25         if self.collide_point(*touch.pos):
26             self.pressed = touch.pos
27             # we consumed the touch. return False here to propagate
28             # the touch further to the children.
29             return True
30         return super(CustomBtn, self).on_touch_down(touch)
31
32     def on_pressed(self, instance, pos):
33         print ('pressed at {pos}'.format(pos=pos))
34
35 class TestApp(App):
36
37     def build(self):
38         return RootWidget()
39
40
41 if __name__ == '__main__':
42     TestApp().run()

```

Running the code above will give you the following output:



Our CustomBtn has no visual representation and thus appears black. You can touch/click on the black area to see the output on your console.

## 10.9 Compound Properties

When defining an **AliasProperty**, you normally define a getter and a setter function yourself. Here, it falls on to you to define when the getter and the setter functions are called using the *bind* argument.

Consider the following code.

```
1 cursor_pos = AliasProperty(_get_cursor_pos, None, bind=()
2     'cursor', 'padding', 'pos', 'size', 'focus',
3     'scroll_x', 'scroll_y'))
4 '''Current position of the cursor, in (x, y).
5
6 :attr:`cursor_pos` is a :class:`~kivy.properties.AliasProperty`, read-only.
7 '''
```

Here *cursor\_pos* is a **AliasProperty** which uses the *getter* *\_get\_cursor\_pos* with the *setter* part set to *None*, implying this is a read only Property.

The bind argument at the end defines that *on\_cursor\_pos* event is dispatched when any of the properties used in the *bind=* argument change.



# Input management

---

## 11.1 Input architecture

Kivy is able to handle most types of input: mouse, touchscreen, accelerometer, gyroscope, etc. It handles the native multitouch protocols on the following platforms: Tuio, WM\_Touch, MacMultitouchSupport, MT Protocol A/B and Android.

The global architecture can be viewed as:

```
Input providers -> Motion event -> Post processing -> Dispatch to Window
```

The class of all input events is the *MotionEvent*. It generates 2 kinds of events:

- Touch events: a motion event that contains at least an X and Y position. All the touch events are dispatched across the Widget tree.
- No-touch events: all the rest. For example, the accelerometer is a continuous event, without position. It never starts or stops. These events are not dispatched across the Widget tree.

A Motion event is generated by an *Input Provider*. An Input Provider is responsible for reading the input event from the operating system, the network or even from another application. Several input providers exist, such as:

- *TuioMotionEventProvider*: create a UDP server and listen for TUIO/OSC messages.
- *WM\_MotionEventProvider*: use the windows API for reading multitouch information and sending it to Kivy.
- *ProbeSysfsHardwareProbe*: In Linux, iterate over all the hardware connected to the computer, and attaches a multitouch input provider for each multitouch device found.
- and much more!

When you write an application, you don't need to create an input provider. Kivy tries to automatically detect available hardware. However, if you want to support custom hardware, you will need to configure kivy to make it work.

Before the newly-created Motion Event is passed to the user, Kivy applies post-processing to the input. Every motion event is analyzed to detect and correct faulty input, as well as make meaningful interpretations like:

- Double/triple-tap detection, according to a distance and time threshold
- Making events more accurate when the hardware is not accurate
- Reducing the amount of generated events if the native touch hardware is sending events with nearly the same position

After processing, the motion event is dispatched to the Window. As explained previously, not all events are dispatched to the whole widget tree: the window filters them. For a given event:

- if it's only a motion event, it will be dispatched to `on_motion()`
- if it's a touch event, the (x,y) position of the touch (0-1 range) will be scaled to the Window size (width/height), and dispatched to:
  - `on_touch_down()`
  - `on_touch_move()`
  - `on_touch_up()`

## 11.2 Motion event profiles

Depending on your hardware and the input providers used, more information may be made available to you. For example, a touch input has an (x,y) position, but might also have pressure information, blob size, an acceleration vector, etc.

A profile is a string that indicates what features are available inside the motion event. Let's imagine that you are in an `on_touch_move` method:

```
def on_touch_move(self, touch):
    print(touch.profile)
    return super(..., self).on_touch_move(touch)
```

The print could output:

```
['pos', 'angle']
```

**Warning:** Many people mix up the profile's name and the name of the corresponding property. Just because '`angle`' is in the available profile doesn't mean that the touch event object will have an `angle` property.

For the '`pos`' profile, the properties `pos`, `x`, and `y` will be available. With the '`angle`' profile, the property `a` will be available. As we said, for touch events '`pos`' is a mandatory profile, but not '`angle`'. You can extend your interaction by checking if the '`angle`' profile exists:

```
def on_touch_move(self, touch):
    print('The touch is at position', touch.pos)
    if 'angle' in touch.profile:
        print('The touch angle is', touch.a)
```

You can find a list of available profiles in the [motionevent](#) documentation.

## 11.3 Touch events

A touch event is a specialized `MotionEvent` where the property `is_touch` evaluates to True. For all touch events, you automatically have the X and Y positions available, scaled to the Window width and height. In other words, all touch events have the '`pos`' profile.

### 11.3.1 Touch event basics

By default, touch events are dispatched to all currently displayed widgets. This means widgets receive the touch event whether it occurs within their physical area or not.

This can be counter intuitive if you have experience with other GUI toolkits. These typically divide the screen into geometric areas and only dispatch touch or mouse events to the widget if the coordinate lies within the widgets area.

This requirement becomes very restrictive when working with touch input. Swipes, pinches and long presses may well originate from outside of the widget that wants to know about them and react to them.

In order to provide the maximum flexibility, Kivy dispatches the events to all the widgets and lets them decide how to react to them. If you only want to respond to touch events inside the widget, you simply check:

```
def on_touch_down(self, touch):
    if self.collide_point(*touch.pos):
        # The touch has occurred inside the widgets area. Do stuff!
        pass
```

### 11.3.2 Coordinates

You must take care of matrix transformation in your touch as soon as you use a widget with matrix transformation. Some widgets such as `Scatter` have their own matrix transformation, meaning the touch must be multiplied by the scatter matrix to be able to correctly dispatch touch positions to the Scatter's children.

- Get coordinate from parent space to local space: `to_local()`
- Get coordinate from local space to parent space: `to_parent()`
- Get coordinate from local space to window space: `to_window()`
- Get coordinate from window space to local space: `to_widget()`

You must use one of them to scale coordinates correctly to the context. Let's look the scatter implementation:

```
def on_touch_down(self, touch):
    # push the current coordinate, to be able to restore it later
    touch.push()

    # transform the touch coordinate to local space
    touch.apply_transform_2d(self.to_local)

    # dispatch the touch as usual to children
    # the coordinate in the touch is now in local space
    ret = super(..., self).on_touch_down(touch)

    # whatever the result, don't forget to pop your transformation
    # after the call, so the coordinate will be back in parent space
    touch.pop()
```

```
# return the result (depending what you want.)  
return ret
```

### 11.3.3 Touch shapes

If the touch has a shape, it will be reflected in the 'shape' property. Right now, only a `ShapeRect` can be exposed:

```
from kivy.input.shape import ShapeRect  
  
def on_touch_move(self, touch):  
    if isinstance(touch.shape, ShapeRect):  
        print('My touch have a rectangle shape of size',  
              (touch.shape.width, touch.shape.height))  
    # ...
```

### 11.3.4 Double tap

A double tap is the action of tapping twice within a time and a distance. It's calculated by the doubletap post-processing module. You can test if the current touch is one of a double tap or not:

```
def on_touch_down(self, touch):  
    if touch.is_double_tap:  
        print('Touch is a double tap !')  
        print(' - interval is', touch.double_tap_time)  
        print(' - distance between previous is', touch.double_tap_distance)  
    # ...
```

### 11.3.5 Triple tap

A triple tap is the action of tapping thrice within a time and a distance. It's calculated by the tripletap post-processing module. You can test if the current touch is one of a triple tap or not:

```
def on_touch_down(self, touch):  
    if touch.is_triple_tap:  
        print('Touch is a triple tap !')  
        print(' - interval is', touch.triple_tap_time)  
        print(' - distance between previous is', touch.triple_tap_distance)  
    # ...
```

### 11.3.6 Grabbing touch events

It's possible for the parent widget to dispatch a touch event to a child widget from within `on_touch_down`, but not from `on_touch_move` or `on_touch_up`. This can happen in certain scenarios, like when a touch movement is outside the bounding box of the parent, so the parent decides not to notify its children of the movement.

But you might want to do something in `on_touch_up`. Say you started something in the `on_touch_down` event, like playing a sound, and you'd like to finish things on the `on_touch_up` event. Grabbing is what you need.

When you grab a touch, you will always receive the move and up event. But there are some limitations to grabbing:

- You will receive the event at least twice: one time from your parent (the normal event), and one time from the window (grab).
- You might receive an event with a grabbed touch, but not from you: it can be because the parent has sent the touch to its children while it was in the grabbed state.
- The touch coordinate is not translated to your widget space because the touch is coming directly from the Window. It's your job to convert the coordinate to your local space.

Here is an example of how to use grabbing:

```
def on_touch_down(self, touch):
    if self.collide_point(*touch.pos):
        # if the touch collides with our widget, let's grab it
        touch.grab(self)

        # and accept the touch.
        return True

def on_touch_up(self, touch):
    # here, you don't check if the touch collides or things like that.
    # you just need to check if it's a grabbed touch event
    if touch.grab_current is self:
        # ok, the current touch is dispatched for us.
        # do something interesting here
        print('Hello world!')

        # don't forget to ungrab ourself, or you might have side effects
        touch.ungrab(self)

        # and accept the last up
        return True
```

### 11.3.7 Touch Event Management

In order to see how touch events are controlled and propagated between widgets, please refer to the [Widget touch event bubbling](#) section.

## 11.4 Joystick events

A joystick input represents raw values received directly from physical or virtual controllers through the SDL2 provider via these events:

- `SDL_JOYAXISMOTION`
- `SDL_JOYHATMOTION`
- `SDL_JOYBALLMOTION`
- `SDL_JOYBUTTONDOWN`
- `SDL_JOYBUTTONUP`

Every motion event has a minimum, maximum and default value which can reach:

Event	Minimum	Maximum	Default
on_joy_axis	-32767	32767	0
on_joy_hat	(-1, -1)	(1, 1)	(0, 0)
on_joy_ball	Unknown	Unknown	Unknown

Button events, on the other hand represent basically only a state of each button i.e. *up* and *down*, therefore no such values are present.

- on\_joy\_button\_up
- on\_joy\_button\_down

#### 11.4.1 Joystick event basics

Unlike touch events, joystick events are dispatched directly to the Window, which means there's only a single value passed for e.g. a specified axis, not multiple ones. This makes things harder if you want to separate input to different widgets, yet not impossible. You can use [Multiple dropfile example](#) as an inspiration.

To get a joystick event, you first need to bind some function to the Window joystick event like this:

```
Window.bind(on_joy_axis=self.on_joy_axis)
```

Then you need to fetch the parameters specified in `Window` for each event you use, for example:

```
def on_joy_axis(self, win, stickid, axisid, value):
    print(win, stickid, axisid, value)
```

A variable `stickid` is an id of a controller that sent the value, `axisid` is an id of an axis to which the value belongs.

#### 11.4.2 Joystick input

Kivy should be able to fetch input from any device specified as `gamepad`, `joystick` or basically any other type of game controller recognized by the SDL2 provider. To make things easier, here are layouts of some common controllers together with ids for each part.

## Xbox 360



#	ID	#	ID
1	axis 1	2	axis 0
3	hat Y	4	hat X
5	axis 4	6	axis 3
7	axis 2	8	axis 5
9	button 4	10	button 5
X	button 2	Y	button 3
A	button 0	B	button 1
back	button 6	start	button 7
center	button 10		

### 11.4.3 Joystick debugging

Mostly you'd want to debug your application with multiple controllers, or test it against `_other_` types of controllers (e.g. different brands). As an alternative you might want to use some of the available controller emulators, such as [vJoy](#).



---

# Widgets

---

## 12.1 Introduction to Widget

A [Widget](#) is the base building block of GUI interfaces in Kivy. It provides a [Canvas](#) that can be used to draw on screen. It receives events and reacts to them. For a in-depth explanation about the [Widget](#) class, look at the module documentation.

## 12.2 Manipulating the Widget tree

Widgets in Kivy are organized in trees. Your application has a *root widget*, which usually has [children](#) that can have [children](#) of their own. Children of a widget are represented as the [children](#) attribute, a Kivy [ListProperty](#).

The widget tree can be manipulated with the following methods:

- [add\\_widget\(\)](#): add a widget as a child
- [remove\\_widget\(\)](#): remove a widget from the children list
- [clear\\_widgets\(\)](#): remove all children from a widget

For example, if you want to add a button inside a BoxLayout, you can do:

```
layout = BoxLayout(padding=10)
button = Button(text='My first button')
layout.add_widget(button)
```

The button is added to layout: the button's parent property will be set to layout; the layout will have the button added to its children list. To remove the button from the layout:

```
layout.remove_widget(button)
```

With removal, the button's parent property will be set to None, and the layout will have button removed from its children list.

If you want to clear all the children inside a widget, use `clear_widgets()` method:

```
layout.clear_widgets()
```

**Warning:** Never manipulate the children list yourself, unless you really know what you are doing. The widget tree is associated with a graphic tree. For example, if you add a widget into the children list without adding its canvas to the graphics tree, the widget will be a child, yes, but nothing will be drawn on the screen. Moreover, you might have issues on further calls of `add_widget`, `remove_widget` and `clear_widgets`.

## 12.3 Traversing the Tree

The Widget class instance's `children` list property contains all the children. You can easily traverse the tree by doing:

```
root = BoxLayout()  
# ... add widgets to root ...  
for child in root.children:  
    print(child)
```

However, this must be used carefully. If you intend to modify the children list with one of the methods shown in the previous section, you must use a copy of the list like this:

```
for child in root.children[:]:  
    # manipulate the tree. For example here, remove all widgets that have a  
    # width < 100  
    if child.width < 100:  
        root.remove_widget(child)
```

Widgets don't influence the size/pos of their children by default. The `pos` attribute is the absolute position in screen co-ordinates (unless, you use the `relativelayout`. More on that later) and `size`, is an absolute size.

## 12.4 Widgets Z Index

The order of widget drawing is based on the widget's position in the widget tree. The `add_widget` method takes an `index` parameter which can be used to specify it's position in the widget tree:



```
root.add_widget(widget, index)
```

The lower indexed widgets will be drawn above those with a higher index. Keep in mind that the default for `index` is 0, so widgets added later are drawn on top of the others unless specified otherwise.


## 12.5 Organize with Layouts

`layout` is a special kind of widget that controls the size and position of its children. There are different kinds of layouts, allowing for different automatic organization of their children. Layouts use `size_hint` and `pos_hint` properties to determine the `size` and `pos` of their `children`.


**BoxLayout:** Arranges widgets in an adjacent manner (either vertically or horizontally) manner, to fill all the space. The size\_hint property of children can be used to change proportions allowed to each child, or set fixed size for some of them.



## Stack Layout



## Anchor Layout





**GridLayout:** Arranges widgets in a grid. You must specify at least one dimension of the grid so kivy can compute the size of the elements and how to arrange them.

**StackLayout:** Arranges widgets adjacent to one another, but with a set size in one of the dimensions, without trying to make them fit within the entire space. This is useful to display children of the same predefined size.

**AnchorLayout:** A simple layout only caring about children positions. It allows putting the children at a position relative to a border of the layout. *size\_hint* is not honored.

**FloatLayout:** Allows placing children with arbitrary locations and size, either absolute or relative to the layout size. Default *size\_hint* (1, 1) will make every child the same size as the whole layout, so you probably want to change this value if you have more than one child. You can set *size\_hint* to (None, None) to use absolute size with *size*. This widget honors *pos\_hint* also, which as a dict setting position relative to layout position.

**RelativeLayout:** Behaves just like FloatLayout, except children positions are relative to layout position, not the screen.

Examine the documentation of the individual layouts for a more in-depth understanding.

*size\_hint* and *pos\_hint*:

- *floatlayout*
- *boxlayout*
- *gridlayout*
- *stacklayout*
- *relativelayout*
- *anchorlayout*

*size\_hint* is a *ReferenceListProperty* of *size\_hint\_x* and *size\_hint\_y*. It accepts values from 0 to 1 or *None* and defaults to (1, 1). This signifies that if the widget is in a layout, the layout will allocate it as much place as possible in both directions (relative to the layouts size).

Setting `size_hint` to (0.5, 0.8), for example, will make the widget 50% the width and 80% the height of available size for the `Widget` inside a `layout`.


Consider the following example:

```
BoxLayout:  
    Button:  
        text: 'Button 1'  
        # default size_hint is 1, 1, we don't need to specify it explicitly  
        # however it's provided here to make things clear  
        size_hint: 1, 1
```

Now load kivy catalog by typing the following, but replacing \$KIVYDIR with the directory of your installation (discoverable via `os.path.dirname(kivy.__file__)`):


```
cd $KIVYDIR/examples/demo/kivycatalog  
python main.py
```

A new window will appear. Click in the area below the 'Welcome' `Spinner` on the left and replace the text there with your kv code from above.




As you can see from the image above, the `Button` takes up 100% of the layout `size`.

Changing the `size_hint_x`/`size_hint_y` to .5 will make the `Widget` take 50% of the `layout width/height`.




You can see here that, although we specify `size_hint_x` and `size_hint_y` both to be .5, only `size_hint_y` seems to be honored. That is because `boxlayout` controls the `size_hint_y` when `orientation` is `vertical` and `size_hint_x` when `orientation` is 'horizontal'. The controlled dimension's size is calculated depending upon the total no. of `children` in the `boxlayout`. In this example, one child has `size_hint_y` controlled (.5/.5 = 1). Thus, the widget takes 100% of the parent layout's height.

Let's add another `Button` to the `layout` and see what happens.



*boxlayout* by its very nature divides the available space between its *children* equally. In our example, the proportion is 50-50, because we have two *children*. Let's use `size_hint` on one of the children and see the results.



If a child specifies `size_hint`, this specifies how much space the `Widget` will take out of the `size` given to it by the `BoxLayout`. In our example, the first `Button` specifies .5 for `size_hint_x`. The space for the widget is calculated like so:

```
first child's size_hint divided by
first child's size_hint + second child's size_hint + ...n(no of children)

.5/(.5+1) = .333...
```

The rest of the `BoxLayout`'s `width` is divided among the rest of the `children`. In our example, this means the second `Button` takes up 66.66% of the `layout width`.

Experiment with `size_hint` to get comfortable with it.

If you want to control the absolute `size` of a `Widget`, you can set `size_hint_x`/`size_hint_y` or both to `None` so that the widget's `width` and or `height` attributes will be honored.

`pos_hint` is a dict, which defaults to empty. As for `size_hint`, layouts honor `pos_hint` differently, but generally you can add values to any of the `pos` attributes (`x, y, right, top, center_x, center_y`) to have the `Widget` positioned relative to its `parent`.

Let's experiment with the following code in kivycatalog to understand `pos_hint` visually:

```
FloatLayout:
    Button:
        text: "We Will"
        pos: 100, 100
        size_hint: .2, .4
    Button:
        text: "Wee Wiill"
```


```

    pos: 200, 200
    size_hint: .4, .2

    Button:
        text: "ROCK YOU!!"
        pos_hint: {'x': .3, 'y': .6}
        size_hint: .5, .2

```

This gives us:



As with `size_hint`, you should experiment with `pos_hint` to understand the effect it has on the widget positions.

## 12.6 Adding a Background to a Layout

One of the frequently asked questions about layouts is::

["How to add a background image/color/video/... to a Layout"](#)

Layouts by their nature have no visual representation: they have no canvas instructions by default. However you can add canvas instructions to a layout instance easily, as with adding a colored background:

In Python:

```
from kivy.graphics import Color, Rectangle
```

```

with layout_instance.canvas.before:
    Color(0, 1, 0, 1) # green; colors range from 0-1 instead of 0-255
    self.rect = Rectangle(size=layout_instance.size,
                          pos=layout_instance.pos)

```

Unfortunately, this will only draw a rectangle at the layout's initial position and size. To make sure the rect is drawn inside the layout, when the layout size/pos changes, we need to listen to any changes and update the rectangles size and pos. We can do that as follows:

```

with layout_instance.canvas.before:
    Color(0, 1, 0, 1) # green; colors range from 0-1 instead of 0-255
    self.rect = Rectangle(size=layout_instance.size,
                          pos=layout_instance.pos)

def update_rect(instance, value):
    instance.rect.pos = instance.pos
    instance.rect.size = instance.size

# listen to size and position changes
layout_instance.bind(pos=update_rect, size=update_rect)

```

In kv:

```

FloatLayout:
    canvas.before:
        Color:
            rgba: 0, 1, 0, 1
        Rectangle:
            # self here refers to the widget i.e BoxLayout
            pos: self.pos
            size: self.size

```

The kv declaration sets an implicit binding: the last two kv lines ensure that the `pos` and `size` values of the rectangle will update when the `pos` of the `floatlayout` changes.

Now we put the snippets above into the shell of Kivy App.

Pure Python way:

```

from kivy.app import App
from kivy.graphics import Color, Rectangle
from kivy.uix.floatlayout import FloatLayout
from kivy.uix.button import Button

class RootWidget(FloatLayout):

    def __init__(self, **kwargs):
        # make sure we aren't overriding any important functionality
        super(RootWidget, self).__init__(**kwargs)

        # let's add a Widget to this layout
        self.add_widget(
            Button(
                text="Hello World",
                size_hint=(.5, .5),
                pos_hint={'center_x': .5, 'center_y': .5}))

class MainApp(App):

```

```

def build(self):
    self.root = root = RootWidget()
    root.bind(size=self._update_rect, pos=self._update_rect)

    with root.canvas.before:
        Color(0, 1, 0, 1) # green; colors range from 0-1 not 0-255
        self.rect = Rectangle(size=root.size, pos=root.pos)
    return root

def _update_rect(self, instance, value):
    self.rect.pos = instance.pos
    self.rect.size = instance.size

if __name__ == '__main__':
    MainApp().run()

```

Using the kv Language:

```

from kivy.app import App
from kivy.lang import Builder


root = Builder.load_string('''
FloatLayout:
    canvas.before:
        Color:
            rgba: 0, 1, 0, 1
        Rectangle:
            # self here refers to the widget i.e FloatLayout
            pos: self.pos
            size: self.size
    Button:
        text: 'Hello World!!!'
        size_hint: .5, .5
        pos_hint: {'center_x':.5, 'center_y': .5}
''')


class MainApp(App):

    def build(self):
        return root

if __name__ == '__main__':
    MainApp().run()

```

Both of the Apps should look something like this:



### 12.6.1 Add a color to the background of a **custom layouts rule/class**

The way we add background to the layout's instance can quickly become cumbersome if we need to use multiple layouts. To help with this, you can subclass the Layout and create your own layout that adds a background.

Using Python:

```
from kivy.app import App
from kivy.graphics import Color, Rectangle
from kivy.uix.boxlayout import BoxLayout
from kivy.uix.floatlayout import FloatLayout
from kivy.uix.image import AsyncImage

class RootWidget(BoxLayout):
    pass

class CustomLayout(FloatLayout):
    def __init__(self, **kwargs):
        # make sure we aren't overriding any important functionality
        super(CustomLayout, self).__init__(**kwargs)

        with self.canvas.before:
            Color(0, 1, 0, 1) # green; colors range from 0-1 instead of 0-255
            self.rect = Rectangle(size=self.size, pos=self.pos)
```

```

        self.bind(size=self._update_rect, pos=self._update_rect)

    def _update_rect(self, instance, value):
        self.rect.pos = instance.pos
        self.rect.size = instance.size

class MainApp(App):

    def build(self):
        root = RootWidget()
        c = CustomLayout()
        root.add_widget(c)
        c.add_widget(
            AsyncImage(
                source="http://www.everythingzoomer.com/wp-content/uploads/2013/01/
→Monday-joke-289x277.jpg",
                size_hint= (1, .5),
                pos_hint={'center_x':.5, 'center_y':.5}))
        root.add_widget(AsyncImage(source='http://www.stuffistumbledupon.com/wp-
→content/uploads/2012/05/Have-you-seen-this-dog-because-its-awesome-meme-puppy-
→doggy.jpg'))
        c = CustomLayout()
        c.add_widget(
            AsyncImage(
                source="http://www.stuffistumbledupon.com/wp-content/uploads/2012/
→04/Get-a-Girlfriend-Meme-empty-wallet.jpg",
                size_hint= (1, .5),
                pos_hint={'center_x':.5, 'center_y':.5}))
        root.add_widget(c)
        return root

if __name__ == '__main__':
    MainApp().run()

```

Using the kv Language:

```

from kivy.app import App
from kivy.uix.floatlayout import FloatLayout
from kivy.uix.boxlayout import BoxLayout
from kivy.lang import Builder


Builder.load_string('''
<CustomLayout>
    canvas.before:
        Color:
            rgba: 0, 1, 0, 1
        Rectangle:
            pos: self.pos
            size: self.size

<RootWidget>
    CustomLayout:
        AsyncImage:
            source: 'http://www.everythingzoomer.com/wp-content/uploads/2013/01/
→Monday-joke-289x277.jpg'
            size_hint: 1, .5
            pos_hint: {'center_x':.5, 'center_y': .5}

```

```

    AsyncImage:
        source: 'http://www.stuffistumbledupon.com/wp-content/uploads/2012/05/Have-
→you-seen-this-dog-because-its-awesome-meme-puppy-doggy.jpg'
    CustomLayout
        AsyncImage:
            source: 'http://www.stuffistumbledupon.com/wp-content/uploads/2012/04/
→Get-a-Girlfriend-Meme-empty-wallet.jpg'
            size_hint: 1, .5
            pos_hint: {'center_x':.5, 'center_y': .5}
    ...)

class RootWidget(BoxLayout):
    pass

class CustomLayout(FloatLayout):
    pass


class MainApp(App):

    def build(self):
        return RootWidget()

if __name__ == '__main__':
    MainApp().run()

```

Both of the Apps should look something like this:



Defining the background in the custom layout class, assures that it will be used in every instance of CustomLayout.

Now, to add an image or color to the background of a built-in Kivy layout, **globally**, we need to override the kv rule for the layout in question. Consider GridLayout:

```
<GridLayout>
    canvas.before:
        Color:
            rgba: 0, 1, 0, 1
        BorderImage:
            source: '../examples/widgets/sequenced_images/data/images/button_white.
→png'
            pos: self.pos
            size: self.size
```

Then, when we put this snippet into a Kivy app:

```
from kivy.app import App
from kivy.uix.floatlayout import FloatLayout
from kivy.lang import Builder


Builder.load_string('''
<GridLayout>
    canvas.before:
        BorderImage:
            # BorderImage behaves like the CSS BorderImage
            border: 10, 10, 10, 10
            source: '../examples/widgets/sequenced_images/data/images/button_white.
→png'
            pos: self.pos
            size: self.size

<RootWidget>
    GridLayout:
        size_hint: .9, .9
        pos_hint: {'center_x': .5, 'center_y': .5}
        rows:1
        Label:
            text: "I don't suffer from insanity, I enjoy every minute of it"
            text_size: self.width-20, self.height-20
            valign: 'top'
        Label:
            text: "When I was born I was so surprised; I didn't speak for a year_
→and a half."
            text_size: self.width-20, self.height-20
            valign: 'middle'
            halign: 'center'
        Label:
            text: "A consultant is someone who takes a subject you understand and_
→makes it sound confusing"
            text_size: self.width-20, self.height-20
            valign: 'bottom'
            halign: 'justify'
''')

class RootWidget(FloatLayout):
    pass


class MainApp(App):
    pass
```


```

def build(self):
    return RootWidget()

if __name__ == '__main__':
    MainApp().run()

```

The result should look something like this:



As we are overriding the rule of the class GridLayout, any use of this class in our app will display that image.

How about an **Animated background?**

You can set the drawing instructions like Rectangle/BorderImage/Ellipse/... to use a particular texture:

```

Rectangle:
    texture: reference to a texture

```

We use this to display an animated background:

```

from kivy.app import App
from kivy.uix.floatlayout import FloatLayout
from kivy.uix.gridlayout import GridLayout
from kivy.uix.image import Image
from kivy.properties import ObjectProperty
from kivy.lang import Builder

```

```

Builder.load_string('''
<CustomLayout>
    canvas.before:
        BorderImage:
            # BorderImage behaves like the CSS BorderImage
            border: 10, 10, 10, 10
            texture: self.background_image.texture
            pos: self.pos
            size: self.size

<RootWidget>
    CustomLayout:
        size_hint: .9, .9
        pos_hint: {'center_x': .5, 'center_y': .5}
        rows:1
        Label:
            text: "I don't suffer from insanity, I enjoy every minute of it"
            text_size: self.width-20, self.height-20
            valign: 'top'
        Label:
            text: "When I was born I was so surprised; I didn't speak for a year_
→and a half."
            text_size: self.width-20, self.height-20
            valign: 'middle'
            halign: 'center'
        Label:
            text: "A consultant is someone who takes a subject you understand and_
→makes it sound confusing"
            text_size: self.width-20, self.height-20
            valign: 'bottom'
            halign: 'justify'
    ...
)

class CustomLayout(GridLayout):
    background_image = ObjectProperty(
        Image(
            source='..../examples/widgets/sequenced_images/data/images/button_white_
→animated.zip',
            anim_delay=.1))

class RootWidget(FloatLayout):
    pass

class MainApp(App):
    def build(self):
        return RootWidget()

if __name__ == '__main__':
    MainApp().run()

```

To try to understand what is happening here, start from line 13:

```
texture: self.background_image.texture
```

This specifies that the *texture* property of *BorderImage* will be updated whenever the *texture* property of *background\_image* updates. We define the *background\_image* property at line 40:

```
background_image = ObjectProperty(...)
```

This sets up *background\_image* as an *ObjectProperty* in which we add an *Image* widget. An image widget has a *texture* property; where you see *self.background\_image.texture*, this sets a reference, *texture*, to this property. The *Image* widget supports animation: the texture of the image is updated whenever the animation changes, and the texture of *BorderImage* instruction is updated in the process.

You can also just blit custom data to the texture. For details, look at the documentation of *Texture*.

## 12.7 Nesting Layouts

Yes! It is quite fun to see how extensible the process can be.

## 12.8 Size and position metrics

Kivy's default unit for length is the pixel, all sizes and positions are expressed in it by default. You can express them in other units, which is useful to achieve better consistency across devices (they get converted to the size in pixels automatically).

Available units are *pt*, *mm*, *cm*, *inch*, *dp* and *sp*. You can learn about their usage in the *metrics* documentation.

You can also experiment with the *screen* usage to simulate various devices screens for your application.

## 12.9 Screen Separation with Screen Manager

If your application is composed of various screens, you likely want an easy way to navigate from one *Screen* to another. Fortunately, there is the *ScreenManager* class, that allows you to define screens separately, and to set the *TransitionBase* from one to another.



# Graphics

---

## 13.1 Introduction to Canvas

A Widgets graphical representation is rendered using a canvas, which you can see as both an unlimited drawing board or as a set of drawing instructions. There are numerous instructions you can apply (add) to your canvas, but there are two main variations:

- *context instructions*
- *vertex instructions*

Context instructions don't draw anything, but they change the results of the vertex instructions.

Canvasses can contain two subsets of instructions. They are the *canvas.before* and the *canvas.after* instruction groups. The instructions in these groups will be executed before and after the *canvas* group respectively. This means that they will appear under (be executed before) and above (be executed after) them. Those groups are not created until the user accesses them.

To add a canvas instruction to a widget, you use the canvas context:

```
class MyWidget(Widget):
    def __init__(self, **kwargs):
        super(MyWidget, self).__init__(**kwargs)
        with self.canvas:
            # add your instruction for main canvas here

        with self.canvas.before:
            # you can use this to add instructions rendered before

        with self.canvas.after:
            # you can use this to add instructions rendered after
```

## 13.2 Context instructions

Context instructions manipulate the opengl context. You can rotate, translate, and scale your canvas. You can also attach a texture or change the drawing color. This one is the most commonly used, but others are really useful too:

```
with self.canvas.before:  
    Color(1, 0, .4, mode='rgb')
```

## 13.3 Drawing instructions

Drawing instructions range from very simple ones, like drawing a line or a polygon, to more complex ones, like meshes or bezier curves:

```
with self.canvas:  
    # draw a line using the default color  
    Line(points=(x1, y1, x2, y2, x3, y3))  
  
    # lets draw a semi-transparent red square  
    Color(1, 0, 0, .5, mode='rgba')  
    Rectangle(pos=self.pos, size=self.size)
```

## 13.4 Manipulating instructions

Sometimes you want to update or remove the instructions you have added to a canvas. This can be done in various ways depending on your needs:

You can keep a reference to your instructions and update them:

```
class MyWidget(Widget):  
    def __init__(self, **kwargs):  
        super(MyWidget, self).__init__(**kwargs)  
        with self.canvas:  
            self.rect = Rectangle(pos=self.pos, size=self.size)  
  
            self.bind(pos=self.update_rect)  
            self.bind(size=self.update_rect)  
  
    def update_rect(self, *args):  
        self.rect.pos = self.pos  
        self.rect.size = self.size
```

Or you can clean your canvas and start fresh:

```
class MyWidget(Widget):  
    def __init__(self, **kwargs):  
        super(MyWidget, self).__init__(**kwargs)  
        self.draw_my_stuff()  
  
        self.bind(pos=self.draw_my_stuff)  
        self.bind(size=self.draw_my_stuff)  
  
    def draw_my_stuff(self):  
        self.canvas.clear()
```

```
with self.canvas:  
    self.rect = Rectangle(pos=self.pos, size=self.size)
```

Note that updating the instructions is considered the best practice as it involves less overhead and avoids creating new instructions.



# Kv language

---

## 14.1 Concept behind the language

As your application grow more complex, it's common that the construction of widget trees and explicit declaration of bindings, becomes verbose and hard to maintain. The KV Language is a attempt to overcome these short-comings.

The KV language (sometimes called kvlang, or kivy language), allows you to create your widget tree in a declarative way and to bind widget properties to each other or to callbacks in a natural manner. It allows for very fast prototyping and agile changes to your UI. It also facilitates a good separation between the logic of your application and its User Interface.

## 14.2 How to load KV

There are two ways to load Kv code into your application:

- By name convention:

Kivy looks for a Kv file with the same name as your App class in lowercase, minus "App" if it ends with 'App' e.g:

```
MyApp -> my.kv
```

If this file defines a *Root Widget* it will be attached to the App's *root* attribute and used as the base of the application widget tree.

- **Builder:** You can tell Kivy to directly load a string or a file. If this string or file defines a root widget, it will be returned by the method:

```
Builder.load_file('path/to/file.kv')
```

or:

```
Builder.load_string(kv_string)
```

## 14.3 Rule context

A Kv source constitutes of *rules*, which are used to describe the content of a Widget, you can have one *root* rule, and any number of *class* or *template* rules.

The *root* rule is declared by declaring the class of your root widget, without any indentation, followed by : and will be set as the *root* attribute of the App instance:

```
Widget:
```

A *class* rule, declared by the name of a widget class between < > and followed by :, defines how any instance of that class will be graphically represented:

```
<MyWidget>:
```

Rules use indentation for delimitation, as python, indentation should be of four spaces per level, like the python good practice recommendations.

There are three keywords specific to Kv language:

- *app*: always refers to the instance of your application.
- *root*: refers to the base widget/template in the current rule
- *self*: always refer to the current widget

## 14.4 Special syntaxes

There are two special syntaxes to define values for the whole Kv context:

To access python modules and classes from kv,

```
#:import name x.y.z
#:import isdir os.path.isdir
#:import np numpy
```

is equivalent to:

```
from x.y import z as name
from os.path import isdir
import numpy as np
```

in python.

To set a global value,

```
#:set name value
```

is equivalent to:

```
name = value
```

in python.

## 14.5 Instantiate children

To declare the widget has a child widget, instance of some class, just declare this child inside the rule:

```
MyWidget:  
    BoxLayout:  
        Button:  
        Button:
```

The example above defines that our root widget, an instance of *MyWidget*, which has a child that is an instance of the *BoxLayout*. That BoxLayout further has two children, instances of the *Button* class.

A python equivalent of this code could be:

```
root = MyWidget()  
box = BoxLayout()  
box.add_widget(Button())  
box.add_widget(Button())  
root.add_widget(box)
```

Which you may find less nice, both to read and to write.

Of course, in python, you can pass keyword arguments to your widgets at creation to specify their behaviour. For example, to set the number of columns of a *GridLayout*, we would do:

```
grid = GridLayout(cols=3)
```

To do the same thing in kv, you can set properties of the child widget directly in the rule:

```
GridLayout:  
    cols: 3
```

The value is evaluated as a python expression, and all the properties used in the expression will be observed, that means that if you had something like this in python (this assume *self* is a widget with a *data ListProperty*):

```
grid = GridLayout(cols=len(self.data))  
self.bind(data=grid.setter('cols'))
```

To have your display updated when your data change, you can now have just:

```
GridLayout:  
    cols: len(root.data)
```

---

**Note:** Widget names should start with upper case letters while property names should start with lower case ones. Following the [PEP8 Naming Conventions](#) is encouraged.

---

## 14.6 Event Bindings

You can bind to events in Kv using the ":" syntax, that is, associating a callback to an event:

```
Widget:  
    on_size: my_callback()
```

You can pass the values dispatched by the signal using the `args` keyword:

```
TextInput:  
    on_text: app.search(args[1])
```

More complex expressions can be used, like:

```
pos: self.center_x - self.texture_size[0] / 2., self.center_y - self.texture_  
size[1] / 2.
```

This expression listens for a change in `center_x`, `center_y`, and `texture_size`. If one of them changes, the expression will be re-evaluated to update the `pos` field.

You can also handle `on_` events inside your kv language. For example the `TextInput` class has a `focus` property whose auto-generated `on_focus` event can be accessed inside the kv language like so:

```
TextInput:  
    on_focus: print(args)
```

## 14.7 Extend canvas

Kv lang can be used to define the canvas instructions of your widget like this:

```
MyWidget:  
    canvas:  
        Color:  
            rgba: 1, .3, .8, .5  
        Line:  
            points: zip(self.data.x, self.data.y)
```

And they get updated when properties values change.

Of course you can use `canvas.before` and `canvas.after`.

## 14.8 Referencing Widgets

In a widget tree there is often a need to access/reference other widgets. The Kv Language provides a way to do this using `id`'s. Think of them as class level variables that can only be used in the Kv language. Consider the following:

```
<MyFirstWidget>:  
    Button:  
        id: f_but  
    TextInput:  
        text: f_but.state  
  
<MySecondWidget>:  
    Button:  
        id: s_but  
    TextInput:  
        text: s_but.state
```

An `id` is limited in scope to the rule it is declared in, so in the code above `s_but` can not be accessed outside the `<MySecondWidget>` rule.

**Warning:** When assigning a value to `id`, remember that the value isn't a string. There are no quotes:  
good -> `id: value`, bad -> `id: 'value'`

An `id` is a `weakref` to the widget and not the widget itself. As a consequence, storing the `id` is not sufficient to keep the widget from being garbage collected. To demonstrate:

```
<MyWidget>:
    label_widget: label_widget
    Button:
        text: 'Add Button'
        on_press: root.add_widget(label_widget)
    Button:
        text: 'Remove Button'
        on_press: root.remove_widget(label_widget)
    Label:
        id: label_widget
        text: 'widget'
```

Although a reference to `label_widget` is stored in `MyWidget`, it is not sufficient to keep the object alive once other references have been removed because it's only a `weakref`. Therefore, after the remove button is clicked (which removes any direct reference to the widget) and the window is resized (which calls the garbage collector resulting in the deletion of `label_widget`), when the add button is clicked to add the widget back, a `ReferenceError: weakly-referenced object no longer exists` will be thrown.

To keep the widget alive, a direct reference to the `label_widget` widget must be kept. This is achieved using `id.__self__` or `label_widget.__self__` in this case. The correct way to do this would be:

```
<MyWidget>:
    label_widget: label_widget.__self__
```

## 14.9 Accessing Widgets defined inside Kv lang in your python code

Consider the code below in `my.kv`:

```
<MyFirstWidget>:
    # both these variables can be the same name and this doesn't lead to
    # an issue with uniqueness as the id is only accessible in kv.
    txt_inpt: txt_inpt
    Button:
        id: f_but
    TextInput:
        id: txt_inpt
        text: f_but.state
        on_text: root.check_status(f_but)
```

In `myapp.py`:

```
...
class MyFirstWidget(BoxLayout):
    txt_inpt = ObjectProperty(None)

    def check_status(self, btn):
        print('button state is: {}'.format(state=btn.state))
```

```
    print('text input text is: {}'.format(txt=self.txt_inpt))
...
```

*txt\_inpt* is defined as a *ObjectProperty* initialized to *None* inside the Class.

```
txt_inpt = ObjectProperty(None)
```

At this point *self.txt\_inpt* is *None*. In Kv lang this property is updated to hold the instance of the *TextInput* referenced by the id *txt\_inpt*:

```
txt_inpt: txt_inpt
```

From this point onwards, *self.txt\_inpt* holds a reference to the widget identified by the id *txt\_input* and can be used anywhere in the class, as in the function *check\_status*. In contrast to this method you could also just pass the *id* to the function that needs to use it, like in case of *f\_but* in the code above.

There is a simpler way to access objects with *id* tags in Kv using the *ids* lookup object. You can do this as follows:

```
<Marvel>
    Label:
        id: loki
        text: 'loki: I AM YOUR GOD!'
    Button:
        id: hulk
        text: "press to smash loki"
        on_release: root.hulk_smash()
```

In your python code:

```
class Marvel(BoxLayout):

    def hulk_smash(self):
        self.ids.hulk.text = "hulk: puny god!"
        self.ids["loki"].text = "loki: ><!!!" # alternative syntax
```

When your kv file is parsed, kivy collects all the widgets tagged with *id*'s and places them in this *self.ids* dictionary type property. That means you can also iterate over these widgets and access them dictionary style:

```
for key, val in self.ids.items():
    print("key={0}, val={1}".format(key, val))
```

---

**Note:** Although the *self.ids* method is very concise, it is generally regarded as 'best practice' to use the *ObjectProperty*. This creates a direct reference, provides faster access and is more explicit.

---

## 14.10 Dynamic Classes

Consider the code below:

```
<MyWidget>
    Button:
        text: "Hello world, watch this text wrap inside the button"
        text_size: self.size
        font_size: '25sp'
```

```

        markup: True
Button:
    text: "Even absolute is relative to itself"
    text_size: self.size
    font_size: '25sp'
    markup: True
Button:
    text: "Repeating the same thing over and over in a comp = fail"
    text_size: self.size
    font_size: '25sp'
    markup: True
Button:

```

Instead of having to repeat the same values for every button, we can just use a template instead, like so:

```

<MyBigButt@Button>:
    text_size: self.size
    font_size: '25sp'
    markup: True

<MyWidget>:
    MyBigButt:
        text: "Hello world, watch this text wrap inside the button"
    MyBigButt:
        text: "Even absolute is relative to itself"
    MyBigButt:
        text: "repeating the same thing over and over in a comp = fail"
    MyBigButt:

```

This class, created just by the declaration of this rule, inherits from the Button class and allows us to change default values and create bindings for all its instances without adding any new code on the Python side.

## 14.11 Re-using styles in multiple widgets

Consider the code below in my.kv:

```

<MyFirstWidget>:
    Button:
        on_press: root.text(txt_inpt.text)
    TextInput:
        id: txt_inpt

<MySecondWidget>:
    Button:
        on_press: root.text(txt_inpt.text)
    TextInput:
        id: txt_inpt

```

In myapp.py:

```

class MyFirstWidget(BoxLayout):
    def text(self, val):
        print('text input text is: {}'.format(txt=val))

class MySecondWidget(BoxLayout):

```

```
writing = StringProperty('')

def text(self, val):
    self.writing = val
```

Because both classes share the same .kv style, this design can be simplified if we reuse the style for both widgets. You can do this in .kv as follows. In my.kv:

```
<MyFirstWidget,MySecondWidget>:
    Button:
        on_press: root.text(txt_inpt.text)
    TextInput:
        id: txt_inpt
```

By separating the class names with a comma, all the classes listed in the declaration will have the same kv properties.

## 14.12 Designing with the Kivy Language

One of aims of the Kivy language is to **Separate the concerns** of presentation and logic. The presentation (layout) side is addressed by your kv file and the logic by your py file.

### 14.12.1 The code goes in py files

Let's start with a little example. First, the Python file named *main.py*:

```
import kivy
kivy.require('1.0.5')

from kivy.uix.floatlayout import FloatLayout
from kivy.app import App
from kivy.properties import ObjectProperty, StringProperty

class Controller(FloatLayout):
    '''Create a controller that receives a custom widget from the kv lang file.

    Add an action to be called from the kv lang file.
    '''
    label_wid = ObjectProperty()
    info = StringProperty()

    def do_action(self):
        self.label_wid.text = 'My label after button press'
        self.info = 'New info text'

class ControllerApp(App):

    def build(self):
        return Controller(info='Hello world')

if __name__ == '__main__':
    ControllerApp().run()
```

In this example, we are creating a Controller class with 2 properties:

- `info` for receiving some text
- `label_wid` for receiving the label widget

In addition, we are creating a `do_action()` method that will use both of these properties. It will change the `info` text and change text in the `label_wid` widget.

#### 14.12.2 The layout goes in controller.kv

Executing this application without a corresponding `.kv` file will work, but nothing will be shown on the screen. This is expected, because the `Controller` class has no widgets in it, it's just a `FloatLayout`. We can create the UI around the `Controller` class in a file named `controller.kv`, which will be loaded when we run the `ControllerApp`. How this is done and what files are loaded is described in the `kivy.app.App.load_kv()` method.

```
1 #:kivy 1.0
2
3 <Controller>:
4     label_wid: my_custom_label
5
6     BoxLayout:
7         orientation: 'vertical'
8         padding: 20
9
10    Button:
11        text: 'My controller info is: ' + root.info
12        on_press: root.do_action()
13
14    Label:
15        id: my_custom_label
16        text: 'My label before button press'
```

One label and one button in a vertical `BoxLayout`. Seems very simple. There are 3 things going on here:

1. Using data from the `Controller`. As soon as the `info` property is changed in the controller, the expression `text: 'My controller info is: ' + root.info` will automatically be re-evaluated, changing the text in the `Button`.
2. Giving data to the `Controller`. The expression `id: my_custom_label` is assigning the created `Label` the id of `my_custom_label`. Then, using `my_custom_label` in the expression `label_wid: my_custom_label` gives the instance of that `Label` widget to your `Controller`.
3. Creating a custom callback in the `Button` using the `Controller`'s `on_press` method.
  - `root` and `self` are reserved keywords, useable anywhere. `root` represents the top widget in the rule and `self` represents the current widget.
  - You can use any id declared in the rule the same as `root` and `self`. For example, you could do this in the `on_press()`:

```
Button:
    on_press: root.do_action(); my_custom_label.font_size = 18
```

And that's that. Now when we run `main.py`, `controller.kv` will be loaded so that the `Button` and `Label` will show up and respond to our touch events.



# Integrating with other Frameworks

---

New in version 1.0.8.

## 15.1 Using Twisted inside Kivy

---

**Note:** You can use the `kivy.support.install_twisted_reactor` function to install a twisted reactor that will run inside the kivy event loop.

Any arguments or keyword arguments passed to this function will be passed on the `threadedselect` reactors `interleave` function. These are the arguments one would usually pass to twisted's `reactor.startRunning`

---

**Warning:** Unlike the default twisted reactor, the installed reactor will not handle any signals unless you set the 'installSignalHandlers' keyword argument to 1 explicitly. This is done to allow kivy to handle the signals as usual, unless you specifically want the twisted reactor to handle the signals (e.g. SIGINT).

The kivy examples include a small example of a twisted server and client. The server app has a simple twisted server running and logs any messages. The client app can send messages to the server and will print its message and the response it got. The examples are based mostly on the simple Echo example from the twisted docs, which you can find here:

- [http://twistedmatrix.com/documents/current/\\_downloads/simpleserv.py](http://twistedmatrix.com/documents/current/_downloads/simpleserv.py)
- [http://twistedmatrix.com/documents/current/\\_downloads/simpleclient.py](http://twistedmatrix.com/documents/current/_downloads/simpleclient.py)

To try the example, run `echo_server_app.py` first, and then launch `echo_client_app.py`. The server will reply with simple echo messages to anything the client app sends when you hit enter after typing something in the textbox.

### 15.1.1 Server App

```
# install_twisted_reactor must be called before importing and using the reactor
from kivy.support import install_twisted_reactor

install_twisted_reactor()

from twisted.internet import reactor
from twisted.internet import protocol

class EchoServer(protocol.Protocol):
    def dataReceived(self, data):
        response = self.factory.app.handle_message(data)
        if response:
            self.transport.write(response)

class EchoServerFactory(protocol.Factory):
    protocol = EchoServer

    def __init__(self, app):
        self.app = app

from kivy.app import App
from kivy.uix.label import Label

class TwistedServerApp(App):
    label = None

    def build(self):
        self.label = Label(text="server started\n")
        reactor.listenTCP(8000, EchoServerFactory(self))
        return self.label

    def handle_message(self, msg):
        msg = msg.decode('utf-8')
        self.label.text = "received: {}\n".format(msg)

        if msg == "ping":
            msg = "Pong"
        if msg == "plop":
            msg = "Kivy Rocks!!!"
        self.label.text += "responded: {}\n".format(msg)
        return msg.encode('utf-8')

if __name__ == '__main__':
    TwistedServerApp().run()
```

### 15.1.2 Client App

```
# install_twisted_reactor must be called before importing the reactor
from __future__ import unicode_literals

from kivy.support import install_twisted_reactor
```

```

install_twisted_reactor()

# A Simple Client that send messages to the Echo Server
from twisted.internet import reactor, protocol


class EchoClient(protocol.Protocol):
    def connectionMade(self):
        self.factory.app.on_connection(self.transport)

    def dataReceived(self, data):
        self.factory.app.print_message(data.decode('utf-8'))


class EchoClientFactory(protocol.ClientFactory):
    protocol = EchoClient

    def __init__(self, app):
        self.app = app

    def startedConnecting(self, connector):
        self.app.print_message('Started to connect.')

    def clientConnectionLost(self, connector, reason):
        self.app.print_message('Lost connection.')

    def clientConnectionFailed(self, connector, reason):
        self.app.print_message('Connection failed.')


from kivy.app import App
from kivy.uix.label import Label
from kivy.uix.textinput import TextInput
from kivy.uix.boxlayout import BoxLayout


# A simple kivy App, with a textbox to enter messages, and
# a large label to display all the messages received from
# the server
class TwistedClientApp(App):
    connection = None
    textbox = None
    label = None

    def build(self):
        root = self.setup_gui()
        self.connect_to_server()
        return root

    def setup_gui(self):
        self.textbox = TextInput(size_hint_y=.1, multiline=False)
        self.textbox.bind(on_text_validate=self.send_message)
        self.label = Label(text='connecting...\n')
        layout = BoxLayout(orientation='vertical')
        layout.add_widget(self.label)
        layout.add_widget(self.textbox)
        return layout

    def connect_to_server(self):

```

```
reactor.connectTCP('localhost', 8000, EchoClientFactory(self))

def on_connection(self, connection):
    self.print_message("Connected successfully!")
    self.connection = connection

def send_message(self, *args):
    msg = self.textbox.text
    if msg and self.connection:
        self.connection.write(msg.encode('utf-8'))
        self.textbox.text = ""

def print_message(self, msg):
    self.label.text += "{}\n".format(msg)

if __name__ == '__main__':
    TwistedClientApp().run()
```

# Packaging your application

---

## 16.1 Create a package for Windows

---

**Note:** This document only applies for kivy 1.9.1 and greater.

---

Packaging your application for the Windows platform can only be done inside the Windows OS. The following process has been tested on Windows with the Kivy **wheels** installation, see at the end for alternate installations.

The package will be either 32 or 64 bits depending on which version of Python you ran it with.

### 16.1.1 Requirements

- Latest Kivy (installed as described in [Installation on Windows](#)).
- PyInstaller 3.1+ (`pip install --upgrade pyinstaller`).

## 16.2 PyInstaller default hook

This section applies to PyInstaller (>= 3.1) that includes the kivy hooks. To overwrite the default hook the following examples need to be slightly modified. See [Overwriting the default hook](#).

### 16.2.1 Packaging a simple app

For this example, we'll package the **touchtracer** example project and embed a custom icon. The location of the kivy examples is, when using the wheels, installed to `python\\share\\kivy-examples` and when using the github source code installed as `kivy\\examples`. We'll just refer to the full path leading to the examples as `examples-path`. The touchtracer example is in `examples-path\\demo\\touchtracer` and the main file is named `main.py`.

1. Open your command line shell and ensure that python is on the path (i.e. `python` works).
2. Create a folder into which the packaged app will be created. For example create a `TouchApp` folder and [change to that directory](#) with e.g. `cd TouchApp`. Then type:

```
python -m PyInstaller --name touchtracer examples-path\demo\touchtracer\main.py
```

You can also add an `icon.ico` file to the application folder in order to create an icon for the executable. If you don't have a .ico file available, you can convert your `icon.png` file to ico using the web app [ConvertICO](#). Save the `icon.ico` in the `touchtracer` directory and type:

```
python -m PyInstaller --name touchtracer --icon examples-path\demo\touchtracer\icon.ico examples-path\demo\touchtracer\main.py
```

For more options, please consult the [PyInstaller Manual](#).

3. The spec file will be `touchtracer.spec` located in `TouchApp`. Now we need to edit the spec file to add the dependencies hooks to correctly build the exe. Open the spec file with your favorite editor and add these lines at the beginning of the spec (assuming `sdl2` is used, the default now):

```
from kivy.deps import sdl2, glew
```

Then, find `COLLECT()` and add the data for `touchtracer` (`touchtracer.kv`, `particle.png`, ...): Change the line to add a `Tree()` object, e.g. `Tree('examples-path\\demo\\touchtracer\\')`. This `Tree` will search and add every file found in the `touchtracer` directory to your final package.

To add the dependencies, before the first keyword argument in `COLLECT` add a `Tree` object for every path of the dependencies. E.g. `*[Tree(p) for p in (sdl2.dep_bins + glew.dep_bins)]` so it'll look something like:

```
coll = COLLECT(exe, Tree('examples-path\\demo\\touchtracer\\'),
                 a.binaries,
                 a.zipfiles,
                 a.datas,
                 *[Tree(p) for p in (sdl2.dep_bins + glew.dep_bins)],
                 strip=False,
                 upx=True,
                 name='touchtracer')
```

4. Now we build the spec file in `TouchApp` with:

```
python -m PyInstaller touchtracer.spec
```

5. The compiled package will be in the `TouchApp\dist\touchtracer` directory.

### 16.2.2 Packaging a video app with gstreamer

Following we'll slightly modify the example above to package a app that uses gstreamer for video. We'll use the `videoplayer` example found at `examples-path\widgets\videoplayer.py`. Create a folder somewhere called `VideoPlayer` and on the command line change your current directory to that folder and do:

```
python -m PyInstaller --name gstvideo examples-path\widgets\videoplayer.py
```

to create the `gstvideo.spec` file. Edit as above and this time include the gstreamer dependency as well:

```
from kivy.deps import sdl2, glew, gstreamer
```

and add the `Tree()` to include the video files, e.g. `Tree('examples-path\\widgets')` as well as the gstreamer dependencies so it should look something like:

```
coll = COLLECT(exe, Tree('examples-path\\widgets'),
                a.binaries,
                a.zipfiles,
                a.datas,
                *[Tree(p) for p in (sdl2.dep_bins + glew.dep_bins + gstreamer.dep_
→bins)],
                strip=False,
                upx=True,
                name='gstvideo')
```

Then build the spec file in `VideoPlayer` with:

```
python -m PyInstaller gstvideo.spec
```

and you should find `gstvideo.exe` in `VideoPlayer\dist\gstvideo`, which when run will play a video.

---

**Note:** If you're using Pygame and need PyGame in your packaging app, you'll have to add the following code to your spec file due to kivy issue #1638. After the imports add the following:

```
def getResource(identifier, *args, **kwargs):
    if identifier == 'pygame_icon.tiff':
        raise IOError()
    return _original_getResource(identifier, *args, **kwargs)

import pygame.pkgdata
_original_getResource = pygame.pkgdata.getResource
pygame.pkgdata.getResource = getResource
```

---

## 16.3 Overwriting the default hook

### 16.3.1 Including/excluding video and audio and reducing app size

PyInstaller includes a hook for kivy that by default adds **all** the core modules used by kivy, e.g. audio, video, spelling etc (you still need to package the gstreamer dlls manually with `Tree()` - see the example above) and their dependencies. If the hook is not installed or to reduce app size some of these modules may be excluded, e.g. if no audio/video is used, with an alternative hook.

Kivy provides the alternate hook at `hookspath()`. In addition, if and only if PyInstaller doesn't have the default hooks `runtime_hooks()` must also be provided. When overwriting the hook, the latter one typically is not required to be overwritten.

The alternate `hookspath()` hook does not include any of the kivy providers. To add them, they have to be added with `get_deps_minimal()` or `get_deps_all()`. See their documentation and `pyinstaller_hooks` for more details. But essentially, `get_deps_all()` add all the providers like in the default hook while `get_deps_minimal()` only adds those that are loaded when the app is run. Each method provides a list of hidden kivy imports and excluded imports that can be passed on to Analysis.

One can also generate a alternate hook which literally lists every kivy provider module and those not required can be commented out. See [pyinstaller\\_hooks](#).

To use the the alternate hooks with the examples above modify as following to add the hooks with `hookspath()` and `runtime_hooks` (if required) and `**get_deps_minimal()` or `**get_deps_all()` to specify the providers.

For example, add the import statement:

```
from kivy.tools.packaging.pyinstaller_hooks import get_deps_minimal, get_deps_all,  
    ↪hookspath, runtime_hooks
```

and then modify `Analysis` as follows:

```
a = Analysis(['examples-path\\demo\\touchtracer\\main.py'],  
            ...  
            hookspath=hookspath(),  
            runtime_hooks=runtime_hooks(),  
            ...  
            **get_deps_all())
```

to include everything like the default hook. Or:

```
a = Analysis(['examples-path\\demo\\touchtracer\\main.py'],  
            ...  
            hookspath=hookspath(),  
            runtime_hooks=runtime_hooks(),  
            ...  
            **get_deps_minimal(video=None, audio=None))
```

e.g. to exclude the audio and video providers and for the other core modules only use those loaded.

The key points is to provide the alternate `hookspath()` which does not list by default all the kivy providers and instead manually to hiddenimports add the required providers while removing the undesired ones (audio and video in this example) with `get_deps_minimal()`.

### 16.3.2 Alternate installations

The previous examples used e.g. `*[Tree(p) for p in (sdl2.dep_bins + glew.dep_bins + gstreamer.dep_bins)]`, to make PyInstaller add all the dlls used by these dependencies. If kivy was not installed using the wheels method these commands will not work and e.g. `Kivy.deps.sdl2` will fail to import. Instead, one must find the location of these dlls and manually pass them to the Tree class in a similar fashion as the example.

## 16.4 Create a package for Android

You can create a package for android using the [python-for-android](#) project. This page explains how to download and use it directly on your own machine (see [Packaging with python-for-android](#)) or use the [Buildozer](#) tool to automate the entire process. You can also see [Packaging your application for the Kivy Launcher](#) to run kivy programs without compiling them.

For new users, we recommend using [Buildozer](#) as the easiest way to make a full APK. You can also run your Kivy app without a compilation step with the [Kivy Launcher](#) app.

Kivy applications can be [released on an Android market](#) such as the Play store, with a few extra steps to create a fully signed APK.

The Kivy project includes tools for accessing Android APIs to accomplish vibration, sensor access, text-ing etc. These, along with information on debugging on the device, are documented at the [main Android page](#).

---

**Note:** Python 3 support on Android is now available experimentally.

---

### 16.4.1 Buildozer

Buildozer is a tool that automates the entire build process. It downloads and sets up all the prerequisites for python-for-android, including the android SDK and NDK, then builds an apk that can be automatically pushed to the device.

Buildozer currently works only in Linux, and is an alpha release, but it already works well and can significantly simplify the apk build.

You can get buildozer at <https://github.com/kivy/buildozer>:

```
git clone https://github.com/kivy/buildozer.git
cd buildozer
sudo python2.7 setup.py install
```

This will install buildozer in your system. Afterwards, navigate to your project directory and run:

```
buildozer init
```

This creates a *buildozer.spec* file controlling your build configuration. You should edit it appropriately with your app name etc. You can set variables to control most or all of the parameters passed to python-for-android.

Install buildozer's [dependencies](#).

Finally, plug in your android device and run:

```
buildozer android debug deploy run
```

to build, push and automatically run the apk on your device.

Buildozer has many available options and tools to help you, the steps above are just the simplest way to build and run your APK. The full documentation is available [here](#). You can also check the Buildozer README at <https://github.com/kivy/buildozer>.

### 16.4.2 Packaging with python-for-android

You can also package directly with python-for-android, which can give you more control but requires you to manually download parts of the Android toolchain.

See the [python-for-android documentation](#) for full details.

### 16.4.3 Packaging your application for the Kivy Launcher

The [Kivy launcher](#) is an Android application that runs any Kivy examples stored on your SD Card. To install the Kivy launcher, you must:

1. Go to the [Kivy Launcher page](#) on the Google Play Store
2. Click on Install
3. Select your phone... And you're done!

If you don't have access to the Google Play Store on your phone/tablet, you can download and install the APK manually from <http://kivy.org/#download>.

Once the Kivy launcher is installed, you can put your Kivy applications in the Kivy directory in your external storage directory (often available at /sdcard even in devices where this memory is internal), e.g.

```
/sdcard/kivy/<yourapplication>
```

<yourapplication> should be a directory containing:

```
# Your main application file:  
main.py  
# Some info Kivy requires about your app on android:  
android.txt
```

The file *android.txt* must contain:

```
title=<Application Title>  
author=<Your Name>  
orientation=<portrait|landscape>
```

These options are just a very basic configuration. If you create your own APK using the tools above, you can choose many other settings.

#### Installation of Examples

Kivy comes with many examples, and these can be a great place to start trying the Kivy launcher. You can run them as below:

```
#. Download the `Kivy demos for Android <https://storage.googleapis.com/google-code-archive-downloads/v2/code.google.com/kivy/kivydemo-for-android.zip>`_  
#. Unzip the contents and go to the folder `kivydemo-for-android`  
#. Copy all the the subfolders here to
```

```
/sdcard/kivy
```

1. Run the launcher and select one of the Pictures, Showcase, Touchtracer, Cymunk or other demos...

#### 16.4.4 Release on the market

If you have built your own APK with Buildozer or with python-for-android, you can create a release version that may be released on the Play store or other Android markets.

To do this, you must run Buildozer with the `release` parameter (e.g. `buildozer android release`), or if using python-for-android use the `--release` option to build.py. This creates a release APK in the `bin` directory, which you must properly sign and zipalign. The procedure for doing this is described in the Android documentation at <https://developer.android.com/studio/publish/app-signing.html#signing-manually> - all the necessary tools come with the Android SDK.

#### 16.4.5 Targeting Android

Kivy is designed to operate identically across platforms and as a result, makes some clear design decisions. It includes its own set of widgets and by default, builds an APK with all the required core dependencies and libraries.

It is possible to target specific Android features, both directly and in a (somewhat) cross-platform way. See the *Using Android APIs* section of the [Kivy on Android documentation](#) for more details.

## 16.5 The Kivy Android Virtual Machine

---

**Note:** The VM is now updated. Please check the [Kivy website](#) for the latest version.

---

### 16.5.1 Introduction

Currently, Kivy Android applications can only be built in a Linux environment configured with python-for-android, the Android SDK and the Android NDK. As this environment is not only tricky to setup but also impossible on Windows or OS X operating systems, we provide a fully configured [VirtualBox](#) disk image to ease your building woes.

If you are not familiar with virtualization, we encourage you to read the [Wikipedia Virtualization page](#).

### 16.5.2 Getting started

1. Download the [Kivy / Buildozer VM](#), in the *Virtual Machine* section. The download is 1.2GB. Extract the file and remember the location of the extracted directory.
2. Download the version of VirtualBox for your machine from the [VirtualBox download area](#) and install it.
3. Start VirtualBox, click on “File”, “Import Appliance”.
4. Select the extracted directory, file should be named “Buildozer VM.ovf”
5. Start the Virtual machine and click on the “Buildozer” icon.

### 16.5.3 Building the APK

Once the VM is loaded, you can follow the instructions from [Packaging with python-for-android](#). You don't need to download with *git clone* though, as python-for-android is already installed and set up in the virtual machine home directory.

### 16.5.4 Hints and tips

#### 1. Shared folders

Generally, your development environment and toolset are set up on your host machine but the APK is build in your guest. VirtualBox has a feature called ‘Shared folders’ which allows your guest direct access to a folder on your host.

If it often convenient to use this feature (usually with ‘Permanent’ and ‘Auto-mount’ options) to copy the built APK to the host machine so it can form part of your normal dev environment. A simple script can easily automate the build and copy/move process.

Currently, VirtualBox doesn't allow symlink anymore in a shared folder. Adjust your `buildozer.spec` to build outside the shared folder. Also, ensure the `kivy` user is in the `vboxsf` group.

#### 2. Copy and paste

By default, you will not be able to share clipboard items between the host and the guest machine. You can achieve this by enabling the “bi-directional” shared clipboard option under “Settings -> General -> Advanced”.

### 3. Snapshots

If you are working on the Kivy development branch, pulling the latest version can sometimes break things (as much as we try not to). You can guard against this by taking a snapshot before pulling. This allows you to easily restore your machine to its previous state should you have the need.

### 4. Insufficient memory

Assigning the Virtual Machine insufficient memory may result in the compile failing with cryptic errors, such as:

```
arm-linux-androideabi-gcc: Internal error: Killed (program cc1)
```

If this occurs, please check the amount of free memory in the Kivy VM and increase the amount of RAM allocated to it if required.

### 5. No space left

Read the section about resizing the VM at <https://github.com/kivy/buildozer#buildozer-virtual-machine>

## 16.6 Kivy on Android

You can run Kivy applications on Android, on (more or less) any device with OpenGL ES 2.0 (Android 2.2 minimum). This is standard on modern devices; Google reports the requirement is met by [99.9% of devices](#).

Kivy APKs are normal Android apps that you can distribute like any other, including on stores like the Play store. They behave properly when paused or restarted, may utilise Android services and have access to most of the normal java API as described below.

Follow the instructions below to learn how to [package your app for Android](#), [debug your code on the device](#), and [use Android APIs](#) such as for vibration and reading sensors.

### 16.6.1 Package for Android

The Kivy project provides all the necessary tools to package your app on Android, including building your own standalone APK that may be distributed on a market like the Play store. This is covered fully in the [Create a package for Android](#) documentation.

### 16.6.2 Debugging your application on the Android platform

You can view the normal output of your code (stdout, stderr), as well as the normal Kivy logs, through the Android logcat stream. This is accessed through adb, provided by the [Android SDK](#). You may need to enable adb in your device’s developer options, then connect your device to your computer and run:

```
adb logcat
```

You’ll see all the logs including your stdout/stderr and Kivy logger.

If you packaged your app with Buildozer, the *adb* tool may not be in your `$PATH` and the above command may not work. You can instead run:

```
buildozer android logcat
```

to run the version installed by Buildozer, or find the SDK tools at \$HOME/.buildozer/android/platform.

You can also run and debug your application using the [Kivy Launcher](#). If you run your application this way, you will find log files inside the “./kivy/logs” sub-folder within your application folder.

### 16.6.3 Using Android APIs

Although Kivy is a Python framework, the Kivy project maintains tools to easily use the normal java APIs, for everything from vibration to sensors to sending messages through SMS or email.

For new users, we recommend using [Plyer](#). For more advanced access or for APIs not currently wrapped, you can use [Pyjnius](#) directly. Kivy also supplies an [android module](#) for basic Android functionality.

User contributed Android code and examples are available on the [Kivy wiki](#).

#### Plyer

[Plyer](#) is a pythonic, platform-independent API to use features commonly found on various platforms, particularly mobile ones. The idea is that your app can call simply call a Plyer function, such as to present a notification to the user, and Plyer will take care of doing so in the right way regardless of the platform or operating system. Internally, Plyer uses Pyjnius (on Android), Pyobjus (on iOS) and some platform specific APIs on desktop platforms.

For instance, the following code would make your Android device vibrate, or raise a NotImplementedException that you can handle appropriately on other platforms such as desktops that don't have appropriate hardware::

```
from plyer import vibrator
vibrator.vibrate(10) # vibrate for 10 seconds
```

Plyer's list of supported APIs is growing quite quickly, you can see the full list in the Plyer [README](#).

#### Pyjnius

Pyjnius is a Python module that lets you access java classes directly from Python, automatically converting arguments to the right type, and letting you easily convert the java results to Python.

Pyjnius can be obtained from [github](#), and has its [own documentation](#).

Here is a simple example showing Pyjnius' ability to access the normal Android vibration API, the same result of the plyer code above:

```
# 'autoclass' takes a java class and gives it a Python wrapper
from jnius import autoclass

# Context is a normal java class in the Android API
Context = autoclass('android.content.Context')

# PythonActivity is provided by the Kivy bootstrap app in python-for-android
PythonActivity = autoclass('org.renpy.android.PythonActivity')

# The PythonActivity stores a reference to the currently running activity
# We need this to access the vibrator service
activity = PythonActivity.mActivity
```

```
# This is almost identical to the java code for the vibrator
vibrator = activity.getSystemService(Context.VIBRATOR_SERVICE)

vibrator.vibrate(10000) # The value is in milliseconds - this is 10s
```

This code directly follows the java API functions to call the vibrator, with Pyjnius automatically translating the api to Python code and our calls back to the equivalent java. It is much more verbose and java-like than Plyer's version, for no benefit in this case, though Plyer does not wrap every API available to Pyjnius.

Pyjnius also has powerful abilities to implement java interfaces, which is important for wrapping some APIs, but these are not documented here - you can see Pyjnius' [own documentation](#).

#### Android module

Python-for-android includes a python module (actually cython wrapping java) to access a limited set of Android APIs. This has been largely superseded by the more flexible Pyjnius and Plyer as above, but may still occasionally be useful. The available functions are given in the [python-for-android documentation](#).

This includes code for billing/IAP and creating/accessing Android services, which is not yet available in the other tools above.

#### 16.6.4 Status of the Project and Tested Devices

These sections previously described the existence of Kivy's Android build tools, with their limitations and some devices that were known to work.

The Android tools are now quite stable, and should work with practically any device; our minimum requirements are OpenGL ES 2.0 and Android 2.2. These are very common now - Kivy has even been run on an Android smartwatch!

A current technical limitation is that the Android build tools compile only ARM APKs, which will not run on Android devices with x86 processors (these are currently rare). This should be added soon.

As Kivy works fine on most devices, the list of supported phones/tablets has been retired - all Android devices are likely to work if they meet the conditions above.

### 16.7 Creating packages for OS X

---

**Note:** This guide describes multiple ways for packaging Kivy applications. Packaging with PyInstaller is recommended for general use.

---

#### 16.7.1 Using PyInstaller and Homebrew

---

**Note:** Package your app on the oldest OS X version you want to support.

---

## Complete guide

### 1. Install Homebrew

### 2. Install Python:

```
$ brew install python
```

---

**Note:** To use Python 3, `brew install python3` and replace `pip` with `pip3` in the guide below.

---

### 3. (Re)install your dependencies with `--build-bottle` to make sure they can be used on other machines:

```
$ brew reinstall --build-bottle sdl2 sdl2_image sdl2_ttf sdl2_mixer
```

---

**Note:** If your project depends on GStreamer or other additional libraries (re)install them with `--build-bottle` as described [below](#).

---

### 4. Install Cython and Kivy:

```
$ pip install Cython==0.26.1
$ pip install -U kivy
```

### 5. Install PyInstaller:

```
$ pip install -U pyinstaller
```

### 6. Package your app using the path to your main.py:

```
$ pyinstaller -y --clean --windowed --name touchtracer \
  --exclude-module _tkinter \
  --exclude-module Tkinter \
  --exclude-module enchant \
  --exclude-module twisted \
  /usr/local/share/kivy-examples/demo/touchtracer/main.py
```

---

**Note:** This will not yet copy additional image or sound files. You would need to adapt the created `.spec` file for that.

---

## Editing the spec file

The specs file is named `touchtracer.spec` and is located in the directory where you ran the `pyinstaller` command.

You need to change the `COLLECT()` call to add the data of `touchtracer` (`touchtracer.kv`, `particle.png`, ...). Change the line to add a `Tree()` object. This `Tree` will search and add every file found in the `touchtracer` directory to your final package. Your `COLLECT` section should look something like this:

```
coll = COLLECT(exe, Tree('/usr/local/share/kivy-examples/demo/touchtracer/'),
                a.binaries,
                a.zipfiles,
                a.datas,
```

```
strip=None,  
upx=True,  
name='touchtracer')
```

This will add the required hooks so that PyInstaller gets the required Kivy files. We are done. Your spec is ready to be executed.

Build the spec and create a DMG

1. Open a console.
2. Go to the PyInstaller directory, and build the spec:

```
$ pyinstaller -y --clean --windowed touchtracer.spec
```

3. Run:

```
$ pushd dist  
$ hdiutil create ./Touchtracer.dmg -srcfolder touchtracer.app -ov  
$ popd
```

4. You will now have a Touchtracer.dmg available in the *dist* directory.

Additional Libraries

GStreamer

If your project depends on GStreamer:

```
$ brew reinstall --build-bottle gstreamer gst-plugins-{base,good,bad,ugly}
```

---

**Note:** If your Project needs Ogg Vorbis support be sure to add the `--with-libvorbis` option to the command above.

---

If you are using Python from Homebrew you will also need the following step until [this pull request](#) gets merged:

```
$ brew reinstall --with-python --build-bottle https://github.com/cbenhagen/  
→homebrew/raw/patch-3/Library/Formula/gst-python.rb
```

## 16.7.2 Using PyInstaller without Homebrew

First install Kivy and its dependencies without using Homebrew as mentioned here <http://kivy.org/docs/installation/installation.html#development-version>.

Once you have kivy and its deps installed, you need to install PyInstaller.

Let's assume we use a folder like *testpackaging*:

```
cd testpackaging  
git clone http://github.com/pyinstaller/pyinstaller
```

Create a file named *touchtracer.spec* in this directory and add the following code to it:

```
# -*- mode: python -*-

block_cipher = None
from kivy.tools.packaging.pyinstaller_hooks import get_deps_all, hookspath,
    runtime_hooks

a = Analysis(['/path/to/yout/folder/containing/examples/demo/touchtracer/main.py'],
            pathex=['/path/to/yout/folder/containing/testpackaging'],
            binaries=None,
            win_no_prefer_redirects=False,
            win_private_assemblies=False,
            cipher=block_cipher,
            hookspath=hookspath(),
            runtime_hooks=runtime_hooks(),
            **get_deps_all())
pyz = PYZ(a.pure, a.zipped_data,
           cipher=block_cipher)
exe = EXE(pyz,
          a.scripts,
          exclude_binaries=True,
          name='touchtracer',
          debug=False,
          strip=False,
          upx=True,
          console=False )
coll = COLLECT(exe, Tree('../kivy/examples/demo/touchtracer/'),
                Tree('/Library/Frameworks/SDL2_ttf.framework/Versions/A/Frameworks/' +
                     'FreeType.framework'),
                a.binaries,
                a.zipfiles,
                a.datas,
                strip=False,
                upx=True,
                name='touchtracer')
app = BUNDLE(coll,
              name='touchtracer.app',
              icon=None,
              bundle_identifier=None)
```

Change the paths with your relevant paths:

```
a = Analysis(['/path/to/yout/folder/containing/examples/demo/touchtracer/main.py'],
            pathex=['/path/to/yout/folder/containing/testpackaging'],
            ...
            ...
coll = COLLECT(exe, Tree('../kivy/examples/demo/touchtracer/'),
```

Then run the following command:

```
pyinstaller/pyinstaller.py touchtracer.spec
```

Replace *touchtracer* with your app where appropriate. This will give you a <yourapp>.app in the dist/ folder.

### 16.7.3 Using Buildozer

```
pip install git+http://github.com/kivy/buildozer cd /to/where/I/Want/to/package buildozer init
```

---

**Note:** Packaging Kivy applications with the following method must be done inside OS X, 32-bit platforms are no longer supported.

---

Edit the buildozer.spec and add the details for your app. Dependencies can be added to the *requirements*= section.

By default the kivy version specified in the requirements is ignored.

If you have a Kivy.app at /Applications/Kivy.app then that is used, for packaging. Otherwise the latest build from kivy.org using Kivy master will be downloaded and used.

If you want to package for python 3.x.x simply download the package named Kivy3.7z from the download section of kivy.org and extract it to Kivy.app in /Applications, then run:

```
buildozer osx debug
```

Once the app is packaged, you might want to remove unneeded packages like gstreamer, if you don't need video support. Same logic applies for other things you do not use, just reduce the package to its minimal state that is needed for the app to run.

As an example we are including the showcase example packaged using this method for both Python 2 (9.xMB) and 3 (15.xMB), you can find the packages here: [https://drive.google.com/drive/folders/0B1WO07-OL50\\_alFzSXJUajBFdnc](https://drive.google.com/drive/folders/0B1WO07-OL50_alFzSXJUajBFdnc).

That's it. Enjoy!

Buildozer right now uses the Kivy SDK to package your app. If you want to control more details about your app than buildozer currently offers then you can use the SDK directly, as detailed in the section below.

#### 16.7.4 Using the Kivy SDK

---

**Note:** Kivy.app is not available for download at the moment. For details, see [this](#) issue.

---

**Note:** Packaging Kivy applications with the following method must be done inside OS X, 32-bit platforms are no longer supported.

---

Since version 1.9.0, Kivy is released for the OS X platform in a self-contained, portable distribution.

Apps can be packaged and distributed with the Kivy SDK using the method described below, making it easier to include frameworks like SDL2 and GStreamer.

1. Make sure you have the unmodified Kivy SDK (Kivy.app) from the download page.
2. Run the following commands:

```
> mkdir packaging
> cd packaging
packaging> git clone https://github.com/kivy/kivy-sdk-packager
packaging> cd kivy-sdk-packager/osx
osx> cp -a /Applications/Kivy.app ./Kivy.App
```

---

**Note:** This step above is important, you have to make sure to preserve the paths and permissions. A command like `cp -rf` will copy but make the app unusable and lead to

---

error later on.

---

- Now all you need to do is to include your compiled app in the Kivy.app by running the following command:

```
osx> ./package-app.sh /path/to/your/<app_folder_name>/
```

Where <app\_folder\_name> is the name of your app.

This copies Kivy.app to <app\_folder\_name>.app and includes a compiled copy of your app into this package.

- That's it, your self-contained package is ready to be deployed! You can now further customize your app as described below.

### Installing modules

Kivy package on osx uses its own virtual env that is activated when you run your app using *kivy* command. To install any module you need to install the module like so:

```
$ kivy -m pip install <modulename>
```

Where are the modules/files installed?

Inside the portable venv within the app at:

```
Kivy.app/Contents/Resources/venv/
```

If you install a module that installs a binary for example like kivy-garden That binary will be only available from the venv above, as in after you do:

```
kivy -m pip install kivy-garden
```

The garden lib will be only available when you activate this env.

```
source /Applications/Kivy.app/Contents/Resources/venv/bin/activate
garden install
mapview deactivate
```

To install binary files

Just copy the binary to the Kivy.app/Contents/Resources/venv/bin/ directory.

To include other frameworks

Kivy.app comes with SDL2 and Gstreamer frameworks provided. To include frameworks other than the ones provided do the following:

```
git clone http://github.com/tito/osxrelocator
export PYTHONPATH=~/path/to/osxrelocator
cd Kivy.app
python -m osxrelocator -r . /Library/Frameworks/<Framework_name>.framework/ \
@executable_path/./Frameworks/<Framework_name>.framework/
```

Do not forget to replace <Framework\_name> with your framework. This tool *osxrelocator* essentially changes the path for the libs in the framework such that they are relative to the executable within the .app, making the Framework portable with the .app.

## Shrinking the app size

The app has a considerable size right now, however the unneeded parts can be removed from the package.

For example if you don't use GStreamer, simply remove it from YourApp.app/Contents/Frameworks. Similarly you can remove the examples folder from /Applications/Kivy.app/Contents/Resources/kivy/examples/ or kivy/tools, kivy/docs etc.

This way the package can be made to only include the parts that are needed for your app.

## Adjust settings

Icons and other settings of your app can be changed by editing YourApp/Contents/info.plist to suit your needs.

## Create a DMG

To make a DMG of your app use the following command:

```
osx> ./create-osx-dmg.sh YourApp.app
```

Note the lack of / at the end. This should give you a compressed dmg that will further shrink the size of your distributed app.

## 16.8 Create a package for IOS

---

**Note:** Currently, packages for iOS can only be generated with Python 2.7. Python 3.3+ support is on the way.

---

The overall process for creating a package for IOS can be explained in 4 steps:

1. Compile python + modules for IOS
2. Create an Xcode project and link your source code
3. Customize

### 16.8.1 Prerequisites

You need to install some dependencies, like cython, autotools, etc. We encourage you to use [Homebrew](#) to install those dependencies:

```
brew install autoconf automake libtool pkg-config
brew link libtool
sudo easy_install pip
sudo pip install Cython==0.26.1
```

For more detail, see [IOS Prerequisites](#). Just ensure that everything is ok before starting the second step!

## 16.8.2 Compile the distribution

Open a terminal, and type:

```
$ git clone git://github.com/kivy/kivy-ios  
$ cd kivy-ios  
$ ./toolchain.py build kivy
```

Most of the python distribution is packed into *python27.zip*. If you experience any issues, please refer to our [user group](#) or the [kivy-ios project page](#).

## 16.8.3 Create an Xcode project

Before proceeding to the next step, ensure your application entry point is a file named *main.py*.

We provide a script that creates an initial Xcode project to start with. In the command line below, replace *test* with your project name. It must be a name without any spaces or illegal characters:

```
$ ./toolchain.py create <title> <app_directory>  
$ ./toolchain.py create Touchtracer ~/code/kivy/examples/demo/touchtracer
```

---

**Note:** You must use a fully qualified path to your application directory.

---

A directory named *<title>-ios* will be created, with an Xcode project in it. You can open the Xcode project:

```
$ open touchtracer-ios/touchtracer.xcodeproj
```

Then click on *Play*, and enjoy.

---

**Note:** Everytime you press *Play*, your application directory will be synced to the *<title>-ios/YourApp* directory. Don't make changes in the -ios directory directly.

---

## 16.8.4 Updating an Xcode project

Let's say you want to add numpy to your project but you did not compile it prior to creating your XCode project. First, ensure it is built:

```
$ ./toolchain.py build numpy
```

Then, update your Xcode project:

```
$ ./toolchain.py update touchtracer-ios
```

All the libraries / frameworks necessary to run all the compiled recipes will be added to your Xcode project.

## 16.8.5 Customize

There are various ways to customize and configure your app. Please refer to the [kivy-ios](#) documentation for more information.

## 16.8.6 Known issues

All known issues with packaging for iOS are currently tracked on our [issues](#) page. If you encounter an issue specific to packaging for iOS that isn't listed there, please feel free to file a new issue, and we will get back to you on it.

While most are too technical to be written here, one important known issue is that removing some libraries (e.g. `SDL_Mixer` for audio) is currently not possible because the kivy project requires it. We will fix this and others in future versions.

## 16.8.7 FAQ

Application quit abnormally!

By default, all the print statements to the console and files are ignored. If you have an issue when running your application, you can activate the log by commenting out this line in `main.m`:

```
putenv("KIVY_NO_CONSOLELOG=1");
```

Then you should see all the Kivy logging on the Xcode console.

How can Apple accept a python app ?

We managed to merge the app binary with all the libraries into a single binary, called `libpython`. This means all binary modules are loaded beforehand, so nothing is dynamically loaded.

Have you already submitted a Kivy application to the App store ?

Yes, check:

- [Defletouch on iTunes](#),
- [ProcessCraft on iTunes](#)

For a more complete list, visit the [Kivy wiki](#).

## 16.9 IOS Prerequisites

The following guide assumes:

- XCode 5.1 or above
- OS X 10.9 or above

Your experience may vary with different versions.

### 16.9.1 Getting started

In order to submit any application to the iTunes store, you will need an [iOS Developer License](#). For testing, you can use a physical device or the XCode iOS emulator.

Please note that in order to test on the device, you need to register these devices and install your “provisioning profile” on them. Please refer to the Apple’s [Getting started](#) guide for more information.

## 16.9.2 Homebrew

We use the [Homebrew](#) package manager for OSX to install some of the dependencies and tools used by Kivy. It's a really helpful tool and is an Open Source project hosted on [Github](#).

Due to the nature of package management (complications with versions and Operating Systems), this process can be error prone and cause failures in the build process. The **Missing requirement: <pkg> is not installed!** message is typically such an error.

The first thing is to ensure you have run the following commands:

```
brew install autoconf automake libtool pkg-config mercurial  
brew link libtool  
brew link mercurial  
sudo easy_install pip  
sudo pip install cython
```

If you still receive build errors, check your Homebrew is in a healthy state:

```
brew doctor
```

For further help, please refer to the [Homebrew wiki](#).

The last, final and desperate step to get things working might be to remove Homebrew altogether, get the latest version, install that and then re-install the dependencies.

[How to Uninstall and Remove Homebrew for Mac OSX](#)



# Package licensing

---

**Warning:** This is not a legally authoritative guide! The Kivy organisation, authors and contributors take no responsibility for any lack of knowledge, information or advice presented here. The guide is merely informative and is meant to protect inexperienced users.

Your code alone may not require including licensing information or copyright notices of other included software, but binaries are something else. When a binary (.exe, .app, .apk, ...) is created, it includes Kivy, its dependencies and other packages that your application uses.

Some of them are licensed in a way that requires including a copyright notice somewhere in your app (or more). Before distributing any of the binaries, please **check all the created files** that don't belong to your source (.dll, .pyd, .so, ...) and include the appropriate copyright notices if required by the license the files belong to. This way you may satisfy licensing requirements of the Kivy deps.

## 17.1 Dependencies

All of the dependencies will be used at least partially on each platform Kivy supports. You therefore need to comply to their licenses, which mostly requires only pasting a copyright notice in your app and not pretending you wrote the code.

- [docutils](#)
- [pygments](#)
- [sdl2](#)
- [glew](#)
- [gstreamer](#) (if used)
- image & audio libraries(e.g. [SDL\\_mixer](#) has them)

You'll probably need to check image and audio libraries manually (most begin with `lib`). The `LICENSE*` files that belong to them should be included by PyInstaller, but are not included by python-for-android and you need to find them.

## 17.2 Windows (PyInstaller)

To access some Windows API features, Kivy uses the [pypiwin32](#) package. This package is released under the [PSF license](#).

### 17.2.1 Visual Studio Redistributables

Python compiled with Visual Studio (official) includes files from Microsoft and you are only allowed to redistribute them under specific conditions listed in the CRTlicense. You need to include the names of the files and a reworded version of [Py2 CRT license](#) or [Py3 CRT license](#) (depending which interpreter you use) and present these to the end-user of your application in order to satisfy their requirements.

- [List of redistributables](#)

### 17.2.2 Other libraries

- [zlib](#)

---

**Note:** Please add the attributions for other libraries that you *don't use directly* but are present after packaging with e.g. PyInstaller on Windows.

---

## 17.3 Linux

Linux has many distributions which means there's no correct guide for all of the distributions. This applies to the RPi too. However, it can be simplified in two ways depending on how you create a package (also with PyInstaller): with or without including binaries.

If the binaries are included, you should check every file (e.g. `.so`) that's not your source and find the license it belongs to. According to that license, you'll probably need to put an attribution into your application or possibly more, depending on the requirements of that license.

If the binaries are not included (which allows packaging your app as e.g. a `.deb` package), there's a [situation bad for your user](#). It's up to you to decide whether you satisfy the conditions of other licenses and, for example, include copyright attributions into your app or not.

## 17.4 Android

As APK is just an archive of files: you can extract files from it and (as in Windows redistributables) check all the files.

`APK/assets/private.mp3/private.mp3` contains all the included files. Most of them are related to Kivy, Python or your source, but those that aren't need checking.

Known packages:

- [pygame](#) (if old\_toolchain is used)

- [sqlite3](#)
- [six](#)

There are other included libraries, included either by Kivy directly or through Pygame/SDL2, that are located in `APK/lib/armeabi/`. Most of them are related to dependencies or are produced by `python-for-android` and are part of its source (and licensing).

- `libapplication.so`

## 17.5 Mac

Missing.

## 17.6 iOS

Missing.

## 17.7 Avoiding binaries

There might be a way how to avoid this licensing process by avoiding creating a distribution with third-party stuff completely. With Python you can create a module, which is only your code with `--main__.py + setup.py` that only lists required dependencies.

This way, you can still distribute your app - your *code* - and you might not need to care about other licenses. The combination of your code and the dependencies could be specified as a “usage” rather than a “distribution”. The responsibility of satisfying licenses, however, most likely transfers to your user, who needs to assemble the environment to even run the module. If you care about your users, you might want to slow down a little and read more about the [consequences](#).



Part III  
**TUTORIALS**




# Pong Game Tutorial

---

## 18.1 Introduction

Welcome to the Pong tutorial

This tutorial will teach you how to write pong using Kivy. We'll start with a basic application like the one described in the [Create an application](#) and turn it into a playable pong game, describing each step along the way.



Here is a check list before starting this tutorial:

- You have a working Kivy installation. See the [Installation](#) section for detailed descriptions
- You know how to run a basic Kivy application. See [Create an application](#) if you don't.

If you have read the programming guide, and understand both basic Widget concepts ([A Simple Paint App](#)) and basic concepts of the kv language ([Kv language](#)), you can probably skip the first 2 steps and go straight to step 3.

---

**Note:** You can find the entire source code, and source code files for each step in the Kivy examples directory under `tutorials/pong/`

---

Ready? Sweet, let's get started!

## 18.2 Getting Started

### Getting Started

Let's start by getting a really simple Kivy app up and running. Create a directory for the game and a file named `main.py`

```
1 from kivy.app import App
2 from kivy.uix.widget import Widget
3
4
5 class PongGame(Widget):
6     pass
7
8
9 class PongApp(App):
10     def build(self):
11         return PongGame()
12
13
14 if __name__ == '__main__':
15     PongApp().run()
```

Go ahead and run the application. It should just show a black window at this point. What we've done is create a very simple Kivy [App](#), which creates an instance of our `PongGame` Widget class and returns it as the root element for the applications UI, which you should imagine at this point as a hierarchical tree of Widgets. Kivy places this widget-tree in the default Window. In the next step, we will draw the Pong background and scores by defining how the `PongGame` widget looks.

## 18.3 Add Simple Graphics

### Creation of pong.kv

We will use a .kv file to define the look and feel of the `PongGame` class. Since our [App](#) class is called `PongApp`, we can simply create a file called `pong.kv` in the same directory that will be automatically loaded when the application is run. So create a new file called "`pong.kv`" and add the following contents.

```
1 #:kivy 1.0.9
2
3 <PongGame>:
4     canvas:
```

```

5      Rectangle:
6          pos: self.center_x - 5, 0
7          size: 10, self.height
8
9      Label:
10         font_size: 70
11         center_x: root.width / 4
12         top: root.top - 50
13         text: "0"
14
15     Label:
16         font_size: 70
17         center_x: root.width * 3 / 4
18         top: root.top - 50
19         text: "0"

```

---

**Note:** COMMON ERROR: The name of the kv file, e.g. pong.kv, must match the name of the app, e.g. PongApp (the part before the App ending).

---

If you run the app now, you should see a vertical bar in the middle, and two zeros where the player scores will be displayed.

### 18.3.1 Explaining the Kv File Syntax

Before going on to the next step, you might want to take a closer look at the contents of the kv file we just created and figure out what is going on. If you understand what's happening, you can probably skip ahead to the next step.

On the very first line we have:

```
#:kivy 1.0.9
```

This first line is required in every kv file. It should start with `#:kivy` followed by a space and the Kivy version it is intended for (so Kivy can make sure you have at least the required version, or handle backwards compatibility later on).

After that, we begin defining rules that are applied to all `PongGame` instances:

```
<PongGame>:
    ...
```

Like Python, kv files use indentation to define nested blocks. A block defined with a class name inside the `<` and `>` characters is a `Widget` rule. It will be applied to any instance of the named class. If you replaced `PongGame` with `Widget` in our example, all `Widget` instances would have the vertical line and the two `Label` widgets inside them because it would define these rules for all `Widget` instances.

Inside a rule section, you can add various blocks to define the style and contents of the widgets they will be applied to. You can:

- set property values,
- add child widgets
- define a `canvas` section in which you can add Graphics instructions that define how the widget is rendered.

The first block inside the `<PongGame>` rule we have is a `canvas` block:

```
<PongGame>:
    canvas:
        Rectangle:
            pos: self.center_x - 5, 0
            size: 10, self.height
```

So this canvas block says that the `PongGame` widget should draw some graphics primitives. In this case, we add a rectangle to the canvas. We set the pos of the rectangle to be 5 pixels left of the horizontal center of the widget, and 0 for y. The size of the rectangle is set to 10 pixels in width, and the widget's height in height. The nice thing about defining the graphics like this, is that the rendered rectangle will be automatically updated when the properties of any widgets used in the value expression change.

---

**Note:** Try to resize the application window and notice what happens. That's right, the entire UI resizes automatically. The standard behaviour of the Window is to resize an element based on its property `size_hint`. The default widget `size_hint` is (1,1), meaning it will be stretched 100% in both x-direction and y-direction and hence fill the available space. Since the pos and size of the rectangle and `center_x` and `top` of the score labels were defined within the context of the `PongGame` class, these properties will automatically update when the corresponding widget properties change. Using the Kv language gives you automatic property binding. :)

---

The last two sections we add look pretty similar. Each of them adds a `Label` widget as a child widget to the `PongGame` widget. For now, the text on both of them is just set to "0". We'll hook that up to the actual score once we have the logic implemented, but the labels already look good since we set a bigger `font_size`, and positioned them relatively to the root widget. The `root` keyword can be used inside the child block to refer back to the parent/root widget the rule applies to (`PongGame` in this case):

```
<PongGame>:
    # ...

    Label:
        font_size: 70
        center_x: root.width / 4
        top: root.top - 50
        text: "0"

    Label:
        font_size: 70
        center_x: root.width * 3 / 4
        top: root.top - 50
        text: "0"
```

## 18.4 Add the Ball

### Add the Ball

Ok, so we have a basic pong arena to play in, but we still need the players and a ball to hit around. Let's start with the ball. We'll add a new `PongBall` class to create a widget that will be our ball and make it bounce around.

#### 18.4.1 PongBall Class

Here is the Python code for the `PongBall` class:

```

1 class PongBall(Widget):
2
3     # velocity of the ball on x and y axis
4     velocity_x = NumericProperty(0)
5     velocity_y = NumericProperty(0)
6
7     # referencelist property so we can use ball.velocity as
8     # a shorthand, just like e.g. w.pos for w.x and w.y
9     velocity = ReferenceListProperty(velocity_x, velocity_y)
10
11    # ``move`` function will move the ball one step. This
12    # will be called in equal intervals to animate the ball
13    def move(self):
14        self.pos = Vector(*self.velocity) + self.pos

```

And here is the kv rule used to draw the ball as a white circle:

```

<PongBall>:
    size: 50, 50
    canvas:
        Ellipse:
            pos: self.pos
            size: self.size

```

To make it all work, you also have to add the imports for the *Properties* Property classes used and the *Vector*.

Here is the entire updated python code and kv file for this step:

**main.py:**

```

1 from kivy.app import App
2 from kivy.uix.widget import Widget
3 from kivy.properties import NumericProperty, ReferenceListProperty
4 from kivy.vector import Vector
5
6
7 class PongBall(Widget):
8     velocity_x = NumericProperty(0)
9     velocity_y = NumericProperty(0)
10    velocity = ReferenceListProperty(velocity_x, velocity_y)
11
12    def move(self):
13        self.pos = Vector(*self.velocity) + self.pos
14
15
16 class PongGame(Widget):
17     pass
18
19
20 class PongApp(App):
21     def build(self):
22         return PongGame()
23
24
25 if __name__ == '__main__':
26     PongApp().run()

```

**pong.kv:**

```

1 #:kivy 1.0.9
2
3 <PongBall>:
4     size: 50, 50
5     canvas:
6         Ellipse:
7             pos: self.pos
8             size: self.size
9
10 <PongGame>:
11     canvas:
12         Rectangle:
13             pos: self.center_x-5, 0
14             size: 10, self.height
15
16     Label:
17         font_size: 70
18         center_x: root.width / 4
19         top: root.top - 50
20         text: "0"
21
22     Label:
23         font_size: 70
24         center_x: root.width * 3 / 4
25         top: root.top - 50
26         text: "0"
27
28     PongBall:
29         center: self.parent.center
30

```

Note that not only a `<PongBall>` widget rule has been added, but also a child widget `PongBall` in the `<PongGame>` widget rule.

## 18.5 Adding Ball Animation

Making the ball move

Cool, so now we have a ball, and it even has a `move` function... but it's not moving yet. Let's fix that.

### 18.5.1 Scheduling Functions on the Clock

We need the `move` method of our ball to be called regularly. Luckily, Kivy makes this pretty easy by letting us schedule any function we want using the `Clock` and specifying the interval:

```
Clock.schedule_interval(game.update, 1.0/60.0)
```

This line for example, would cause the `update` function of the game object to be called once every 60th of a second (60 times per second).

### 18.5.2 Object Properties/References

We have another problem though. We'd like to make sure the `PongBall` has its `move` function called regularly, but in our code we don't have any references to the ball object since we just added it via the

kv file inside the kv rule for the `PongGame` class. The only reference to our game is the one we return in the applications build method.

Since we're going to have to do more than just move the ball (e.g. bounce it off the walls and later the players racket), we'll probably need an `update` method for our `PongGame` class anyway. Furthermore, given that we have a reference to the game object already, we can easily schedule its new `update` method when the application gets built:

```
1 class PongGame(Widget):
2
3     def update(self, dt):
4         # call ball.move and other stuff
5         pass
6
7 class PongApp(App):
8
9     def build(self):
10        game = PongGame()
11        Clock.schedule_interval(game.update, 1.0/60.0)
12        return game
```

However, that still doesn't change the fact that we don't have a reference to the `PongBall` child widget created by the kv rule. To fix this, we can add an `ObjectProperty` to the `PongGame` class, and hook it up to the widget created in the kv rule. Once that's done, we can easily reference the ball property inside the `update` method and even make it bounce off the edges:

```
1 class PongGame(Widget):
2     ball = ObjectProperty(None)
3
4     def update(self, dt):
5         self.ball.move()
6
7         # bounce off top and bottom
8         if (self.ball.y < 0) or (self.ball.top > self.height):
9             self.ball.velocity_y *= -1
10
11         # bounce off left and right
12         if (self.ball.x < 0) or (self.ball.right > self.width):
13             self.ball.velocity_x *= -1
```

Don't forget to hook it up in the kv file, by giving the child widget an id and setting the `PongGame`'s `ball` `ObjectProperty` to that id:

```
<PongGame>:
    ball: pong_ball

    # ... (canvas and Labels)

    PongBall:
        id: pong_ball
        center: self.parent.center
```

---

**Note:** At this point everything is hooked up for the ball to bounce around. If you're coding along as we go, you might be wondering why the ball isn't moving anywhere. The ball's velocity is set to 0 on both x and y. In the code listing below, a `serve_ball` method is added to the `PongGame` class and called in the app's `build` method. It sets a random x and y velocity for the ball, and also resets the position, so we can use it later to reset the ball when a player has scored a point.

---

Here is the entire code for this step:

**main.py:**

```
1  from kivy.app import App
2  from kivy.uix.widget import Widget
3  from kivy.properties import NumericProperty, ReferenceListProperty,\ 
4      ObjectProperty
5  from kivy.vector import Vector
6  from kivy.clock import Clock
7  from random import randint
8
9
10 class PongBall(Widget):
11     velocity_x = NumericProperty(0)
12     velocity_y = NumericProperty(0)
13     velocity = ReferenceListProperty(velocity_x, velocity_y)
14
15     def move(self):
16         self.pos = Vector(*self.velocity) + self.pos
17
18
19 class PongGame(Widget):
20     ball = ObjectProperty(None)
21
22     def serve_ball(self):
23         self.ball.center = self.center
24         self.ball.velocity = Vector(4, 0).rotate(randint(0, 360))
25
26     def update(self, dt):
27         self.ball.move()
28
29         # bounce off top and bottom
30         if (self.ball.y < 0) or (self.ball.top > self.height):
31             self.ball.velocity_y *= -1
32
33         # bounce off left and right
34         if (self.ball.x < 0) or (self.ball.right > self.width):
35             self.ball.velocity_x *= -1
36
37
38 class PongApp(App):
39     def build(self):
40         game = PongGame()
41         game.serve_ball()
42         Clock.schedule_interval(game.update, 1.0 / 60.0)
43         return game
44
45
46 if __name__ == '__main__':
47     PongApp().run()
```

**pong.kv:**

```
1 #:kivy 1.0.9
2
3 <PongBall>:
4     size: 50, 50
5     canvas:
6         Ellipse:
7             pos: self.pos
```

```

8         size: self.size
9
10    <PongGame>:
11        ball: pong_ball
12
13        canvas:
14            Rectangle:
15                pos: self.center_x-5, 0
16                size: 10, self.height
17
18        Label:
19            font_size: 70
20            center_x: root.width / 4
21            top: root.top - 50
22            text: "0"
23
24        Label:
25            font_size: 70
26            center_x: root.width * 3 / 4
27            top: root.top - 50
28            text: "0"
29
30        PongBall:
31            id: pong_ball
32            center: self.parent.center
33

```

## 18.6 Connect Input Events

Adding Players and reacting to touch input

Sweet, our ball is bouncing around. The only things missing now are the movable player rackets and keeping track of the score. We won't go over all the details of creating the class and kv rules again, since those concepts were already covered in the previous steps. Instead, let's focus on how to move the Player widgets in response to user input. You can get the whole code and kv rules for the `PongPaddle` class at the end of this section.

In Kivy, a widget can react to input by implementing the `on_touch_down`, the `on_touch_move` and the `on_touch_up` methods. By default, the Widget class implements these methods by just calling the corresponding method on all its child widgets to pass on the event until one of the children returns True.

Pong is pretty simple. The rackets just need to move up and down. In fact it's so simple, we don't even really need to have the player widgets handle the events themselves. We'll just implement the `on_touch_move` function for the `PongGame` class and have it set the position of the left or right player based on whether the touch occurred on the left or right side of the screen.

Check the `on_touch_move` handler:

```

1 def on_touch_move(self, touch):
2     if touch.x < self.width/3:
3         self.player1.center_y = touch.y
4     if touch.x > self.width - self.width/3:
5         self.player2.center_y = touch.y

```

We'll keep the score for each player in a `NumericProperty`. The score labels of the `PongGame` are kept updated by changing the `NumericProperty` `score`, which in turn updates the `PongGame` child labels `text` property. This binding occurs because Kivy `properties` automatically bind to any references in

their corresponding kv files. When the ball escapes out of the sides, we'll update the score and serve the ball again by changing the update method in the PongGame class. The PongPaddle class also implements a `bounce_ball` method, so that the ball bounces differently based on where it hits the racket. Here is the code for the `PongPaddle` class:

```
1 class PongPaddle(Widget):
2
3     score = NumericProperty(0)
4
5     def bounce_ball(self, ball):
6         if self.collide_widget(ball):
7             speedup = 1.1
8             offset = 0.02 * Vector(0, ball.center_y-self.center_y)
9             ball.velocity = speedup * (offset - ball.velocity)
```

---

**Note:** This algorithm for ball bouncing is very simple, but will have strange behavior if the ball hits the paddle from the side or bottom... this is something you could try to fix yourself if you like.

---

And here it is in context. Pretty much done:

`main.py`:

```
1 from kivy.app import App
2 from kivy.uix.widget import Widget
3 from kivy.properties import NumericProperty, ReferenceListProperty,\n    ObjectProperty
4 from kivy.vector import Vector
5 from kivy.clock import Clock
6
7
8 class PongPaddle(Widget):
9     score = NumericProperty(0)
10
11     def bounce_ball(self, ball):
12         if self.collide_widget(ball):
13             vx, vy = ball.velocity
14             offset = (ball.center_y - self.center_y) / (self.height / 2)
15             bounced = Vector(-1 * vx, vy)
16             vel = bounced * 1.1
17             ball.velocity = vel.x, vel.y + offset
18
19
20 class PongBall(Widget):
21     velocity_x = NumericProperty(0)
22     velocity_y = NumericProperty(0)
23     velocity = ReferenceListProperty(velocity_x, velocity_y)
24
25     def move(self):
26         self.pos = Vector(*self.velocity) + self.pos
27
28
29 class PongGame(Widget):
30     ball = ObjectProperty(None)
31     player1 = ObjectProperty(None)
32     player2 = ObjectProperty(None)
33
34     def serve_ball(self, vel=(4, 0)):
35         self.ball.center = self.center
36         self.ball.velocity = vel
```

```

38
39     def update(self, dt):
40         self.ball.move()
41
42         # bounce of paddles
43         self.player1.bounce_ball(self.ball)
44         self.player2.bounce_ball(self.ball)
45
46         # bounce ball off bottom or top
47         if (self.ball.y < self.y) or (self.ball.top > self.top):
48             self.ball.velocity_y *= -1
49
50         # went of to a side to score point?
51         if self.ball.x < self.x:
52             self.player2.score += 1
53             self.serve_ball(vel=(4, 0))
54         if self.ball.x > self.width:
55             self.player1.score += 1
56             self.serve_ball(vel=(-4, 0))
57
58     def on_touch_move(self, touch):
59         if touch.x < self.width / 3:
60             self.player1.center_y = touch.y
61         if touch.x > self.width - self.width / 3:
62             self.player2.center_y = touch.y
63
64
65 class PongApp(App):
66     def build(self):
67         game = PongGame()
68         game.serve_ball()
69         Clock.schedule_interval(game.update, 1.0 / 60.0)
70         return game
71
72
73 if __name__ == '__main__':
74     PongApp().run()

```

pong.kv:

```

1 #:kivy 1.0.9
2
3 <PongBall>:
4     size: 50, 50
5     canvas:
6         Ellipse:
7             pos: self.pos
8             size: self.size
9
10 <PongPaddle>:
11     size: 25, 200
12     canvas:
13         Rectangle:
14             pos: self.pos
15             size: self.size
16
17 <PongGame>:
18     ball: pong_ball
19     player1: player_left
20     player2: player_right

```

```

21
22     canvas:
23         Rectangle:
24             pos: self.center_x-5, 0
25             size: 10, self.height
26
27     Label:
28         font_size: 70
29         center_x: root.width / 4
30         top: root.top - 50
31         text: str(root.player1.score)
32
33     Label:
34         font_size: 70
35         center_x: root.width * 3 / 4
36         top: root.top - 50
37         text: str(root.player2.score)
38
39     PongBall:
40         id: pong_ball
41         center: self.parent.center
42
43     PongPaddle:
44         id: player_left
45         x: root.x
46         center_y: root.center_y
47
48     PongPaddle:
49         id: player_right
50         x: root.width-self.width
51         center_y: root.center_y
52

```

## 18.7 Where To Go Now?

Have some fun

Well, the pong game is pretty much complete. If you understood all of the things that are covered in this tutorial, give yourself a pat on the back and think about how you could improve the game. Here are a few ideas of things you could do:

- Add some nicer graphics / images. (Hint: check out the `source` property on the graphics instructions like `circle` or `Rectangle`, to set an image as the texture.)
- Make the game end after a certain score. Maybe once a player has 10 points, you can display a large “PLAYER 1 WINS” label and/or add a main menu to start, pause and reset the game. (Hint: check out the `Button` and `Label` classes, and figure out how to use their `add_widget` and `remove_widget` functions to add or remove widgets dynamically.)
- Make it a 4 player Pong Game. Most tablets have Multi-Touch support, so wouldn’t it be cool to have a player on each side and have four people play at the same time?
- Fix the simplistic collision check so hitting the ball with an end of the paddle results in a more realistic bounce.

---

**Note:** You can find the entire source code and source code files for each step in the Kivy examples directory under `tutorials/pong/`

---

# A Simple Paint App

---

In the following tutorial, you will be guided through the creation of your first widget. This provides powerful and important knowledge when programming Kivy applications, as it lets you create completely new user interfaces with custom elements for your specific purpose.

## 19.1 Basic Considerations

When creating an application, you have to ask yourself three important questions:

- What data does my application process?
- How do I visually represent that data?
- How does the user interact with that data?

If you want to write a very simple line drawing application for example, you most likely want the user to just draw on the screen with his/her fingers. That's how the user *interacts* with your application. While doing so, your application would memorize the positions where the user's finger were, so that you can later draw lines between those positions. So the points where the fingers were would be your *data* and the lines that you draw between them would be your *visual representation*.

In Kivy, an application's user interface is composed of Widgets. Everything that you see on the screen is somehow drawn by a widget. Often you would like to be able to reuse code that you already wrote in a different context, which is why widgets typically represent one specific instance that answers the three questions above. A widget encapsulates data, defines the user's interaction with that data and draws its visual representation. You can build anything from simple to complex user interfaces by nesting widgets. There are many widgets built in, such as buttons, sliders and other common stuff. In many cases, however, you need a custom widget that is beyond the scope of what is shipped with Kivy (e.g. a medical visualization widget).

So keep these three questions in mind when you design your widgets. Try to write them in a minimal and reusable manner (i.e. a widget does exactly what its supposed to do and nothing more. If you need more, write more widgets or compose other widgets of smaller widgets. We try to adhere to the [Single Responsibility Principle](#)).

## 19.2 Paint Widget

We're sure one of your childhood dreams has always been creating your own multitouch paint program. Allow us to help you achieve that. In the following sections you will successively learn how to write a program like that using Kivy. Make sure that you have read and understood [Create an application](#). You have? Great! Let's get started!

### 19.2.1 Initial Structure

Let's start by writing the very basic code structure that we need. By the way, all the different pieces of code that are used in this section are also available in the `examples/guide/firstwidget` directory that comes with Kivy, so you don't need to copy & paste it all the time. Here is the basic code skeleton that we will need:

```
1 from kivy.app import App
2 from kivy.uix.widget import Widget
3
4
5 class MyPaintWidget(Widget):
6     pass
7
8
9 class MyPaintApp(App):
10     def build(self):
11         return MyPaintWidget()
12
13
14 if __name__ == '__main__':
15     MyPaintApp().run()
```

This is actually really simple. Save it as `paint.py`. If you run it, you should only see a black screen. As you can see, instead of using a built-in widget such as a Button (see [Create an application](#)), we are going to write our own widget to do the drawing. We do that by creating a class that inherits from `Widget` (line 5-6) and although that class does nothing yet, we can still treat it like a normal Kivy widget (line 11). The `if __name__ == '__main__':` construct (line 14) is a Python mechanism that prevents you from executing the code in the if-statement when importing from the file, i.e. if you write `import paint`, it won't do something unexpected but just nicely provide the classes defined in the file.

---

**Note:** You may be wondering why you have to import App and Widget separately, instead of doing something like `from kivy import *`. While shorter, this would have the disadvantage of [polluting your namespace](#) and make the start of the application potentially much slower. It can also introduce ambiguity into class and variable naming, so is generally frowned upon in the Python community. The way we do it is faster and cleaner.

---

### 19.2.2 Adding Behaviour

Let's now add some actual behaviour to the widget, i.e. make it react to user input. Change the code like so:

```
1 from kivy.app import App
2 from kivy.uix.widget import Widget
3
4
5 class MyPaintWidget(Widget):
```

```

6     def on_touch_down(self, touch):
7         print(touch)
8
9
10    class MyPaintApp(App):
11        def build(self):
12            return MyPaintWidget()
13
14
15    if __name__ == '__main__':
16        MyPaintApp().run()

```


This is just to show how easy it is to react to user input. When a *MotionEvent* (i.e. a touch, click, etc.) occurs, we simply print the information about the touch object to the console. You won't see anything on the screen, but if you observe the command-line from which you are running the program, you will see a message for every touch. This also demonstrates that a widget does not have to have a visual representation.

Now that's not really an overwhelming user experience. Let's add some code that actually draws something into our window:

```

1   from kivy.app import App
2   from kivy.uix.widget import Widget
3   from kivy.graphics import Color, Ellipse
4
5
6   class MyPaintWidget(Widget):
7
8       def on_touch_down(self, touch):
9           with self.canvas:
10               Color(1, 1, 0)
11               d = 30.
12               Ellipse(pos=(touch.x - d / 2, touch.y - d / 2), size=(d, d))
13
14
15   class MyPaintApp(App):
16
17       def build(self):
18           return MyPaintWidget()
19
20
21   if __name__ == '__main__':
22       MyPaintApp().run()

```



If you run your code with these modifications, you will see that every time you touch, there will be a small yellow circle drawn where you touched. How does it work?

- Line 9: We use Python's `with` statement with the widget's `Canvas` object. This is like an area in which the widget can draw things to represent itself on the screen. By using the `with` statement with it, all successive drawing commands that are properly indented will modify this canvas. The `with` statement also makes sure that after our drawing, internal state can be cleaned up properly.
- Line 10: You might have guessed it already: This sets the `Color` for successive drawing operations to yellow (default color format is RGB, so `(1, 1, 0)` is yellow). This is true until another `Color` is set. Think of this as dipping your brushes in that color, which you can then use to draw on a canvas until you dip the brushes into another color.
- Line 11: We specify the diameter for the circle that we are about to draw. Using a variable for that is preferable since we need to refer to that value multiple times and we don't want to have to change it in several places if we want the circle bigger or smaller.
- Line 12: To draw a circle, we simply draw an `Ellipse` with equal width and height. Since we want the circle to be drawn where the user touches, we pass the touch's position to the ellipse. Note that we need to shift the ellipse by `-d/2` in the x and y directions (i.e. left and downwards) because the position specifies the bottom left corner of the ellipse's bounding box, and we want it to be centered around our touch.


That was easy, wasn't it? It gets better! Update the code to look like this:

```
1 from kivy.app import App
2 from kivy.uix.widget import Widget
3 from kivy.graphics import Color, Ellipse, Line
4
5
6 class MyPaintWidget(Widget):
7
8     def on_touch_down(self, touch):
9         with self.canvas:
10             Color(1, 1, 0)
11             d = 30.
12             Ellipse(pos=(touch.x - d / 2, touch.y - d / 2), size=(d, d))
13             touch.ud['line'] = Line(points=(touch.x, touch.y))
14
15     def on_touch_move(self, touch):
```

```

16 touch.ud['line'].points += [touch.x, touch.y]
17
18
19 class MyPaintApp(App):
20
21     def build(self):
22         return MyPaintWidget()
23
24
25 if __name__ == '__main__':
26     MyPaintApp().run()

```




This is what has changed:

- Line 3: We now not only import the *Ellipse* drawing instruction, but also the *Line* drawing instruction. If you look at the documentation for *Line*, you will see that it accepts a *points* argument that has to be a list of 2D point coordinates, like  $(x_1, y_1, x_2, y_2, \dots, x_N, y_N)$ .
- Line 13: This is where it gets interesting. *touch.ud* is a Python dictionary (type *<dict>*) that allows us to store *custom attributes* for a touch.
- Line 13: We make use of the *Line* instruction that we imported and set a *Line* up for drawing. Since this is done in *on\_touch\_down*, there will be a new line for every new touch. By creating the line inside the *with* block, the canvas automatically knows about the line and will draw it. We just want to modify the line later, so we store a reference to it in the *touch.ud* dictionary under the arbitrarily chosen but aptly named key '*line*'. We pass the line that we're creating the initial touch position because that's where our line will begin.
- Lines 15: We add a new method to our widget. This is similar to the *on\_touch\_down* method, but instead of being called when a *new* touch occurs, this method is being called when an *existing* touch (for which *on\_touch\_down* was already called) moves, i.e. its position changes. Note that this is the **same** *MotionEvent* object with updated attributes. This is something we found incredibly handy and you will shortly see why.
- Line 16: Remember: This is the same touch object that we got in *on\_touch\_down*, so we can simply access the data we stored away in the *touch.ud* dictionary! To the line we set up for this touch earlier, we now add the current position of the touch as a new point. We know that we need to extend the line because this happens in *on\_touch\_move*, which is only called

when the touch has moved, which is exactly why we want to update the line. Storing the line in the `touch.ud` makes it a whole lot easier for us as we don't have to maintain our own touch-to-line bookkeeping.

So far so good. This isn't exactly beautiful yet, though. It looks a bit like spaghetti bolognese. How about giving each touch its own color? Great, let's do it:

```
1  from random import random
2  from kivy.app import App
3  from kivy.uix.widget import Widget
4  from kivy.graphics import Color, Ellipse, Line
5
6
7  class MyPaintWidget(Widget):
8
9      def on_touch_down(self, touch):
10         color = (random(), random(), random())
11         with self.canvas:
12             Color(*color)
13             d = 30.
14             Ellipse(pos=(touch.x - d / 2, touch.y - d / 2), size=(d, d))
15             touch.ud['line'] = Line(points=(touch.x, touch.y))
16
17     def on_touch_move(self, touch):
18         touch.ud['line'].points += [touch.x, touch.y]
19
20
21 class MyPaintApp(App):
22
23     def build(self):
24         return MyPaintWidget()
25
26
27 if __name__ == '__main__':
28     MyPaintApp().run()
```



Here are the changes:

- Line 1: We import Python's `random()` function that will give us random values in the range of [0., 1.).

- Line 10: In this case we simply create a new tuple of 3 random float values that will represent a random RGB color. Since we do this in `on_touch_down`, every new touch will get its own color. Don't get confused by the use of `tuples`. We're just binding the tuple to `color` for use as a shortcut within this method because we're lazy.
- Line 12: As before, we set the color for the canvas. Only this time we use the random values we generated and feed them to the color class using Python's tuple unpacking syntax (since the Color class expects three individual color components instead of just 1. If we were to pass the tuple directly, that would be just 1 value being passed, regardless of the fact that the tuple itself contains 3 values).

This looks a lot nicer already! With a lot of skill and patience, you might even be able to create a nice little drawing!

---

**Note:** Since by default the `Color` instructions assume RGB mode and we're feeding a tuple with three random float values to it, it might very well happen that we end up with a lot of dark or even black colors if we are unlucky. That would be bad because by default the background color is dark as well, so you wouldn't be able to (easily) see the lines you draw. There is a nice trick to prevent this: Instead of creating a tuple with three random values, create a tuple like this: `(random(), 1., 1.)`. Then, when passing it to the color instruction, set the mode to HSV color space: `Color(*color, mode='hsv')`. This way you will have a smaller number of possible colors, but the colors that you get will always be equally bright: only the hue changes.

---

### 19.2.3 Bonus Points

At this point, we could say we are done. The widget does what it's supposed to do: it traces the touches and draws lines. It even draws circles at the positions where a line begins.

But what if the user wants to start a new drawing? With the current code, the only way to clear the window would be to restart the entire application. Luckily, we can do better. Let us add a `Clear` button that erases all the lines and circles that have been drawn so far. There are two options now:

- We could either create the button as a child of our widget. That would imply that if you create more than one widget, every widget gets its own button. If you're not careful, this will also allow users to draw on top of the button, which might not be what you want.
- Or we set up the button only once, initially, in our app class and when it's pressed we clear the widget.

For our simple example, it doesn't really matter that much. For larger applications you should give some thought to who does what in your app. We'll go with the second option here so that you see how you can build up your application's widget tree in your app class's `build()` method. We'll also change to the HSV color space (see preceding note):

```


1  from random import random
2  from kivy.app import App
3  from kivy.uix.widget import Widget
4  from kivy.uix.button import Button
5  from kivy.graphics import Color, Ellipse, Line
6
7
8  class MyPaintWidget(Widget):
9
10     def on_touch_down(self, touch):
11         color = (random(), 1, 1)
12         with self.canvas:
13             Color(*color, mode='hsv')

```

```

14     d = 30.
15     Ellipse(pos=(touch.x - d / 2, touch.y - d / 2), size=(d, d))
16     touch.ud['line'] = Line(points=(touch.x, touch.y))
17
18 def on_touch_move(self, touch):
19     touch.ud['line'].points += [touch.x, touch.y]
20
21
22 class MyPaintApp(App):
23
24     def build(self):
25         parent = Widget()
26         self.painter = MyPaintWidget()
27         clearbtn = Button(text='Clear')
28         clearbtn.bind(on_release=self.clear_canvas)
29         parent.add_widget(self.painter)
30         parent.add_widget(clearbtn)
31         return parent
32
33 def clear_canvas(self, obj):
34     self.painter.canvas.clear()
35
36
37 if __name__ == '__main__':
38     MyPaintApp().run()

```



Here's what happens:

- Line 4: We added an import statement to be able to use the `Button` class.
- Line 25: We create a dummy `Widget()` object as a parent for both our painting widget and the button we're about to add. This is just a poor-man's approach to setting up a widget tree hierarchy. We could just as well use a layout or do some other fancy stuff. Again: this widget does absolutely nothing except holding the two widgets we will now add to it as children.
- Line 26: We create our `MyPaintWidget()` as usual, only this time we don't return it directly but bind it to a variable name.
- Line 27: We create a button widget. It will have a label on it that displays the text 'Clear'.
- Line 28: We then bind the button's `on_release` event (which is fired when the button is pressed

and then released) to the **callback function** `clear_canvas` defined on below on Lines 33 & 34.

- Line 29 & 30: We set up the widget hierarchy by making both the painter and the clearbtn children of the dummy parent widget. That means `painter` and `clearbtn` are now siblings in the usual computer science tree terminology.
- Line 33 & 34: Up to now, the button did nothing. It was there, visible, and you could press it, but nothing would happen. We change that here: we create a small, throw-away function that is going to be our **callback function** when the button is pressed. The function just clears the painter's canvas' contents, making it black again.

---

**Note:** The Kivy Widget class, by design, is kept simple. There are no general properties such as background color and border color. Instead, the examples and documentation illustrate how to easily handle such simple things yourself, as we have done here, setting the color for the canvas, and drawing the shape. From a simple start, you can move to more elaborate customization. Higher-level built-in widgets, deriving from Widget, such as Button, do have convenience properties such as `background_color`, but these vary by widget. Use the API docs to see what is offered by a widget, and subclass if you need to add more functionality.

---

Congratulations! You've written your first Kivy widget. Obviously this was just a quick introduction. There is much more to discover. We suggest taking a short break to let what you just learned sink in. Maybe draw some nice pictures to relax? If you feel like you've understood everything and are ready for more, we encourage you to read on.



# Crash Course

---

The Kivy Crash Course is a series of YouTube video tutorials by Kivy core developer [inclement](#). They provide a simple walkthrough in Kivy for users who know how to code in Python and is friendly to Python beginners. After the Pong and Paint tutorials, this set of videos covers basic features and techniques that can be used to create your app quicker, keeping your code elegant and eye-friendly.

## 20.1 Basic Info

The Crash Course primarily consists of a series of YouTube videos, each roughly 10 minutes long. There are also articles describing some of the videos and the code used in the videos.

### 20.1.1 Topics covered by the Crash Course include:

- Use of the basic Kivy widgets such as the Label, Button, Scatter and TextInput
- Building an app for android with python-for-android's [old toolchain](#)
- Binding functions to events
- Using changes in variables on the go
- Smart user interface ([Kv language](#))
- Properties
- Canvas and drawing
- Label with scrolling
- Positioning and layouts
- Animation and Clock
- Accessing android API ([pyjnius](#), [plyer](#))
- Settings panel (and building your own options)

- ScreenManager

#### 20.1.2 Links:

- Videos
- Articles
- Code

## Part IV

# API REFERENCE

The API reference is a lexicographic list of all the different classes, methods and features that Kivy offers.



# Kivy framework

---

Kivy is an open source library for developing multi-touch applications. It is cross-platform (Linux/OSX/Windows/Android/iOS) and released under the terms of the [MIT License](#).

It comes with native support for many multi-touch input devices, a growing library of multi-touch aware widgets and hardware accelerated OpenGL drawing. Kivy is designed to let you focus on building custom and highly interactive applications as quickly and easily as possible.

With Kivy, you can take full advantage of the dynamic nature of Python. There are thousands of high-quality, free libraries that can be integrated in your application. At the same time, performance-critical parts are implemented using [Cython](#).

See <http://kivy.org> for more information.

## `kivy.require(version)`

Require can be used to check the minimum version required to run a Kivy application. For example, you can start your application code like this:

```
import kivy
kivy.require('1.0.1')
```

If a user attempts to run your application with a version of Kivy that is older than the specified version, an Exception is raised.

The Kivy version string is built like this:

```
X.Y.Z[-tag[-tagrevision]]
```

X is the major version  
Y is the minor version  
Z is the bugfixes revision

The tag is optional, but may be one of ‘dev’, ‘alpha’, or ‘beta’. The tagrevision is the revision of the tag.

**Warning:** You must not ask for a version with a tag, except -dev. Asking for a ‘dev’ version will just warn the user if the current Kivy version is not a -dev, but it will never raise an exception. You must not ask for a version with a tagrevision.

### **kivy.kivy\_configure()**

Call post-configuration of Kivy. This function must be called if you create the window yourself.

### **kivy.kivy\_register\_post\_configuration(callback)**

Register a function to be called when kivy\_configure() is called.

**Warning:** Internal use only.

**kivy.kivy\_options = {'window': ('egl\_rpi', 'sdl2', 'pygame', 'sdl', 'x11'), 'camera':}**  
Global settings options for kivy

**kivy.kivy\_base\_dir = '/home/docs/checkouts/readthedocs.org/user\_builds/kivy/envs/latest'**  
Kivy directory

**kivy.kivy\_modules\_dir = '/home/docs/checkouts/readthedocs.org/user\_builds/kivy/envs/latest'**  
Kivy modules directory

**kivy.kivy\_data\_dir = '/home/docs/checkouts/readthedocs.org/user\_builds/kivy/envs/latest'**  
Kivy data directory

**kivy.kivy\_shader\_dir = '/home/docs/checkouts/readthedocs.org/user\_builds/kivy/envs/latest'**  
Kivy glsl shader directory

**kivy.kivy\_icons\_dir = '/home/docs/checkouts/readthedocs.org/user\_builds/kivy/envs/latest'**  
Kivy icons config path (don’t remove the last ”)

**kivy.kivy\_home\_dir = ''**  
Kivy user-home storage directory

**kivy.kivy\_config\_fn = ''**  
Kivy configuration filename

**kivy.kivy\_usermodules\_dir = ''**  
Kivy user modules directory

## 21.1 Animation

*Animation* and *AnimationTransition* are used to animate *Widget* properties. You must specify at least a property name and target value. To use an Animation, follow these steps:

- Setup an Animation object
- Use the Animation object on a Widget

### 21.1.1 Simple animation

To animate a Widget’s x or y position, simply specify the target x/y values where you want the widget positioned at the end of the animation:

```
anim = Animation(x=100, y=100)
anim.start(widget)
```

The animation will last for 1 second unless `duration` is specified. When `anim.start()` is called, the Widget will move smoothly from the current x/y position to (100, 100).

### 21.1.2 Multiple properties and transitions

You can animate multiple properties and use built-in or custom transition functions using `transition` (or the `t=` shortcut). For example, to animate the position and size using the ‘in\_quad’ transition:

```
anim = Animation(x=50, size=(80, 80), t='in_quad')
anim.start(widget)
```

Note that the `t=` parameter can be the string name of a method in the *AnimationTransition* class or your own animation function.

### 21.1.3 Sequential animation

To join animations sequentially, use the ‘+’ operator. The following example will animate to x=50 over 1 second, then animate the size to (80, 80) over the next two seconds:

```
anim = Animation(x=50) + Animation(size=(80, 80), duration=2.)
anim.start(widget)
```

### 21.1.4 Parallel animation

To join animations in parallel, use the ‘&’ operator. The following example will animate the position to (80, 10) over 1 second, whilst in parallel animating the size to (800, 800):

```
anim = Animation(pos=(80, 10))
anim &= Animation(size=(800, 800), duration=2.)
anim.start(widget)
```

Keep in mind that creating overlapping animations on the same property may have unexpected results. If you want to apply multiple animations to the same property, you should either schedule them sequentially (via the ‘+’ operator or using the `on_complete` callback) or cancel previous animations using the `cancel_all` method.

### 21.1.5 Repeating animation

New in version 1.8.0.

---

**Note:** This is currently only implemented for ‘Sequence’ animations.

---

To set an animation to repeat, simply set the `Sequence.repeat` property to `True`:

```
anim = Animation(...) + Animation(...)
anim.repeat = True
anim.start(widget)
```

For flow control of animations such as stopping and cancelling, use the methods already in place in the animation module.

```
class kivy.animation.Animation(**kw)
Bases: kivy.event.EventDispatcher
```

Create an animation definition that can be used to animate a Widget.

#### Parameters

**duration or d: float, defaults to 1.** Duration of the animation, in seconds.

**transition or t: str or func** Transition function for animate properties. It can be the name of a method from *AnimationTransition*.

**step or s: float** Step in milliseconds of the animation. Defaults to 0, which means the animation is updated for every frame.

To update the animation less often, set the step value to a float. For example, if you want to animate at 30 FPS, use s=1/30.

#### Events

**on\_start: animation, widget** Fired when the animation is started on a widget.

**on\_complete: animation, widget** Fired when the animation is completed or stopped on a widget.

**on\_progress: animation, widget, progression** Fired when the progression of the animation is changing.

Changed in version 1.4.0: Added s/step parameter.

Changed in version 1.10.0: The default value of the step parameter was changed from 1/60. to 0.

#### animated\_properties

Return the properties used to animate.

#### cancel(widget)

Cancel the animation previously applied to a widget. Same effect as *stop*, except the *on\_complete* event will *not* be triggered!

New in version 1.4.0.

#### static cancel\_all(widget, \*largs)

Cancel all animations that concern a specific widget / list of properties. See *cancel*.

Example:

```
anim = Animation(x=50)
anim.start(widget)

# and later
Animation.cancel_all(widget, 'x')
```

New in version 1.4.0.

#### cancel\_property(widget, prop)

Even if an animation is running, remove a property. It will not be animated further. If it was the only/last property being animated, the animation will be canceled (see *cancel*)

New in version 1.4.0.

#### duration

Return the duration of the animation.

#### have\_properties\_to\_animate(widget)

Return True if a widget still has properties to animate.

New in version 1.8.0.

**start(widget)**

Start the animation on a widget.

**stop(widget)**

Stop the animation previously applied to a widget, triggering the *on\_complete* event.

**static stop\_all(widget, \*largs)**

Stop all animations that concern a specific widget / list of properties.

Example:

```
anim = Animation(x=50)
anim.start(widget)

# and later
Animation.stop_all(widget, 'x')
```

**stop\_property(widget, prop)**

Even if an animation is running, remove a property. It will not be animated futher. If it was the only/last property being animated, the animation will be stopped (see *stop*).

**transition**



Return the transition of the animation.


**class kivy.animation.AnimationTransition**

Bases: object


Collection of animation functions to be used with the Animation object. Easing Functions ported to Kivy from the Clutter Project <https://developer.gnome.org/clutter/stable/ClutterAlpha.html>

The *progress* parameter in each animation function is in the range 0-1.


**static in\_back(progress)****static in\_bounce(progress)****static in\_circ(progress)**




**static in\_cubic(progress)**




**static in\_elastic(progress)**




**static in\_expo(progress)**



**static in\_out\_back(progress)**




**static\_in\_out\_bounce**(*progress*)



**static\_in\_out\_circ**(*progress*)




**static\_in\_out\_cubic**(*progress*)




**static\_in\_out\_elastic**(*progress*)




**static\_in\_out\_expo**(*progress*)




**static\_in\_out\_quad**(*progress*)



**static\_in\_out\_quart**(*progress*)




**static\_in\_out\_quint**(*progress*)




**static in\_out\_sine(*progress*)**




**static in\_quad(*progress*)**




**static in\_quart(*progress*)**




**static in\_quint(*progress*)**




**static in\_sine(progress)**




**static linear(progress)**




**static out\_back(progress)**




**static out\_bounce(progress)**



**static\_out\_circ**(*progress*)




**static\_out\_cubic**(*progress*)




**static\_out\_elastic**(*progress*)




**static\_out\_expo**(*progress*)




**static out\_quad**(*progress*)




**static out\_quart**(*progress*)



**static out\_quint**(*progress*)



**static out\_sine**(*progress*)



## 21.2 Application

The `App` class is the base for creating Kivy applications. Think of it as your main entry point into the Kivy run loop. In most cases, you subclass this class and make your own app. You create an instance of your specific app class and then, when you are ready to start the application's life cycle, you call your instance's `App.run()` method.

### 21.2.1 Creating an Application

Method using `build()` override

To initialize your app with a widget tree, override the `build()` method in your app class and return the widget tree you constructed.

Here's an example of a very simple application that just shows a button:

```
...
Application example using build() + return
=====

An application can be built if you return a widget on build(), or if you set
self.root.
...

import kivy
kivy.require('1.0.7')

from kivy.app import App
from kivy.uix.button import Button


class TestApp(App):

    def build(self):
        # return a Button() as a root widget
        return Button(text='hello world')


if __name__ == '__main__':
    TestApp().run()
```

The file is also available in the examples folder at `kivy/examples/application/app_with_build.py`.

Here, no widget tree was constructed (or if you will, a tree with only the root node).

## Method using kv file

You can also use the [Kivy Language](#) for creating applications. The .kv can contain rules and root widget definitions at the same time. Here is the same example as the Button one in a kv file.

Contents of ‘test.kv’:

```
#:kivy 1.0

Button:
    text: 'Hello from test.kv'
```

Contents of ‘main.py’:

```
...
Application built from a .kv file
=====

This shows how to implicitly use a .kv file for your application. You
should see a full screen button labelled "Hello from test.kv".

After Kivy instantiates a subclass of App, it implicitly searches for a .kv
file. The file test.kv is selected because the name of the subclass of App is
TestApp, which implies that kivy should try to load "test.kv". That file
contains a root Widget.
...

import kivy
kivy.require('1.0.7')

from kivy.app import App

class TestApp(App):
    pass

if __name__ == '__main__':
    TestApp().run()
```

See `kivy/examples/application/app_with_kv.py`.

The relationship between main.py and test.kv is explained in [App.load\\_kv\(\)](#).

## 21.2.2 Application configuration

Use the configuration file

Your application might need its own configuration file. The [App](#) class handles ‘ini’ files automatically if you add the section key-value pair to the [App.build\\_config\(\)](#) method using the `config` parameter (an instance of [ConfigParser](#)):

```
class TestApp(App):
    def build_config(self, config):
        config.setdefault('section1', {
            'key1': 'value1',
            'key2': '42'
        })
```

As soon as you add one section to the config, a file is created on the disk (see [get\\_application\\_config](#) for its location) and named based your class name. "TestApp" will give a config file named "test.ini" with the content:

```
[section1]
key1 = value1
key2 = 42
```

The "test.ini" will be automatically loaded at runtime and you can access the configuration in your [App.build\(\)](#) method:

```
class TestApp(App):
    def build_config(self, config):
        config.setdefault('section1', {
            'key1': 'value1',
            'key2': '42'
        })

    def build(self):
        config = self.config
        return Label(text='key1 is %s and key2 is %d' % (
            config.get('section1', 'key1'),
            config.getint('section1', 'key2')))
```

## Create a settings panel

Your application can have a settings panel to let your user configure some of your config tokens. Here is an example done in the KinectViewer example (available in the examples directory):



You can add your own panels of settings by extending the [App.build\\_settings\(\)](#) method. Check the [Settings](#) about how to create a panel, because you need a JSON file / data first.

Let's take as an example the previous snippet of TestApp with custom config. We could create a JSON like this:

```
[{"type": "title",
  "title": "Test application"},

{"type": "options",
  "title": "My first key",
  "desc": "Description of my first key",
  "section": "section1",
```

```

    "key": "key1",
    "options": ["value1", "value2", "another value"] },

    { "type": "numeric",
      "title": "My second key",
      "desc": "Description of my second key",
      "section": "section1",
      "key": "key2" }
]

```

Then, we can create a panel using this JSON to automatically create all the options and link them to our `App.config` ConfigParser instance:

```

class TestApp(App):
    # ...
    def build_settings(self, settings):
        jsondata = """... put the json data here ..."""
        settings.add_json_panel('Test application',
                               self.config, data=jsondata)

```

That's all! Now you can press F1 (default keystroke) to toggle the settings panel or press the "settings" key on your android device. You can manually call `App.open_settings()` and `App.close_settings()` if you want to handle this manually. Every change in the panel is automatically saved in the config file.

You can also use `App.build_settings()` to modify properties of the settings panel. For instance, the default panel has a sidebar for switching between json panels whose width defaults to 200dp. If you'd prefer this to be narrower, you could add:

```
settings.interface.menu.width = dp(100)
```

to your `build_settings()` method.

You might want to know when a config value has been changed by the user in order to adapt or reload your UI. You can then overload the `on_config_change()` method:

```

class TestApp(App):
    # ...
    def on_config_change(self, config, section, key, value):
        if config is self.config:
            token = (section, key)
            if token == ('section1', 'key1'):
                print('Our key1 has been changed to', value)
            elif token == ('section1', 'key2'):
                print('Our key2 has been changed to', value)

```

The Kivy configuration panel is added by default to the settings instance. If you don't want this panel, you can declare your Application as follows:

```

class TestApp(App):
    use_kivy_settings = False
    # ...

```

This only removes the Kivy panel but does not stop the settings instance from appearing. If you want to prevent the settings instance from appearing altogether, you can do this:

```

class TestApp(App):
    def open_settings(self, *largs):
        pass

```

New in version 1.0.7.

### 21.2.3 Profiling with on\_start and on\_stop

It is often useful to profile python code in order to discover locations to optimise. The standard library profilers (<http://docs.python.org/2/library/profile.html>) provides multiple options for profiling code. For profiling the entire program, the natural approaches of using `profile` as a module or `profile's run` method does not work with Kivy. It is however, possible to use `App.on_start()` and `App.on_stop()` methods:

```
import cProfile

class MyApp(App):
    def on_start(self):
        self.profile = cProfile.Profile()
        self.profile.enable()

    def on_stop(self):
        self.profile.disable()
        self.profile.dump_stats('myapp.profile')
```

This will create a file called `myapp.profile` when you exit your app.

### 21.2.4 Customising layout

You can choose different settings widget layouts by setting `App.settings_cls`. By default, this is a `Settings` class which provides the pictured sidebar layout, but you could set it to any of the other layouts provided in `kivy.uix.settings` or create your own. See the module documentation for `kivy.uix.settings` for more information.

You can customise how the settings panel is displayed by overriding `App.display_settings()` which is called before displaying the settings panel on the screen. By default, it simply draws the panel on top of the window, but you could modify it to (for instance) show the settings in a `Popup` or add it to your app's `ScreenManager` if you are using one. If you do so, you should also modify `App.close_settings()` to exit the panel appropriately. For instance, to have the settings panel appear in a popup you can do:

```
def display_settings(self, settings):
    try:
        p = self.settings_popup
    except AttributeError:
        self.settings_popup = Popup(content=settings,
                                     title='Settings',
                                     size_hint=(0.8, 0.8))
    p = self.settings_popup
    if p.content is not settings:
        p.content = settings
    p.open()

def close_settings(self, *args):
    try:
        p = self.settings_popup
        p.dismiss()
    except AttributeError:
        pass # Settings popup doesn't exist
```

Finally, if you want to replace the current settings panel widget, you can remove the internal references to it using `App.destroy_settings()`. If you have modified `App.display_settings()`, you should be careful to detect if the settings panel has been replaced.

### 21.2.5 Pause mode

New in version 1.1.0.

On tablets and phones, the user can switch at any moment to another application. By default, your application will close and the `App.on_stop()` event will be fired.

If you support Pause mode, when switching to another application, your application will wait indefinitely until the user switches back to your application. There is an issue with OpenGL on Android devices: it is not guaranteed that the OpenGL ES Context will be restored when your app resumes. The mechanism for restoring all the OpenGL data is not yet implemented in Kivy.

The currently implemented Pause mechanism is:

1. Kivy checks every frame if Pause mode is activated by the Operating System due to the user switching to another application, a phone shutdown or any other reason.
2. `App.on_pause()` is called:
3. If False is returned, then `App.on_stop()` is called.
4. If True is returned (default case), the application will sleep until the OS resumes our App.
5. When the app is resumed, `App.on_resume()` is called.
6. If our app memory has been reclaimed by the OS, then nothing will be called.

Here is a simple example of how `on_pause()` should be used:

```
class TestApp(App):  
  
    def on_pause(self):  
        # Here you can save data if needed  
        return True  
  
    def on_resume(self):  
        # Here you can check if any data needs replacing (usually nothing)  
        pass
```

**Warning:** Both `on_pause` and `on_stop` must save important data because after `on_pause` is called, `on_resume` may not be called at all.

```
class kivy.app.App(**kwargs)  
Bases: kivy.event.EventDispatcher
```

Application class, see module documentation for more information.

#### Events

`on_start`: Fired when the application is being started (before the `runTouchApp()` call).

`on_stop`: Fired when the application stops.

`on_pause`: Fired when the application is paused by the OS.

***on\_resume***: Fired when the application is resumed from pause by the OS. Beware: you have no guarantee that this event will be fired after the *on\_pause* event has been called.

Changed in version 1.7.0: Parameter *kv\_file* added.

Changed in version 1.8.0: Parameters *kv\_file* and *kv\_directory* are now properties of App.

### **build()**

Initializes the application; it will be called only once. If this method returns a widget (tree), it will be used as the root widget and added to the window.

**Returns** None or a root *Widget* instance if no self.root exists.

### **build\_config(config)**

New in version 1.0.7.

This method is called before the application is initialized to construct your *ConfigParser* object. This is where you can put any default section / key / value for your config. If anything is set, the configuration will be automatically saved in the file returned by *get\_application\_config()*.

#### Parameters

*config*: *ConfigParser* Use this to add default section / key / value items

### **build\_settings(settings)**

New in version 1.0.7.

This method is called when the user (or you) want to show the application settings. It is called once when the settings panel is first opened, after which the panel is cached. It may be called again if the cached settings panel is removed by *destroy\_settings()*.

You can use this method to add settings panels and to customise the settings widget e.g. by changing the sidebar width. See the module documentation for full details.

#### Parameters

*settings*: *Settings* Settings instance for adding panels

### **close\_settings(\*args)**

Close the previously opened settings panel.

**Returns** True if the settings has been closed.

### **config = None**

Returns an instance of the *ConfigParser* for the application configuration. You can use this to query some config tokens in the *build()* method.

### **create\_settings()**

Create the settings panel. This method will normally be called only one time per application life-time and the result is cached internally, but it may be called again if the cached panel is removed by *destroy\_settings()*.

By default, it will build a settings panel according to *settings\_cls*, call *build\_settings()*, add a Kivy panel if *use\_kivy\_settings* is True, and bind to on\_close/on\_config\_change.

If you want to plug your own way of doing settings, without the Kivy panel or close/config change events, this is the method you want to overload.

New in version 1.8.0.

### **destroy\_settings()**

New in version 1.8.0.

Dereferences the current settings panel if one exists. This means that when `App.open_settings()` is next run, a new panel will be created and displayed. It doesn't affect any of the contents of the panel, but lets you (for instance) refresh the settings panel layout if you have changed the settings widget in response to a screen size change.

If you have modified `open_settings()` or `display_settings()`, you should be careful to correctly detect if the previous settings widget has been destroyed.

### **directory**

New in version 1.0.7.

Return the directory where the application lives.

### **display\_settings(*settings*)**

New in version 1.8.0.

Display the settings panel. By default, the panel is drawn directly on top of the window. You can define other behaviour by overriding this method, such as adding it to a ScreenManager or Popup.

You should return True if the display is successful, otherwise False.

#### **Parameters**

`settings: Settings` You can modify this object in order to modify the settings display.

### **get\_application\_config(*defaultpath*='%(appdir)s/%(appname)s.ini')**

New in version 1.0.7.

Changed in version 1.4.0: Customized the default path for iOS and Android platforms. Added a defaultpath parameter for desktop OS's (not applicable to iOS and Android.)

Return the filename of your application configuration. Depending on the platform, the application file will be stored in different locations:

- on iOS: <appdir>/Documents/.<appname>.ini
- on Android: /sdcard/.<appname>.ini
- otherwise: <appdir>/<appname>.ini

When you are distributing your application on Desktops, please note that if the application is meant to be installed system-wide, the user might not have write-access to the application directory. If you want to store user settings, you should overload this method and change the default behavior to save the configuration file in the user directory.

```
class TestApp(App):
    def get_application_config(self):
        return super(TestApp, self).get_application_config(
            '~/.%(appname)s.ini')
```

Some notes:

- The tilda ‘~’ will be expanded to the user directory.
- %(appdir)s will be replaced with the application `directory`
- %(appname)s will be replaced with the application `name`

### **get\_application\_icon()**

Return the icon of the application.

### **get\_application\_name()**

Return the name of the application.

**static get\_running\_app()**

Return the currently running application instance.

New in version 1.1.0.

**icon**

Icon of your application. The icon can be located in the same directory as your main file. You can set this as follows:

```
class MyApp(App):
    def build(self):
        self.icon = 'myicon.png'
```

New in version 1.0.5.

Changed in version 1.8.0: *icon* is now a *StringProperty*. Don't set the icon in the class as previously stated in the documentation.

---

**Note:** For Kivy prior to 1.8.0, you need to set this as follows:

```
class MyApp(App):
    icon = 'customicon.png'
```

Recommended 256x256 or 1024x1024? for GNU/Linux and Mac OSX 32x32 for Windows7 or less. <= 256x256 for windows 8 256x256 does work (on Windows 8 at least), but is scaled down and doesn't look as good as a 32x32 icon.

---

**kv\_directory**

Path of the directory where application kv is stored, defaults to None

New in version 1.8.0.

If a kv\_directory is set, it will be used to get the initial kv file. By default, the file is assumed to be in the same directory as the current App definition file.

**kv\_file**

Filename of the Kv file to load, defaults to None.

New in version 1.8.0.

If a kv\_file is set, it will be loaded when the application starts. The loading of the "default" kv file will be prevented.

**load\_config()**

(internal) This function is used for returning a ConfigParser with the application configuration. It's doing 3 things:

1. Creating an instance of a ConfigParser
2. Loading the default configuration by calling *build\_config()*, then
3. If it exists, it loads the application configuration file, otherwise it creates one.

**Returns** *ConfigParser* instance

**load\_kv(filename=None)**

This method is invoked the first time the app is being run if no widget tree has been constructed before for this app. This method then looks for a matching kv file in the same directory as the file that contains the application class.

For example, say you have a file named main.py that contains:

```
class ShowcaseApp(App):  
    pass
```

This method will search for a file named *showcase.kv* in the directory that contains main.py. The name of the kv file has to be the lowercase name of the class, without the 'App' postfix at the end if it exists.

You can define rules and a root widget in your kv file:

```
<ClassName>: # this is a rule  
...  
  
ClassName: # this is a root widget  
...
```

There must be only one root widget. See the [Kivy Language](#) documentation for more information on how to create kv files. If your kv file contains a root widget, it will be used as self.root, the root widget for the application.

---

**Note:** This function is called from `run()`, therefore, any widget whose styling is defined in this kv file and is created before `run()` is called (e.g. in `__init__`), won't have its styling applied. Note that `build()` is called after `load_kv` has been called.

---

#### **name**

New in version 1.0.7.

Return the name of the application based on the class name.

#### **on\_config\_change(config, section, key, value)**

Event handler fired when a configuration token has been changed by the settings page.

Changed in version 1.10.1: Added corresponding `on_config_change` event.

#### **on\_pause()**

Event handler called when Pause mode is requested. You should return True if your app can go into Pause mode, otherwise return False and your application will be stopped.

You cannot control when the application is going to go into this mode. It's determined by the Operating System and mostly used for mobile devices (android/ios) and for resizing.

The default return value is True.

New in version 1.1.0.

Changed in version 1.10.0: The default return value is now True.

#### **on\_resume()**

Event handler called when your application is resuming from the Pause mode.

New in version 1.1.0.

**Warning:** When resuming, the OpenGL Context might have been damaged / freed. This is where you can reconstruct some of your OpenGL state e.g. FBO content.

#### **on\_start()**

Event handler for the `on_start` event which is fired after initialization (after `build()` has been called) but before the application has started running.

### **on\_stop()**

Event handler for the *on\_stop* event which is fired when the application has finished running (i.e. the window is about to be closed).

### **open\_settings(\*args)**

Open the application settings panel. It will be created the very first time, or recreated if the previously cached panel has been removed by *destroy\_settings()*. The settings panel will be displayed with the *display\_settings()* method, which by default adds the settings panel to the Window attached to your application. You should override that method if you want to display the settings panel differently.

**Returns** True if the settings has been opened.

### **options = None**

Options passed to the *\_\_init\_\_* of the App

### **root = None**

The *root* widget returned by the *build()* method or by the *load\_kv()* method if the kv file contains a root widget.

### **root\_window**

New in version 1.9.0.

Returns the root window instance used by *run()*.

### **run()**

Launches the app in standalone mode.

### **settings\_cls**

New in version 1.8.0.

The class used to construct the settings panel and the instance passed to *build\_config()*. You should use either *Settings* or one of the provided subclasses with different layouts (*SettingsWithSidebar*, *SettingsWithSpinner*, *SettingsWithTabbedPanel*, *SettingsWithNoMenu*). You can also create your own Settings subclass. See the documentation of *Settings* for more information.

*settings\_cls* is an *ObjectProperty* and defaults to *SettingsWithSpinner* which displays settings panels with a spinner to switch between them. If you set a string, the *Factory* will be used to resolve the class.

### **stop(\*args)**

Stop the application.

If you use this method, the whole application will stop by issuing a call to *stopTouchApp()*.

### **title**

Title of your application. You can set this as follows:

```
class MyApp(App):
    def build(self):
        self.title = 'Hello world'
```

New in version 1.0.5.

Changed in version 1.8.0: *title* is now a *StringProperty*. Don't set the title in the class as previously stated in the documentation.

---

**Note:** For Kivy < 1.8.0, you can set this as follows:

```
class MyApp(App):
    title = 'Custom title'
```

If you want to dynamically change the title, you can do:

```
from kivy.base import EventLoop
EventLoop.window.title = 'New title'
```

### **use\_kivy\_settings = True**

New in version 1.0.7.

If True, the application settings will also include the Kivy settings. If you don't want the user to change any kivy settings from your settings UI, change this to False.

### **user\_data\_dir**

New in version 1.7.0.

Returns the path to the directory in the users file system which the application can use to store additional data.

Different platforms have different conventions with regards to where the user can store data such as preferences, saved games and settings. This function implements these conventions. The <app\_name> directory is created when the property is called, unless it already exists.

On iOS, *~/Documents/<app\_name>* is returned (which is inside the app's sandbox).

On Android, */sdcard/<app\_name>* is returned.

On Windows, *%APPDATA%/<app\_name>* is returned.

On OS X, *~/Library/Application Support/<app\_name>* is returned.

On Linux, *\$XDG\_CONFIG\_HOME/<app\_name>* is returned.

## 21.3 Asynchronous data loader

This is the Asynchronous Loader. You can use it to load an image and use it, even if data are not yet available. You must specify a default loading image when using the loader:

```
from kivy.loader import Loader
image = Loader.image('mysprite.png')
```

You can also load an image from a url:

```
image = Loader.image('http://mysite.com/test.png')
```

If you want to change the default loading image, you can do:

```
Loader.loading_image = Image('another_loading.png')
```

### 21.3.1 Tweaking the asynchronous loader

New in version 1.6.0.

You can tweak the loader to provide a better user experience or more performance, depending of the images you are going to load. Take a look at the parameters:

- `Loader.num_workers` - define the number of threads to start for loading images.
- `Loader.max_upload_per_frame` - define the maximum image uploads in GPU to do per frame.

## **class kivy.loader.LoaderBase**

Bases: object

Common base for the Loader and specific implementations. By default, the Loader will be the best available loader implementation.

The `_update()` function is called every 1 / 25.s or each frame if we have less than 25 FPS.

### **error\_image**

Image used for error. You can change it by doing:

```
Loader.error_image = 'error.png'
```

Changed in version 1.6.0: Not readonly anymore.

### **image(filename, load\_callback=None, post\_callback=None, \*\*kwargs)**

Load a image using the Loader. A ProxyImage is returned with a loading image. You can use it as follows:

```
from kivy.app import App
from kivy.uix.image import Image
from kivy.loader import Loader

class TestApp(App):
    def _image_loaded(self, proxyImage):
        if proxyImage.image.texture:
            self.image.texture = proxyImage.image.texture

    def build(self):
        proxyImage = Loader.image("myPic.jpg")
        proxyImage.bind(on_load=self._image_loaded)
        self.image = Image()
        return self.image

TestApp().run()
```

In order to cancel all background loading, call `Loader.stop()`.

### **loading\_image**

Image used for loading. You can change it by doing:

```
Loader.loading_image = 'loading.png'
```

Changed in version 1.6.0: Not readonly anymore.

### **max\_upload\_per\_frame**

The number of images to upload per frame. By default, we'll upload only 2 images to the GPU per frame. If you are uploading many small images, you can easily increase this parameter to 10 or more. If you are loading multiple full HD images, the upload time may have consequences and block the application. If you want a smooth experience, use the default.

As a matter of fact, a Full-HD RGB image will take ~6MB in memory, so it may take time. If you have activated `mipmap=True` too, then the GPU must calculate the mipmap of these big images too, in real time. Then it may be best to reduce the `max_upload_per_frame` to 1 or 2. If you want to get rid of that (or reduce it a lot), take a look at the DDS format.

New in version 1.6.0.

### **num\_workers**

Number of workers to use while loading (used only if the loader implementation supports it). This setting impacts the loader only on initialization. Once the loader is started, the setting has no impact:

```
from kivy.loader import Loader  
Loader.num_workers = 4
```

The default value is 2 for giving a smooth user experience. You could increase the number of workers, then all the images will be loaded faster, but the user will not be able to use the application while loading. Prior to 1.6.0, the default number was 20, and loading many full-hd images was completely blocking the application.

New in version 1.6.0.

### pause()

Pause the loader, can be useful during interactions.

New in version 1.6.0.

### resume()

Resume the loader, after a [pause\(\)](#).

New in version 1.6.0.

### run(\*largs)

Main loop for the loader.

### start()

Start the loader thread/process.

### stop()

Stop the loader thread/process.

## class kivy.loader.ProxyImage(arg, \*\*kwargs)

Bases: [kivy.core.image.Image](#)

Image returned by the Loader.image() function.

### Properties

**loaded: bool, defaults to False** This value may be True if the image is already cached.

### Events

**on\_load** Fired when the image is loaded or changed.

**on\_error** Fired when the image cannot be loaded. *error*: Exception data that occurred

## 21.4 Atlas

New in version 1.1.0.

Atlas manages texture atlases: packing multiple textures into one. With it, you reduce the number of images loaded and speedup the application loading. This module contains both the `Atlas` class and command line processing for creating an atlas from a set of individual PNG files. The command line section requires the Pillow library, or the defunct Python Imaging Library (PIL), to be installed.

### An Atlas is composed of 2 or more files:

- a json file (.atlas) that contains the image file names and texture locations of the atlas.
- one or multiple image files containing textures referenced by the .atlas file.

#### 21.4.1 Definition of .atlas files

A file with `<basename>.atlas` is a json file formatted like this:

```
{  
    "<basename>-<index>.png": {  
        "id1": [ <x>, <y>, <width>, <height> ],  
        "id2": [ <x>, <y>, <width>, <height> ],  
        # ...  
    },  
    # ...  
}
```

Example from the Kivy `data/images/defaulttheme.atlas`:

```
{  
    "defaulttheme-0.png": {  
        "progressbar_background": [431, 224, 59, 24],  
        "image-missing": [253, 344, 48, 48],  
        "filechooser_selected": [1, 207, 118, 118],  
        "bubble_btn": [83, 174, 32, 32],  
        # ... and more ...  
    }  
}
```

In this example, “`defaulttheme-0.png`” is a large image, with the pixels in the rectangle from  $(431, 224)$  to  $(431 + 59, 224 + 24)$  usable as `atlas://data/images/defaulttheme/progressbar_background` in any image parameter.

#### 21.4.2 How to create an Atlas

**Warning:** The atlas creation requires the Pillow library (or the defunct Imaging/PIL library). This requirement will be removed in the future when the Kivy core Image is able to support loading, blitting, and saving operations.

You can directly use this module to create atlas files with this command:

```
$ python -m kivy.atlas <basename> <size> <list of images...>
```

Let’s say you have a list of images that you want to put into an Atlas. The directory is named `images` with lots of 64x64 png files inside:

```
$ ls  
images  
$ cd images  
$ ls  
bubble.png bubble-red.png button.png button-down.png
```

You can combine all the png’s into one and generate the atlas file with:

```
$ python -m kivy.atlas myatlas 256x256 *.png  
Atlas created at myatlas.atlas  
1 image has been created  
$ ls  
bubble.png bubble-red.png button.png button-down.png myatlas.atlas  
myatlas-0.png
```

As you can see, we get 2 new files: `myatlas.atlas` and `myatlas-0.png`. `myatlas-0.png` is a new 256x256 .png composed of all your images.

---

**Note:** When using this script, the ids referenced in the atlas are the base names of the images without the extension. So, if you are going to name a file `../images/button.png`, the id for this image will be `button`.

If you need path information included, you should include `use_path` as follows:

```
$ python -m kivy.atlas use_path myatlas 256 *.png
```

In which case the id for `../images/button.png` will be `images_button`

---

### 21.4.3 How to use an Atlas

Usually, you would specify the images by supplying the path:

```
a = Button(background_normal='images/button.png',
            background_down='images/button_down.png')
```

In our previous example, we have created the atlas containing both images and put them in `images/myatlas.atlas`. You can use url notation to reference them:

```
a = Button(background_normal='atlas://images/myatlas/button',
            background_down='atlas://images/myatlas/button_down')
```

In other words, the path to the images is replaced by:

```
atlas://path/to/myatlas/id
# will search for the ``path/to/myatlas.atlas`` and get the image ``id``
```

---

**Note:** In the atlas url, there is no need to add the `.atlas` extension. It will be automatically append to the filename.

---

### 21.4.4 Manual usage of the Atlas

```
>>> from kivy.atlas import Atlas
>>> atlas = Atlas('path/to/myatlas.atlas')
>>> print(atlas.textures.keys())
['bubble', 'bubble-red', 'button', 'button-down']
>>> print(atlas['button'])
<kivy.graphics.texture.TextureRegion object at 0x2404d10>
```

```
class kivy.atlas.Atlas(filename)
    Bases: kivy.event.EventDispatcher
```

Manage texture atlas. See module documentation for more information.

```
static create(outname, filenames, size, padding=2, use_path=False)
```

This method can be used to create an atlas manually from a set of images.

#### Parameters

`outname: str` Basename to use for `.atlas` creation and `-<idx>.png` associated images.

**filenames: list** List of filenames to put in the atlas.

**size: int or list (width, height)** Size of the atlas image.

**padding: int, defaults to 2** Padding to put around each image.

Be careful. If you're using a padding < 2, you might have issues with the borders of the images. Because of the OpenGL linearization, it might use the pixels of the adjacent image.

If you're using a padding >= 2, we'll automatically generate a "border" of 1px around your image. If you look at the result, don't be scared if the image inside is not exactly the same as yours :).

**use\_path: bool, defaults to False** If True, the relative path of the source png file names will be included in the atlas ids rather than just in the file names. Leading dots and slashes will be excluded and all other slashes in the path will be replaced with underscores. For example, if *use\_path* is False (the default) and the file name is `../data/tiles/green_grass.png`, the id will be `green_grass`. If *use\_path* is True, it will be `data_tiles_green_grass`.

Changed in version 1.8.0: Parameter *use\_path* added

### filename

Filename of the current Atlas.

*filename* is an *AliasProperty* and defaults to None.

### original\_textures

List of original atlas textures (which contain the *textures*).

*original\_textures* is a *ListProperty* and defaults to [].

New in version 1.9.1.

### textures

List of available textures within the atlas.

*textures* is a *DictProperty* and defaults to {}.

## 21.5 Cache manager

The cache manager can be used to store python objects attached to a unique key. The cache can be controlled in two ways: with a object limit or a timeout.

For example, we can create a new cache with a limit of 10 objects and a timeout of 5 seconds:

```
# register a new Cache
Cache.register('mycache', limit=10, timeout=5)

# create an object + id
key = 'objectid'
instance = Label(text=text)
Cache.append('mycache', key, instance)

# retrieve the cached object
instance = Cache.get('mycache', key)
```

If the instance is NULL, the cache may have trashed it because you've not used the label for 5 seconds and you've reach the limit.

### class kivy.cache.Cache

Bases: object

See module documentation for more information.

**static append**(*category*, *key*, *obj*, *timeout=None*)

Add a new object to the cache.

**Parameters**

*category*: str Identifier of the category.

*key*: str Unique identifier of the object to store.

*obj*: object Object to store in cache.

*timeout*: double (optional) Time after which to delete the object if it has not been used. If None, no timeout is applied.

**static get**(*category*, *key*, *default=None*)

Get a object from the cache.

**Parameters**

*category*: str Identifier of the category.

*key*: str Unique identifier of the object in the store.

*default*: anything, defaults to None Default value to be returned if the key is not found.

**static get\_lastaccess**(*category*, *key*, *default=None*)

Get the objects last access time in the cache.

**Parameters**

*category*: str Identifier of the category.

*key*: str Unique identifier of the object in the store.

*default*: anything, defaults to None Default value to be returned if the key is not found.

**static get\_timestamp**(*category*, *key*, *default=None*)

Get the object timestamp in the cache.

**Parameters**

*category*: str Identifier of the category.

*key*: str Unique identifier of the object in the store.

*default*: anything, defaults to None Default value to be returned if the key is not found.

**static print\_usage()**

Print the cache usage to the console.

**static register**(*category*, *limit=None*, *timeout=None*)

Register a new category in the cache with the specified limit.

**Parameters**

*category*: str Identifier of the category.

*limit*: int (optional) Maximum number of objects allowed in the cache. If None, no limit is applied.

*timeout*: double (optional) Time after which to delete the object if it has not been used. If None, no timeout is applied.

**static remove**(*category*, *key=None*)

Purge the cache.

## Parameters

*category: str* Identifier of the category.

*key: str (optional)* Unique identifier of the object in the store. If this argument is not supplied, the entire category will be purged.

## 21.6 Clock object

The **Clock** object allows you to schedule a function call in the future; once or repeatedly at specified intervals. You can get the time elapsed between the scheduling and the calling of the callback via the *dt* argument:

```
# dt means delta-time
def my_callback(dt):
    pass

# call my_callback every 0.5 seconds
Clock.schedule_interval(my_callback, 0.5)

# call my_callback in 5 seconds
Clock.schedule_once(my_callback, 5)

# call my_callback as soon as possible (usually next frame.)
Clock.schedule_once(my_callback)
```

---

**Note:** If the callback returns False, the schedule will be canceled and won't repeat.

---

If you want to schedule a function to call with default arguments, you can use the `functools.partial` python module:

```
from functools import partial

def my_callback(value, key, *largs):
    pass

Clock.schedule_interval(partial(my_callback, 'my value', 'my key'), 0.5)
```

Conversely, if you want to schedule a function that doesn't accept the *dt* argument, you can use a `lambda` expression to write a short function that does accept *dt*. For Example:

```
def no_args_func():
    print("I accept no arguments, so don't schedule me in the clock")

Clock.schedule_once(lambda dt: no_args_func(), 0.5)
```

---

**Note:** You cannot unschedule an anonymous function unless you keep a reference to it. It's better to add `*args` to your function definition so that it can be called with an arbitrary number of parameters.

---

**Important:** The callback is weak-referenced: you are responsible for keeping a reference to your original object/callback. If you don't keep a reference, the ClockBase will never execute your callback. For example:

```

class Foo(object):
    def start(self):
        Clock.schedule_interval(self.callback, 0.5)

    def callback(self, dt):
        print('In callback')

# A Foo object is created and the method start is called.
# Because no reference is kept to the instance returned from Foo(),
# the object will be collected by the Python Garbage Collector and
# your callback will be never called.
Foo().start()

# So you should do the following and keep a reference to the instance
# of foo until you don't need it anymore!
foo = Foo()
foo.start()

```

### 21.6.1 Schedule before frame

New in version 1.0.5.

Sometimes you need to schedule a callback BEFORE the next frame. Starting from 1.0.5, you can use a timeout of -1:

```

Clock.schedule_once(my_callback, 0) # call after the next frame
Clock.schedule_once(my_callback, -1) # call before the next frame

```

The Clock will execute all the callbacks with a timeout of -1 before the next frame even if you add a new callback with -1 from a running callback. However, **Clock** has an iteration limit for these callbacks: it defaults to 10.

If you schedule a callback that schedules a callback that schedules a ... etc more than 10 times, it will leave the loop and send a warning to the console, then continue after the next frame. This is implemented to prevent bugs from hanging or crashing the application.

If you need to increase the limit, set the `max_iteration` property:

```

from kivy.clock import Clock
Clock.max_iteration = 20

```

### 21.6.2 Triggered Events

New in version 1.0.5.

A triggered event is a way to defer a callback. It functions exactly like `schedule_once()` and `schedule_interval()` except that it doesn't immediately schedule the callback. Instead, one schedules the callback using the **ClockEvent** returned by it. This ensures that you can call the event multiple times but it won't be scheduled more than once. This is not the case with `Clock.schedule_once()`:

```

# will run the callback twice before the next frame
Clock.schedule_once(my_callback)
Clock.schedule_once(my_callback)

# will run the callback once before the next frame
event = Clock.create_trigger(my_callback)

```

```

event()
event()

# will also run the callback only once before the next frame
event = Clock.schedule_once(my_callback) # now it's already scheduled
event() # won't be scheduled again
event()

```

In addition, it is more convenient to create and bind to the triggered event than using `Clock.schedule_once()` in a function:

```

from kivy.clock import Clock
from kivy.uix.widget import Widget

class Sample(Widget):
    def __init__(self, **kwargs):
        self._trigger = Clock.create_trigger(self.cb)
        super(Sample, self).__init__(**kwargs)
        self.bind(x=self._trigger, y=self._trigger)

    def cb(self, *largs):
        pass

```

Even if x and y changes within one frame, the callback is only run once.

`CyClockBase.create_trigger()` has a `timeout` parameter that behaves exactly like `CyClockBase.schedule_once()`.

Changed in version 1.10.0: `CyClockBase.create_trigger()` now has a `interval` parameter. If `False`, the default, it'll create an event similar to `CyClockBase.schedule_once()`. Otherwise it'll create an event similar to `CyClockBase.schedule_interval()`.

### 21.6.3 Unscheduling

An event scheduled with `CyClockBase.schedule_once()`, `CyClockBase.schedule_interval()`, or with `CyClockBase.create_trigger()` and then triggered can be unscheduled in multiple ways. E.g:

```

def my_callback(dt):
    pass

# call my_callback every 0.5 seconds
event = Clock.schedule_interval(my_callback, 0.5)

# call my_callback in 5 seconds
event2 = Clock.schedule_once(my_callback, 5)

event_trig = Clock.create_trigger(my_callback, 5)
event_trig()

# unschedule using cancel
event.cancel()

# unschedule using Clock.unschedule
Clock.unschedule(event2)

# unschedule using Clock.unschedule with the callback
# NOT RECOMMENDED
Clock.unschedule(my_callback)

```

The best way to unschedule a callback is with `ClockEvent.cancel()`. `CyClockBase.unschedule()` is mainly an alias for that for that function. However, if the original callback itself is passed to `CyClockBase.unschedule()`, it'll unschedule all instances of that callback (provided `all` is True, the default, other just the first match is removed).

Calling `CyClockBase.unschedule()` on the original callback is highly discouraged because it's significantly slower than when using the event.

#### 21.6.4 Threading and Callback Order

Beginning with 1.10.0, all the events scheduled for the same frame, e.g. all the events scheduled in the same frame with a `timeout` of 0, will be executed in the order they were scheduled.

Also, all the scheduling and canceling methods are fully thread safe and can be safely used from external threads.

As a consequence, calling `CyClockBase.unschedule()` with the original callback is now significantly slower and highly discouraged. Instead, the returned events should be used to cancel. As a tradeoff, all the other methods are now significantly faster than before.

#### 21.6.5 Advanced Clock Details

The following section goes into the internal kivy clock details as well as the various clock options. It is meant only for advanced users.

Fundamentally, the Kivy clock attempts to execute any scheduled callback rhythmically as determined by the specified fps (frame per second, see `maxfps` in [config](#)). That is, ideally, given e.g. a desired fps of 30, the clock will execute the callbacks at intervals of  $1 / 30$  seconds, or every 33.33 ms. All the callbacks in a frame are given the same timestamp, i.e. the `dt` passed to the callback are all the same and it's the difference in time between the start of this and the previous frame.

Because of inherent indeterminism, the frames do not actually occur exactly at intervals of the fps and `dt` may be under or over the desired fps. Also, once the timeout is "close enough" to the desired timeout, as determined internally, Kivy will execute the callback in the current frame even when the "actual time" has not elapsed the `timeout` amount.

Kivy offers now, since 1.10.0, multiple clocks with different behaviors.

##### Default Clock

The default clock (`default`) behaves as described above. When a callback with a timeout of zero or non-zero is scheduled, they are executed at the frame that is near the timeout, which is a function of the fps. So a timeout of zero would still result in a delay of one frame or about  $1 / \text{fps}$ , typically a bit less but sometimes more depending on the CPU usage of the other events scheduled for that frame.

In a test using a fps of 30, a callback with a timeout of 0, 0.001, and 0.05, resulted in a mean callback delay of 0.02487, 0.02488, and 0.05011 seconds, respectively. When tested with a fps of 600 the delay for 0.05 was similar, except the standard deviation was reduced resulting in overall better accuracy.

##### Interruptible Clock

The default clock suffers from the quantization problem, as frames occur only on intervals and any scheduled timeouts will not be able to occur during an interval. For example, with the timeout of 0.05, while the mean was 0.05011, its values ranged between 0.02548 - 0.07348 and a standard deviation of 0.002. Also, there's the minimum timeout of about 0.02487.

The interruptible clock (`interrupt`) will execute timeouts even during a frame. So a timeout of zero will execute as quickly as possible and similarly a non-zero timeout will be executed even during the interval.

This clock, and all the clocks described after this have an option, `ClockBaseInterruptBehavior.interrupt_next_only`. When True, any of the behavior new behavior will only apply to the callbacks with a timeout of zero. Non-zero timeouts will behave like in the default clock. E.g. for this clock when True, only zero timeouts will execute during the the interval.

In a test using a fps of 30, a callback with a timeout of 0, 0.001, and 0.05, resulted in a mean callback delay of 0.00013, 0.00013, and 0.04120 seconds, respectively when `ClockBaseInterruptBehavior.interrupt_next_only` was False. Also, compared to the default clock the standard deviation was reduced. When `ClockBaseInterruptBehavior.interrupt_next_only` was True, the values were 0.00010, 0.02414, and 0.05034, respectively.

### Free Clock

The interruptible clock may not be ideal for all cases because all the events are executed during the intervals and events are not executed anymore rhythmically as multiples of the fps. For example, there may not be any benefit for the graphics to update in a sub-interval, so the additional accuracy wastes CPU.

The Free clock (`free_all`) solves this by having `Clock.xxx_free` versions of all the Clock scheduling methods. By free, we mean the event is free from the fps because it's not fps limited. E.g. `CyClockBaseFree.create_trigger_free()` corresponds to `CyClockBase.create_trigger()`. Only when an event scheduled using the `Clock.xxx_free` methods is present will the clock interrupt and execute the events during the interval. So, if no `free` event is present the clock behaves like the `default` clock, otherwise it behaves like the `interrupt` clock.

In a test using a fps of 30, a callback with a timeout of 0s, 0.001s, and 0.05s, resulted in a mean callback delay of 0.00012s, 0.00017s, and 0.04121s seconds, respectively when it was a free event and 0.02403s, 0.02405s, and 0.04829s, respectively when it wasn't.

### Free Only Clock

The Free clock executes all events when a free event was scheduled. This results in normal events also being execute in the middle of the interval when a free event is scheduled. For example, above, when a free event was absent, a normal event with a 0.001s timeout was delayed for 0.02405s. However, if a free event happened to be also scheduled, the normal event was only delayed 0.00014s, which may be undesirable.

The Free only clock (`free_only`) solves it by only executing free events during the interval and normal events are always executed like with the default clock. For example, in the presence of a free event, a normal event with a timeout of 0.001s still had a delay of 0.02406. So this clock, treats free and normal events independently, with normal events always being fps limited, but never the free events.

### Summary

The kivy clock type to use can be set with the `kivy_clock` option the `config`. If KIVY\_CLOCK is present in the environment it overwrites the config selection. Its possible values are as follows:

- When `kivy_clock` is `default`, the normal clock, `ClockBase`, which limits callbacks to the maxfps quantization - is used.
- When `kivy_clock` is `interrupt`, a interruptible clock, `ClockBaseInterrupt`, which doesn't limit any callbacks to the maxfps - is used. Callbacks will be executed at any time.

- When `kivy_clock` is `free_all`, a interruptible clock, `ClockBaseFreeInterruptAll`, which doesn't limit any callbacks to the maxfps in the presence of free events, but in their absence it limits events to the fps quantization interval - is used.
- When `kivy_clock` is `free_only`, a interruptible clock, `ClockBaseFreeInterruptAll`, which treats free and normal events independently; normal events are fps limited while free events are not - is used.

### `kivy.clock.Clock = None`

The kivy Clock instance. See module documentation for details.

### `class kivy.clock.ClockEvent`

Bases: `object`

A class that describes a callback scheduled with kivy's `Clock`. This class is never created by the user; instead, kivy creates and returns an instance of this class when scheduling a callback.

An event can be triggered (scheduled) by calling it. If it's already scheduled, nothing will happen, otherwise it'll be scheduled. E.g.:

```
event = Clock.schedule_once(my_callback, .5)
event() # nothing will happen since it's already scheduled.
event.cancel() # cancel it
event() # now it's scheduled again.
```

#### `cancel()`

Cancels the callback if it was scheduled to be called. If not scheduled, nothing happens.

#### `clock`

The `CyClockBase` instance associated with the event.

#### `get_callback()`

Returns the callback associated with the event. Callbacks get stored with a indirect ref so that it doesn't keep objects alive. If the callback is dead, `None` is returned.

#### `is_triggered`

Returns whether the event is scheduled to have its callback executed by the kivy thread.

#### `loop`

Whether this event repeats at intervals of `timeout`.

#### `next`

The next `ClockEvent` in order they were scheduled.

#### `prev`

The previous `ClockEvent` in order they were scheduled.

#### `release()`

(internal method) Converts the callback into a indirect ref.

#### `tick()`

(internal method) Processes the event for the kivy thread.

#### `timeout`

The duration after scheduling when the callback should be executed.

### `class kivy.clock.FreeClockEvent`

Bases: `kivy._clock.ClockEvent`

The event returned by the `Clock.XXX_free` methods of `CyClockBaseFree`. It stores whether the event was scheduled as a free event.

#### `free`

Whether this event was scheduled as a free event.

**class kivy.clock.CyClockBase**

Bases: object

The base clock object with event support.

**clock\_resolution**

If the remaining time until the event timeout is less than *clock\_resolution*, the clock will execute the callback even if it hasn't exactly timed out.

If -1, the default, the resolution will be computed from config's maxfps. Otherwise, the provided value is used. Defaults to -1.

**create\_trigger()**

Create a Trigger event. Check module documentation for more information.

**Returns** A *ClockEvent* instance. To schedule the callback of this instance, you can call it.

New in version 1.0.5.

Changed in version 1.10.0: interval has been added. If True, it creates a event that is called every <timeout> seconds similar to *schedule\_interval()*. Defaults to False.

**get\_events()**

Returns the list of *ClockEvent* instances currently scheduled.

**get\_min\_timeout()**

Returns the remaining time since the start of the current frame for the event with the smallest timeout.

**get\_resolution()**

Returns the minimum resolution the clock has. It's a function of *clock\_resolution* and maxfps provided at the config.

**max\_iteration**

The maximum number of callback iterations at the end of the frame, before the next frame. If more iterations occur, a warning is issued.

**on\_schedule()**

Function that is called internally every time an event is triggered for this clock. It takes the event as a parameter.

**schedule\_interval()**

Schedule an event to be called every <timeout> seconds.

**Returns** A *ClockEvent* instance. As opposed to *create\_trigger()* which only creates the trigger event, this method also schedules it.

**schedule\_once()**

Schedule an event in <timeout> seconds. If <timeout> is unspecified or 0, the callback will be called after the next frame is rendered.

**Returns** A *ClockEvent* instance. As opposed to *create\_trigger()* which only creates the trigger event, this method also schedules it.

Changed in version 1.0.5: If the timeout is -1, the callback will be called before the next frame (*at tick\_draw()*).

**unschedule()**

Remove a previously scheduled event.

**Parameters**

*callback*: **ClockEvent** or a callable. If it's a *ClockEvent* instance, then the callback associated with this event will be canceled if it is scheduled.

If it's a callable, then the callable will be unscheduled if it was scheduled.

**Warning:** Passing the callback function rather than the returned `ClockEvent` will result in a significantly slower unscheduling.

**all: bool** If True and if `callback` is a callable, all instances of this callable will be unscheduled (i.e. if this callable was scheduled multiple times). Defaults to `True`.

Changed in version 1.9.0: The `all` parameter was added. Before, it behaved as if `all` was `True`.

**class kivy.clock.CyClockBaseFree**  
Bases: `kivy._clock.CyClockBase`

A clock class that supports scheduling free events in addition to normal events.

Each of the `create_trigger()`, `schedule_once()`, and `schedule_interval()` methods, which create a normal event, have a corresponding method for creating a free event.

**create\_trigger\_free()**

Similar to `create_trigger()`, but instead creates a free event.

**get\_min\_free\_timeout()**

Returns the remaining time since the start of the current frame for the `free` event with the smallest timeout.

**schedule\_interval\_free()**

Similar to `schedule_interval()`, but instead creates a free event.

**schedule\_once\_free()**

Similar to `schedule_once()`, but instead creates a free event.

**class kivy.clock.ClockBaseBehavior(\*\*kwargs)**  
Bases: `object`

The base of the kivy clock.

**MIN\_SLEEP = 0.005**

The minimum time to sleep. If the remaining time is less than this, the event loop will continue.

**frames**

Number of internal frames (not necessarily drawn) from the start of the clock.

New in version 1.8.0.

**frames\_displayed**

Number of displayed frames from the start of the clock.

**frametime**

Time spent between the last frame and the current frame (in seconds).

New in version 1.8.0.

**get\_boottime()**

Get the time in seconds from the application start.

**get\_fps()**

Get the current average FPS calculated by the clock.

**get\_rfps()**

Get the current “real” FPS calculated by the clock. This counter reflects the real framerate displayed on the screen.

In contrast to `get_fps()`, this function returns a counter of the number of frames, not the average of frames per second.

**get\_time()**

Get the last tick made by the clock.

**idle()**

(internal) waits here until the next frame.

**tick()**

Advance the clock to the next step. Must be called every frame. The default clock has a `tick()` function called by the core Kivy framework.

**tick\_draw()**

Tick the drawing counter.

**time = <functools.partial object>**

**usleep(microseconds)**

Sleeps for the number of microseconds.

**class kivy.clock.ClockBaseInterruptBehavior(interrupt\_next\_only=False, \*\*kwargs)**

Bases: *kivy.clock.ClockBaseBehavior*

A kivy clock which can be interrupted during a frame to execute events.

**class kivy.clock.ClockBaseInterruptFreeBehavior(\*\*kwargs)**

Bases: *kivy.clock.ClockBaseInterruptBehavior*

A base class for the clock that interrupts the sleep interval for free events.

**class kivy.clock.ClockBase(\*\*kwargs)**

Bases: *kivy.clock.ClockBaseBehavior*, *kivy.\_clock.CyClockBase*

The default kivy clock. See module for details.

**class kivy.clock.ClockBaseInterrupt(interrupt\_next\_only=False, \*\*kwargs)**

Bases: *kivy.clock.ClockBaseInterruptBehavior*, *kivy.\_clock.CyClockBase*

The interrupt kivy clock. See module for details.

**class kivy.clock.ClockBaseFreeInterruptAll(\*\*kwargs)**

Bases: *kivy.clock.ClockBaseInterruptFreeBehavior*, *kivy.\_clock.CyClockBaseFree*

The free\_all kivy clock. See module for details.

**class kivy.clock.ClockBaseFreeInterruptOnly(\*\*kwargs)**

Bases: *kivy.clock.ClockBaseInterruptFreeBehavior*, *kivy.\_clock.CyClockBaseFree*

The free\_only kivy clock. See module for details.

**kivy.clock.mainthread(func)**

Decorator that will schedule the call of the function for the next available frame in the mainthread. It can be useful when you use *UrlRequest* or when you do Thread programming: you cannot do any OpenGL-related work in a thread.

Please note that this method will return directly and no result can be returned:

```
@mainthread
def callback(self, *args):
    print('The request succeeded!',
          'This callback is called in the main thread.')
```

```
self.req = UrlRequest(url='http://...', on_success=callback)
```

New in version 1.8.0.

## 21.7 Compatibility module for Python 2.7 and > 3.3

This module provides a set of utility types and functions for optimization and to aid in writing Python 2/3 compatible code.

**kivy.compat.PY2 = True**

True if this version of python is 2.x.

**kivy.compat.clock()** → floating point number

A clock with the highest available resolution on your current Operating System.

**kivy.compat.string\_types**

A utility type for detecting string in a Python 2/3 friendly way. For example:

```
if isinstance(s, string_types):
    print("It's a string or unicode type")
else:
    print("It's something else.")
```

alias of basestring

**kivy.compat.isclose(a, b, rel\_tol=1e-09, abs\_tol=0.0)**

Measures whether two floats are “close” to each other. Identical to <https://docs.python.org/3.6/library/math.html#math.isclose>, for older versions of python.

## 21.8 Configuration object

The **Config** object is an instance of a modified Python ConfigParser. See the [ConfigParser documentation](#) for more information.

Kivy has a configuration file which determines the default settings. In order to change these settings, you can alter this file manually or use the Config object. Please see the [Configure Kivy](#) section for more information.

### 21.8.1 Applying configurations

Configuration options control the initialization of the **App**. In order to avoid situations where the config settings do not work or are not applied before window creation (like setting an initial window size), **Config.set** should be used before importing any other Kivy modules. Ideally, this means setting them right at the start of your main.py script.

Alternatively, you can save these settings permanently using **Config.set** then **Config.write**. In this case, you will need to restart the app for the changes to take effect. Note that this approach will effect all Kivy apps system wide.

### 21.8.2 Usage of the Config object

To read a configuration token from a particular section:

```
>>> from kivy.config import Config  
>>> Config.getint('kivy', 'show_fps')  
0
```

Change the configuration and save it:

```
>>> Config.set('postproc', 'retain_time', '50')  
>>> Config.write()
```

For information on configuring your *App*, please see the [Application configuration](#) section.

Changed in version 1.7.1: The ConfigParser should work correctly with utf-8 now. The values are converted from ascii to unicode only when needed. The method get() returns utf-8 strings.

### 21.8.3 Available configuration tokens

#### kivy

**desktop: int, 0 or 1** This option controls desktop OS specific features, such as enabling drag-able scroll-bar in scroll views, disabling of bubbles in TextInput etc. 0 is disabled, 1 is enabled.

**exit\_on\_escape: int, 0 or 1** Enables exiting kivy when escape is pressed. 0 is disabled, 1 is enabled.

**pause\_on\_minimize: int, 0 or 1** If set to 1, the main loop is paused and the *on\_pause* event is dispatched when the window is minimized. This option is intended for desktop use only. Defaults to 0.

**keyboard\_layout: string** Identifier of the layout to use.

**keyboard\_mode: string** Specifies the keyboard mode to use. It can be one of the following:

- “ - Let Kivy choose the best option for your current platform.
- ‘system’ - real keyboard.
- ‘dock’ - one virtual keyboard docked to a screen side.
- ‘multi’ - one virtual keyboard for every widget request.
- ‘systemanddock’ - virtual docked keyboard plus input from real keyboard.
- ‘systemandmulti’ - analogous.

**log\_dir: string** Path of log directory.

**log\_enable: int, 0 or 1** Activate file logging. 0 is disabled, 1 is enabled.

**log\_level: string, one of ‘trace’, ‘debug’, ‘info’, ‘warning’, ‘error’ or ‘critical’** Set the minimum log level to use.

**log\_name: string** Format string to use for the filename of log file.

**log\_maxfiles: int** Keep log\_maxfiles recent logfiles while purging the log directory. Set ‘log\_maxfiles’ to -1 to disable logfile purging (eg keep all logfiles).

---

**Note:** You end up with ‘log\_maxfiles + 1’ logfiles because the logger adds a new one after purging.

---

**window\_icon: string** Path of the window icon. Use this if you want to replace the default pygame icon.

## postproc

**double\_tap\_distance: float** Maximum distance allowed for a double tap, normalized inside the range 0 - 1000.

**double\_tap\_time: int** Time allowed for the detection of double tap, in milliseconds.

**ignore: list of tuples** List of regions where new touches are ignored. This configuration token can be used to resolve hotspot problems with DIY hardware. The format of the list must be:

```
ignore = [(xmin, ymin, xmax, ymax), ...]
```

All the values must be inside the range 0 - 1.

**jitter\_distance: int** Maximum distance for jitter detection, normalized inside the range 0 - 1000.

**jitter\_ignore\_devices: string, separated with commas** List of devices to ignore from jitter detection.

**retain\_distance: int** If the touch moves more than is indicated by retain\_distance, it will not be retained. Argument should be an int between 0 and 1000.

**retain\_time: int** Time allowed for a retain touch, in milliseconds.

**triple\_tap\_distance: float** Maximum distance allowed for a triple tap, normalized inside the range 0 - 1000.

**triple\_tap\_time: int** Time allowed for the detection of triple tap, in milliseconds.

## graphics

**borderless: int, one of 0 or 1** If set to 1, removes the window border/decoration. Window resizing must also be disabled to hide the resizing border.

**window\_state: string, one of 'visible', 'hidden', 'maximized'**

or 'minimized'

Sets the window state, defaults to 'visible'. This option is available only for the SDL2 window provider and it should be used on desktop OSes.

**fbo: string, one of 'hardware', 'software' or 'force-hardware'** Selects the FBO backend to use.

**fullscreen: int or string, one of 0, 1, 'fake' or 'auto'** Activate fullscreen. If set to 1, a resolution of *width* times *height* pixels will be used. If set to *auto*, your current display's resolution will be used instead. This is most likely what you want. If you want to place the window in another display, use *fake*, or set the *borderless* option from the graphics section, then adjust *width*, *height*, *top* and *left*.

**height: int** Height of the Window, not used if *fullscreen* is set to *auto*.

**left: int** Left position of the Window.

**maxfps: int, defaults to 60** Maximum FPS allowed.

**Warning:** Setting maxfps to 0 will lead to max CPU usage.

**'multisamples': int, defaults to 2** Sets the [MultiSample Anti-Aliasing \(MSAA\)](#) level. Increasing this value results in smoother graphics but at the cost of processing time.

---

**Note:** This feature is limited by device hardware support and will have no effect on devices which do not support the level of MSAA requested.

---

**position: string, one of ‘auto’ or ‘custom’** Position of the window on your display. If *auto* is used, you have no control of the initial position: *top* and *left* are ignored.

**show\_cursor: int, one of 0 or 1** Set whether or not the cursor is shown on the window.

**top: int** Top position of the Window.

**resizable: int, one of 0 or 1** If 0, the window will have a fixed size. If 1, the window will be resizable.

**rotation: int, one of 0, 90, 180 or 270** Rotation of the Window.

**width: int** Width of the Window, not used if *fullscreen* is set to *auto*.

**minimum\_width: int** Minimum width to restrict the window to. (sdl2 only)

**minimum\_height: int** Minimum height to restrict the window to. (sdl2 only)

**min\_state\_time: float, defaults to .035** Minimum time for widgets to display a given visual state. This attrib is currently used by widgets like *DropDown* & *ButtonBehavior* to make sure they display their current visual state for the given time.

**kivy\_clock: one of default, interrupt, free\_all, free\_only** The clock type to use with kivy. See [kivy.clock](#).

**default\_font: list** Default fonts used for widgets displaying any text. It defaults to ['Roboto', 'data/fonts/Roboto-Regular.ttf', 'data/fonts/Roboto-Italic.ttf', 'data/fonts/Roboto-Bold.ttf', 'data/fonts/Roboto-BoldItalic.ttf'].

**allow\_screensaver: int, one of 0 or 1, defaults to 1** Allow the device to show a screen saver, or to go to sleep on mobile devices. Only works for the sdl2 window provider.

**input** You can create new input devices using this syntax:

```
# example of input provider instance
yourid = providerid,parameters

# example for tuio provider
default = tuio,127.0.0.1:3333
mytable = tuio,192.168.0.1:3334
```

#### See also:

Check the providers in [kivy.input.providers](#) for the syntax to use inside the configuration file.

#### widgets

**scroll\_distance: int** Default value of the *scroll\_distance* property used by the *ScrollView* widget. Check the widget documentation for more information.

**scroll\_friction: float** Default value of the *scroll\_friction* property used by the *ScrollView* widget. Check the widget documentation for more information.

Deprecated since version 1.7.0: Please use *effect\_cls* instead.

**scroll\_timeout: int** Default value of the *scroll\_timeout* property used by the *ScrollView* widget. Check the widget documentation for more information.

`scroll_stoptime: int` Default value of the `scroll_stoptime` property used by the `ScrollView` widget. Check the widget documentation for more information.

Deprecated since version 1.7.0: Please use `effect_cls` instead.

`scroll_moves: int` Default value of the `scroll_moves` property used by the `ScrollView` widget. Check the widget documentation for more information.

Deprecated since version 1.7.0: Please use `effect_cls` instead.

**modules** You can activate modules with this syntax:

```
modulename =
```

Anything after the `=` will be passed to the module as arguments. Check the specific module's documentation for a list of accepted arguments.

Changed in version 1.10.0: `min_state_time` and `allow_screensaver` have been added to the `graphics` section. `kivy_clock` has been added to the `kivy` section. `default_font` has been added to the `kivy` section.

Changed in version 1.9.0: `borderless` and `window_state` have been added to the `graphics` section. The `fake` setting of the `fullscreen` option has been deprecated, use the `borderless` option instead. `pause_on_minimize` has been added to the `kivy` section.

Changed in version 1.8.0: `systemanddock` and `systemandmulti` has been added as possible values for `keyboard_mode` in the `kivy` section. `exit_on_escape` has been added to the `kivy` section.

Changed in version 1.2.0: `resizable` has been added to `graphics` section.

Changed in version 1.1.0: tuio no longer listens by default. Window icons are not copied to user directory anymore. You can still set a new window icon by using the `window_icon` config setting.

Changed in version 1.0.8: `scroll_timeout`, `scroll_distance` and `scroll_friction` have been added. `list_friction`, `list_trigger_distance` and `list_friction_bound` have been removed. `keyboard_type` and `keyboard_layout` have been removed from the `widget`. `keyboard_mode` and `keyboard_layout` have been added to the `kivy` section.

## `kivy.config.Config = None`

The default Kivy configuration object. This is a `ConfigParser` instance with the `name` set to 'kivy'.

```
Config = ConfigParser(name='kivy')
```

**class kivy.config.ConfigParser(name='', \*\*kwargs)**

Bases: `ConfigParser.ConfigParser, object`

Enhanced ConfigParser class that supports the addition of default sections and default values.

By default, the kivy ConfigParser instance, `Config`, is named 'kivy' and the ConfigParser instance used by the `App.build_settings` method is named 'app'.

### Parameters

`name: string` The name of the instance. See `name`. Defaults to ''.

Changed in version 1.9.0: Each ConfigParser can now be `named`. You can get the ConfigParser associated with a name using `get_configparser()`. In addition, you can now control the config values with `ConfigParserProperty`.

New in version 1.0.7.

**add\_callback(callback, section=None, key=None)**

Add a callback to be called when a specific section or key has changed. If you don't specify a section or key, it will call the callback for all section/key changes.

Callbacks will receive 3 arguments: the section, key and value.

New in version 1.4.1.

### **adddefaultsection(*section*)**

Add a section if the section is missing.

### **static get\_configparser(*name*)**

Returns the *ConfigParser* instance whose name is *name*, or None if not found.

#### **Parameters**

*name: string* The name of the *ConfigParser* instance to return.

### **getdefault(*section*, *option*, *defaultvalue*)**

Get the value of an option in the specified section. If not found, it will return the default value.

### **getdefaultint(*section*, *option*, *defaultvalue*)**

Get the value of an option in the specified section. If not found, it will return the default value. The value will always be returned as an integer.

New in version 1.6.0.

#### **name**

The name associated with this ConfigParser instance, if not ''. Defaults to ''. It can be safely changed dynamically or set to ''.

When a ConfigParser is given a name, that config object can be retrieved using *get\_configparser()*. In addition, that config instance can also be used with a *ConfigParserProperty* instance that set its *config* value to this name.

Setting more than one ConfigParser with the same name will raise a *ValueError*.

### **read(*filename*)**

Read only one filename. In contrast to the original ConfigParser of Python, this one is able to read only one file at a time. The last read file will be used for the *write()* method.

Changed in version 1.9.0: *read()* now calls the callbacks if read changed any values.

### **remove\_callback(*callback*, *section=None*, *key=None*)**

Removes a callback added with *add\_callback()*. *remove\_callback()* must be called with the same parameters as *add\_callback()*.

Raises a *ValueError* if not found.

New in version 1.9.0.

### **set(*section*, *option*, *value*)**

Functions similarly to PythonConfigParser's set method, except that the value is implicitly converted to a string.

### **setall(*section*, *keyvalues*)**

Sets multiple key-value pairs in a section. *keyvalues* should be a dictionary containing the key-value pairs to be set.

### **setdefault(*section*, *option*, *value*)**

Set the default value for an option in the specified section.

### **setdefaults(*section*, *keyvalues*)**

Set multiple key-value defaults in a section. *keyvalues* should be a dictionary containing the new key-value defaults.

### **update\_config(*filename*, *overwrite=False*)**

Upgrade the configuration based on a new default config file. Overwrite any existing values if overwrite is True.

### `write()`

Write the configuration to the last file opened using the `read()` method.

Return True if the write finished successfully, False otherwise.

## 21.9 Context

New in version 1.8.0.

**Warning:** This is experimental and subject to change as long as this warning notice is present.

Kivy has a few “global” instances that are used directly by many pieces of the framework: *Cache*, *Builder*, *Clock*.

TODO: document this module.

### `kivy.context.register_context(name, cls, *args, **kwargs)`

Register a new context.

### `kivy.context.get_current_context()`

Return the current context.

## 21.10 Event dispatcher

All objects that produce events in Kivy implement the `EventDispatcher` which provides a consistent interface for registering and manipulating event handlers.

Changed in version 1.0.9: Property discovery and methods have been moved from the `Widget` to the `EventDispatcher`.

### `class kivy.event.EventDispatcher`

Bases: `kivy.event.ObjectWithUid`

Generic event dispatcher interface.

See the module docstring for usage.

### `apply_property()`

Adds properties at runtime to the class. The function accepts keyword arguments of the form `prop_name=prop`, where `prop` is a `Property` instance and `prop_name` is the name of the attribute of the property.

New in version 1.9.1.

**Warning:** This method is not recommended for common usage because you should declare the properties in your class instead of using this method.

For example:

```
>>> print(wid.property('sticks', quiet=True))
None
>>> wid.apply_property(sticks=ObjectProperty(55, max=10))
>>> print(wid.property('sticks', quiet=True))
<kivy.properties.ObjectProperty object at 0x04303130>
```

## **bind()**

Bind an event type or a property to a callback.

Usage:

```
# With properties
def my_x_callback(obj, value):
    print('on object', obj, 'x changed to', value)
def my_width_callback(obj, value):
    print('on object', obj, 'width changed to', value)
self.bind(x=my_x_callback, width=my_width_callback)

# With event
def my_press_callback(obj):
    print('event on object', obj)
self.bind(on_press=my_press_callback)
```

In general, property callbacks are called with 2 arguments (the object and the property's new value) and event callbacks with one argument (the object). The example above illustrates this.

The following example demonstrates various ways of using the bind function in a complete application:

```
from kivy.uix.boxlayout import BoxLayout
from kivy.app import App
from kivy.uix.button import Button
from functools import partial


class DemoBox(BoxLayout):
    """
        This class demonstrates various techniques that can be used for
        binding to
        events. Although parts could me made more optimal, advanced Python_
        concepts
        are avoided for the sake of readability and clarity.
    """
    def __init__(self, **kwargs):
        super(DemoBox, self).__init__(**kwargs)
        self.orientation = "vertical"

        # We start with binding to a normal event. The only argument
        # passed to the callback is the object which we have bound to.
        btn = Button(text="Normal binding to event")
        btn.bind(on_press=self.on_event)

        # Next, we bind to a standard property change event. This_
        # typically
        # passes 2 arguments: the object and the value
        btn2 = Button(text="Normal binding to a property change")
        btn2.bind(state=self.on_property)

        # Here we use anonymous functions (a.k.a lambdas) to perform_
        # binding.
        # Their advantage is that you can avoid declaring new functions i.
        # e.
        # they offer a concise way to "redirect" callbacks.
        btn3 = Button(text="Using anonymous functions.")
        btn3.bind(on_press=lambda x: self.on_event(None))
```

```

# You can also declare a function that accepts a variable number
→of
    # positional and keyword arguments and use introspection to
→determine
        # what is being passed in. This is very handy for debugging as
→well
        # as function re-use. Here, we use standard event binding to a
→function
            # that accepts optional positional and keyword arguments.
            btn4 = Button(text="Use a flexible function")
            btn4.bind(on_press=self.on_anything)

            # Lastly, we show how to use partial functions. They are sometimes
            # difficult to grasp, but provide a very flexible and powerful
→way to
            # reuse functions.
            btn5 = Button(text="Using partial functions. For hardcores.")
            btn5.bind(on_press=partial(self.on_anything, "1", "2", monthly=
→"python"))

        for but in [btn, btn2, btn3, btn4, btn5]:
            self.add_widget(but)

    def on_event(self, obj):
        print("Typical event from", obj)

    def on_property(self, obj, value):
        print("Typical property change from", obj, "to", value)

    def on_anything(self, *args, **kwargs):
        print('The flexible function has *args of', str(args),
              "and **kwargs of", str(kwargs))

class DemoApp(App):
    def build(self):
        return DemoBox()

if __name__ == "__main__":
    DemoApp().run()

```

When binding a function to an event or property, a [Kivy.weakmethod.WeakMethod](#) of the callback is saved, and when dispatching the callback is removed if the callback reference becomes invalid.

If a callback has already been bound to a given event or property, it won't be added again.

### **create\_property()**

Create a new property at runtime.

New in version 1.0.9.

Changed in version 1.8.0: *value* parameter added, can be used to set the default value of the property. Also, the type of the value is used to specialize the created property.

Changed in version 1.9.0: In the past, if *value* was of type *bool*, a *NumericProperty* would be created, now a *BooleanProperty* is created.

Also, now and positional and keyword arguments are passed to the property when created.

**Warning:** This function is designed for the Kivy language, don't use it in your code. You should declare the property in your class instead of using this method.

### Parameters

*name: string* Name of the property

*value: object, optional* Default value of the property. Type is also used for creating more appropriate property types. Defaults to None.

```
>>> mywidget = Widget()
>>> mywidget.create_property('custom')
>>> mywidget.custom = True
>>> print(mywidget.custom)
True
```

### dispatch()

Dispatch an event across all the handlers added in bind / fbind(). As soon as a handler returns True, the dispatching stops.

The function collects all the positional and keyword arguments and passes them on to the handlers.

---

**Note:** The handlers are called in reverse order than they were registered with *bind()*.

---

### Parameters

*event\_type: basestring* the event name to dispatch.

Changed in version 1.9.0: Keyword arguments collection and forwarding was added. Before, only positional arguments would be collected and forwarded.

### events()

Return all the events in the class. Can be used for introspection.

New in version 1.8.0.

### fbind()

A method for advanced, and typically faster binding. This method is different than *bind()* and is meant for more advanced users and internal usage. It can be used as long as the following points are heeded.

1. As opposed to *bind()*, it does not check that this function and largs/kwargs has not been bound before to this name. So binding the same callback multiple times will just keep adding it.
2. Although *bind()* creates a **WeakMethod** of the callback when binding to an event or property, this method stores the callback directly, unless a keyword argument *ref* with value True is provided and then a **WeakMethod** is saved. This is useful when there's no risk of a memory leak by storing the callback directly.
3. This method returns a unique positive number if *name* was found and bound, and 0, otherwise. It does not raise an exception, like *bind()* if the property *name* is not found. If not zero, the uid returned is unique to this *name* and callback and can be used with *unbind\_uid()* for unbinding.

When binding a callback with largs and/or kwargs, `funbind()` must be used for unbinding. If no largs and kwargs are provided, `unbind()` may be used as well. `unbind_uid()` can be used in either case.

This method passes on any caught positional and/or keyword arguments to the callback, removing the need to call partial. When calling the callback the expended largs are passed on followed by instance/value (just instance for kwargs) followed by expended kwargs.

Following is an example of usage similar to the example in `bind()`:

```
class DemoBox(BoxLayout):

    def __init__(self, **kwargs):
        super(DemoBox, self).__init__(**kwargs)
        self.orientation = "vertical"

        btn = Button(text="Normal binding to event")
        btn.fbind('on_press', self.on_event)

        btn2 = Button(text="Normal binding to a property change")
        btn2.fbind('state', self.on_property)

        btn3 = Button(text="A: Using function with args.")
        btn3.fbind('on_press', self.on_event_with_args, 'right',
                   tree='birch', food='apple')

        btn4 = Button(text="Unbind A.")
        btn4.fbind('on_press', self.unbind_a, btn3)

        btn5 = Button(text="Use a flexible function")
        btn5.fbind('on_press', self.on_anything)

        btn6 = Button(text="B: Using flexible functions with args. For_"
                     "→hardcores.")
        btn6.fbind('on_press', self.on_anything, "1", "2", monthy="python"
                   "→")

        btn7 = Button(text="Force dispatch B with different params")
        btn7.fbind('on_press', btn6.dispatch, 'on_press', 6, 7, monthy=
                   "→other python")

        for but in [btn, btn2, btn3, btn4, btn5, btn6, btn7]:
            self.add_widget(but)

    def on_event(self, obj):
        print("Typical event from", obj)

    def on_event_with_args(self, side, obj, tree=None, food=None):
        print("Event with args", obj, side, tree, food)

    def on_property(self, obj, value):
        print("Typical property change from", obj, "to", value)

    def on_anything(self, *args, **kwargs):
        print('The flexible function has *args of', str(args),
              "and **kwargs of", str(kwargs))
        return True

    def unbind_a(self, btn, event):
        btn.funbind('on_press', self.on_event_with_args, 'right',
                   tree='birch', food='apple')
```

---

**Note:** Since the kv lang uses this method to bind, one has to implement this method, instead of `bind()` when creating a non `EventDispatcher` based class used with the kv lang. See `Observable` for an example.

---

New in version 1.9.0.

Changed in version 1.9.1: The `ref` keyword argument has been added.

### **funbind()**

Similar to `fbind()`.

When unbinding, `unbind()` will unbind all callbacks that match the callback, while this method will only unbind the first.

To unbind, the same positional and keyword arguments passed to `fbind()` must be passed on to funbind.

---

**Note:** It is safe to use `funbind()` to unbind a function bound with `bind()` as long as no keyword and positional arguments are provided to `funbind()`.

---

New in version 1.9.0.

### **get\_property\_observers()**

Returns a list of methods that are bound to the property/event passed as the `name` argument:

```
widget_instance.get_property_observers('on_release')
```

#### **Parameters**

`name: str` The name of the event or property.

`args: bool` Whether to return the bound args. To keep compatibility, only the callback functions and not their provided args will be returned in the list when `args` is False.

If True, each element in the list is a 5-tuple of (`callback, largs, kwargs, is_ref, uid`), where `is_ref` indicates whether `callback` is a weakref, and `uid` is the uid given by `fbind()`, or None if `bind()` was used. Defaults to `False`.

**Returns** The list of bound callbacks. See `args` for details.

New in version 1.8.0.

Changed in version 1.9.0: `args` has been added.

### **getter()**

Return the getter of a property.

New in version 1.0.9.

### **is\_event\_type()**

Return True if the event\_type is already registered.

New in version 1.0.4.

### **properties()**

Return all the properties in the class in a dictionary of key/property class. Can be used for introspection.

New in version 1.0.9.

## **property()**

Get a property instance from the property name. If quiet is True, None is returned instead of raising an exception when *name* is not a property. Defaults to *False*.

New in version 1.0.9.

**Returns** A *Property* derived instance corresponding to the name.

Changed in version 1.9.0: quiet was added.

## **proxy\_ref**

Default implementation of proxy\_ref, returns self. .. versionadded:: 1.9.0

## **register\_event\_type()**

Register an event type with the dispatcher.

Registering event types allows the dispatcher to validate event handler names as they are attached and to search attached objects for suitable handlers. Each event type declaration must:

1. start with the prefix *on\_*.
2. have a default handler in the class.

Example of creating a custom event:

```
class MyWidget(Widget):
    def __init__(self, **kwargs):
        super(MyWidget, self).__init__(**kwargs)
        self.register_event_type('on_swipe')

    def on_swipe(self):
        pass

    def on_swipe_callback(*largs):
        print('my swipe is called', largs)
w = MyWidget()
w.dispatch('on_swipe')
```

## **setter()**

Return the setter of a property. Use: `instance.setter('name')`. The setter is a convenient callback function useful if you want to directly bind one property to another. It returns a partial function that will accept (obj, value) args and results in the property 'name' of instance being set to value.

New in version 1.0.9.

For example, to bind number2 to number1 in python you would do:

```
class ExampleWidget(Widget):
    number1 = NumericProperty(None)
    number2 = NumericProperty(None)

    def __init__(self, **kwargs):
        super(ExampleWidget, self).__init__(**kwargs)
        self.bind(number1=self.setter('number2'))
```

This is equivalent to kv binding:

```
<ExampleWidget>:
    number2: self.number1
```

## **unbind()**

Unbind properties from callback functions with similar usage as *bind()*.

If a callback has been bound to a given event or property multiple times, only the first occurrence will be unbound.

---

**Note:** It is safe to use `unbind()` on a function bound with `fbind()` as long as that function was originally bound without any keyword and positional arguments. Otherwise, the function will fail to be unbound and you should use `funbind()` instead.

---

### `unbind_uid()`

Uses the uid returned by `fbind()` to unbind the callback.

This method is much more efficient than `funbind()`. If `uid` evaluates to False (e.g. 0) a `ValueError` is raised. Also, only callbacks bound with `fbind()` can be unbound with this method.

Since each call to `fbind()` will generate a unique `uid`, only one callback will be removed. If `uid` is not found among the callbacks, no error is raised.

E.g.:

```
btn6 = Button(text="B: Using flexible functions with args. For hardcores.  
→")  
uid = btn6.fbind('on_press', self.on_anything, "1", "2", monthy="python")  
if not uid:  
    raise Exception('Binding failed').  
...  
btn6.unbind_uid('on_press', uid)
```

New in version 1.9.0.

### `unregister_event_types()`

Unregister an event type in the dispatcher.

## `class kivy.event.ObjectWithUid`

Bases: `object`

(internal) This class assists in providing unique identifiers for class instances. It is not intended for direct usage.

## `class kivy.event.Observable`

Bases: `kivy.event.ObjectWithUid`

`Observable` is a stub class defining the methods required for binding. `EventDispatcher` is (the) one example of a class that implements the binding interface. See `EventDispatcher` for details.

New in version 1.9.0.

### `fbind()`

See `EventDispatcher.fbind()`.

---

**Note:** To keep backward compatibility with derived classes which may have inherited from `Observable` before, the `fbind()` method was added. The default implementation of `fbind()` is to create a partial function that it passes to bind while saving the uid and largs/kwargs. However, `funbind()` (and `unbind_uid()`) are fairly inefficient since we have to first lookup this partial function using the largs/kwargs or uid and then call `unbind()` on the returned function. It is recommended to overwrite these methods in derived classes to bind directly for better performance.

Similarly to `EventDispatcher.fbind()`, this method returns 0 on failure and a positive unique uid on success. This uid can be used with `unbind_uid()`.

---

### **funbind()**

See [fbind\(\)](#) and [EventDispatcher.funbind\(\)](#).

### **unbind\_uid()**

See [fbind\(\)](#) and [EventDispatcher.unbind\\_uid\(\)](#).

## 21.11 Factory object

The factory can be used to automatically register any class or module and instantiate classes from it anywhere in your project. It is an implementation of the [Factory Pattern](#).

The class list and available modules are automatically generated by setup.py.

Example for registering a class/module:

```
>>> from kivy.factory import Factory
>>> Factory.register('Widget', module='kivy.uix.widget')
>>> Factory.register('Vector', module='kivy.vector')
```

Example of using the Factory:

```
>>> from kivy.factory import Factory
>>> widget = Factory.Widget(pos=(456, 456))
>>> vector = Factory.Vector(9, 2)
```

Example using a class name:

```
>>> from kivy.factory import Factory
>>> Factory.register('MyWidget', cls=MyWidget)
```

By default, the first classname you register via the factory is permanent. If you wish to change the registered class, you need to unregister the classname before you re-assign it:

```
>>> from kivy.factory import Factory
>>> Factory.register('MyWidget', cls=MyWidget)
>>> widget = Factory.MyWidget()
>>> Factory.unregister('MyWidget')
>>> Factory.register('MyWidget', cls=CustomWidget)
>>> customWidget = Factory.MyWidget()
```

**kivy.factory.Factory = <kivy.factory.FactoryBase object>**

Factory instance to use for getting new classes

## 21.12 Geometry utilities

This module contains some helper functions for geometric calculations.

### **kivy.geometry.circumcircle(a, b, c)**

Computes the circumcircle of a triangle defined by a, b, c. See: [http://en.wikipedia.org/wiki/Circumscribed\\_circle](http://en.wikipedia.org/wiki/Circumscribed_circle)

#### **Parameters**

**a: iterable containing at least 2 values (for x and y)** The 1st point of the triangle.

**b: iterable containing at least 2 values (for x and y)** The 2nd point of the triangle.

**c: iterable containing at least 2 values (for x and y)** The 3rd point of the triangle.

## Return

A tuple that defines the circle :

- The first element in the returned tuple is the center as (x, y)
- The second is the radius (float)

`kivy.geometry.minimum_bounding_circle(points)`

Returns the minimum bounding circle for a set of points.

For a description of the problem being solved, see the [Smallest Circle Problem](#).

The function uses Applet's Algorithm, the runtime is  $O(h^3, *n)$ , where h is the number of points in the convex hull of the set of points. But it runs in linear time in almost all real world cases. See: <http://tinyurl.com/6e4n5yb>

## Parameters

`points: iterable` A list of points (2 tuple with x,y coordinates)

## Return

A tuple that defines the circle:

- The first element in the returned tuple is the center (x, y)
- The second the radius (float)

## 21.13 Gesture recognition

This class allows you to easily create new gestures and compare them:

```
from kivy.gesture import Gesture, GestureDatabase

# Create a gesture
g = Gesture()
g.add_stroke(point_list=[(1,1), (3,4), (2,1)])
g.normalize()

# Add it to the database
gdb = GestureDatabase()
gdb.add_gesture(g)

# And for the next gesture, try to find it!
g2 = Gesture()
# ...
gdb.find(g2)
```

**Warning:** You don't really want to do this: it's more of an example of how to construct gestures dynamically. Typically, you would need a lot more points, so it's better to record gestures in a file and reload them to compare later. Look in the examples/gestures directory for an example of how to do that.

`class kivy.gesture.Gesture(tolerance=None)`

A python implementation of a gesture recognition algorithm by Oleg Dopertchouk: <http://www.gamedev.net/reference/articles/article2039.asp>

Implemented by Jeiel Aranal ([chemikhazi@gmail.com](mailto:chemikhazi@gmail.com)), released into the public domain.

**add\_stroke**(*point\_list=None*)  
 Adds a stroke to the gesture and returns the Stroke instance. Optional point\_list argument is a list of the mouse points for the stroke.

**dot\_product**(*comparison\_gesture*)  
 Calculates the dot product of the gesture with another gesture.

**get\_rigid\_rotation**(*dstpts*)  
 Extract the rotation to apply to a group of points to minimize the distance to a second group of points. The two groups of points are assumed to be centered. This is a simple version that just picks an angle based on the first point of the gesture.

**get\_score**(*comparison\_gesture, rotation\_invariant=True*)  
 Returns the matching score of the gesture against another gesture.

**normalize**(*stroke\_samples=32*)  
 Runs the gesture normalization algorithm and calculates the dot product with self.

**class kivy.gesture.GestureDatabase**  
 Bases: object  
 Class to handle a gesture database.

**add\_gesture**(*gesture*)  
 Add a new gesture to the database.

**find**(*gesture, minscore=0.9, rotation\_invariant=True*)  
 Find a matching gesture in the database.

**gesture\_to\_str**(*gesture*)  
 Convert a gesture into a unique string.

**str\_to\_gesture**(*data*)  
 Convert a unique string to a gesture.

**class kivy.gesture.GestureStroke**  
 Gestures can be made up of multiple strokes.

**add\_point**(*x=x\_pos, y=y\_pos*)  
 Adds a point to the stroke.

**center\_stroke**(*offset\_x, offset\_y*)  
 Centers the stroke by offsetting the points.

**normalize\_stroke**(*sample\_points=32*)  
 Normalizes strokes so that every stroke has a standard number of points. Returns True if stroke is normalized, False if it can't be normalized. sample\_points controls the resolution of the stroke.

**points\_distance**(*point1=GesturePoint, point2=GesturePoint*)  
 Returns the distance between two GesturePoints.

**scale\_stroke**(*scale\_factor=float*)  
 Scales the stroke down by scale\_factor.

**stroke\_length**(*point\_list=None*)  
 Finds the length of the stroke. If a point list is given, finds the length of that list.

## 21.14 Interactive launcher

New in version 1.3.0.

Deprecated since version 1.10.0: The interactive launcher has been deprecated.

The `InteractiveLauncher` provides a user-friendly python shell interface to an `App` so that it can be prototyped and debugged interactively.

---

**Note:** The Kivy API intends for some functions to only be run once or before the main EventLoop has started. Methods that can normally be called during the course of an application will work as intended, but specifically overriding methods such as `on_touch()` dynamically leads to trouble.

---

### 21.14.1 Creating an InteractiveLauncher

Take your existing subclass of `App` (this can be production code) and pass an instance to the `InteractiveLauncher` constructor.

```
from kivy.interactive import InteractiveLauncher
from kivy.app import App
from kivy.uix.button import Button

class MyApp(App):
    def build(self):
        return Button(text='Hello Shell')

launcher = InteractiveLauncher(MyApp())
launcher.run()
```

After pressing `enter`, the script will return. This allows the interpreter to continue running. Inspection or modification of the `App` can be done safely through the `InteractiveLauncher` instance or the provided `SafeMembrane` class instances.

---

**Note:** If you want to test this example, start Python without any file to have already an interpreter, and copy/paste all the lines. You'll still have the interpreter at the end + the kivy application running.

---

### 21.14.2 Interactive Development

IPython provides a fast way to learn the Kivy API. The `App` instance and all of its attributes, including methods and the entire widget tree, can be quickly listed by using the `'.'` operator and pressing `'tab'`. Try this code in an Ipython shell.

```
from kivy.interactive import InteractiveLauncher
from kivy.app import App
from kivy.uix.widget import Widget
from kivy.graphics import Color, Ellipse

class MyPaintWidget(Widget):
    def on_touch_down(self, touch):
        with self.canvas:
            Color(1, 1, 0)
            d = 30.
            Ellipse(pos=(touch.x - d/2, touch.y - d/2), size=(d, d))

class TestApp(App):
    def build(self):
        return Widget()
```

```

i = InteractiveLauncher(TestApp())
i.run()
i.      # press 'tab' to list attributes of the app
i.root. # press 'tab' to list attributes of the root widget

# App is boring. Attach a new widget!
i.root.add_widget(MyPaintWidget())

i.safeIn()
# The application is now blocked.
# Click on the screen several times.
i.safeOut()
# The clicks will show up now

# Erase artwork and start over
i.root.canvas.clear()

```

---

**Note:** All of the proxies used in the module store their referent in the `_ref` attribute, which can be accessed directly if needed, such as for getting doc strings. `help()` and `type()` will access the proxy, not its referent.

---

### 21.14.3 Directly Pausing the Application

Both the `InteractiveLauncher` and `SafeMembrane` hold internal references to the `EventLoop`'s 'safe' and 'confirmed' `threading.Event` objects. You can use their safing methods to control the application manually.

`SafeMembrane.safeIn()` will cause the application to pause and `SafeMembrane.safeOut()` will allow a paused application to continue running. This is potentially useful for scripting actions into functions that need the screen to update etc.

---

**Note:** The pausing is implemented via the `Clocks.schedule_once()` method and occurs before the start of each frame.

---

### 21.14.4 Adding Attributes Dynamically

---

**Note:** This module uses threading and object proxies to encapsulate the running App. Deadlocks and memory corruption can occur if making direct references inside the thread without going through the provided proxy(s).

---

The `InteractiveLauncher` can have attributes added to it exactly like a normal object and if these were created from outside the membrane, they will not be threadsafe because the external references to them in the python interpreter do not go through `InteractiveLauncher`'s membrane behavior, inherited from `SafeMembrane`.

To threadsafe these external references, simply assign them to `SafeMembrane` instances of themselves like so:

```
from kivy.interactive import SafeMembrane
```

```

interactiveLauncher.attribute = myNewObject
# myNewObject is unsafe
myNewObject = SafeMembrane(myNewObject)
# myNewObject is now safe. Call at will.
myNewObject.method()

```

## TODO

Unit tests, examples, and a better explanation of which methods are safe in a running application would be nice. All three would be excellent.

Could be re-written with a context-manager style i.e.

```

with safe:
    foo()

```

Any use cases besides compacting code?

```

class kivy.interactive.SafeMembrane(ob, *args, **kwargs)
Bases: object

```

This help is for a proxy object. Did you want help on the proxy's referent instead? Try using help(<instance>.\_ref)

The SafeMembrane is a threadsafe proxy that also returns attributes as new thread-safe objects and makes thread-safe method calls, preventing thread-unsafe objects from leaking into the user's environment.

**safeIn()**

Provides a thread-safe entry point for interactive launching.

**safeOut()**

Provides a thread-safe exit point for interactive launching.

```

class kivy.interactive.InteractiveLauncher(*args, **kwargs)
Bases: kivy.interactive.SafeMembrane

```

Proxy to an application instance that launches it in a thread and then returns and acts as a proxy to the application in the thread.

## 21.15 Kivy Base

This module contains the Kivy core functionality and is not intended for end users. Feel free to look through it, but bare in mind that calling any of these methods directly may result in an unpredictable behavior as the calls access directly the event loop of an application.

```

kivy.base.EventLoop = <kivy.base.EventLoopBase object>
EventLoop instance

```

```

class kivy.base.EventLoopBase
Bases: kivy.event.EventDispatcher

```

Main event loop. This loop handles the updating of input and dispatching events.

**add\_event\_listener(*listener*)**

Add a new event listener for getting touch events.

**add\_input\_provider(*provider, auto\_remove=False*)**

Add a new input provider to listen for touch events.

**add\_postproc\_module(mod)**

Add a postproc input module (DoubleTap, TripleTap, DeJitter RetainTouch are defaults).

**close()**

Exit from the main loop and stop all configured input providers.

**dispatch\_input()**

Called by *EventLoopBase.idle()* to read events from input providers, pass events to postproc, and dispatch final events.

**ensure\_window()**

Ensure that we have a window.

**exit()**

Close the main loop and close the window.

**idle()**

This function is called after every frame. By default:

- it “ticks” the clock to the next frame.
- it reads all input and dispatches events.
- it dispatches *on\_update*, *on\_draw* and *on\_flip* events to the window.

**on\_pause()**

Event handler for *on\_pause* which will be fired when the event loop is paused.

**on\_start()**

Event handler for *on\_start* which will be fired right after all input providers have been started.

**on\_stop()**

Event handler for *on\_stop* events which will be fired right after all input providers have been stopped.

**post\_dispatch\_input(etype, me)**

This function is called by *EventLoopBase.dispatch\_input()* when we want to dispatch an input event. The event is dispatched to all listeners and if grabbed, it's dispatched to grabbed widgets.

**remove\_android\_splash(\*args)**

Remove android presplash in SDL2 bootstrap.

**remove\_event\_listener(listener)**

Remove an event listener from the list.

**remove\_input\_provider(provider)**

Remove an input provider.

**remove\_postproc\_module(mod)**

Remove a postproc module.

**run()**

Main loop

**set\_window(window)**

Set the window used for the event loop.

**start()**

Must be called only once before *EventLoopBase.run()*. This starts all configured input providers.

**stop()**

Stop all input providers and call callbacks registered using *EventLoop.add\_stop\_callback()*.

## **touches**

Return the list of all touches currently in down or move states.

### **class kivy.base.ExceptionHandler**

Bases: object

Base handler that catches exceptions in `runTouchApp()`. You can subclass and extend it as follows:

```
class E(ExceptionHandler):
    def handle_exception(self, inst):
        Logger.exception('Exception caught by ExceptionHandler')
        return ExceptionManager.PASS

ExceptionManager.add_handler(E())
```

All exceptions will be set to PASS, and logged to the console!

#### **handle\_exception(exception)**

Handle one exception, defaults to returning `ExceptionManager.RAISE`.

### **class kivy.base.ExceptionManagerBase**

ExceptionManager manages exceptions handlers.

#### **add\_handler(cls)**

Add a new exception handler to the stack.

#### **handle\_exception(inst)**

Called when an exception occurred in the `runTouchApp()` main loop.

#### **remove\_handler(cls)**

Remove a exception handler from the stack.

### **kivy.base.ExceptionManager = <kivy.base.ExceptionManagerBase instance>**

Instance of a `ExceptionManagerBase` implementation.

### **kivy.base.runTouchApp(widget=None, slave=False)**

Static main function that starts the application loop. You can access some magic via the following arguments:

#### **Parameters**

`<empty>` To make dispatching work, you need at least one input listener. If not, application will leave. (MTWindow act as an input listener)

`widget` If you pass only a widget, a MTWindow will be created and your widget will be added to the window as the root widget.

`slave` No event dispatching is done. This will be your job.

`widget + slave` No event dispatching is done. This will be your job but we try to get the window (must be created by you beforehand) and add the widget to it. Very useful for embedding Kivy in another toolkit. (like Qt, check kivy-designed)

### **kivy.base.stopTouchApp()**

Stop the current application by leaving the main loop

## 21.16 Logger object

Differents logging levels are available : trace, debug, info, warning, error and critical.

Examples of usage:

```

from kivy.logger import Logger

Logger.info('title: This is a info message.')
Logger.debug('title: This is a debug message.')

try:
    raise Exception('bleh')
except Exception:
    Logger.exception('Something happened!')

```

The message passed to the logger is split into two parts, separated by a colon (:). The first part is used as a title, and the second part is used as the message. This way, you can “categorize” your message easily.

```

Logger.info('Application: This is a test')

# will appear as

[INFO] [Application] This is a test

```

### 21.16.1 Logger configuration

The Logger can be controlled via the Kivy configuration file:

```

[kivy]
log_level = info
log_enable = 1
log_dir = logs
log_name = kivy_%y-%m-%d_.txt
log_maxfile = 100

```

More information about the allowed values are described in the [kivy.config](#) module.

### 21.16.2 Logger history

Even if the logger is not enabled, you still have access to the last 100 messages:

```

from kivy.logger import LoggerHistory

print(LoggerHistory.history)

```

```

kivy.logger.Logger = <logging.Logger object>
    Kivy default logger instance

class kivy.logger.LoggerHistory(level=0)
    Bases: logging.Handler
        Kivy history handler

```

## 21.17 Metrics

New in version 1.5.0.

A screen is defined by its physical size, density and resolution. These factors are essential for creating UI's with correct size everywhere.

In Kivy, all the graphics pipelines work with pixels. But using pixels as a measurement unit is problematic because sizes change according to the screen.

### 21.17.1 Dimensions

If you want to design your UI for different screen sizes, you will want better measurement units to work with. Kivy provides some more scalable alternatives.

#### Units

**pt** Points - 1/72 of an inch based on the physical size of the screen. Prefer to use **sp** instead of **pt**.

**mm** Millimeters - Based on the physical size of the screen.

**cm** Centimeters - Based on the physical size of the screen.

**in** Inches - Based on the physical size of the screen.

**dp** Density-independent Pixels - An abstract unit that is based on the physical density of the screen. With a **density** of 1, 1dp is equal to 1px. When running on a higher density screen, the number of pixels used to draw 1dp is scaled up a factor appropriate to the screen's dpi, and the inverse for a lower dpi. The ratio of dp-to-pixels will change with the screen density, but not necessarily in direct proportion. Using the **dp** unit is a simple solution to making the view dimensions in your layout resize properly for different screen densities. In other words, it provides consistency for the real-world size of your UI across different devices.

**sp** Scale-independent Pixels - This is like the **dp** unit, but it is also scaled by the user's font size preference. We recommend you use this unit when specifying font sizes, so the font size will be adjusted to both the screen density and the user's preference.

### 21.17.2 Examples

Here is an example of creating a label with a **sp** font\_size and setting the height manually with a 10dp margin:

```
#:kivy 1.5.0
<MyWidget>:
    Label:
        text: 'Hello world'
        font_size: '15sp'
        size_hint_y: None
        height: self.texture_size[1] + dp(10)
```

### 21.17.3 Manual control of metrics

The metrics cannot be changed at runtime. Once a value has been converted to pixels, you can't retrieve the original value anymore. This stems from the fact that the DPI and density of a device cannot be changed at runtime.

We provide some environment variables to control metrics:

- **KIVY\_METRICS\_DENSITY**: if set, this value will be used for **density** instead of the systems one. On android, the value varies between 0.75, 1, 1.5 and 2.
- **KIVY\_METRICS\_FONTSIZE**: if set, this value will be used for **fontscale** instead of the systems one. On android, the value varies between 0.8 and 1.2.

- `KIVY_DPI`: if set, this value will be used for `dpi`. Please note that setting the DPI will not impact the dp/sp notation because these are based on the screen density.

For example, if you want to simulate a high-density screen (like the HTC One X):

```
KIVY_DPI=320 KIVY_METRICS_DENSITY=2 python main.py --size 1280x720
```

Or a medium-density (like Motorola Droid 2):

```
KIVY_DPI=240 KIVY_METRICS_DENSITY=1.5 python main.py --size 854x480
```

You can also simulate an alternative user preference for `fontscale` as follows:

```
KIVY_METRICS_FONTSIZE=1.2 python main.py
```

`kivy.metrics.Metrics = <kivy.metrics.MetricsBase object>`

Default instance of `MetricsBase`, used everywhere in the code .. versionadded:: 1.7.0

`class kivy.metrics.MetricsBase`

Bases: `object`

Class that contains the default attributes for Metrics. Don't use this class directly, but use the `Metrics` instance.

`density()`

Return the density of the screen. This value is 1 by default on desktops but varies on android depending on the screen.

`dpi()`

Return the DPI of the screen. Depending on the platform, the DPI can be taken from the Window provider (Desktop mainly) or from a platform-specific module (like android/ios).

`dpi_rounded()`

Return the DPI of the screen, rounded to the nearest of 120, 160, 240 or 320.

`fontscale()`

Return the `fontscale` user preference. This value is 1 by default but can vary between 0.8 and 1.2.

`kivy.metrics.pt(value)`

Convert from points to pixels

`kivy.metrics.inch(value)`

Convert from inches to pixels

`kivy.metrics.cm(value)`

Convert from centimeters to pixels

`kivy.metrics.mm(value)`

Convert from millimeters to pixels

`kivy.metrics.dp(value)`

Convert from density-independent pixels to pixels

`kivy.metrics.sp(value)`

Convert from scale-independent pixels to pixels

## 21.18 Multistroke gesture recognizer

New in version 1.9.0.

**Warning:** This is experimental and subject to change as long as this warning notice is present.

See `kivy/examples/demo/multistroke/main.py` for a complete application example.

### 21.18.1 Conceptual Overview

This module implements the Protractor gesture recognition algorithm.

`Recognizer` is the search/database API similar to `GestureDatabase`. It maintains a list of `MultistrokeGesture` objects and allows you to search for a user-input gestures among them.

`ProgressTracker` tracks the progress of a `Recognizer.recognize()` call. It can be used to interact with the running recognizer task, for example forcing it to stop half-way, or analyzing results as they arrive.

`MultistrokeGesture` represents a gesture in the gesture database (`Recognizer.db`). It is a container for `UnistrokeTemplate` objects, and implements the heap permute algorithm to automatically generate all possible stroke orders (if desired).

`UnistrokeTemplate` represents a single stroke path. It's typically instantiated automatically by `MultistrokeGesture`, but sometimes you may need to create them manually.

`Candidate` represents a user-input gesture that is used to search the gesture database for matches. It is normally instantiated automatically by calling `Recognizer.recognize()`.

### 21.18.2 Usage examples

See `kivy/examples/demo/multistroke/main.py` for a complete application example.

You can bind to events on `Recognizer` to track the state of all calls to `Recognizer.recognize()`. The callback function will receive an instance of `ProgressTracker` that can be used to analyze and control various aspects of the recognition process

```
from kivy.vector import Vector
from kivy.multistroke import Recognizer

gdb = Recognizer()

def search_start(gdb, pt):
    print("A search is starting with %d tasks" % (pt.tasks))

def search_stop(gdb, pt):
    # This will call max() on the result dictionary, so it's best to store
    # it instead of calling it 3 times consecutively
    best = pt.best
    print("Search ended (%s). Best is %s (score %f, distance %f)" % (
        pt.status, best['name'], best['score'], best['dist']))

# Bind your callbacks to track all matching operations
gdb.bind(on_search_start=search_start)
gdb.bind(on_search_complete=search_stop)

# The format below is referred to as `strokes`, a list of stroke paths.
# Note that each path shown here consists of two points, ie a straight
# line; if you plot them it looks like a T, hence the name.
gdb.add_gesture('T', [
    [Vector(30, 7), Vector(103, 7)],
    [Vector(66, 7), Vector(66, 87)]])
```

```
# Now you can search for the 'T' gesture using similar data (user input).
# This will trigger both of the callbacks bound above.
gdb.recognize([
    [Vector(45, 8), Vector(110, 12)],
    [Vector(88, 9), Vector(85, 95)]])
```

On the next *Clock* tick, the matching process starts (and, in this case, completes).

To track individual calls to *Recognizer.recognize()*, use the return value (also a *ProgressTracker* instance)

```
# Same as above, but keep track of progress using returned value
progress = gdb.recognize([
    [Vector(45, 8), Vector(110, 12)],
    [Vector(88, 9), Vector(85, 95)]])

progress.bind(on_progress=my_other_callback)
print(progress.progress) # = 0

# [ assuming a kivy.clock.Clock.tick() here ]

print(result.progress) # = 1
```

### 21.18.3 Algorithm details

For more information about the matching algorithm, see:

“Protractor: A fast and accurate gesture recognizer” by Yang Li <http://yangl.org/pdf/protractor-chi2010.pdf>

“\$N-Protractor” by Lisa Anthony and Jacob O. Wobbrock <http://depts.washington.edu/aimgroup/proj/dollar/ndollar-protractor.pdf>

Some of the code is derived from the JavaScript implementation here: <http://depts.washington.edu/aimgroup/proj/dollar/ndollar.html>

**class** `kivy.multistroke.Recognizer(**kwargs)`  
Bases: `kivy.event.EventDispatcher`

*Recognizer* provides a gesture database with matching facilities.

#### Events

`on_search_start` Fired when a new search is started using this Recognizer.

`on_search_complete` Fired when a running search ends, for whatever reason. (use `ProgressTracker.status` to find out)

#### Properties

`db` A `ListProperty` that contains the available `MultistrokeGesture` objects.

`db` is a `ListProperty` and defaults to []

**add\_gesture**(*name, strokes, \*\*kwargs*)

Add a new gesture to the database. This will instantiate a new `MultistrokeGesture` with *strokes* and append it to self.db.

---

**Note:** If you already have instantiated a `MultistrokeGesture` object and wish to add it, append it to `Recognizer.db` manually.

---

## `export_gesture(filename=None, **kwargs)`

Export a list of `MultistrokeGesture` objects. Outputs a base64-encoded string that can be decoded to a Python list with the `parse_gesture()` function or imported directly to `self.db` using `Recognizer.import_gesture()`. If `filename` is specified, the output is written to disk, otherwise returned.

This method accepts optional `Recognizer.filter()` arguments.

## `filter(**kwargs)`

`filter()` returns a subset of objects in `self.db`, according to given criteria. This is used by many other methods of the `Recognizer`; the arguments below can for example be used when calling `Recognizer.recognize()` or `Recognizer.export_gesture()`. You normally don't need to call this directly.

### Arguments

`name` Limits the returned list to gestures where `MultistrokeGesture.name` matches given regular expression(s). If `re.match(name, MultistrokeGesture.name)` tests true, the gesture is included in the returned list. Can be a string or an array of strings

```
gdb = Recognizer()

# Will match all names that start with a capital N
# (ie Next, New, N, Nebraska etc, but not "n" or "next")
gdb.filter(name='N')

# exactly 'N'
gdb.filter(name='N$')

# Nebraska, teletubbies, France, fraggle, N, n, etc
gdb.filter(name=['[Nn]', '(?i)T', '(?i)F'])
```

`priority` Limits the returned list to gestures with certain `MultistrokeGesture.priority` values. If specified as an integer, only gestures with a lower priority are returned. If specified as a list (min/max)

```
# Max priority 50
gdb.filter(priority=50)

# Max priority 50 (same result as above)
gdb.filter(priority=[0, 50])

# Min priority 50, max 100
gdb.filter(priority=[50, 100])
```

When this option is used, `Recognizer.db` is automatically sorted according to priority, incurring extra cost. You can use `force_priority_sort` to override this behavior if your gestures are already sorted according to priority.

`orientation_sensitive` Limits the returned list to gestures that are orientation sensitive (True), gestures that are not orientation sensitive (False) or None (ignore template sensitivity, this is the default).

`numstrokes` Limits the returned list to gestures that have the specified number of strokes (in `MultistrokeGesture.strokes`). Can be a single integer or a list of integers.

`numpoints` Limits the returned list to gestures that have specific `MultistrokeGesture.numpoints` values. This is provided for flexi-

bility, do not use it unless you understand what it does. Can be a single integer or a list of integers.

`force_priority_sort` Can be used to override the default sort behavior. Normally `MultistrokeGesture` objects are returned in priority order if the `priority` option is used. Setting this to True will return gestures sorted in priority order, False will return in the order gestures were added. None means decide automatically (the default).

---

**Note:** For improved performance, you can load your gesture database in priority order and set this to False when calling `Recognizer.recognize()`

---

`db` Can be set if you want to filter a different list of objects than `Recognizer`.  
`db`. You probably don't want to do this; it is used internally by `import_gesture()`.

#### `import_gesture(data=None, filename=None, **kwargs)`

Import a list of gestures as formatted by `export_gesture()`. One of `data` or `filename` must be specified.

This method accepts optional `Recognizer.filter()` arguments, if none are specified then all gestures in specified data are imported.

#### `parse_gesture(data)`

Parse data formatted by `export_gesture()`. Returns a list of `MultistrokeGesture` objects. This is used internally by `import_gesture()`, you normally don't need to call this directly.

#### `prepare_templates(**kwargs)`

This method is used to prepare `UnistrokeTemplate` objects within the gestures in self.db. This is useful if you want to minimize punishment of lazy resampling by preparing all vectors in advance. If you do this before a call to `Recognizer.export_gesture()`, you will have the vectors computed when you load the data later.

This method accepts optional `Recognizer.filter()` arguments.

`force_numpoints`, if specified, will prepare all templates to the given number of points (instead of each template's preferred n; ie `UnistrokeTemplate.numpoints`). You normally don't want to do this.

#### `recognize(strokes, goodscore=None, timeout=0, delay=0, **kwargs)`

Search for gestures matching `strokes`. Returns a `ProgressTracker` instance.

This method accepts optional `Recognizer.filter()` arguments.

#### Arguments

`strokes` A list of stroke paths (list of lists of `Vector` objects) that will be matched against gestures in the database. Can also be a `Candidate` instance.

**Warning:** If you manually supply a `Candidate` that has a skip-flag, make sure that the correct filter arguments are set. Otherwise the system will attempt to load vectors that have not been computed. For example, if you set `skip_bounded` and do not set `orientation_sensitive` to False, it will raise an exception if an orientation\_sensitive `UnistrokeTemplate` is encountered.

`goodscore` If this is set (between 0.0 - 1.0) and a gesture score is equal to or higher than the specified value, the search is immediately halted and the `on_search_complete` event is fired (+ the `on_complete` event of the associated `ProgressTracker` instance). Default is None (disabled).

*timeout* Specifies a timeout (in seconds) for when the search is aborted and the results returned. This option applies only when *max\_gpf* is not 0. Default value is 0, meaning all gestures in the database will be tested, no matter how long it takes.

*max\_gpf* Specifies the maximum number of *MultistrokeGesture* objects that can be processed per frame. When exceeded, will cause the search to halt and resume work in the next frame. Setting to 0 will complete the search immediately (and block the UI).

**Warning:** This does not limit the number of *UnistrokeTemplate* objects matched! If a single gesture has a million templates, they will all be processed in a single frame with *max\_gpf*=1!

*delay* Sets an optional delay between each run of the recognizer loop. Normally, a run is scheduled for the next frame until the tasklist is exhausted. If you set this, there will be an additional delay between each run (specified in seconds). Default is 0, resume in the next frame.

*force\_numpoints* forces all templates (and candidate) to be prepared to a certain number of points. This can be useful for example if you are evaluating templates for optimal n (do not use this unless you understand what it does).

### **transfer\_gesture**(*tgt*, \*\**kwargs*)

Transfers *MultistrokeGesture* objects from *Recognizer.db* to another *Recognizer* instance *tgt*.

This method accepts optional *Recognizer.filter()* arguments.

## **class kivy.multistroke.ProgressTracker(*candidate*, *tasks*, \*\**kwargs*)**

Bases: *kivy.event.EventDispatcher*

Represents an ongoing (or completed) search operation. Instantiated and returned by the *Recognizer.recognize()* method when it is called. The *results* attribute is a dictionary that is updated as the recognition operation progresses.

---

**Note:** You do not need to instantiate this class.

---

### **Arguments**

*candidate* *Candidate* object to be evaluated

*tasks* Total number of gestures in tasklist (to test against)

### **Events**

*on\_progress* Fired for every gesture that is processed

*on\_result* Fired when a new result is added, and it is the first match for the *name* so far, or a consecutive match with better score.

*on\_complete* Fired when the search is completed, for whatever reason. (use *ProgressTracker.status* to find out)

### **Attributes**

*results* A dictionary of all results (so far). The key is the name of the gesture (ie *UnistrokeTemplate.name* usually inherited from *MultistrokeGesture*). Each item in the dictionary is a dict with the following entries:

**name** Name of the matched template (redundant)  
**score** Computed score from 1.0 (perfect match) to 0.0  
**dist** Cosine distance from candidate to template (low=closer)  
**gesture** The **MultistrokeGesture** object that was matched  
**best\_template** Index of the best matching template (in **MultistrokeGesture.templates**)  
**template\_results** List of distances for all templates. The list index corresponds to a **UnistrokeTemplate** index in **gesture.templates**.

#### **status**

**search** Currently working  
**stop** Was stopped by the user (**stop()** called)  
**timeout** A timeout occurred (specified as **timeout=** to **recognize()**)  
**goodscore** The search was stopped early because a gesture with a high enough score was found (specified as **goodscore=** to **recognize()**)  
**complete** The search is complete (all gestures matching filters were tested)

#### **best**

Return the best match found by **recognize()** so far. It returns a dictionary with three keys, 'name', 'dist' and 'score' representing the template's name, distance (from candidate path) and the computed score value. This is a Python property.

#### **progress**

Returns the progress as a float, 0 is 0% done, 1 is 100%. This is a Python property.

#### **stop()**

Raises a stop flag that is checked by the search process. It will be stopped on the next clock tick (if it is still running).

**class** kivy.multistroke.**MultistrokeGesture**(*name*, *strokes=None*, *\*\*kwargs*)  
Bases: **object**

**MultistrokeGesture** represents a gesture. It maintains a set of *strokes* and generates unistroke (ie **UnistrokeTemplate**) permutations that are used for evaluating candidates against this gesture later.

#### **Arguments**

**name** Identifies the name of the gesture - it is returned to you in the results of a **Recognizer.recognize()** search. You can have any number of MultistrokeGesture objects with the same name; many definitions of one gesture. The same name is given to all the generated unistroke permutations. Required, no default.

**strokes** A list of paths that represents the gesture. A path is a list of Vector objects:

```
gesture = MultistrokeGesture('my_gesture', strokes=[  
    [Vector(x1, y1), Vector(x2, y2), .....], # stroke 1  
    [Vector(), Vector(), Vector(), Vector()] # stroke 2  
    #, [stroke 3], [stroke 4], ...  
])
```

For template matching purposes, all the strokes are combined to a single list (unistroke). You should still specify the strokes individually, and set *stroke\_sensitive* True (whenever possible).

Once you do this, unistroke permutations are immediately generated and stored in `self.templates` for later, unless you set the `permute` flag to False.

**priority** Determines when `Recognizer.recognize()` will attempt to match this template, lower priorities are evaluated first (only if a priority filter is used). You should use lower priority on gestures that are more likely to match. For example, set user templates at lower number than generic templates. Default is 100.

**numpoints** Determines the number of points this gesture should be resampled to (for matching purposes). The default is 16.

**stroke\_sensitive** Determines if the number of strokes (paths) in this gesture is required to be the same in the candidate (user input) gesture during matching. If this is False, candidates will always be evaluated, disregarding the number of strokes. Default is True.

**orientation\_sensitive** Determines if this gesture is orientation sensitive. If True, aligns the indicative orientation with the one of eight base orientations that requires least rotation. Default is True.

**angle\_similarity** This is used by the `Recognizer.recognize()` function when a candidate is evaluated against this gesture. If the angles between them are too far off, the template is considered a non-match. Default is 30.0 (degrees)

**permute** If False, do not use Heap Permute algorithm to generate different stroke orders when instantiated. If you set this to False, a single `UnistrokeTemplate` built from `strokes` is used.

#### **add\_stroke(stroke, permute=False)**

Add a stroke to the `self.strokes` list. If `permute` is True, the `permute()` method is called to generate new unistroke templates

#### **get\_distance(cand, tpl, numpoints=None)**

Compute the distance from this Candidate to a `UnistrokeTemplate`. Returns the Cosine distance between the stroke paths.

`numpoints` will prepare both the `UnistrokeTemplate` and Candidate path to n points (when necessary), you probably don't want to do this.

#### **match\_candidate(cand, \*\*kwargs)**

Match a given candidate against this `MultistrokeGesture` object. Will test against all templates and report results as a list of four items:

**index 0** Best matching template's index (in `self.templates`)

**index 1** Computed distance from the template to the candidate path

**index 2** List of distances for all templates. The list index corresponds to a `UnistrokeTemplate` index in `self.templates`.

**index 3** Counter for the number of performed matching operations, ie templates matched against the candidate

#### **permute()**

Generate all possible unistroke permutations from `self.strokes` and save the resulting list of `UnistrokeTemplate` objects in `self.templates`.

Quote from <http://faculty.washington.edu/wobbrock/pubs/gi-10.2.pdf>

We use Heap Permute [16] (p. 179) to generate all stroke orders in a multistroke gesture. Then, to generate stroke directions for each order, we treat each component stroke as a dichotomous [0,1] variable. There are  $2^N$  combinations for N strokes, so we

convert the decimal values `0` to `2N-1`, inclusive, to binary representations **and** regard each bit **as** indicating forward (`0`) or reverse (`1`). This algorithm **is** often used to generate truth tables **in** propositional logic.

See section 4.1: “\$N Algorithm” of the linked paper for details.

**Warning:** Using heap permute for gestures with more than 3 strokes can result in very large number of templates (a 9-stroke gesture = 38 million templates). If you are dealing with these types of gestures, you should manually compose all the desired stroke orders.

---

**class** `kivy.multistroke.UnistrokeTemplate(name, points=None, **kwargs)`

Bases: `object`

Represents a (uni)stroke path as a list of Vectors. Normally, this class is instantiated by `MultistrokeGesture` and not by the programmer directly. However, it is possible to manually compose `UnistrokeTemplate` objects.

#### Arguments

`name` Identifies the name of the gesture. This is normally inherited from the parent `MultistrokeGesture` object when a template is generated.

`points` A list of points that represents a unistroke path. This is normally one of the possible stroke order permutations from a `MultistrokeGesture`.

`numpoints` The number of points this template should (ideally) be resampled to before the matching process. The default is 16, but you can use a template-specific settings if that improves results.

`orientation_sensitive` Determines if this template is orientation sensitive (True) or fully rotation invariant (False). The default is True.

---

**Note:** You will get an exception if you set a skip-flag and then attempt to retrieve those vectors.

**add\_point(*p*)**

Add a point to the unistroke/path. This invalidates all previously computed vectors.

**prepare(*numpoints=None*)**

This function prepares the `UnistrokeTemplate` for matching given a target number of points (for resample). 16 is optimal.

---

**class** `kivy.multistroke.Candidate(strokes=None, numpoints=16, **kwargs)`

Bases: `object`

Represents a set of unistroke paths of user input, ie data to be matched against a `UnistrokeTemplate` object using the Protractor algorithm. By default, data is precomputed to match both rotation bounded and fully invariant `UnistrokeTemplate` objects.

#### Arguments

`strokes` See `MultistrokeGesture.strokes` for format example. The Candidate strokes are simply combined to a unistroke in the order given. The idea is that this will match one of the unistroke permutations in `MultistrokeGesture.templates`.

`numpoints` The Candidate’s default N; this is only for a fallback, it is not normally used since n is driven by the `UnistrokeTemplate` we are being compared to.

`skip_bounded` If True, do not generate/store rotation bounded vectors

***skip\_invariant*** If True, do not generate/store rotation invariant vectors

Note that you WILL get errors if you set a skip-flag and then attempt to retrieve the data.

**add\_stroke(*stroke*)**

Add a stroke to the candidate; this will invalidate all previously computed vectors

**get\_angle\_similarity(*tpl*, \*\**kwargs*)**

(Internal use only) Compute the angle similarity between this Candidate and a UnistrokeTemplate object. Returns a number that represents the angle similarity (lower is more similar).

**get\_protractor\_vector(*numpoints*, *orientation\_sens*)**

(Internal use only) Return vector for comparing to a UnistrokeTemplate with Protractor

**get\_start\_unit\_vector(*numpoints*, *orientation\_sens*)**

(Internal use only) Get the start vector for this Candidate, with the path resampled to *numpoints* points. This is the first step in the matching process. It is compared to a UnistrokeTemplate object's start vector to determine angle similarity.

**prepare(*numpoints=None*)**

Prepare the Candidate vectors. self.strokes is combined to a single unistroke (connected end-to-end), resampled to *numpoints* points, and then the vectors are calculated and stored in self.db (for use by *get\_distance* and *get\_angle\_similarity*)

## 21.19 Parser utilities

Helper functions used for CSS parsing.

**kivy.parser.parse\_color(*text*)**

Parse a string to a kivy color. Supported formats:

- `rgb(r, g, b)`
- `rgba(r, g, b, a)`
- `rgb`
- `rgba`
- `rrggbb`
- `rrggbbaa`

For hexadecimal values, you can also use:

- `#rgb`
- `#rgba`
- `#rrggbb`
- `#rrggbbaa`

**kivy.parser.parse\_int**

alias of `int`

**kivy.parser.parse\_float**

alias of `float`

**kivy.parser.parse\_string(*text*)**

Parse a string to a string (removing single and double quotes).

`kivy.parser.parse_bool(text)`

Parse a string to a boolean, ignoring case. “true”/“1” is True, “false”/“0” is False. Anything else throws an exception.

`kivy.parser.parse_int2(text)`

Parse a string to a list of exactly 2 integers.

```
>>> print(parse_int2("12 54"))
12, 54
```

`kivy.parser.parse_float4(text)`

Parse a string to a list of exactly 4 floats.

```
>>> parse_float4('54 87. 35 0')
54, 87., 35, 0
```

`kivy.parser.parse_filename(filename)`

Parse a filename and search for it using `resource_find()`. If found, the resource path is returned, otherwise return the unmodified filename (as specified by the caller).

## 21.20 Properties

The *Properties* classes are used when you create an *EventDispatcher*.

**Warning:** Kivy’s Properties are **not to be confused** with Python’s properties (i.e. the `@property` decorator and the `<property>` type).

Kivy’s property classes support:

**Value Checking / Validation** When you assign a new value to a property, the value is checked against validation constraints. For example, validation for an *OptionProperty* will make sure that the value is in a predefined list of possibilities. Validation for a *NumericProperty* will check that your value is a numeric type. This prevents many errors early on.

**Observer Pattern** You can specify what should happen when a property’s value changes. You can bind your own function as a callback to changes of a *Property*. If, for example, you want a piece of code to be called when a widget’s *pos* property changes, you can *bind* a function to it.

**Better Memory Management** The same instance of a property is shared across multiple widget instances.

### 21.20.1 Comparison Python vs. Kivy

Basic example

Let’s compare Python and Kivy properties by creating a Python class with ‘a’ as a float property:

```
class MyClass(object):
    def __init__(self, a=1.0):
        super(MyClass, self).__init__()
        self.a = a
```

With Kivy, you can do:

```
class MyClass(EventDispatcher):
    a = NumericProperty(1.0)
```

Depth being tracked

Only the “top level” of a nested object is being tracked. For example:

```
my_list_prop = ListProperty([1, {'hi': 0}])
# Changing a top level element will trigger all `on_my_list_prop` callbacks
my_list_prop[0] = 4
# Changing a deeper element will be ignored by all `on_my_list_prop` callbacks
my_list_prop[1]['hi'] = 4
```

The same holds true for all container-type kivy properties.

Value checking

If you wanted to add a check for a minimum / maximum value allowed for a property, here is a possible implementation in Python:

```
class MyClass(object):
    def __init__(self, a=1):
        super(MyClass, self).__init__()
        self.a_min = 0
        self.a_max = 100
        self.a = a

    def _get_a(self):
        return self._a
    def _set_a(self, value):
        if value < self.a_min or value > self.a_max:
            raise ValueError('a out of bounds')
        self._a = value
    a = property(_get_a, _set_a)
```

The disadvantage is you have to do that work yourself. And it becomes laborious and complex if you have many properties. With Kivy, you can simplify the process:

```
class MyClass(EventDispatcher):
    a = BoundedNumericProperty(1, min=0, max=100)
```

That's all!

Error Handling

If setting a value would otherwise raise a `ValueError`, you have two options to handle the error gracefully within the property. The first option is to use an `errorvalue` parameter. An `errorvalue` is a substitute for the invalid value:

```
# simply returns 0 if the value exceeds the bounds
bnp = BoundedNumericProperty(0, min=-500, max=500, errorvalue=0)
```

The second option is to use an `errorhandler` parameter. An `errorhandler` is a callable (single argument function or lambda) which can return a valid substitute:

```
# returns the boundary value when exceeded
bnp = BoundedNumericProperty(0, min=-500, max=500,
    errorhandler=lambda x: 500 if x > 500 else -500)
```

Keyword arguments and `__init__()`

When working with inheritance, namely with the `__init__()` of an object that inherits from `EventDispatcher` e.g. a `Widget`, the properties protect you from a Python 3 object error. This error occurs when passing kwargs to the *object* instance through a `super()` call:

```
class MyClass(EventDispatcher):
    def __init__(self, **kwargs):
        super(MyClass, self).__init__(**kwargs)
        self.my_string = kwargs.get('my_string')

print(MyClass(my_string='value').my_string)
```

While this error is silenced in Python 2, it will stop the application in Python 3 with:

```
TypeError: object.__init__() takes no parameters
```

Logically, to fix that you'd either put `my_string` directly in the `__init__()` definition as a required argument or as an optional keyword argument with a default value i.e.:

```
class MyClass(EventDispatcher):
    def __init__(self, my_string, **kwargs):
        super(MyClass, self).__init__(**kwargs)
        self.my_string = my_string
```

or:

```
class MyClass(EventDispatcher):
    def __init__(self, my_string='default', **kwargs):
        super(MyClass, self).__init__(**kwargs)
        self.my_string = my_string
```

Alternatively, you could pop the key-value pair from the `kwargs` dictionary before calling `super()`:

```
class MyClass(EventDispatcher):
    def __init__(self, **kwargs):
        self.my_string = kwargs.pop('my_string')
        super(MyClass, self).__init__(**kwargs)
```

Kivy properties are more flexible and do the required `kwargs.pop()` in the background automatically (within the `super()` call to `EventDispatcher`) to prevent this distraction:

```
class MyClass(EventDispatcher):
    my_string = StringProperty('default')
    def __init__(self, **kwargs):
        super(MyClass, self).__init__(**kwargs)

print(MyClass(my_string='value').my_string)
```

## Conclusion

Kivy properties are easier to use than the standard ones. See the next chapter for examples of how to use them :)

## 21.20.2 Observe Property changes

As we said in the beginning, Kivy's Properties implement the [Observer pattern](#). That means you can [bind\(\)](#) to a property and have your own function called when the value changes.

There are multiple ways to observe the changes.

Observe using bind()

You can observe a property change by using the bind() method outside of the class:

```
class MyClass(EventDispatcher):
    a = NumericProperty(1)

def callback(instance, value):
    print('My callback is call from', instance)
    print('and the a value changed to', value)

ins = MyClass()
ins.bind(a=callback)

# At this point, any change to the a property will call your callback.
ins.a = 5      # callback called
ins.a = 5      # callback not called, because the value did not change
ins.a = -1     # callback called
```

---

**Note:** Property objects live at the class level and manage the values attached to instances. Re-assigning at class level will remove the Property. For example, continuing with the code above, `MyClass.a = 5` replaces the property object with a simple int.

---

Observe using 'on\_<propname>'

If you defined the class yourself, you can use the 'on\_<propname>' callback:

```
class MyClass(EventDispatcher):
    a = NumericProperty(1)

    def on_a(self, instance, value):
        print('My property a changed to', value)
```

**Warning:** Be careful with 'on\_<propname>'. If you are creating such a callback on a property you are inheriting, you must not forget to call the superclass function too.

## 21.20.3 Binding to properties of properties.

When binding to a property of a property, for example binding to a numeric property of an object saved in a object property, updating the object property to point to a new object will not re-bind the numeric property to the new object. For example:

```
<MyWidget>:
    Label:
        id: first
```

```

        text: 'First label'
Label:
    id: second
    text: 'Second label'
Button:
    label: first
    text: self.label.text
    on_press: self.label = second

```

When clicking on the button, although the label object property has changed to the second widget, the button text will not change because it is bound to the text property of the first label directly.

In 1.9.0, the `rebind` option has been introduced that will allow the automatic updating of the `text` when `label` is changed, provided it was enabled. See [ObjectProperty](#).

### `class kivy.properties.Property`

Bases: `object`

Base class for building more complex properties.

This class handles all the basic setters and getters, `None` type handling, the observer list and storage initialisation. This class should not be directly instantiated.

By default, a `Property` always takes a default value:

```

class MyObject(Widget):
    hello = Property('Hello world')

```

The default value must be a value that agrees with the `Property` type. For example, you can't set a list to a `StringProperty` because the `StringProperty` will check the default value.

`None` is a special case: you can set the default value of a `Property` to `None`, but you can't set `None` to a property afterward. If you really want to do that, you must declare the `Property` with `allownone=True`:

```

class MyObject(Widget):
    hello = ObjectProperty(None, allownone=True)

# then later
a = MyObject()
a.hello = 'bleh' # working
a.hello = None # working too, because allownone is True.

```

### Parameters

`default`: Specifies the default value for the property.

`**kwargs`: If the parameters include `errorhandler`, this should be a callable which must take a single argument and return a valid substitute value.

If the parameters include `errorvalue`, this should be an object. If set, it will replace an invalid property value (overrides errorhandler).

If the parameters include `force_dispatch`, it should be a boolean. If `True`, no value comparison will be done, so the property event will be dispatched even if the new value matches the old value (by default identical values are not dispatched to avoid infinite recursion in two-way binds). Be careful, this is for advanced use only.

Changed in version 1.4.2: Parameters errorhandler and errorvalue added

Changed in version 1.9.0: Parameter force\_dispatch added

### **bind()**

Add a new observer to be called only when the value is changed.

### **dispatch()**

Dispatch the value change to all observers.

Changed in version 1.1.0: The method is now accessible from Python.

This can be used to force the dispatch of the property, even if the value didn't change:

```
button = Button()  
# get the Property class instance  
prop = button.property('text')  
# dispatch this property on the button instance  
prop.dispatch(button)
```

### **fbind()**

Similar to bind, except it doesn't check if the observer already exists. It also expands and forwards largs and kwargs to the callback. funbind or unbind\_uid should be called when unbinding. It returns a unique positive uid to be used with unbind\_uid.

### **funbind()**

Remove the observer from our widget observer list bound with fbind. It removes the first match it finds, as opposed to unbind which searches for all matches.

### **get()**

Return the value of the property.

### **link()**

Link the instance with its real name.

**Warning:** Internal usage only.

When a widget is defined and uses a *Property* class, the creation of the property object happens, but the instance doesn't know anything about its name in the widget class:

```
class MyWidget(Widget):  
    uid = NumericProperty(0)
```

In this example, the uid will be a NumericProperty() instance, but the property instance doesn't know its name. That's why *link()* is used in *Widget.\_\_new\_\_*. The link function is also used to create the storage space of the property for this specific widget instance.

### **set()**

Set a new value for the property.

### **unbind()**

Remove the observer from our widget observer list.

### **unbind\_uid()**

Remove the observer from our widget observer list bound with fbind using the uid.

## **class kivy.properties.NumericProperty**

Bases: *kivy.properties.Property*

Property that represents a numeric value.

### **Parameters**

**defaultvalue: int or float, defaults to 0** Specifies the default value of the property.

```
>>> wid = Widget()
>>> wid.x = 42
>>> print(wid.x)
42
>>> wid.x = "plop"
Traceback (most recent call last):
  File "<stdin>", line 1, in <module>
    File "properties.pyx", line 93, in kivy.properties.Property.__set__
      File "properties.pyx", line 111, in kivy.properties.Property.set
      File "properties.pyx", line 159, in kivy.properties.NumericProperty.check
ValueError: NumericProperty accept only int/float
```

Changed in version 1.4.1: NumericProperty can now accept custom text and tuple value to indicate a type, like "in", "pt", "px", "cm", "mm", in the format: '10pt' or (10, 'pt').

### get\_format()

Return the format used for Numeric calculation. Default is px (mean the value have not been changed at all). Otherwise, it can be one of 'in', 'pt', 'cm', 'mm'.

## class kivy.properties.StringProperty

Bases: *kivy.properties.Property*

Property that represents a string value.

### Parameters

**defaultvalue: string, defaults to ''** Specifies the default value of the property.

## class kivy.properties.ListProperty

Bases: *kivy.properties.Property*

Property that represents a list.

### Parameters

**defaultvalue: list, defaults to []** Specifies the default value of the property.

**Warning:** When assigning a list to a *ListProperty*, the list stored in the property is a shallow copy of the list and not the original list. This can be demonstrated with the following example:

```
>>> class MyWidget(Widget):
...     my_list = ListProperty([])

...     widget = MyWidget()
...     my_list = [1, 5, {'hi': 'hello'}]
...     widget.my_list = my_list
...     print(my_list is widget.my_list)
False
...     my_list.append(10)
...     print(my_list, widget.my_list)
[1, 5, {'hi': 'hello'}, 10] [1, 5, {'hi': 'hello'}]
```

However, changes to nested levels will affect the property as well, since the property uses a shallow copy of my\_list.

```
>>> my_list[2]['hi'] = 'bye'
>>> print(my_list, widget.my_list)
[1, 5, {'hi': 'bye'}, 10] [1, 5, {'hi': 'bye'}]
```

## `class kivy.properties.ObjectProperty`

Bases: `kivy.properties.Property`

Property that represents a Python object.

### Parameters

`defaultvalue: object type` Specifies the default value of the property.

`rebind: bool, defaults to False` Whether kv rules using this object as an intermediate attribute in a kv rule, will update the bound property when this object changes.

That is the standard behavior is that if there's a kv rule `text: self.a.b.c.d`, where `a`, `b`, and `c` are properties with `rebind=False` and `d` is a `StringProperty`. Then when the rule is applied, `text` becomes bound only to `d`. If `a`, `b`, or `c` change, `text` still remains bound to `d`. Furthermore, if any of them were `None` when the rule was initially evaluated, e.g. `b` was `None`; then `text` is bound to `b` and will not become bound to `d` even when `b` is changed to not be `None`.

By setting `rebind` to `True`, however, the rule will be re-evaluated and all the properties rebound when that intermediate property changes. E.g. in the example above, whenever `b` changes or becomes not `None` if it was `None` before, `text` is evaluated again and becomes rebound to `d`. The overall result is that `text` is now bound to all the properties among `a`, `b`, or `c` that have `rebind` set to `True`.

`**kwargs: a list of keyword arguments`

`baseclass` If `kwargs` includes a `baseclass` argument, this value will be used for validation: `isinstance(value, kwargs['baseclass'])`.

**Warning:** To mark the property as changed, you must reassign a new python object.

Changed in version 1.9.0: `rebind` has been introduced.

Changed in version 1.7.0: `baseclass` parameter added.

## `class kivy.properties.BooleanProperty`

Bases: `kivy.properties.Property`

Property that represents only a boolean value.

### Parameters

`defaultvalue: boolean` Specifies the default value of the property.

## `class kivy.properties.BoundedNumericProperty`

Bases: `kivy.properties.Property`

Property that represents a numeric value within a minimum bound and/or maximum bound – within a numeric range.

### Parameters

`default: numeric` Specifies the default value of the property.

`**kwargs: a list of keyword arguments` If a `min` parameter is included, this specifies the minimum numeric value that will be accepted. If a `max` parameter is included, this specifies the maximum numeric value that will be accepted.

### bounds

Return min/max of the value.

New in version 1.0.9.

### `get_max()`

Return the maximum value acceptable for the BoundedNumericProperty in *obj*. Return None if no maximum value is set. Check [get\\_min](#) for a usage example.

New in version 1.1.0.

### `get_min()`

Return the minimum value acceptable for the BoundedNumericProperty in *obj*. Return None if no minimum value is set:

```
class MyWidget(Widget):
    number = BoundedNumericProperty(0, min=-5, max=5)

    widget = MyWidget()
    print(widget.property('number').get_min(widget))
    # will output -5
```

New in version 1.1.0.

### `set_max()`

Change the maximum value acceptable for the BoundedNumericProperty, only for the *obj* instance. Set to None if you want to disable it. Check [set\\_min](#) for a usage example.

**Warning:** Changing the bounds doesn't revalidate the current value.

New in version 1.1.0.

### `set_min()`

Change the minimum value acceptable for the BoundedNumericProperty, only for the *obj* instance. Set to None if you want to disable it:

```
class MyWidget(Widget):
    number = BoundedNumericProperty(0, min=-5, max=5)

    widget = MyWidget()
    # change the minimum to -10
    widget.property('number').set_min(widget, -10)
    # or disable the minimum check
    widget.property('number').set_min(widget, None)
```

**Warning:** Changing the bounds doesn't revalidate the current value.

New in version 1.1.0.

## `class kivy.properties.OptionProperty`

Bases: [kivy.properties.Property](#)

Property that represents a string from a predefined list of valid options.

If the string set in the property is not in the list of valid options (passed at property creation time), a ValueError exception will be raised.

### Parameters

**default: any valid type in the list of options** Specifies the default value of the property.

**\*\*kwargs: a list of keyword arguments** Should include an *options* parameter specifying a list (not tuple) of valid options.

For example:

```
class MyWidget(Widget):
    state = OptionProperty("None", options=["On", "Off", "None"])
```

### options

Return the options available.

New in version 1.0.9.

## class kivy.properties.ReferenceListProperty

Bases: *kivy.properties.Property*

Property that allows the creation of a tuple of other properties.

For example, if *x* and *y* are *NumericProperty*s, we can create a *ReferenceListProperty* for the *pos*. If you change the value of *pos*, it will automatically change the values of *x* and *y* accordingly. If you read the value of *pos*, it will return a tuple with the values of *x* and *y*.

For example:

```
class MyWidget(EventDispatcher):
    x = NumericProperty(0)
    y = NumericProperty(0)
    pos = ReferenceListProperty(x, y)
```

## class kivy.properties.AliasProperty

Bases: *kivy.properties.Property*

Create a property with a custom getter and setter.

If you don't find a Property class that fits to your needs, you can make your own by creating custom Python getter and setter methods.

Example from kivy/uix/widget.py:

```
def get_right(self):
    return self.x + self.width
def set_right(self, value):
    self.x = value - self.width
right = AliasProperty(get_right, set_right, bind=['x', 'width'])
```

### Parameters

**getter: function** Function to use as a property getter

**setter: function** Function to use as a property setter. Properties listening to the alias property won't be updated when the property is set (e.g. *right* = 10), unless the *setter* returns *True*.

**bind: list/tuple** Properties to observe for changes, as property name strings

**cache: boolean** If True, the value will be cached, until one of the binded elements will changes

**rebind: bool, defaults to False** See *ObjectProperty* for details.

Changed in version 1.9.0: *rebind* has been introduced.

Changed in version 1.4.0: Parameter *cache* added.

```
class kivy.properties.DictProperty
```

Bases: *kivy.properties.Property*

Property that represents a dict.

#### Parameters

*defaultvalue: dict, defaults to None* Specifies the default value of the property.

*rebind: bool, defaults to False* See *ObjectProperty* for details.

Changed in version 1.9.0: *rebind* has been introduced.

**Warning:** Similar to *ListProperty*, when assigning a dict to a *DictProperty*, the dict stored in the property is a shallow copy of the dict and not the original dict. See *ListProperty* for details.

```
class kivy.properties.VariableListProperty
```

Bases: *kivy.properties.Property*

A ListProperty that allows you to work with a variable amount of list items and to expand them to the desired list size.

For example, GridLayout's padding used to just accept one numeric value which was applied equally to the left, top, right and bottom of the GridLayout. Now padding can be given one, two or four values, which are expanded into a length four list [left, top, right, bottom] and stored in the property.

#### Parameters

*default: a default list of values* Specifies the default values for the list.

*length: int, one of 2 or 4.* Specifies the length of the final list. The *default* list will be expanded to match a list of this length.

*\*\*kwargs: a list of keyword arguments* Not currently used.

Keeping in mind that the *default* list is expanded to a list of length 4, here are some examples of how VariabelListProperty's are handled.

- VariableListProperty([1]) represents [1, 1, 1, 1].
- VariableListProperty([1, 2]) represents [1, 2, 1, 2].
- VariableListProperty(['1px', (2, 'px'), 3, 4.0]) represents [1, 2, 3, 4.0].
- VariableListProperty(5) represents [5, 5, 5, 5].
- VariableListProperty(3, length=2) represents [3, 3].

New in version 1.7.0.

```
class kivy.properties.ConfigParserProperty
```

Bases: *kivy.properties.Property*

Property that allows one to bind to changes in the configuration values of a *ConfigParser* as well as to bind the ConfigParser values to other properties.

A ConfigParser is composed of sections, where each section has a number of keys and values associated with these keys. ConfigParserProperty lets you automatically listen to and change the values of specified keys based on other kivy properties.

For example, say we want to have a TextInput automatically write its value, represented as an int, in the *info* section of a ConfigParser. Also, the textinputs should update its values from the ConfigParser's fields. Finally, their values should be displayed in a label. In py:

```

class Info(Label):

    number = ConfigParserProperty(0, 'info', 'number', 'example',
                                 val_type=int, errorvalue=41)

    def __init__(self, **kw):
        super(Info, self).__init__(**kw)
        config = ConfigParser(name='example')

```

The above code creates a property that is connected to the *number* key in the *info* section of the ConfigParser named *example*. Initially, this ConfigParser doesn't exist. Then, in *\_\_init\_\_*, a ConfigParser is created with name *example*, which is then automatically linked with this property. then in kv:

```

BoxLayout:
    TextInput:
        id: number
        text: str(info.number)
    Info:
        id: info
        number: number.text
        text: 'Number: {}'.format(self.number)

```

You'll notice that we have to do *text: str(info.number)*, this is because the value of this property is always an int, because we specified *int* as the *val\_type*. However, we can assign anything to the property, e.g. *number: number.text* which assigns a string, because it is instantly converted with the *val\_type* callback.

---

**Note:** If a file has been opened for this ConfigParser using *read()*, then *write()* will be called every property change, keeping the file updated.

---

**Warning:** It is recommended that the config parser object be assigned to the property after the kv tree has been constructed (e.g. schedule on next frame from init). This is because the kv tree and its properties, when constructed, are evaluated on its own order, therefore, any initial values in the parser might be overwritten by objects it's bound to. So in the example above, the TextInput might be initially empty, and if *number: number.text* is evaluated before *text: str(info.number)*, the config value will be overwritten with the (empty) text value.

## Parameters

**default: object type** Specifies the default value for the key. If the parser associated with this property doesn't have this section or key, it'll be created with the current value, which is the default value initially.

**section: string type** The section in the ConfigParser where the key / value will be written. Must be provided. If the section doesn't exist, it'll be created.

**key: string type** The key in section *section* where the value will be written to. Must be provided. If the key doesn't exist, it'll be created and the current value written to it, otherwise its value will be used.

**config: string or ConfigParser instance.** The ConfigParser instance to associate with this property if not None. If it's a string, the ConfigParser instance whose *name* is the value of *config* will be used. If no such parser exists yet, whenever a ConfigParser with this name is created, it will automatically be linked to this property.

Whenever a ConfigParser becomes linked with a property, if the section or key doesn't exist, the current property value will be used to create that key, otherwise, the existing key value will be used for the property value; overwriting its current value. You can change the ConfigParser associated with this property if a string was used here, by changing the `name` of an existing or new ConfigParser instance. Or through `set_config()`.

**\*\*kwargs: a list of keyword arguments**

**`val_type`: a callable object** The key values are saved in the ConfigParser as strings. When the ConfigParser value is read internally and assigned to the property or when the user changes the property value directly, if `val_type` is not None, it will be called with the new value as input and it should return the value converted to the proper type accepted by this property. For example, if the property represent ints, `val_type` can simply be `int`.

If the `val_type` callback raises a `ValueError`, `errorvalue` or `errorhandler` will be used if provided. Tip: the `getboolean` function of the ConfigParser might also be useful here to convert to a boolean type.

**`verify`: a callable object** Can be used to restrict the allowable values of the property. For every value assigned to the property, if this is specified, `verify` is called with the new value, and if it returns `True` the value is accepted, otherwise, `errorvalue` or `errorhandler` will be used if provided or a `ValueError` is raised.

New in version 1.9.0.

### **set\_config()**

Sets the ConfigParser object to be used by this property. Normally, the ConfigParser is set when initializing the Property using the `config` parameter.

**Parameters**

**`config`: A `ConfigParser` instance.** The instance to use for listening to and saving property value changes. If None, it disconnects the currently used `ConfigParser`.

```
class MyWidget(Widget):
    username = ConfigParserProperty('', 'info', 'name', None)

    widget = MyWidget()
    widget.property('username').set_config(ConfigParser())
```

## 21.21 Resources management

Resource management can be a pain if you have multiple paths and projects. Kivy offers 2 functions for searching for specific resources across a list of paths.

### 21.21.1 Resource lookup

When Kivy looks for a resource e.g. an image or a kv file, it searches through a predetermined set of folders. You can modify this folder list using the `resource_add_path()` and `resource_remove_path()` functions.

## 21.21.2 Customizing Kivy

These functions can also be helpful if you want to replace standard Kivy resources with your own. For example, if you wish to customize or re-style Kivy, you can force your *style.kv* or *data/defaulttheme-0.png* files to be used in preference to the defaults simply by adding the path to your preferred alternatives via the `resource_add_path()` method.

As almost all Kivy resources are looked up using the `resource_find()`, so you can use this approach to add fonts and keyboard layouts and to replace images and icons.

**kivy.resources.resource\_find(filename)**

Search for a resource in the list of paths. Use `resource_add_path` to add a custom path to the search.

**kivy.resources.resource\_add\_path(path)**

Add a custom path to search in.

**kivy.resources.resource\_remove\_path(path)**

Remove a search path.

New in version 1.0.8.

## 21.22 Support

Activate other frameworks/toolkits inside the kivy event loop.

**kivy.support.install\_gobject\_iteration()**

Import and install gobject context iteration inside our event loop. This is used as soon as gobject is used (like gstreamer).

**kivy.support.install\_twisted\_reactor(\*\*kwargs)**

Installs a threaded twisted reactor, which will schedule one reactor iteration before the next frame only when twisted needs to do some work.

Any arguments or keyword arguments passed to this function will be passed on to the threaded-select reactors interleave function. These are the arguments one would usually pass to twisted's `reactor.startRunning`.

Unlike the default twisted reactor, the installed reactor will not handle any signals unless you set the 'installSignalHandlers' keyword argument to 1 explicitly. This is done to allow kivy to handle the signals as usual unless you specifically want the twisted reactor to handle the signals (e.g. SIGINT).

---

**Note:** Twisted is not included in iOS build by default. To use it on iOS, put the twisted distribution (and zope.interface dependency) in your application directory.

---

**kivy.support.uninstall\_twisted\_reactor()**

Uninstalls the Kivy's threaded Twisted Reactor. No more Twisted tasks will run after this got called. Use this to clean the `twisted.internet.reactor`.

New in version 1.9.0.

**kivy.support.install\_android()**

Install hooks for the android platform.

- Automatically sleep when the device is paused.
- Automatically kill the application when the return key is pressed.

## 21.23 Utils

The Utils module provides a selection of general utility functions and classes that may be useful for various applications. These include maths, color, algebraic and platform functions.

Changed in version 1.6.0: The OrderedDict class has been removed. Use collections.OrderedDict instead.

`kivy.utils.intersection(set1, set2)`

Return the intersection of 2 lists.

`kivy.utils.difference(set1, set2)`

Return the difference between 2 lists.

`kivy.utils.strtotuple(s)`

Convert a tuple string into a tuple with some security checks. Designed to be used with the eval() function:

```
a = (12, 54, 68)
b = str(a)          # return '(12, 54, 68)'
c = strtotuple(b)  # return (12, 54, 68)
```

`kivy.utils.get_color_from_hex(s)`

Transform a hex string color to a kivy `Color`.

`kivy.utils.get_hex_from_color(color)`

Transform a kivy `Color` to a hex value:

```
>>> get_hex_from_color((0, 1, 0))
'#00ff00'
>>> get_hex_from_color((.25, .77, .90, .5))
'#3fc4e57f'
```

New in version 1.5.0.

`kivy.utils.get_random_color(alpha=1.0)`

Returns a random color (4 tuple).

### Parameters

`alpha: float, defaults to 1.0` If alpha == 'random', a random alpha value is generated.

`kivy.utils.is_color_transparent(c)`

Return True if the alpha channel is 0.

`kivy.utils.boundary(value, minvalue, maxvalue)`

Limit a value between a minvalue and maxvalue.

`kivy.utils.deprecated(func)`

This is a decorator which can be used to mark functions as deprecated. It will result in a warning being emitted the first time the function is used.

`class kivy.utils.SafeList`

Bases: `list`

List with a clear() method.

**Warning:** Usage of the iterate() function will decrease your performance.

```
kivy.utils.interpolate(value_from, value_to, step=10)
```

Interpolate between two values. This can be useful for smoothing some transitions. For example:

```
# instead of setting directly
self.pos = pos

# use interpolate, and you'll have a nicer transition
self.pos = interpolate(self.pos, new_pos)
```

**Warning:** These interpolations work only on lists/tuples/doubles with the same dimensions. No test is done to check the dimensions are the same.

```
class kivy.utils.QueryDict
```

Bases: dict

QueryDict is a dict() that can be queried with dot.

```
d = QueryDict()
# create a key named toto, with the value 1
d.toto = 1
# it's the same as
d['toto'] = 1
```

New in version 1.0.4.

```
kivy.utils.platform = 'linux'
```

A string identifying the current operating system. It is one of: 'win', 'linux', 'android', 'macosx', 'ios' or 'unknown'. You can use it as follows:

```
from kivy.utils import platform
if platform == 'linux':
    do_linux_things()
```

New in version 1.3.0.

Changed in version 1.8.0: platform is now a variable instead of a function.

```
kivy.utils.escape_markup(text)
```

Escape markup characters found in the text. Intended to be used when markup text is activated on the Label:

```
untrusted_text = escape_markup('Look at the example [1]')
text = '[color=ff0000]' + untrusted_text + '[/color]'
w = Label(text=text, markup=True)
```

New in version 1.3.0.

```
class kivy.utils.reify(func)
```

Bases: object

Put the result of a method which uses this (non-data) descriptor decorator in the instance dict after the first call, effectively replacing the decorator with an instance variable.

It acts like @property, except that the function is only ever called once; after that, the value is cached as a regular attribute. This gives you lazy attribute creation on objects that are meant to be immutable.

Taken from the [Pyramid project](#).

To use this as a decorator:

```

@reify
def lazy(self):
    ...
    return hard_to_compute_int
first_time = self.lazy # lazy is reify obj, reify.__get__() runs
second_time = self.lazy # lazy is hard_to_compute_int

```

## kivy.utils.rgb(a, \*args)

Return a Kivy color (4 value from 0-1 range) from either a hex string or a list of 0-255 values.

New in version 1.10.0.

## 21.24 Vector

The `Vector` represents a 2D vector (x, y). Our implementation is built on top of a Python list.

An example of constructing a Vector:

```

>>> # Construct a point at 82,34
>>> v = Vector(82, 34)
>>> v[0]
82
>>> v.x
82
>>> v[1]
34
>>> v.y
34

>>> # Construct by giving a list of 2 values
>>> pos = (93, 45)
>>> v = Vector(pos)
>>> v[0]
93
>>> v.x
93
>>> v[1]
45
>>> v.y
45

```

### 21.24.1 Optimized usage

Most of the time, you can use a list for arguments instead of using a Vector. For example, if you want to calculate the distance between 2 points:

```

a = (10, 10)
b = (87, 34)

# optimized method
print('distance between a and b:', Vector(a).distance(b))

# non-optimized method
va = Vector(a)
vb = Vector(b)
print('distance between a and b:', va.distance(vb))

```

## 21.24.2 Vector operators

The `Vector` supports some numeric operators such as `+, -, /`:

```
>>> Vector(1, 1) + Vector(9, 5)
[10, 6]

>>> Vector(9, 5) - Vector(5, 5)
[4, 0]

>>> Vector(10, 10) / Vector(2., 4.)
[5.0, 2.5]

>>> Vector(10, 10) / 5.
[2.0, 2.0]
```

You can also use in-place operators:

```
>>> v = Vector(1, 1)
>>> v += 2
>>> v
[3, 3]
>>> v *= 5
[15, 15]
>>> v /= 2.
[7.5, 7.5]
```

`class kivy.vector.Vector(*args)`

Bases: `list`

Vector class. See module documentation for more information.

`angle(a)`

Computes the angle between a and b, and returns the angle in degrees.

```
>>> Vector(100, 0).angle((0, 100))
-90.0
>>> Vector(87, 23).angle((-77, 10))
-157.7920283010705
```

`distance(to)`

Returns the distance between two points.

```
>>> Vector(10, 10).distance((5, 10))
5.
>>> a = (90, 33)
>>> b = (76, 34)
>>> Vector(a).distance(b)
14.035668847618199
```

`distance2(to)`

Returns the distance between two points squared.

```
>>> Vector(10, 10).distance2((5, 10))
25
```

`dot(a)`

Computes the dot product of a and b.

```
>>> Vector(2, 4).dot((2, 2))  
12
```

### **static in\_bbox(point, a, b)**

Return True if *point* is in the bounding box defined by *a* and *b*.

```
>>> bmin = (0, 0)  
>>> bmax = (100, 100)  
>>> Vector.in_bbox((50, 50), bmin, bmax)  
True  
>>> Vector.in_bbox((647, -10), bmin, bmax)  
False
```

### **length()**

Returns the length of a vector.

```
>>> Vector(10, 10).length()  
14.142135623730951  
>>> pos = (10, 10)  
>>> Vector(pos).length()  
14.142135623730951
```

### **length2()**

Returns the length of a vector squared.

```
>>> Vector(10, 10).length2()  
200  
>>> pos = (10, 10)  
>>> Vector(pos).length2()  
200
```

### **static line\_intersection(v1, v2, v3, v4)**

Finds the intersection point between the lines (1)v1->v2 and (2)v3->v4 and returns it as a vector object.

```
>>> a = (98, 28)  
>>> b = (72, 33)  
>>> c = (10, -5)  
>>> d = (20, 88)  
>>> Vector.line_intersection(a, b, c, d)  
[15.25931928687196, 43.911669367909241]
```

**Warning:** This is a line intersection method, not a segment intersection.

For math see: [http://en.wikipedia.org/wiki/Line-line\\_intersection](http://en.wikipedia.org/wiki/Line-line_intersection)

### **normalize()**

Returns a new vector that has the same direction as vec, but has a length of one.

```
>>> v = Vector(88, 33).normalize()  
>>> v  
[0.93632917756904444, 0.3511234415883917]  
>>> v.length()  
1.0
```

### **rotate(angle)**

Rotate the vector with an angle in degrees.

```
>>> v = Vector(100, 0)
>>> v.rotate(45)
>>> v
[70.710678118654755, 70.710678118654741]
```

### **static segment\_intersection(*v1, v2, v3, v4*)**

Finds the intersection point between segments (1) $v_1 \rightarrow v_2$  and (2) $v_3 \rightarrow v_4$  and returns it as a vector object.

```
>>> a = (98, 28)
>>> b = (72, 33)
>>> c = (10, -5)
>>> d = (20, 88)
>>> Vector.segment_intersection(a, b, c, d)
None
```

```
>>> a = (0, 0)
>>> b = (10, 10)
>>> c = (0, 10)
>>> d = (10, 0)
>>> Vector.segment_intersection(a, b, c, d)
[5, 5]
```

### **x**

*x* represents the first element in the list.

```
>>> v = Vector(12, 23)
>>> v[0]
12
>>> v.x
12
```

### **y**

*y* represents the second element in the list.

```
>>> v = Vector(12, 23)
>>> v[1]
23
>>> v.y
23
```

## 21.25 Weak Method

The **WeakMethod** is used by the **Clock** class to allow references to a bound method that permits the associated object to be garbage collected. Please refer to *examples/core/clock\_method.py* for more information.

This WeakMethod class is taken from the recipe <http://code.activestate.com/recipes/81253/>, based on the nicodemus version. Many thanks nicodemus!

**class kivy.weakmethod.WeakMethod(*method*)**

Bases: **object**

Implementation of a **weakref** for functions and bound methods.

**is\_dead()**

Returns True if the referenced callable was a bound method and the instance no longer exists. Otherwise, return False.

## 21.26 Weak Proxy

In order to allow garbage collection, the weak proxy provides [weak references](#) to objects. It effectively enhances the [weakref.proxy](#) by adding comparison support.

**class kivy.weakproxy.WeakProxy**

Bases: object

Replacement for weakref.proxy to support comparisons

# Adapters

---

New in version 1.5.0.


Deprecated since version 1.10.0: The feature has been deprecated.

An adapter is a mediating controller-type class that processes and presents data for use in views. It does this by generating models, generally lists of [SelectableView](#) items, that are consumed and presented by views. Views are top-level widgets, such as a [ListView](#), that allow users to scroll through and (optionally) interact with your data.

## 22.1 The Concept

Kivy adapters are modelled on the [Adapter design pattern](#). Conceptually, they play the role of a ‘controller’ between your data and views in a [Model-View-Controller](#) type architecture.

The role of an adapter can be depicted as follows:



## 22.2 The Components

The components involved in this process are:

- **Adapters:** The adapter plays a mediating role between the user interface and your data. It manages the creation of the view elements for the model using the args\_converter to prepare the constructor arguments for your cls/template view items.

The base `Adapter` is subclassed by the `SimpleListAdapter` and `ListAdapter`. The `DictAdapter` is a more advanced and flexible subclass of `ListAdapter`.

*Adapter, SimpleListAdapter, ListAdapter, DictAdapter.*

- **Models:** The data for which an adapter serves as a bridge to views can be any sort of data. However, for convenience, model mixin classes can ease the preparation or shaping of data for use in the system. For selection operations, the `SelectableDataItem` can optionally prepare data items to provide and receive selection information (data items are not required to be “selection-aware”, but in some cases it may be desired).

*SelectableDataItem.*

- **Args Converters:** Argument converters are made by the application programmer to do the work of converting data items to argument dictionaries suitable for instantiating views. In effect, they take each row of your data and create dictionaries that are passed into the constructors of your cls/template which are then used to populate your View.

*List Item View Argument Converters.*

- **Views:** Models of your data are presented to the user via views. Each of your data items creates a corresponding view subitem (the cls or template) presented in a list by the View. The base `AbstractView` currently has one concrete implementation: the `ListView`.

*Abstract View, List View.*

## 22.3 Adapter

New in version 1.5.

Deprecated since version 1.10.0: The feature has been deprecated.

**Warning:** This code is still experimental, and its API is subject to change in a future version.

An [Adapter](#) is a bridge between data and an [AbstractView](#) or one of its subclasses, such as a [ListView](#).

The following arguments can be passed to the constructor to initialise the corresponding properties:

- **data**: for any sort of data to be used in a view. For an [Adapter](#), data can be an object as well as a list, dict, etc. For a [ListAdapter](#), data should be a list. For a [DictAdapter](#), data should be a dict.
- **cls**: the class used to instantiate each list item view instance (Use this or the template argument).
- **template**: a kv template to use to instantiate each list item view instance (Use this or the cls argument).
- **args\_converter**: a function used to transform the data items in preparation for either a cls instantiation or a kv template invocation. If no args\_converter is provided, the data items are assumed to be simple strings.

Please refer to the [adapters](#) documentation for an overview of how adapters are used.

**class** `kivy.adapters.adapter.Adapter(*args, **kwargs)`  
Bases: `kivy.event.EventDispatcher`

An [Adapter](#) is a bridge between data and an [AbstractView](#) or one of its subclasses, such as a [ListView](#).

### **args\_converter**

A function that prepares an args dict for the cls or kv template to build a view from a data item.

If an args\_converter is not provided, a default one is set that assumes simple content in the form of a list of strings.

`args_converter` is an [ObjectProperty](#) and defaults to None.

### **cls**

A class for instantiating a given view item (Use this or template). If this is not set and neither is the template, a [Label](#) is used for the view item.

`cls` is an [ObjectProperty](#) and defaults to None.

### **data**

The data for which a view is to be constructed using either the cls or template provided, together with the args\_converter provided or the default args\_converter.

In this base class, data is an ObjectProperty, so it could be used for a wide variety of single-view needs.

Subclasses may override it in order to use another data type, such as a [ListProperty](#) or [DictProperty](#) as appropriate. For example, in a [ListAdapter](#), data is a [ListProperty](#).

`data` is an [ObjectProperty](#) and defaults to None.

### **get\_cls()**

New in version 1.9.0.

Returns the widget type specified by self.cls. If it is a string, the *Factory* is queried to retrieve the widget class with the given name, otherwise it is returned directly.

### **template**

A kv template for instantiating a given view item (Use this or cls).

*template* is an *ObjectProperty* and defaults to None.

## 22.4 DictAdapter

New in version 1.5.

Deprecated since version 1.10.0: The feature has been deprecated.

**Warning:** This code is still experimental, and its API is subject to change in a future version.

A *DictAdapter* is an adapter around a python dictionary of records. It extends the list-like capabilities of the *ListAdapter*.

If you wish to have a bare-bones list adapter, without selection, use the *SimpleListAdapter*.

**class** `kivy.adapters.dictadapter.DictAdapter(*args, **kwargs)`

Bases: *kivy.adapters.listadapterListAdapter*

A *DictAdapter* is an adapter around a python dictionary of records. It extends the list-like capabilities of the *ListAdapter*.

**cut\_to\_sel(\*args)**

Same as trim\_to\_sel, but intervening list items within the selected range are also cut, leaving only list items that are selected.

sorted\_keys will be updated by update\_for\_new\_data().

**data**

A dict that indexes records by keys that are equivalent to the keys in sorted\_keys, or they are a superset of the keys in sorted\_keys.

The values can be strings, class instances, dicts, etc.

*data* is a *DictProperty* and defaults to None.

**sorted\_keys**

The sorted\_keys list property contains a list of hashable objects (can be strings) that will be used directly if no args\_converter function is provided. If there is an args\_converter, the record received from a lookup of the data, using keys from sorted\_keys, will be passed to it for instantiation of list item view class instances.

*sorted\_keys* is a *ListProperty* and defaults to [].

**trim\_left\_of\_sel(\*args)**

Cut list items with indices in sorted\_keys that are less than the index of the first selected item, if there is a selection.

sorted\_keys will be updated by update\_for\_new\_data().

**trim\_right\_of\_sel(\*args)**

Cut list items with indices in sorted\_keys that are greater than the index of the last selected item, if there is a selection.

sorted\_keys will be updated by update\_for\_new\_data().

### **trim\_to\_sel(\*args)**

Cut list items with indices in sorted\_keys that are less than or greater than the index of the last selected item, if there is a selection. This preserves intervening list items within the selected range.

sorted\_keys will be updated by update\_for\_new\_data().

## 22.5 List Item View Argument Converters

New in version 1.5.

Deprecated since version 1.10.0: The feature has been deprecated.

The default list item args converter for list adapters is a function (shown below) that takes a row index and a string. It returns a dict with the string as the *text* item, along with two properties suited for simple text items with a height of 25.

### 22.5.1 Simple Usage

Argument converters may be normal functions or, as in the case of the default args converter, lambdas:

```
list_item_args_converter = lambda row_index, x: {'text': x,
                                                'size_hint_y': None,
                                                'height': 25}
```

### 22.5.2 Advanced Usage

Typically, having the argument converter perform a simple mapping suffices. There are times, however, when more complex manipulation is required. When using *CompositeListItem*, it is possible to specify a list of cls dictionaries. This allows you to compose a single view item out of multiple classes, each of which can receive their own class constructor arguments via the *kwargs* keyword:

```
args_converter = lambda row_index, rec: \
    {'text': rec['text'],
     'size_hint_y': None,
     'height': 25,
     'cls_dicts': [{ 'cls': ListItemButton,
                     'kwargs': { 'text': rec['text']}},
                   { 'cls': ListItemLabel,
                     'kwargs': { 'text': rec['text'],
                                'is_representing_cls': True}},
                   { 'cls': ListItemButton,
                     'kwargs': { 'text': rec['text']} } ]}
```

Please see the [list\\_composite.py](#) for a complete example.

## 22.6 ListAdapter

New in version 1.5.

Deprecated since version 1.10.0: The feature has been deprecated.

**Warning:** This code is still experimental, and its API is subject to change in a future version.

A [ListAdapter](#) is an adapter around a python list and adds support for selection operations. If you wish to have a bare-bones list adapter, without selection, use a [SimpleListAdapter](#).

From an [Adapter](#), a [ListAdapter](#) inherits cls, template, and args\_converter properties and adds others that control selection behaviour:

- [selection](#): a list of selected items.
- [selection\\_mode](#): one of 'single', 'multiple' or 'none'.
- [allow\\_empty\\_selection](#): a boolean. If False, a selection is forced. If True, and only user or programmatic action will change selection, it can be empty.

A [DictAdapter](#) is a subclass of a [ListAdapter](#). They both dispatch the [on\\_selection\\_change](#) event when selection changes.

Changed in version 1.6.0: Added data = ListProperty([]), which was probably inadvertently deleted at some point. This means that whenever data changes an update will fire, instead of having to reset the data object (Adapter has data defined as an ObjectProperty, so we need to reset it here to ListProperty). See also DictAdapter and its set of data = DictProperty().

**class kivy.adapters.listadapter.ListAdapter(\*args, \*\*kwargs)**  
Bases: [kivy.adapters.adapter.Adapter](#), [kivy.event.EventDispatcher](#)

A base class for adapters interfacing with lists, dictionaries or other collection type data, adding selection, view creation and management functionality.

#### **allow\_empty\_selection**

The allow\_empty\_selection may be used for cascading selection between several list views, or between a list view and an observing view. Such automatic maintenance of the selection is important for all but simple list displays. Set allow\_empty\_selection to False and the selection is auto-initialized and always maintained, so any observing views may likewise be updated to stay in sync.

[allow\\_empty\\_selection](#) is a [BooleanProperty](#) and defaults to True.

#### **cached\_views**

View instances for data items are instantiated and managed by the adapter. Here we maintain a dictionary containing the view instances keyed to the indices in the data.

This dictionary works as a cache. get\_view() only asks for a view from the adapter if one is not already stored for the requested index.

[cached\\_views](#) is a [DictProperty](#) and defaults to {}.

#### **create\_view(index)**

This method is more complicated than the ones in the [Adapter](#) and [SimpleListAdapter](#) classes because here we create bindings for the data items and their children back to the self.handle\_selection() event. We also perform other selection-related tasks to keep item views in sync with the data.

#### **cut\_to\_sel(\*args)**

Same as trim\_to\_sel, but intervening list items within the selected range are also cut, leaving only list items that are selected.

#### **data**

The data list property is redefined here, overriding its definition as an ObjectProperty in the Adapter class. We bind to data so that any changes will trigger updates. See also how the DictAdapter redefines data as a [DictProperty](#).

[data](#) is a [ListProperty](#) and defaults to [].

## **on\_selection\_change(\*args)**

`on_selection_change()` is the default handler for the `on_selection_change` event. You can bind to this event to get notified of selection changes.

### **Parameters**

**adapter:** *ListAdapter* or subclass The instance of the list adapter where the selection changed. Use the adapters `selection` property to see what has been selected.

## **propagate\_selection\_to\_data**

Normally, data items are not selected/deselected because the data items might not have an `is_selected` boolean property – only the item view for a given data item is selected/deselected as part of the maintained selection list. However, if the data items do have an `is_selected` property, or if they mix in *SelectableDataItem*, the selection machinery can propagate selection to data items. This can be useful for storing selection state in a local database or backend database for maintaining state in game play or other similar scenarios. It is a convenience function.

To propagate selection or not?

Consider a shopping list application for shopping for fruits at the market. The app allows for the selection of fruits to buy for each day of the week, presenting seven lists: one for each day of the week. Each list is loaded with all the available fruits, but the selection for each is a subset. There is only one set of fruit data shared between the lists, so it would not make sense to propagate selection to the data because selection in any of the seven lists would clash and mix with that of the others.

However, consider a game that uses the same fruits data for selecting fruits available for fruit-tossing. A given round of play could have a full fruits list, with fruits available for tossing shown selected. If the game is saved and rerun, the full fruits list, with selection marked on each item, would be reloaded correctly if selection is always propagated to the data. You could accomplish the same functionality by writing code to operate on list selection, but having selection stored in the data `ListProperty` might prove convenient in some cases.

---

**Note:** This setting should be set to True if you wish to initialize the view with item views already selected.

---

`propagate_selection_to_data` is a *BooleanProperty* and defaults to False.

## **select\_list(view\_list, extend=True)**

The select call is made for the items in the provided `view_list`.

Arguments:

`view_list`: the list of item views to become the new selection, or to add to the existing selection

`extend`: boolean for whether or not to extend the existing list

## **selection**

The selection list property is the container for selected items.

`selection` is a *ListProperty* and defaults to [].

## **selection\_limit**

When the `selection_mode` is ‘multiple’ and the `selection_limit` is non-negative, this number will limit the number of selected items. It can be set to 1, which is equivalent to single selection. If `selection_limit` is not set, the default value is -1, meaning that no limit will be enforced.

`selection_limit` is a *NumericProperty* and defaults to -1 (no limit).

### **selection\_mode**

The selection\_mode is a string and can be set to one of the following values:

- ‘none’: use the list as a simple list (no select action). This option is here so that selection can be turned off, momentarily or permanently, for an existing list adapter. A [ListAdapter](#) is not meant to be used as a primary no-selection list adapter. Use a [SimpleListAdapter](#) for that.
- ‘single’: multi-touch/click ignored. Single item selection only.
- ‘multiple’: multi-touch / incremental addition to selection allowed; may be limited to a count by setting the [selection\\_limit](#).

`selection_mode` is an [OptionProperty](#) and defaults to ‘single’.

### **trim\_left\_of\_sel(\*args)**

Cut list items with indices in sorted\_keys that are less than the index of the first selected item if there is a selection.

### **trim\_right\_of\_sel(\*args)**

Cut list items with indices in sorted\_keys that are greater than the index of the last selected item if there is a selection.

### **trim\_to\_sel(\*args)**

Cut list items with indices in sorted\_keys that are less than or greater than the index of the last selected item if there is a selection. This preserves intervening list items within the selected range.

## 22.7 SelectableDataItem

New in version 1.5.

Deprecated since version 1.10.0: The feature has been deprecated.

**Warning:** This code is still experimental, and its API is subject to change in a future version.

### 22.7.1 Data Models

Kivy is open about the type of data used in applications built with the system. However, base classes are sometimes needed to ensure data conforms to the requirements of some parts of the system.

A [SelectableDataItem](#) is a basic Python data model class that can be used as a mixin to build data objects that are compatible with Kivy’s [Adapter](#) and selection system and which work with views such as a [ListView](#). A boolean `is_selected` property a requirement.

The default operation of the selection system is to not propagate selection in views such as ListView to the underlying data: selection is by default a view-only operation. However, in some cases, it is useful to propagate selection to the actual data items.

You may, of course, build your own Python data model system as the backend for a Kivy application. For instance, to use the [Google App Engine Data Modeling](#) system with Kivy, you could define your class as follows:

```
from google.appengine.ext import db

class MySelectableDataItem(db.Model):
    # ... other properties
    is_selected = db.BooleanProperty()
```

It is easy to build such a class with plain Python.

```
class kivy.adapters.models.SelectableDataItem(*args, **kwargs)
    Bases: object
```

A mixin class containing requirements for selection operations.

**is\_selected**

A boolean property indicating whether the data item is selected or not.

## 22.8 SimpleListAdapter

New in version 1.5.

Deprecated since version 1.10.0: The feature has been deprecated.

**Warning:** This code is still experimental, and its API is subject to change in a future version.

The *SimpleListAdapter* is used for basic lists. For example, it can be used for displaying a list of read-only strings that do not require user interaction.

```
class kivy.adapters.simplelistadapter.SimpleListAdapter(*args, **kwargs)
    Bases: kivy.adapters.adapter.Adapter
```

A *SimpleListAdapter* is an adapter around a Python list.

From *Adapter*, the *ListAdapter* gets *cls*, *template*, and *args\_converter* properties.

**data**

The *data* list property contains a list of objects (which can be strings) that will be used directly if no *args\_converter* function is provided. If there is an *args\_converter*, the data objects will be passed to it for instantiating the item view class instances.

*data* is a *ListProperty* and defaults to [].



---

# Core Abstraction

---

This module defines the abstraction layers for our core providers and their implementations. For further information, please refer to [Architectural Overview](#) and the [Core Providers and Input Providers](#) section of the documentation.

In most cases, you shouldn't directly use a library that's already covered by the core abstraction. Always try to use our providers first. In case we are missing a feature or method, please let us know by opening a new Bug report instead of relying on your library.

**Warning:** These are **not** widgets! These are just abstractions of the respective functionality. For example, you cannot add a core image to your window. You have to use the image **widget** class instead. If you're really looking for widgets, please refer to [kivy.uix](#) instead.

## 23.1 Audio

Load an audio sound and play it with:

```
from kivy.core.audio import SoundLoader

sound = SoundLoader.load('mytest.wav')
if sound:
    print("Sound found at %s" % sound.source)
    print("Sound is %.3f seconds" % sound.length)
    sound.play()
```

You should not use the Sound class directly. The class returned by [SoundLoader.load\(\)](#) will be the best sound provider for that particular file type, so it might return different Sound classes depending the file type.

### 23.1.1 Event dispatching and state changes

Audio is often processed in parallel to your code. This means you often need to enter the Kivy [eventloop](#) in order to allow events and state changes to be dispatched correctly.

You seldom need to worry about this as Kivy apps typically always require this event loop for the GUI to remain responsive, but it is good to keep this in mind when debugging or running in a [REPL](#) (Read-eval-print loop).

Changed in version 1.10.0: The pygst and gi providers have been removed.

Changed in version 1.8.0: There are now 2 distinct Gstreamer implementations: one using Gi/Gst working for both Python 2+3 with Gstreamer 1.0, and one using PyGST working only for Python 2 + Gstreamer 0.10.

---

**Note:** The core audio library does not support recording audio. If you require this functionality, please refer to the [audiostream](#) extension.

---

## **class** kivy.core.audio.Sound

Bases: [kivy.event.EventDispatcher](#)

Represents a sound to play. This class is abstract, and cannot be used directly.

Use SoundLoader to load a sound.

### Events

*on\_play*: [None](#) Fired when the sound is played.

*on\_stop*: [None](#) Fired when the sound is stopped.

### filename

Deprecated since version 1.3.0: Use [source](#) instead.

### get\_pos()

Returns the current position of the audio file. Returns 0 if not playing.

New in version 1.4.1.

### length

Get length of the sound (in seconds).

### load()

Load the file into memory.

### loop

Set to True if the sound should automatically loop when it finishes.

New in version 1.8.0.

*loop* is a [BooleanProperty](#) and defaults to False.

### pitch

Pitch of a sound. 2 is an octave higher, .5 one below. This is only implemented for SDL2 audio provider yet.

New in version 1.10.0.

*pitch* is a [NumericProperty](#) and defaults to 1.

### play()

Play the file.

### seek(*position*)

Go to the <*position*> (in seconds).

---

**Note:** Most sound providers cannot seek when the audio is stopped. Play then seek.

---

**source**

Filename / source of your audio file.

New in version 1.3.0.

`source` is a *StringProperty* that defaults to None and is read-only. Use the `SoundLoader.load()` for loading audio.

**state**

State of the sound, one of 'stop' or 'play'.

New in version 1.3.0.

`state` is a read-only *OptionProperty*.

**status**

Deprecated since version 1.3.0: Use `state` instead.

**stop()**

Stop playback.

**unload()**

Unload the file from memory.

**volume**

Volume, in the range 0-1. 1 means full volume, 0 means mute.

New in version 1.3.0.

`volume` is a *NumericProperty* and defaults to 1.

**class kivy.core.audio.SoundLoader**

Load a sound, using the best loader for the given file type.

**static load(filename)**

Load a sound, and return a Sound() instance.

**static register(classobj)**

Register a new class to load the sound.

## 23.2 Camera

Core class for acquiring the camera and converting its input into a *Texture*.

Changed in version 1.10.0: The pygst and videocapture providers have been removed.

Changed in version 1.8.0: There is now 2 distinct Gstreamer implementation: one using Gi/Gst working for both Python 2+3 with Gstreamer 1.0, and one using PyGST working only for Python 2 + Gstreamer 0.10.

**class kivy.core.camera.CameraBase(\*\*kwargs)**

Bases: *kivy.event.EventDispatcher*

Abstract Camera Widget class.

Concrete camera classes must implement initialization and frame capturing to a buffer that can be uploaded to the gpu.

**Parameters**

`index: int` Source index of the camera.

**size: tuple (int, int)** Size at which the image is drawn. If no size is specified, it defaults to the resolution of the camera image.

**resolution: tuple (int, int)** Resolution to try to request from the camera. Used in the gstreamer pipeline by forcing the appsink caps to this resolution. If the camera doesn't support the resolution, a negotiation error might be thrown.

#### Events

**on\_load** Fired when the camera is loaded and the texture has become available.

**on\_texture** Fired each time the camera texture is updated.

#### index

Source index of the camera

#### init\_camera()

Initialise the camera (internal)

#### resolution

Resolution of camera capture (width, height)

#### start()

Start the camera acquire

#### stop()

Release the camera

#### texture

Return the camera texture with the latest capture

## 23.3 Clipboard

Core class for accessing the Clipboard. If we are not able to access the system clipboard, a fake one will be used.

Usage example:

```
#:import Clipboard kivy.core.clipboard.Clipboard

Button:
    on_release:
        self.text = Clipboard.paste()
        Clipboard.copy('Data')
```

## 23.4 OpenGL

Select and use the best OpenGL library available. Depending on your system, the core provider can select an OpenGL ES or a 'classic' desktop OpenGL library.

## 23.5 Image

Core classes for loading images and converting them to a **Texture**. The raw image data can be kept in memory for further access.

### 23.5.1 In-memory image loading

New in version 1.9.0: Official support for in-memory loading. Not all the providers support it, but currently SDL2, pygame, pil and imageio work.

To load an image with a filename, you would usually do:

```
from kivy.core.image import Image as CoreImage
im = CoreImage("image.png")
```

You can also load the image data directly from a memory block. Instead of passing the filename, you'll need to pass the data as a BytesIO object together with an "ext" parameter. Both are mandatory:

```
import io
from kivy.core.image import Image as CoreImage
data = io.BytesIO(open("image.png", "rb").read())
im = CoreImage(data, ext="png")
```

By default, the image will not be cached as our internal cache requires a filename. If you want caching, add a filename that represents your file (it will be used only for caching):

```
import io
from kivy.core.image import Image as CoreImage
data = io.BytesIO(open("image.png", "rb").read())
im = CoreImage(data, ext="png", filename="image.png")
```

**class kivy.core.image.Image(arg, \*\*kwargs)**  
Bases: *kivy.event.EventDispatcher*

Load an image and store the size and texture.

Changed in version 1.0.7: *mipmap* attribute has been added. The *texture\_mipmap* and *texture\_rectangle* have been deleted.

Changed in version 1.0.8: An Image widget can change its texture. A new event 'on\_texture' has been introduced. New methods for handling sequenced animation have been added.

#### Parameters

**arg: can be a string (str), Texture, BytesIO or Image object** A string path to the image file or data URI to be loaded; or a Texture object, which will be wrapped in an Image object; or a BytesIO object containing raw image data; or an already existing image object, in which case, a real copy of the given image object will be returned.

**keep\_data: bool, defaults to False** Keep the image data when the texture is created.

**mipmap: bool, defaults to False** Create mipmap for the texture.

**anim\_delay: float, defaults to .25** Delay in seconds between each animation frame.  
Lower values means faster animation.

**ext: str, only with BytesIO arg** File extension to use in determining how to load raw image data.

**filename: str, only with BytesIO arg** Filename to use in the image cache for raw image data.

#### anim\_available

Return True if this Image instance has animation available.

New in version 1.0.8.

**anim\_delay**

Delay between each animation frame. A lower value means faster animation.

New in version 1.0.8.

**anim\_index**

Return the index number of the image currently in the texture.

New in version 1.0.8.

**anim\_reset(allow\_anim)**

Reset an animation if available.

New in version 1.0.8.

**Parameters**

*allow\_anim: bool* Indicate whether the animation should restart playing or not.

Usage:

```
# start/reset animation
image.anim_reset(True)

# or stop the animation
image.anim_reset(False)
```

You can change the animation speed whilst it is playing:

```
# Set to 20 FPS
image.anim_delay = 1 / 20.
```

**filename**

Get/set the filename of image

**height**

Image height

**image**

Get/set the data image object

**static load(filename, \*\*kwargs)**

Load an image

**Parameters**

*filename: str* Filename of the image.

***keep\_data: bool, defaults to False*** Keep the image data when the texture is created.

**load\_memory(data, ext, filename='\_\_inline\_\_')**

(internal) Method to load an image from raw data.

**nocache**

Indicate whether the texture will not be stored in the cache or not.

New in version 1.6.0.

**on\_texture(\*largs)**

**This event is fired when the texture reference or content has changed.** It is normally used for sequenced images.

New in version 1.0.8.

### **read\_pixel(x, y)**

For a given local x/y position, return the pixel color at that position.

**Warning:** This function can only be used with images loaded with the `keep_data=True` keyword. For example:

```
m = Image.load('image.png', keep_data=True)
color = m.read_pixel(150, 150)
```

#### **Parameters**

`x: int` Local x coordinate of the pixel in question.

`y: int` Local y coordinate of the pixel in question.

### **remove\_from\_cache()**

Remove the Image from cache. This facilitates re-loading of images from disk in case the image content has changed.

New in version 1.3.0.

Usage:

```
im = CoreImage('1.jpg')
# -- do something --
im.remove_from_cache()
im = CoreImage('1.jpg')
# this time image will be re-loaded from disk
```

### **save(filename, flipped=False)**

Save image texture to file.

The filename should have the '.png' extension because the texture data read from the GPU is in the RGBA format. 'jpg' might work but has not been heavily tested so some providers might break when using it. Any other extensions are not officially supported.

The `flipped` parameter flips the saved image vertically, and defaults to False.

Example:

```
# Save an core image object
from kivy.core.image import Image
img = Image('hello.png')
img.save('hello2.png')

# Save a texture
texture = Texture.create(...)
img = Image(texture)
img.save('hello3.png')
```

New in version 1.7.0.

Changed in version 1.8.0: Parameter `flipped` added to flip the image before saving, default to False.

#### **size**

Image size (width, height)

#### **texture**

Texture of the image

**width**  
Image width

**class kivy.core.image.ImageData**(*width, height, fmt, data, source=None, flip\_vertical=True, source\_image=None, rowlength=0*)  
Bases: `object`

Container for images and mipmap images. The container will always have at least the mipmap level 0.

**add\_mipmap**(*level, width, height, data, rowlength*)  
Add a image for a specific mipmap level.  
New in version 1.0.7.

**data**  
Image data. (If the image is mipmapped, it will use the level 0)

**flip\_vertical**  
Indicate if the texture will need to be vertically flipped

**fmt**  
Decoded image format, one of a available texture format

**get\_mipmap**(*level*)  
Get the mipmap image at a specific level if it exists  
New in version 1.0.7.

**height**  
Image height in pixels. (If the image is mipmapped, it will use the level 0)

**iterate\_mipmaps()**  
Iterate over all mipmap images available.  
New in version 1.0.7.

**mipmaps**  
Data for each mipmap.

**rowlength**  
Image rowlength. (If the image is mipmapped, it will use the level 0)  
New in version 1.9.0.

**size**  
Image (width, height) in pixels. (If the image is mipmapped, it will use the level 0)

**source**  
Image source, if available

**width**  
Image width in pixels. (If the image is mipmapped, it will use the level 0)

## 23.6 Spelling

Provides abstracted access to a range of spellchecking backends as well as word suggestions. The API is inspired by enchant but other backends can be added that implement the same API.

Spelling currently requires *python-enchant* for all platforms except OSX, where a native implementation exists.

```
>>> from kivy.core.spelling import Spelling
>>> s = Spelling()
>>> s.list_languages()
['en', 'en_CA', 'en_GB', 'en_US']
>>> s.select_language('en_US')
>>> s.suggest('hel0')
[u'hole', u'help', u'helot', u'hello', u'halo', u'hero', u'hell', u'held',
 u'helm', u'he-lo']
```

**class** `kivy.core.spelling.SpellingBase`(*language=None*)  
Bases: `object`

Base class for all spelling providers. Supports some abstract methods for checking words and getting suggestions.

**check**(*word*)

If *word* is a valid word in *self.\_language* (the currently active language), returns True. If the word shouldn't be checked, returns None (e.g. for ""). If it is not a valid word in *self.\_language*, return False.

**Parameters**

*word*: `str` The word to check.

**list\_languages**()

Return a list of all supported languages. E.g. ['en', 'en\_GB', 'en\_US', 'de', ...]

**select\_language**(*language*)

From the set of registered languages, select the first language for *language*.

**Parameters**

*language*: `str` Language identifier. Needs to be one of the options returned by `list_languages()`. Sets the language used for spell checking and word suggestions.

**suggest**(*fragment*)

For a given *fragment* (i.e. part of a word or a word by itself), provide corrections (*fragment* may be misspelled) or completions as a list of strings.

**Parameters**

*fragment*: `str` The word fragment to get suggestions/corrections for. E.g. 'foo' might become 'of', 'food' or 'foot'.

**class** `kivy.core.spelling.NoSuchLangError`

Bases: `exceptions.Exception`

Exception to be raised when a specific language could not be found.

**class** `kivy.core.spelling.NoLanguageSelectedError`

Bases: `exceptions.Exception`

Exception to be raised when a language-using method is called but no language was selected prior to the call.

## 23.7 Text

An abstraction of text creation. Depending of the selected backend, the accuracy of text rendering may vary.

Changed in version 1.5.0: `LabelBase.line_height` added.

Changed in version 1.0.7: The `LabelBase` does not generate any texture if the text has a width  $\leq 1$ .

This is the backend layer for getting text out of different text providers, you should only be using this directly if your needs aren't fulfilled by the `Label`.

Usage example:

```
from kivy.core.text import Label as CoreLabel

...
my_label = CoreLabel()
my_label.text = 'hello'
# the label is usually not drawn until needed, so force it to draw.
my_label.refresh()
# Now access the texture of the label and use it wherever and
# however you may please.
hello_texture = my_label.texture

class kivy.core.text.LabelBase(text='', font_size=12, font_name=None, bold=False,
                               italic=False, underline=False, strikethrough=False,
                               halign='left', valign='bottom', shorten=False,
                               text_size=None, mipmap=False, color=None,
                               line_height=1.0, strip=False, strip_reflow=True,
                               shorten_from='center', split_str=' ', uni-
                               code_errors='replace', font_hinting='normal',
                               font_kerning=True, font_blended=True, outline_
                               width=None, outline_color=None, **kwargs)
```

Bases: `object`

Core text label. This is the abstract class used by different backends to render text.

**Warning:** The core text label can't be changed at runtime. You must recreate one.

## Parameters

**`font_size: int, defaults to 12`** Font size of the text  
**`font_name: str, defaults to DEFAULT_FONT`** Font name of the text  
**`bold: bool, defaults to False`** Activate “bold” text style  
**`italic: bool, defaults to False`** Activate “italic” text style  
**`text_size: tuple, defaults to (None, None)`** Add constraint to render the text (inside a bounding box). If no size is given, the label size will be set to the text size.  
**`padding: float, defaults to None`** If it's a float, it will set padding\_x and padding\_y  
**`padding_x: float, defaults to 0.0`** Left/right padding  
**`padding_y: float, defaults to 0.0`** Top/bottom padding  
**`halign: str, defaults to "left"`** Horizontal text alignment inside the bounding box  
**`valign: str, defaults to "bottom"`** Vertical text alignment inside the bounding box  
**`shorten: bool, defaults to False`** Indicate whether the label should attempt to shorten its textual contents as much as possible if a `size` is given. Setting this to True without an appropriately set size will lead to unexpected results.

**shorten\_from: str, defaults to center** The side from which we should shorten the text from, can be left, right, or center. E.g. if left, the ellipsis will appear towards the left side and it will display as much text starting from the right as possible.

**split\_str: string, defaults to '' (space)** The string to use to split the words by when shortening. If empty, we can split after every character filling up the line as much as possible.

**max\_lines: int, defaults to 0 (unlimited)** If set, this indicate how maximum line are allowed to render the text. Works only if a limitation on text\_size is set.

**mipmap: bool, defaults to False** Create a mipmap for the texture

**strip: bool, defaults to False** Whether each row of text has its leading and trailing spaces stripped. If *halign* is *justify* it is implicitly True.

**strip\_reflow: bool, defaults to True** Whether text that has been reflowed into a second line should be stripped, even if *strip* is False. This is only in effect when *size\_hint\_x* is not None, because otherwise lines are never split.

**unicode\_errors: str, defaults to 'replace'** How to handle unicode decode errors. Can be 'strict', 'replace' or 'ignore'.

**outline\_width: int, defaults to None** Width in pixels for the outline.

**outline\_color: tuple, defaults to (0, 0, 0)** Color of the outline.

Changed in version 1.10.0: *outline\_width* and *outline\_color* were added.

Changed in version 1.9.0: *strip*, *strip\_reflow*, *shorten\_from*, *split\_str*, and *unicode\_errors* were added.

Changed in version 1.9.0: *padding\_x* and *padding\_y* has been fixed to work as expected. In the past, the text was padded by the negative of their values.

Changed in version 1.8.0: *max\_lines* parameters has been added.

Changed in version 1.0.8: *size* have been deprecated and replaced with *text\_size*.

Changed in version 1.0.7: The *valign* is now respected. This wasn't the case previously so you might have an issue in your application if you have not considered this.

### **content\_height**

Return the content height; i.e. the height of the text without any padding.

### **content\_size**

Return the content size (width, height)

### **content\_width**

Return the content width; i.e. the width of the text without any padding.

### **fontid**

Return a unique id for all font parameters

### **get\_cached\_extents()**

Returns a cached version of the *get\_extents()* function.

```
>>> func = self._get_cached_extents()
>>> func
<built-in method size of pygame.font.Font object at 0x01E45650>
>>> func('a line')
(36, 18)
```

**Warning:** This method returns a size measuring function that is valid for the font settings used at the time `get_cached_extents()` was called. Any change in the font settings will render the returned function incorrect. You should only use this if you know what you're doing.

New in version 1.9.0.

**get\_extents(*text*)**

Return a tuple (width, height) indicating the size of the specified text

**static get\_system\_fonts\_dir()**

Return the directories used by the system for fonts.

**label**

Get/Set the text

**refresh()**

Force re-rendering of the text

**static register(*name, fn\_regular, fn\_italic=None, fn\_bold=None, fn\_bolditalic=None*)**

Register an alias for a Font.

New in version 1.1.0.

If you're using a ttf directly, you might not be able to use the bold/italic properties of the ttf version. If the font is delivered in multiple files (one regular, one italic and one bold), then you need to register these files and use the alias instead.

All the `fn_regular/fn_italic/fn_bold` parameters are resolved with `kivy.resources.resource_find()`. If `fn_italic/fn_bold` are None, `fn_regular` will be used instead.

**render(*real=False*)**

Return a tuple (width, height) to create the image with the user constraints. (width, height) includes the padding.

**shorten(*text, margin=2*)**

Shortens the text to fit into a single line by the width specified by `text_size` [0]. If `text_size` [0] is None, it returns text text unchanged.

`split_str` and `shorten_from` determines how the text is shortened.

**Params** *text* str, the text to be shortened. *margin* int, the amount of space to leave between the margins and the text. This is in addition to `padding_x`.

**Returns** the text shortened to fit into a single line.

**text**

Get/Set the text

**text\_size**

Get/set the (width, height) of the 'constrained rendering box

**usersize**

(deprecated) Use `text_size` instead.

### 23.7.1 Text layout

An internal module for laying out text according to options and constraints. This is not part of the API and may change at any time.

## `kivy.core.text.text_layout.layout_text()`

Lays out text into a series of `LayoutWord` and `LayoutLine` instances according to the options specified.

The function is designed to be called many times, each time new text is appended to the last line (or first line if appending upwards), unless a newline is present in the text. Each text appended is described by its own options which can change between successive calls. If the text is constrained, we stop as soon as the constraint is reached.

### Parameters

**`text: string or bytes`** the text to be broken down into lines. If lines is not empty, the text is added to the last line (or first line if `append_down` is False) until a newline is reached which creates a new line in `lines`. See `LayoutLine`.

**`lines: list`** a list of `LayoutLine` instances, each describing a line of the text. Calls to `layout_text()` append or create new `LayoutLine` instances in `lines`.

**`size: 2-tuple of ints`** the size of the laid out text so far. Upon first call it should probably be (0, 0), afterwards it should be the (w, h) returned by this function in a previous call. When size reaches the constraining size, `text_size`, we stop adding lines and return True for the clipped parameter. size includes the x and y padding.

**`text_size: 2-tuple of ints or None`**. the size constraint on the laid out text. If either element is None, the text is not constrained in that dimension. For example, (None, 200) will constrain the height, including padding to 200, while the width is unconstrained. The first line, and the first character of a line is always returned, even if it exceeds the constraint. The value be changed between different calls.

**`options: dict`** the label options of this `text`. The options are saved with each word allowing different words to have different options from successive calls.

Note, `options` must include a `space_width` key with a value indicating the width of a space for that set of options.

**`get_extents: callable`** a function called with a string, which returns a tuple containing the width, height of the string.

**`append_down: bool`** Whether successive calls to the function appends lines before or after the existing lines. If True, they are appended to the last line and below it. If False, it's appended at the first line and above. For example, if False, everything after the last newline in `text` is appended to the first line in `lines`. Everything before the last newline is inserted at the start of `lines` in same order as text; that is we do not invert the line order.

This allows laying out from top to bottom until the constrained is reached, or from bottom to top until the constrained is reached.

**`complete: bool`** whether this text complete lines. It use is that normally is strip in `options` is True, all leading and trailing spaces are removed from each line except from the last line (or first line if `append_down` is False) which only removes leading spaces. That's because further text can still be appended to the last line so we cannot strip them. If `complete` is True, it indicates no further text is coming and all lines will be stripped.

The function can also be called with `text` set to the empty string and `complete` set to True in order for the last (first) line to be stripped.

**Returns** 3-tuple, (w, h, clipped). w and h is the width and height of the text in `lines` so far and includes padding. This can be larger than `text_size`, e.g. if not even a single

fitted, the first line would still be returned. *clipped* is True if not all the text has been added to lines because w, h reached the constrained size.

Following is a simple example with no padding and no stripping:

```
>>> from kivy.core.text import Label
>>> from kivy.core.text.text_layout import layout_text

>>> l = Label()
>>> lines = []
>>> # layout text with width constraint by 50, but no height constraint
>>> w, h, clipped = layout_text('heres some text\nnah, another line',
... lines, (0, 0), (50, None), l.options, l.get_cached_extents(), True,
... False)
>>> w, h, clipped
(46, 90, False)
# now add text from bottom up, and constrain width only be 100
>>> w, h, clipped = layout_text('\nyay, more text\n', lines, (w, h),
... (100, None), l.options, l.get_cached_extents(), False, True)
>>> w, h, clipped
(77, 120, 0)
>>> for line in lines:
...     print('line w: {}, line h: {}'.format(line.w, line.h))
...     for word in line.words:
...         print('w: {}, h: {}, text: {}'.format(word.lw, word.lh,
... [word.text]))
line w: 0, line h: 15
line w: 77, line h: 15
w: 77, h: 15, text: ['yay, more text']
line w: 31, line h: 15
w: 31, h: 15, text: ['heres']
line w: 34, line h: 15
w: 34, h: 15, text: [' some']
line w: 24, line h: 15
w: 24, h: 15, text: [' text']
line w: 17, line h: 15
w: 17, h: 15, text: ['ah,']
line w: 46, line h: 15
w: 46, h: 15, text: [' another']
line w: 23, line h: 15
w: 23, h: 15, text: [' line']
```

## class kivy.core.text.text\_layout.LayoutWord

Bases: object

Formally describes a word contained in a line. The name word simply means a chunk of text and can be used to describe any text.

A word has some width, height and is rendered according to options saved in [options](#). See [LayoutLine](#) for its usage.

### Parameters

*options*: dict the label options dictionary for this word.

*lw*: int the width of the text in pixels.

*lh*: int the height of the text in pixels.

*text*: string the text of the word.

## class kivy.core.text.text\_layout.LayoutLine

Bases: object

Formally describes a line of text. A line of text is composed of many *LayoutWord* instances, each with its own text, size and options.

A *LayoutLine* instance does not always imply that the words contained in the line ended with a newline. That is only the case if *is\_last\_line* is True. For example a single real line of text can be split across multiple *LayoutLine* instances if the whole line doesn't fit in the constrained width.

#### Parameters

*x: int* the location in a texture from where the left side of this line is began drawn.

*y: int* the location in a texture from where the bottom of this line is drawn.

*w: int* the width of the line. This is the sum of the individual widths of its *LayoutWord* instances. Does not include any padding.

*h: int* the height of the line. This is the maximum of the individual heights of its *LayoutWord* instances multiplied by the *line\_height* of these instance. So this is larger then the word height.

*is\_last\_line: bool* whether this line was the last line in a paragraph. When True, it implies that the line was followed by a newline. Newlines should not be included in the text of words, but is implicit by setting this to True.

*line\_wrap: bool* whether this line is continued from a previous line which didn't fit into a constrained width and was therefore split across multiple *LayoutLine* instances. *line\_wrap* can be True or False independently of *is\_last\_line*.

*words: python list* a list that contains only *LayoutWord* instances describing the text of the line.

### 23.7.2 Text Markup

New in version 1.1.0.

We provide a simple text-markup for inline text styling. The syntax look the same as the [BBCode](#).

A tag is defined as `[tag]`, and should have a corresponding `[/tag]` closing tag. For example:

```
[b]Hello [color=ff0000]world[/color][/b]
```

The following tags are available:

`[b] [/b]` Activate bold text

`[i] [/i]` Activate italic text

`[u] [/u]` Underlined text

`[s] [/s]` Strikethrough text

`[font=<str>] [/font]` Change the font

`[size=<size>] [/size]` Change the font size. `<size>` should be an integer, optionally with a unit (i.e. 16sp)

`[color=#<color>] [/color]` Change the text color

`[ref=<str>] [/ref]` Add an interactive zone. The reference + all the word box inside the reference will be available in [MarkupLabel.refs](#)

`[anchor=<str>]` Put an anchor in the text. You can get the position of your anchor within the text with [MarkupLabel.anchors](#)

`[sub] [/sub]` Display the text at a subscript position relative to the text before it.

**[sup] [/sup]** Display the text at a superscript position relative to the text before it.

If you need to escape the markup from the current text, use `kivy.utils.escape_markup()`.

**class** `kivy.core.text.markup.MarkupLabel(*args, **kwargs)`  
Bases: `kivy.core.text.LabelBase`

Markup text label.

See module documentation for more informations.

### anchors

Get the position of all the [anchor=...]:

```
{ 'anchorA': (x, y), 'anchorB': (x, y), ... }
```

### markup

Return the text with all the markup splitted:

```
>>> MarkupLabel('[b]Hello world[/b]').markup
>>> ('[b]', 'Hello world', '[/b]')
```

### refs

Get the bounding box of all the [ref=...]:

```
{ 'refA': ((x1, y1, x2, y2), (x1, y1, x2, y2)), ... }
```

### shorten\_post(*lines, w, h, margin=2*)

Shortens the text to a single line according to the label options.

This function operates on a text that has already been laid out because for markup, parts of text can have different size and options.

If `text_size` [0] is None, the lines are returned unchanged. Otherwise, the lines are converted to a single line fitting within the constrained width, `text_size` [0].

**Params** *lines*: list of `LayoutLine` instances describing the text. *w*: int, the width of the text in lines, including padding. *h*: int, the height of the text in lines, including padding. *margin* int, the additional space left on the sides. This is in addition to `padding_x`.

**Returns** 3-tuple of (xw, h, lines), where w, and h is similar to the input and contains the resulting width / height of the text, including padding. lines, is a list containing a single `LayoutLine`, which contains the words for the line.

## 23.8 Video

Core class for reading video files and managing the video `Texture`.

Changed in version 1.10.0: The pyglet, pygst and gi providers have been removed.

Changed in version 1.8.0: There are now 2 distinct Gstreamer implementations: one using Gi/Gst working for both Python 2+3 with Gstreamer 1.0, and one using PyGST working only for Python 2 + Gstreamer 0.10.

---

**Note:** Recording is not supported.

---

**class** `kivy.core.video.VideoBase(**kwargs)`  
Bases: `kivy.event.EventDispatcher`

VideoBase, a class used to implement a video reader.

#### Parameters

***filename: str*** Filename of the video. Can be a file or an URI.

***eos: str, defaults to 'pause'*** Action to take when EOS is hit. Can be one of 'pause', 'stop' or 'loop'.

Changed in version unknown: added 'pause'

***async: bool, defaults to True*** Load the video asynchronously (may be not supported by all providers).

***autoplay: bool, defaults to False*** Auto play the video on init.

#### Events

***on\_eos*** Fired when EOS is hit.

***on\_load*** Fired when the video is loaded and the texture is available.

***on\_frame*** Fired when a new frame is written to the texture.

#### **duration**

Get the video duration (in seconds)

#### **filename**

Get/set the filename/uri of the current video

#### **load()**

Load the video from the current filename

#### **pause()**

Pause the video

New in version 1.4.0.

#### **play()**

Play the video

#### **position**

Get/set the position in the video (in seconds)

#### **seek(percent, precise=True)**

Move on percent position

#### **state**

Get the video playing status

#### **stop()**

Stop the video playing

#### **texture**

Get the video texture

#### **unload()**

Unload the actual video

#### **volume**

Get/set the volume in the video (1.0 = 100%)

## 23.9 Window

Core class for creating the default Kivy window. Kivy supports only one window per application: please don't try to create more than one.

```
class kivy.core.window.Keyboard(**kwargs)
Bases: kivy.event.EventDispatcher
```

Keyboard interface that is returned by `WindowBase.request_keyboard()`. When you request a keyboard, you'll get an instance of this class. Whatever the keyboard input is (system or virtual keyboard), you'll receive events through this instance.

### Events

`on_key_down: keycode, text, modifiers` Fired when a new key is pressed down  
`on_key_up: keycode` Fired when a key is released (up)

Here is an example of how to request a Keyboard in accordance with the current configuration:

```
import kivy
kivy.require('1.0.8')

from kivy.core.window import Window
from kivy.uix.widget import Widget

class MyKeyboardListener(Widget):

    def __init__(self, **kwargs):
        super(MyKeyboardListener, self).__init__(**kwargs)
        self._keyboard = Window.request_keyboard(
            self._keyboard_closed, self, 'text')
        if self._keyboard.widget:
            # If it exists, this widget is a VKeyboard object which you can_
            # use
            # to change the keyboard layout.
            pass
        self._keyboard.bind(on_key_down=self._on_keyboard_down)

    def _keyboard_closed(self):
        print('My keyboard have been closed!')
        self._keyboard.unbind(on_key_down=self._on_keyboard_down)
        self._keyboard = None

    def _on_keyboard_down(self, keyboard, keycode, text, modifiers):
        print('The key', keycode, 'have been pressed')
        print(' - text is %r' % text)
        print(' - modifiers are %r' % modifiers)

        # Keycode is composed of an integer + a string
        # If we hit escape, release the keyboard
        if keycode[1] == 'escape':
            keyboard.release()

        # Return True to accept the key. Otherwise, it will be used by
        # the system.
        return True

if __name__ == '__main__':
    from kivy.base import runTouchApp
    runTouchApp(MyKeyboardListener())
```

### callback = None

Callback that will be called when the keyboard is released

**keycode\_to\_string(*value*)**  
Convert a keycode number to a string according to the `Keyboard.keycodes`. If the value is not found in the keycodes, it will return ''.

**release()**  
Call this method to release the current keyboard. This will ensure that the keyboard is no longer attached to your callback.

**string\_to\_keycode(*value*)**  
Convert a string to a keycode number according to the `Keyboard.keycodes`. If the value is not found in the keycodes, it will return -1.

**target = None**  
Target that have requested the keyboard

**widget = None**  
VKeyboard widget, if allowed by the configuration

**window = None**  
Window which the keyboard is attached too

**class kivy.core.window.WindowBase(\*\*kwargs)**  
Bases: `kivy.event.EventDispatcher`

WindowBase is an abstract window widget for any window implementation.

**Parameters**

- borderless*: str, one of ('0', '1')** Set the window border state. Check the [config](#) documentation for a more detailed explanation on the values.
- fullscreen*: str, one of ('0', '1', 'auto', 'fake')** Make the window fullscreen. Check the [config](#) documentation for a more detailed explanation on the values.
- width*: int** Width of the window.
- height*: int** Height of the window.
- minimum\_width*: int** Minimum width of the window (only works for sdl2 window provider).
- minimum\_height*: int** Minimum height of the window (only works for sdl2 window provider).
- allow\_screensaver*: bool** Allow the device to show a screen saver, or to go to sleep on mobile devices. Defaults to True. Only works for sdl2 window provider.

**Events**

- on\_motion*: etype, motionevent** Fired when a new [MotionEvent](#) is dispatched
- on\_touch\_down***: Fired when a new touch event is initiated.
- on\_touch\_move***: Fired when an existing touch event changes location.
- on\_touch\_up***: Fired when an existing touch event is terminated.
- on\_draw***: Fired when the Window is being drawn.
- on\_flip***: Fired when the Window GL surface is being flipped.
- on\_rotate*: rotation** Fired when the Window is being rotated.
- on\_close***: Fired when the Window is closed.
- on\_request\_close***: Fired when the event loop wants to close the window, or if the escape key is pressed and `exit_on_escape` is `True`. If a function bound to this event returns `True`, the window will not be closed. If the the event is triggered because

of the keyboard escape key, the keyword argument `source` is dispatched along with a value of `keyboard` to the bound functions.

New in version 1.9.0.

**`on_cursor_enter`:** Fired when the cursor enters the window.

New in version 1.9.1.

**`on_cursor_leave`:** Fired when the cursor leaves the window.

New in version 1.9.1.

**`on_minimize`:** Fired when the window is minimized.

New in version 1.10.0.

**`on_maximize`:** Fired when the window is maximized.

New in version 1.10.0.

**`on_restore`:** Fired when the window is restored.

New in version 1.10.0.

**`on_hide`:** Fired when the window is hidden.

New in version 1.10.0.

**`on_show`:** Fired when the window is shown.

New in version 1.10.0.

**`on_keyboard: key, scancode, codepoint, modifier`** Fired when the keyboard is used for input.

Changed in version 1.3.0: The `unicode` parameter has been deprecated in favor of `codepoint`, and will be removed completely in future versions.

**`on_key_down: key, scancode, codepoint, modifier`** Fired when a key pressed.

Changed in version 1.3.0: The `unicode` parameter has been deprecated in favor of `codepoint`, and will be removed completely in future versions.

**`on_key_up: key, scancode, codepoint`** Fired when a key is released.

Changed in version 1.3.0: The `unicode` parameter has been deprecated in favor of `codepoint`, and will be removed completely in future versions.

**`on_dropfile: str`** Fired when a file is dropped on the application.

---

**Note:** This event doesn't work for apps with elevated permissions, because the OS API calls are filtered. Check issue [#4999](#) for pointers to workarounds.

---

**`on_memorywarning`:** Fired when the platform have memory issue (iOS / Android mostly) You can listen to this one, and clean whatever you can.

New in version 1.9.0.

**`add_widget(widget, canvas=None)`**

Add a widget to a window

**`allow_screensaver`**

Whether the screen saver is enabled, or on mobile devices whether the device is allowed to go to sleep while the app is open.

New in version 1.10.0.

*allow\_screensaver* is a *BooleanProperty* and defaults to True.

### **borderless**

When set to True, this property removes the window border/decoration. Check the *config* documentation for a more detailed explanation on the values.

New in version 1.9.0.

*borderless* is a *BooleanProperty* and defaults to False.

### **center**

Center of the rotated window.

New in version 1.0.9.

*center* is an *AliasProperty*.

### **children**

List of the children of this window.

*children* is a *ListProperty* instance and defaults to an empty list.

Use *add\_widget()* and *remove\_widget()* to manipulate the list of children. Don't manipulate the list directly unless you know what you are doing.

### **clear()**

Clear the window with the background color

### **clearcolor**

Color used to clear the window.

```
from kivy.core.window import Window

# red background color
Window.clearcolor = (1, 0, 0, 1)

# don't clear background at all
Window.clearcolor = None
```

Changed in version 1.7.2: The clearcolor default value is now: (0, 0, 0, 1).

New in version 1.0.9.

*clearcolor* is an *AliasProperty* and defaults to (0, 0, 0, 1).

### **close()**

Close the window

### **create\_window(\*largs)**

Will create the main window and configure it.

**Warning:** This method is called automatically at runtime. If you call it, it will recreate a RenderContext and Canvas. This means you'll have a new graphics tree, and the old one will be unusable.

This method exist to permit the creation of a new OpenGL context AFTER closing the first one. (Like using runTouchApp() and stopTouchApp()).

This method has only been tested in a unittest environment and is not suitable for Applications.

Again, don't use this method unless you know exactly what you are doing!

**dpi()**

Return the DPI of the screen. If the implementation doesn't support any DPI lookup, it will just return 96.

**Warning:** This value is not cross-platform. Use `kivy.base.EventLoop.dpi` instead.

**flip()**

Flip between buffers

**focus**

Check whether or not the window currently has focus.

New in version 1.9.1.

`focus` is a read-only *AliasProperty* and defaults to True.

**fullscreen**

This property sets the fullscreen mode of the window. Available options are: True, False, 'auto' and 'fake'. Check the `config` documentation for more detailed explanations on these values.

`fullscreen` is an *OptionProperty* and defaults to False.

New in version 1.2.0.

---

**Note:** The 'fake' option has been deprecated, use the `borderless` property instead.

---

**grab\_mouse()**

Grab mouse - so won't leave window

New in version 1.10.0.

---

**Note:** This feature requires the SDL2 window provider.

---

**height**

Rotated window height.

`height` is a read-only *AliasProperty*.

**hide()**

Hides the window. This method should be used on desktop platforms only.

New in version 1.9.0.

---

**Note:** This feature requires the SDL2 window provider and is currently only supported on desktop platforms.

---

**icon**

A path to the window icon.

New in version 1.1.2.

`icon` is a *StringProperty*.

**keyboard\_anim\_args = {'t': 'in\_out\_quart', 'd': 0.5}**

The attributes for animating softkeyboard/IME. *t* = transition, *d* = duration. This value will have no effect on desktops.

New in version 1.10.0.

`keyboard_anim_args` is a dict and defaults to {'t': 'in\_out\_quart', 'd': .5}.

### **keyboard\_height**

Returns the height of the softkeyboard/IME on mobile platforms. Will return 0 if not on mobile platform or if IME is not active.

---

**Note:** This property returns 0 with SDL2 on Android, but setting Window.softinput\_mode does works.

---

New in version 1.9.0.

`keyboard_height` is a read-only *AliasProperty* and defaults to 0.

### **keyboard\_padding**

The padding to have between the softkeyboard/IME & target or bottom of window. Will have no effect on desktops.

New in version 1.10.0.

`keyboard_padding` is a *NumericProperty* and defaults to 0.

### **left**

Left position of the window.

---

**Note:** It's an SDL2 property with [0, 0] in the top-left corner.

---

Changed in version 1.10.0: `left` is now an *AliasProperty*

New in version 1.9.1.

`left` is an *AliasProperty* and defaults to the position set in *Config*.

### **maximize()**

Maximizes the window. This method should be used on desktop platforms only.

New in version 1.9.0.

---

**Note:** This feature requires the SDL2 window provider and is currently only supported on desktop platforms.

---

### **minimize()**

Minimizes the window. This method should be used on desktop platforms only.

New in version 1.9.0.

---

**Note:** This feature requires the SDL2 window provider and is currently only supported on desktop platforms.

---

### **minimum\_height**

The minimum height to restrict the window to.

New in version 1.9.1.

`minimum_height` is a *NumericProperty* and defaults to 0.

### **minimum\_width**

The minimum width to restrict the window to.

New in version 1.9.1.

*minimum\_width* is a *NumericProperty* and defaults to 0.

#### **modifiers**

List of keyboard modifiers currently active.

New in version 1.0.9.

*modifiers* is an *AliasProperty*.

#### **mouse\_pos**

2d position of the mouse within the window.

New in version 1.2.0.

*mouse\_pos* is an *ObjectProperty* and defaults to [0, 0].

#### **on\_close(\*args)**

Event called when the window is closed.

#### **on\_cursor\_enter(\*args)**

Event called when the cursor enters the window.

New in version 1.9.1.

---

**Note:** This feature requires the SDL2 window provider.

---

#### **on\_cursor\_leave(\*args)**

Event called when the cursor leaves the window.

New in version 1.9.1.

---

**Note:** This feature requires the SDL2 window provider.

---

#### **on\_dropfile(filename)**

Event called when a file is dropped on the application.

**Warning:** This event currently works with sdl2 window provider, on pygame window provider and OS X with a patched version of pygame. This event is left in place for further evolution (ios, android etc.)

New in version 1.2.0.

#### **on\_flip()**

Flip between buffers (event)

#### **on\_hide(\*args)**

Event called when the window is hidden.

New in version 1.10.0.

---

**Note:** This feature requires the SDL2 window provider.

---

#### **on\_joy\_axis(stickid, axisid, value)**

Event called when a joystick has a stick or other axis moved.

New in version 1.9.0.

**on\_joy\_ball**(*stickid*, *ballid*, *value*)

Event called when a joystick has a ball moved.

New in version 1.9.0.

**on\_joy\_button\_down**(*stickid*, *buttonid*)

Event called when a joystick has a button pressed.

New in version 1.9.0.

**on\_joy\_button\_up**(*stickid*, *buttonid*)

Event called when a joystick has a button released.

New in version 1.9.0.

**on\_joy\_hat**(*stickid*, *hatid*, *value*)

Event called when a joystick has a hat/dpad moved.

New in version 1.9.0.

**on\_key\_down**(*key*, *scancode=None*, *codepoint=None*, *modifier=None*, *\*\*kwargs*)

Event called when a key is down (same arguments as on\_keyboard)

**on\_key\_up**(*key*, *scancode=None*, *codepoint=None*, *modifier=None*, *\*\*kwargs*)

Event called when a key is released (same arguments as on\_keyboard).

**on\_keyboard**(*key*, *scancode=None*, *codepoint=None*, *modifier=None*, *\*\*kwargs*)

Event called when keyboard is used.

**Warning:** Some providers may omit *scancode*, *codepoint* and/or *modifier*.

**on\_maximize**(\**args*)

Event called when the window is maximized.

New in version 1.10.0.

---

**Note:** This feature requires the SDL2 window provider.

---

**on\_memorywarning()**

Event called when the platform have memory issue. Your goal is to clear the cache in your app as much as you can, release unused widgets, do garbage collection etc.

Currently, this event is fired only from the SDL2 provider, for iOS and Android.

New in version 1.9.0.

**on\_minimize**(\**args*)

Event called when the window is minimized.

New in version 1.10.0.

---

**Note:** This feature requires the SDL2 window provider.

---

**on\_motion**(*etype*, *me*)

Event called when a Motion Event is received.

**Parameters**

*etype*: str One of 'begin', 'update', 'end'

*me*: **MotionEvent** The Motion Event currently dispatched.

**on\_mouse\_down**(*x, y, button, modifiers*)

Event called when the mouse is used (pressed/released).

**on\_mouse\_move**(*x, y, modifiers*)

Event called when the mouse is moved with buttons pressed.

**on\_mouse\_up**(*x, y, button, modifiers*)

Event called when the mouse is moved with buttons pressed.

**on\_request\_close**(\**largs*, \*\**kargs*)

Event called before we close the window. If a bound function returns *True*, the window will not be closed. If the event is triggered because of the keyboard escape key, the keyword argument *source* is dispatched along with a value of *keyboard* to the bound functions.

**Warning:** When the bound function returns True the window will not be closed, so use with care because the user would not be able to close the program, even if the red X is clicked.

**on\_resize**(*width, height*)

Event called when the window is resized.

**on\_restore**(\**largs*)

Event called when the window is restored.

New in version 1.10.0.

---

**Note:** This feature requires the SDL2 window provider.

---

**on\_rotate**(*rotation*)

Event called when the screen has been rotated.

**on\_show**(\**largs*)

Event called when the window is shown.

New in version 1.10.0.

---

**Note:** This feature requires the SDL2 window provider.

---

**on\_textinput**(*text*)

Event called when text: i.e. alpha numeric non control keys or set of keys is entered. As it is not guaranteed whether we get one character or multiple ones, this event supports handling multiple characters.

New in version 1.9.0.

**on\_touch\_down**(*touch*)

Event called when a touch down event is initiated.

Changed in version 1.9.0: The touch *pos* is now transformed to window coordinates before this method is called. Before, the touch *pos* coordinate would be (0, 0) when this method was called.

**on\_touch\_move**(*touch*)

Event called when a touch event moves (changes location).

Changed in version 1.9.0: The touch *pos* is now transformed to window coordinates before this method is called. Before, the touch *pos* coordinate would be (0, 0) when this method was called.

**on\_touch\_up(*touch*)**

Event called when a touch event is released (terminated).

Changed in version 1.9.0: The touch *pos* is now transformed to window coordinates before this method is called. Before, the touch *pos* coordinate would be  $(0, 0)$  when this method was called.

**parent**

Parent of this window.

*parent* is a *ObjectProperty* instance and defaults to None. When created, the parent is set to the window itself. You must take care of it if you are doing a recursive check.

**raise\_window()**

Raise the window. This method should be used on desktop platforms only.

New in version 1.9.1.

---

**Note:** This feature requires the SDL2 window provider and is currently only supported on desktop platforms.

---

**release\_all\_keyboards()**

New in version 1.0.8.

This will ensure that no virtual keyboard / system keyboard is requested. All instances will be closed.

**release\_keyboard(*target=None*)**

New in version 1.0.4.

Internal method for the widget to release the real-keyboard. Check *request\_keyboard()* to understand how it works.

**remove\_widget(*widget*)**

Remove a widget from a window

**request\_keyboard(*callback, target, input\_type='text'*)**

New in version 1.0.4.

Internal widget method to request the keyboard. This method is rarely required by the end-user as it is handled automatically by the *TextInput*. We expose it in case you want to handle the keyboard manually for unique input scenarios.

A widget can request the keyboard, indicating a callback to call when the keyboard is released (or taken by another widget).

### Parameters

***callback: func*** Callback that will be called when the keyboard is closed. This can be because somebody else requested the keyboard or the user closed it.

***target: Widget*** Attach the keyboard to the specified *target*. This should be the widget that requested the keyboard. Ensure you have a different target attached to each keyboard if you're working in a multi user mode.

New in version 1.0.8.

***input\_type: string*** Choose the type of soft keyboard to request. Can be one of 'text', 'number', 'url', 'mail', 'datetime', 'tel', 'address'.

---

**Note:** *input\_type* is currently only honored on mobile devices.

---

New in version 1.8.0.

**Return** An instance of [Keyboard](#) containing the callback, target, and if the configuration allows it, a [VKeyboard](#) instance attached as a `.widget` property.

---

**Note:** The behavior of this function is heavily influenced by the current `keyboard_mode`. Please see the Config's [configuration tokens](#) section for more information.

---

### **restore()**

Restores the size and position of a maximized or minimized window. This method should be used on desktop platforms only.

New in version 1.9.0.

---

**Note:** This feature requires the SDL2 window provider and is currently only supported on desktop platforms.

---

### **rotation**

Get/set the window content rotation. Can be one of 0, 90, 180, 270 degrees.

New in version 1.0.9.

*rotation* is an [AliasProperty](#).

### **screenshot(*name*=`'screenshot{:04d}.png'`)**

Save the actual displayed image to a file.

### **set\_icon(*filename*)**

Set the icon of the window.

New in version 1.0.5.

### **set\_system\_cursor(*cursor\_name*)**

Set type of a mouse cursor in the Window.

It can be one of 'arrow', 'ibeam', 'wait', 'crosshair', 'wait\_arrow', 'size\_nwse', 'size\_nesw', 'size\_we', 'size\_ns', 'size\_all', 'no', or 'hand'.

On some platforms there might not be a specific cursor supported and such an option falls back to one of the substitutable alternatives:

	Windows	MacOS	Linux X11	Linux Wayland
arrow	arrow	arrow	arrow	arrow
ibeam	ibeam	ibeam	ibeam	ibeam
wait	wait	arrow	wait	wait
crosshair	crosshair	crosshair	crosshair	hand
wait_arrow	arrow	arrow	wait	wait
size_nwse	size_nwse	size_all	size_all	hand
size_nesw	size_nesw	size_all	size_all	hand
size_we	size_we	size_we	size_we	hand
size_ns	size_ns	size_ns	size_ns	hand
size_all	size_all	size_all	size_all	hand
no	no	no	no	ibeam
hand	hand	hand	hand	hand

New in version 1.10.1.

---

**Note:** This feature requires the SDL2 window provider and is currently only supported on desktop platforms.

---

**set\_title(*title*)**

Set the window title.

New in version 1.0.5.

**set\_vkeyboard\_class(*cls*)**

New in version 1.0.8.

Set the VKeyboard class to use. If set to *None*, it will use the [kivy.uix.vkeyboard.VKeyboard](#).

**shape\_color\_key**

Color key of the shaped window - sets which color will be hidden from the window *shape\_image* (only works for sdl2 window provider).

New in version 1.10.1.

*shape\_color\_key* is a [ListProperty](#) instance and defaults to [1, 1, 1, 1].

**shape\_cutoff**

The window *shape\_image* cutoff property (only works for sdl2 window provider).

New in version 1.10.1.

*shape\_cutoff* is a [BooleanProperty](#) and defaults to True.

**shape\_image**

An image for the window shape (only works for sdl2 window provider).

**Warning:** The image size has to be the same like the window's size!

New in version 1.10.1.

*shape\_image* is a [StringProperty](#) and defaults to 'data/images/defaultshape.png'. This value is taken from [Config](#).

**shape\_mode**

Window mode for shaping (only works for sdl2 window provider).

- **can be RGB only**

- *default* - does nothing special
- *colorkey* - hides a color of the *shape\_color\_key*

- **has to contain alpha channel**

- *binalpha* - hides an alpha channel of the *shape\_image*
- *reversebinalpha* - shows only the alpha of the *shape\_image*

---

**Note:** Before actually setting the mode make sure the Window has the same size like the *shape\_image*, preferably via Config before the Window is actually created.

If the *shape\_image* isn't set, the default one will be used and the mode might not take the desired visual effect.

---

New in version 1.10.1.

*shape\_mode* is an *AliasProperty*.

### **shaped**

Read only property to check if the window is shapable or not (only works for sdl2 window provider).

New in version 1.10.1.

*shaped* is an *AliasProperty*.

### **show()**

Shows the window. This method should be used on desktop platforms only.

New in version 1.9.0.

---

**Note:** This feature requires the SDL2 window provider and is currently only supported on desktop platforms.

---

### **show\_cursor**

Set whether or not the cursor is shown on the window.

New in version 1.9.1.

*show\_cursor* is a *BooleanProperty* and defaults to True.

### **size**

Get the rotated size of the window. If *rotation* is set, then the size will change to reflect the rotation.

New in version 1.0.9.

*size* is an *AliasProperty*.

### **softinput\_mode**

This specifies the behavior of window contents on display of the soft keyboard on mobile platforms. It can be one of "", 'pan', 'scale', 'resize' or 'below\_target'. Their effects are listed below.

Value	Effect
"	The main window is left as is, allowing you to use the <i>keyboard_height</i> to manage the window contents manually.
'pan'	The main window pans, moving the bottom part of the window to be always on top of the keyboard.
'resize'	The window is resized and the contents scaled to fit the remaining space.
'be-low_target'	The window pans so that the current target TextInput widget requesting the 'below_target' keyboard is presented just above the soft keyboard.

*softinput\_mode* is an *OptionProperty* and defaults to "".

---

**Note:** The *resize* option does not currently work with SDL2 on Android.

---

New in version 1.9.0.

Changed in version 1.9.1: The 'below\_target' option was added.

### **system\_size**

Real size of the window ignoring rotation.

New in version 1.0.9.

*system\_size* is an *AliasProperty*.

**toggle\_fullscreen(\*args, \*\*kwargs)**

Toggle between fullscreen and windowed mode.

Deprecated since version 1.9.0: Use [fullscreen](#) instead.

**top**

Top position of the window.

---

**Note:** It's an SDL2 property with [0, 0] in the top-left corner.

---

Changed in version 1.10.0: *top* is now an [AliasProperty](#)

New in version 1.9.1.

*top* is an [AliasProperty](#) and defaults to the position set in [Config](#).

**ungrab\_mouse()**

Ungrab mouse

New in version 1.10.0.

---

**Note:** This feature requires the SDL2 window provider.

---

**width**

Rotated window width.

*width* is a read-only [AliasProperty](#).



## Kivy module for binary dependencies.

---

Binary dependencies such as gstreamer is installed as a namespace module of kivy.deps. These modules are responsible for making sure that the binaries are available to kivy.



---

# Effects

---

New in version 1.7.0.

Everything starts with the *KineticEffect*, the base class for computing velocity out of a movement.

This base class is used to implement the *ScrollEffect*, a base class used for our *ScrollView* widget effect. We have multiple implementations:

- *ScrollEffect*: base class used for implementing an effect. It only calculates the scrolling and the overscroll.
- *DampedScrollEffect*: uses the overscroll information to allow the user to drag more than expected. Once the user stops the drag, the position is returned to one of the bounds.
- *OpacityScrollEffect*: uses the overscroll information to reduce the opacity of the scrollview widget. When the user stops the drag, the opacity is set back to 1.

## 25.1 Damped scroll effect

New in version 1.7.0.

This damped scroll effect will use the *overscroll* to calculate the scroll value, and slows going back to the upper or lower limit.

```
class kivy.effects.dampedscroll.DampedScrollEffect(**kwargs)
Bases: kivy.effects.scroll.ScrollEffect
```

DampedScrollEffect class. See the module documentation for more information.

### **edge\_damping**

Edge damping.

*edge\_damping* is a *NumericProperty* and defaults to 0.25

### **min\_overscroll**

An overscroll less than this amount will be normalized to 0.

New in version 1.8.0.

`min_overscroll` is a *NumericProperty* and defaults to .5.

#### **round\_value**

If True, when the motion stops, `value` is rounded to the nearest integer.

New in version 1.8.0.

`round_value` is a *BooleanProperty* and defaults to True.

#### **spring\_constant**

Spring constant.

`spring_constant` is a *NumericProperty* and defaults to 2.0

## 25.2 Kinetic effect

New in version 1.7.0.

The *KineticEffect* is the base class that is used to compute the velocity out of a movement. When the movement is finished, the effect will compute the position of the movement according to the velocity, and reduce the velocity with a friction. The movement stop until the velocity is 0.

Conceptually, the usage could be:

```
>>> effect = KineticEffect()
>>> effect.start(10)
>>> effect.update(15)
>>> effect.update(30)
>>> effect.stop(48)
```

Over the time, you will start a movement of a value, update it, and stop the movement. At this time, you'll get the movement value into *KineticEffect.value*. On the example i've typed manually, the computed velocity will be:

```
>>> effect.velocity
3.161900231163046
```

After multiple clock interaction, the velocity will decrease according to *KineticEffect.friction*. The computed value will be stored in *KineticEffect.value*. The output of this `value` could be:

```
46.30038145219605
54.58302451968686
61.9229016256196
# ...
```

**class kivy.effects.kinetic.KineticEffect(\*\*kwargs)**

Bases: *kivy.event.EventDispatcher*

Kinetic effect class. See module documentation for more information.

#### **cancel()**

Cancel a movement. This can be used in case `stop()` cannot be called. It will reset `is_manual` to False, and compute the movement if the velocity is > 0.

#### **friction**

Friction to apply on the velocity

`velocity` is a *NumericProperty* and defaults to 0.05.

#### **is\_manual**

Indicate if a movement is in progress (True) or not (False).

`velocity` is a *BooleanProperty* and defaults to False.

### **max\_history**

Save up to *max\_history* movement value into the history. This is used for correctly calculating the velocity according to the movement.

*max\_history* is a *NumericProperty* and defaults to 5.

### **min\_distance**

The minimal distance for a movement to have nonzero velocity.

New in version 1.8.0.

*min\_distance* is *NumericProperty* and defaults to 0.1.

### **min\_velocity**

Velocity below this quantity is normalized to 0. In other words, any motion whose velocity falls below this number is stopped.

New in version 1.8.0.

*min\_velocity* is a *NumericProperty* and defaults to 0.5.

### **start(val, t=None)**

Start the movement.

#### **Parameters**

*val: float or int* Value of the movement

*t: float, defaults to None* Time when the movement happen. If no time is set, it will use `time.time()`

### **stop(val, t=None)**

Stop the movement.

See [start\(\)](#) for the arguments.

### **update(val, t=None)**

Update the movement.

See [start\(\)](#) for the arguments.

### **update\_velocity(dt)**

(internal) Update the velocity according to the frametime and friction.

### **value**

Value (during the movement and computed) of the effect.

*velocity* is a *NumericProperty* and defaults to 0.

### **velocity**

Velocity of the movement.

*velocity* is a *NumericProperty* and defaults to 0.

## 25.3 Opacity scroll effect

Based on the `DampedScrollEffect`, this one will also decrease the opacity of the target widget during the overscroll.

```
class kivy.effects.opacityscroll.OpacityScrollEffect(**kwargs)
Bases: kivy.effects.dampedscroll.DampedScrollEffect
```

OpacityScrollEffect class. Uses the overscroll information to reduce the opacity of the scrollview widget. When the user stops the drag, the opacity is set back to 1.

## 25.4 Scroll effect

New in version 1.7.0.

Based on the *kinetic* effect, the **ScrollEffect** will limit the movement to bounds determined by its *min* and *max* properties. If the movement exceeds these bounds, it will calculate the amount of *overscroll* and try to return to the value of one of the bounds.

This is very useful for implementing a scrolling list. We actually use this class as a base effect for our **ScrollView** widget.

```
class kivy.effects.scroll.ScrollEffect(**kwargs)
Bases: kivy.effects.kinetic.KineticEffect
```

ScrollEffect class. See the module documentation for more informations.

### **displacement**

Cumulative distance of the movement during the interaction. This is used to determine if the movement is a drag (more than *drag\_threshold*) or not.

*displacement* is a *NumericProperty* and defaults to 0.

### **drag\_threshold**

Minimum distance to travel before the movement is considered as a drag.

*velocity* is a *NumericProperty* and defaults to 20sp.

### **max**

Maximum boundary to use for scrolling.

*max* is a *NumericProperty* and defaults to 0.

### **min**

Minimum boundary to use for scrolling.

*min* is a *NumericProperty* and defaults to 0.

### **overscroll**

Computed value when the user over-scrolls i.e. goes out of the bounds.

*overscroll* is a *NumericProperty* and defaults to 0.

### **reset(pos)**

(internal) Reset the value and the velocity to the *pos*. Mostly used when the bounds are checked.

### **scroll**

Computed value for scrolling. This value is different from *kivy.effects.kinetic.KineticEffect.value* in that it will return to one of the min/max bounds.

*scroll* is a *NumericProperty* and defaults to 0.

### **target\_widget**

Widget to attach to this effect. Even if this class doesn't make changes to the *target\_widget* by default, subclasses can use it to change the graphics or apply custom transformations.

*target\_widget* is a *ObjectProperty* and defaults to None.

---

# Garden

---

New in version 1.7.0.

Changed in version 1.8.0.

Garden is a project to centralize addons for Kivy maintained by users. You can find more information at [Kivy Garden](#). All the garden packages are centralized on the [kivy-garden Github](#) repository.

Garden is now distributed as a separate Python module, kivy-garden. You can install it with pip:

```
pip install kivy-garden
```

The garden module does not initially include any packages. You can download them with the garden tool installed by the pip package:

```
# Installing a garden package
garden install graph

# Upgrade a garden package
garden install --upgrade graph

# Uninstall a garden package
garden uninstall graph

# List all the garden packages installed
garden list

# Search new packages
garden search

# Search all the packages that contain "graph"
garden search graph

# Show the help
garden --help
```

All the garden packages are installed by default in `~/.kivy/garden`.

---

**Note:** In previous versions of Kivy, garden was a tool at kivy/tools/garden. This no longer exists, but the `kivy-garden` module provides exactly the same functionality.

---

## 26.1 Packaging

If you want to include garden packages in your application, you can add `-app` to the `install` command. This will create a `libs/garden` directory in your current directory which will be used by `kivy.garden`.

For example:

```
cd myapp  
garden install --app graph
```

```
kivy.garden.garden_system_dir = 'garden'  
    system path where garden modules can be installed
```

# Graphics

---

This package assembles many low level functions used for drawing. The whole graphics package is compatible with OpenGL ES 2.0 and has many rendering optimizations.

## 27.1 The basics

For drawing on a screen, you will need :

1. a *Canvas* object.
2. *Instruction* objects.

Each *Widget* in Kivy already has a *Canvas* by default. When you create a widget, you can create all the instructions needed for drawing. If *self* is your current widget, you can do:

```
from kivy.graphics import *
with self.canvas:
    # Add a red color
    Color(1., 0, 0)

    # Add a rectangle
    Rectangle(pos=(10, 10), size=(500, 500))
```

The instructions *Color* and *Rectangle* are automatically added to the canvas object and will be used when the window is drawn.

---

**Note:** Kivy drawing instructions are not automatically relative to the widgets position or size. You therefore you need to consider these factors when drawing. In order to make your drawing instructions relative to the widget, the instructions need either to be declared in the *KvLang* or bound to pos and size changes. Please see *Adding a Background to a Layout* for more detail.

---

## 27.2 GL Reloading mechanism

New in version 1.2.0.

During the lifetime of the application, the OpenGL context might be lost. This happens:

- when the window is resized on OS X or the Windows platform and you're using pygame as a window provider. This is due to SDL 1.2. In the SDL 1.2 design, it needs to recreate a GL context everytime the window is resized. This was fixed in SDL 1.3 but pygame is not yet available on it by default.
- when Android releases the app resources: when your application goes to the background, Android might reclaim your opengl context to give the resource to another app. When the user switches back to your application, a newly created gl context is given to your app.

Starting from 1.2.0, we have introduced a mechanism for reloading all the graphics resources using the GPU: Canvas, FBO, Shader, Texture, VBO, and VertexBatch:

- VBO and VertexBatch are constructed by our graphics instructions. We have all the data needed to reconstruct when reloading.
- Shader: same as VBO, we store the source and values used in the shader so we are able to recreate the vertex/fragment/program.
- Texture: if the texture has a source (an image file or atlas), the image is reloaded from the source and reuploaded to the GPU.

You should cover these cases yourself:

- Textures without a source: if you manually created a texture and manually blit data / a buffer to it, you must handle the reloading yourself. Check the [Texture](#) to learn how to manage that case. (The text rendering already generates the texture and handles the reloading. You don't need to reload text yourself.)
- FBO: if you added / removed / drew things multiple times on the FBO, we can't reload it. We don't keep a history of the instructions put on it. As for textures without a source, check the [Framebuffer](#) to learn how to manage that case.

**class kivy.graphics.Bezier**  
Bases: [kivy.graphics.instructions.VertexInstruction](#)

A 2d Bezier curve.

New in version 1.0.8.

### Parameters

**points: list** List of points in the format (x1, y1, x2, y2...)

**segments: int, defaults to 180** Define how many segments are needed for drawing the curve. The drawing will be smoother if you have many segments.

**loop: bool, defaults to False** Set the bezier curve to join the last point to the first.

**dash\_length: int** Length of a segment (if dashed), defaults to 1.

**dash\_offset: int** Distance between the end of a segment and the start of the next one, defaults to 0. Changing this makes it dashed.

### **dash\_length**

Property for getting/setting the length of the dashes in the curve.

### **dash\_offset**

Property for getting/setting the offset between the dashes in the curve.

## **points**

Property for getting/settings the points of the triangle.

**Warning:** This will always reconstruct the whole graphic from the new points list. It can be very CPU intensive.

## **segments**

Property for getting/setting the number of segments of the curve.

### **class kivy.graphics.BindTexture**

Bases: *kivy.graphics.instructions.ContextInstruction*

BindTexture Graphic instruction. The BindTexture Instruction will bind a texture and enable GL\_TEXTURE\_2D for subsequent drawing.

#### **Parameters**

*texture: Texture* Specifies the texture to bind to the given index.

#### **source**

Set/get the source (filename) to load for the texture.

### **class kivy.graphics.BorderImage**

Bases: *kivy.graphics.vertex\_instructions.Rectangle*

A 2d border image. The behavior of the border image is similar to the concept of a CSS3 border-image.

#### **Parameters**

*border: list* Border information in the format (bottom, right, top, left). Each value is in pixels.

*auto\_scale: string* New in version 1.9.1.

Changed in version 1.9.2: This used to be a bool and has been changed to be a string state.

Can be one of 'off', 'both', 'x\_only', 'y\_only', 'y\_full\_x\_lower', 'x\_full\_y\_lower', 'both\_lower'.

Autoscale controls the behavior of the 9-slice.

By default the border values are preserved exactly, meaning that if the total size of the object is smaller than the border values you will have some 'rendering errors' where your texture appears inside out. This also makes it impossible to achieve a rounded button that scales larger than the size of its source texture. The various options for auto\_scale will let you achieve some mixes of the 2 types of rendering.

'off': is the default and behaves as BorderImage did when auto\_scale was False before.

'both': Scales both x and y dimension borders according to the size of the BorderImage, this disables the BorderImage making it render the same as a regular Image.

'x\_only': The Y dimension functions as the default, and the X scales to the size of the BorderImage's width.

'y\_only': The X dimension functions as the default, and the Y scales to the size of the BorderImage's height.

'y\_full\_x\_lower': Y scales as in 'y\_only', Y scales if the size of the scaled version would be smaller than the provided border only.

'x\_full\_y\_lower': X scales as in 'x\_only', Y scales if the size of the scaled version would be smaller than the provided border only.

'both\_lower': This is what auto\_scale did when it was True in 1.9.1 Both X and Y dimensions will be scaled if the BorderImage is smaller than the source.

If the BorderImage's size is less than the sum of its borders, horizontally or vertically, and this property is set to True, the borders will be rescaled to accommodate for the smaller size.

### auto\_scale

Property for setting if the corners are automatically scaled when the BorderImage is too small.

### border

Property for getting/setting the border of the class.

### display\_border

Property for getting/setting the border display size.

## class kivy.graphics.Callback

Bases: *kivy.graphics.instructions.Instruction*

New in version 1.0.4.

A Callback is an instruction that will be called when the drawing operation is performed. When adding instructions to a canvas, you can do this:

```
with self.canvas:  
    Color(1, 1, 1)  
    Rectangle(pos=self.pos, size=self.size)  
    Callback(self.my_callback)
```

The definition of the callback must be:

```
def my_callback(self, instr):  
    print('I have been called!')
```

**Warning:** Note that if you perform many and/or costly calls to callbacks, you might potentially slow down the rendering performance significantly.

The updating of your canvas does not occur until something new happens. From your callback, you can ask for an update:

```
with self.canvas:  
    self.cb = Callback(self.my_callback)  
    # then later in the code  
    self.cb.ask_update()
```

If you use the Callback class to call rendering methods of another toolkit, you will have issues with the OpenGL context. The OpenGL state may have been manipulated by the other toolkit, and as soon as program flow returns to Kivy, it will just break. You can have glitches, crashes, black holes might occur, etc. To avoid that, you can activate the *reset\_context* option. It will reset the OpenGL context state to make Kivy's rendering correct after the call to your callback.

**Warning:** The `reset_context` is not a full OpenGL reset. If you have issues regarding that, please contact us.

### `ask_update()`

Inform the parent canvas that we'd like it to update on the next frame. This is useful when you need to trigger a redraw due to some value having changed for example.

New in version 1.0.4.

### `reset_context`

Set this to True if you want to reset the OpenGL context for Kivy after the callback has been called.

## `class kivy.graphics.Canvas`

Bases: `kivy.graphics.instructions.CanvasBase`

The important Canvas class. Use this class to add graphics or context instructions that you want to be used for drawing.

---

**Note:** The Canvas supports Python's `with` statement and its enter & exit semantics.

---

Usage of a canvas without the `with` statement:

```
self.canvas.add(Color(1., 1., 0))
self.canvas.add(Rectangle(size=(50, 50)))
```

Usage of a canvas with Python's `with` statement:

```
with self.canvas:
    Color(1., 1., 0)
    Rectangle(size=(50, 50))
```

### `after`

Property for getting the 'after' group.

### `ask_update()`

Inform the canvas that we'd like it to update on the next frame. This is useful when you need to trigger a redraw due to some value having changed for example.

### `before`

Property for getting the 'before' group.

### `clear()`

Clears every `Instruction` in the canvas, leaving it clean.

### `draw()`

Apply the instruction to our window.

### `has_after`

Property to see if the `after` group has already been created.

New in version 1.7.0.

### `has_before`

Property to see if the `before` group has already been created.

New in version 1.7.0.

### `opacity`

Property to get/set the opacity value of the canvas.

New in version 1.4.1.

The opacity attribute controls the opacity of the canvas and its children. Be careful, it's a cumulative attribute: the value is multiplied to the current global opacity and the result is applied to the current context color.

For example: if your parent has an opacity of 0.5 and a child has an opacity of 0.2, the real opacity of the child will be  $0.5 * 0.2 = 0.1$ .

Then, the opacity is applied on the shader as:

```
frag_color = color * vec4(1.0, 1.0, 1.0, opacity);
```

## class kivy.graphics.CanvasBase

Bases: *kivy.graphics.instructions.InstructionGroup*

CanvasBase provides the context manager methods for the *Canvas*.

## class kivy.graphics.Color

Bases: *kivy.graphics.instructions.ContextInstruction*

Instruction to set the color state for any vertices being drawn after it.

This represents a color between 0 and 1, but is applied as a *multiplier* to the texture of any vertex instructions following it in a canvas. If no texture is set, the vertex instruction takes the precise color of the Color instruction.

For instance, if a Rectangle has a texture with uniform color (0.5, 0.5, 0.5, 1.0) and the preceding Color has `rgba=(1, 0.5, 2, 1)`, the actual visible color will be (0.5, 0.25, 1.0, 1.0) since the Color instruction is applied as a multiplier to every `rgba` component. In this case, a Color component outside the 0-1 range gives a visible result as the intensity of the blue component is doubled.

To declare a Color in Python, you can do:

```
from kivy.graphics import Color

# create red v
c = Color(1, 0, 0)
# create blue color
c = Color(0, 1, 0)
# create blue color with 50% alpha
c = Color(0, 1, 0, .5)

# using hsv mode
c = Color(0, 1, 1, mode='hsv')
# using hsv mode + alpha
c = Color(0, 1, 1, .2, mode='hsv')
```

You can also set color components that are available as properties by passing them as keyword arguments:

```
c = Color(b=0.5) # sets the blue component only
```

In kv lang you can set the color properties directly:

```
<Rule>:
    canvas:
        # red color
        Color:
            rgb: 1, 0, 0
        # blue color
        Color:
```

```

    rgb: 0, 1, 0
    # blue color with 50% alpha
Color:
    rgba: 0, 1, 0, .5

    # using hsv mode
Color:
    hsv: 0, 1, 1
    # using hsv mode + alpha
Color:
    hsv: 0, 1, 1
    a: .5

```

**a**

Alpha component, between 0 and 1.

**b**

Blue component, between 0 and 1.

**g**

Green component, between 0 and 1.

**h**

Hue component, between 0 and 1.

**hsv**

HSV color, list of 3 values in 0-1 range, alpha will be 1.

**r**

Red component, between 0 and 1.

**rgb**

RGB color, list of 3 values in 0-1 range. The alpha will be 1.

**rgba**

RGBA color, list of 4 values in 0-1 range.

**s**

Saturation component, between 0 and 1.

**v**

Value component, between 0 and 1.

**class kivy.graphics.ContextInstruction**

Bases: *kivy.graphics.instructions.Instruction*

The ContextInstruction class is the base for the creation of instructions that don't have a direct visual representation, but instead modify the current Canvas' state, e.g. texture binding, setting color parameters, matrix manipulation and so on.

**class kivy.graphics.Ellipse**

Bases: *kivy.graphics.vertex\_instructions.Rectangle*

A 2D ellipse.

Changed in version 1.0.7: Added angle\_start and angle\_end.

#### Parameters

**segments: int, defaults to 180** Define how many segments are needed for drawing the ellipse. The drawing will be smoother if you have many segments.

**angle\_start: int, defaults to 0** Specifies the starting angle, in degrees, of the disk portion.

**angle\_end: int, defaults to 360** Specifies the ending angle, in degrees, of the disk portion.

#### angle\_end

End angle of the ellipse in degrees, defaults to 360.

#### angle\_start

Start angle of the ellipse in degrees, defaults to 0.

#### segments

Property for getting/setting the number of segments of the ellipse.

### class kivy.graphics.Fbo

Bases: *kivy.graphics.instructions.RenderContext*

Fbo class for wrapping the OpenGL Framebuffer extension. The Fbo support “with” statement.

#### Parameters

**clear\_color: tuple, defaults to (0, 0, 0, 0)** Define the default color for clearing the framebuffer

**size: tuple, defaults to (1024, 1024)** Default size of the framebuffer

**push\_viewport: bool, defaults to True** If True, the OpenGL viewport will be set to the framebuffer size, and will be automatically restored when the framebuffer released.

**with\_depthbuffer: bool, defaults to False** If True, the framebuffer will be allocated with a Z buffer.

**with\_stencilbuffer: bool, defaults to False** New in version 1.9.0.

If True, the framebuffer will be allocated with a stencil buffer.

**texture: Texture, defaults to None** If None, a default texture will be created.

---

**Note:** Using both of `with_stencilbuffer` and `with_depthbuffer` is not supported in kivy 1.9.0

---

#### add\_reload\_observer()

Add a callback to be called after the whole graphics context has been reloaded. This is where you can reupload your custom data in GPU.

New in version 1.2.0.

#### Parameters

**callback: func(context) -> return None** The first parameter will be the context itself

#### bind()

Bind the FBO to the current opengl context. *Bind* mean that you enable the Framebuffer, and all the drawing operations will act inside the Framebuffer, until `release()` is called.

The bind/release operations are automatically called when you add graphics objects into it. If you want to manipulate a Framebuffer yourself, you can use it like this:

```
self.fbo = FBO()
self.fbo.bind()
# do any drawing command
self.fbo.release()
```

```
# then, your fbo texture is available at
print(self.fbo.texture)
```

### **clear\_buffer()**

Clear the framebuffer with the [clear\\_color](#).

You need to bind the framebuffer yourself before calling this method:

```
fbo.bind()
fbo.clear_buffer()
fbo.release()
```

### **clear\_color**

Clear color in (red, green, blue, alpha) format.

### **get\_pixel\_color()**

Get the color of the pixel with specified window coordinates wx, wy. It returns result in RGBA format.

New in version 1.8.0.

### **pixels**

Get the pixels texture, in RGBA format only, unsigned byte. The origin of the image is at bottom left.

New in version 1.7.0.

### **release()**

Release the Framebuffer (unbind).

### **remove\_reload\_observer()**

Remove a callback from the observer list, previously added by [add\\_reload\\_observer\(\)](#).

New in version 1.2.0.

### **size**

Size of the framebuffer, in (width, height) format.

If you change the size, the framebuffer content will be lost.

### **texture**

Return the framebuffer texture

## **class kivy.graphics.GraphicException**

Bases: [exceptions.Exception](#)

Exception raised when a graphics error is fired.

## **class kivy.graphics.Instruction**

Bases: [kivy.event.ObjectWithUid](#)

Represents the smallest instruction available. This class is for internal usage only, don't use it directly.

### **proxy\_ref**

Return a proxy reference to the Instruction i.e. without creating a reference of the widget.  
See [weakref.proxy](#) for more information.

New in version 1.7.2.

## **class kivy.graphics.InstructionGroup**

Bases: [kivy.graphics.instructions.Instruction](#)

Group of [Instructions](#). Allows for the adding and removing of graphics instructions. It can be used directly as follows:

```

blue = InstructionGroup()
blue.add(Color(0, 0, 1, 0.2))
blue.add(Rectangle(pos=self.pos, size=(100, 100)))

green = InstructionGroup()
green.add(Color(0, 1, 0, 0.4))
green.add(Rectangle(pos=(100, 100), size=(100, 100)))

# Here, self should be a Widget or subclass
[self.canvas.add(group) for group in [blue, green]]

```

### **add()**

Add a new *Instruction* to our list.

### **clear()**

Remove all the *Instructions*.

### **get\_group()**

Return an iterable for all the *Instructions* with a specific group name.

### **insert()**

Insert a new *Instruction* into our list at index.

### **remove()**

Remove an existing *Instruction* from our list.

### **remove\_group()**

Remove all *Instructions* with a specific group name.

## **class kivy.graphics.Line**

Bases: *kivy.graphics.instructions.VertexInstruction*

A 2d line.

Drawing a line can be done easily:


```

with self.canvas:
    Line(points=[100, 100, 200, 100, 100, 200], width=10)

```

The line has 3 internal drawing modes that you should be aware of for optimal results:

1. If the *width* is 1.0, then the standard GL\_LINE drawing from OpenGL will be used. *dash\_length* and *dash\_offset* will work, while properties for cap and joint have no meaning here.
2. If the *width* is greater than 1.0, then a custom drawing method, based on triangulation, will be used. *dash\_length* and *dash\_offset* do not work in this mode. Additionally, if the current color has an alpha less than 1.0, a stencil will be used internally to draw the line.



## Parameters

**points:** `list` List of points in the format `(x1, y1, x2, y2...)`

**dash\_length:** `int` Length of a segment (if dashed), defaults to 1.

**dash\_offset:** `int` Offset between the end of a segment and the beginning of the next one, defaults to 0. Changing this makes it dashed.

**width:** `float` Width of the line, defaults to 1.0.

**cap:** `str, defaults to 'round'` See [cap](#) for more information.

**joint:** `str, defaults to 'round'` See [joint](#) for more information.

**cap\_precision:** `int, defaults to 10` See [cap\\_precision](#) for more information

**joint\_precision:** `int, defaults to 10` See [joint\\_precision](#) for more information  
See [cap\\_precision](#) for more information.

**joint\_precision:** `int, defaults to 10` See [joint\\_precision](#) for more information.

**close:** `bool, defaults to False` If True, the line will be closed.

**circle:** `list` If set, the [points](#) will be set to build a circle. See [circle](#) for more information.

**ellipse:** `list` If set, the [points](#) will be set to build an ellipse. See [ellipse](#) for more information.

**rectangle: list** If set, the *points* will be set to build a rectangle. See [rectangle](#) for more information.

**bezier: list** If set, the *points* will be set to build a bezier line. See [bezier](#) for more information.

**bezier\_precision: int, defaults to 180** Precision of the Bezier drawing.

Changed in version 1.0.8: *dash\_offset* and *dash\_length* have been added.

Changed in version 1.4.1: *width*, *cap*, *joint*, *cap\_precision*, *joint\_precision*, *close*, *ellipse*, *rectangle* have been added.

Changed in version 1.4.1: *bezier*, *bezier\_precision* have been added.

### **bezier**

Use this property to build a bezier line, without calculating the *points*. You can only set this property, not get it.

The argument must be a tuple of 2n elements, n being the number of points.

Usage:

```
Line(bezier=(x1, y1, x2, y2, x3, y3))
```

New in version 1.4.2.

---

**Note:** Bezier lines calculations are inexpensive for a low number of points, but complexity is quadratic, so lines with a lot of points can be very expensive to build, use with care!

---

### **bezier\_precision**

Number of iteration for drawing the bezier between 2 segments, defaults to 180. The *bezier\_precision* must be at least 1.

New in version 1.4.2.

### **cap**

Determine the cap of the line, defaults to ‘round’. Can be one of ‘none’, ‘square’ or ‘round’

New in version 1.4.1.

### **cap\_precision**

Number of iteration for drawing the “round” cap, defaults to 10. The *cap\_precision* must be at least 1.

New in version 1.4.1.

### **circle**

Use this property to build a circle, without calculating the *points*. You can only set this property, not get it.

The argument must be a tuple of (center\_x, center\_y, radius, angle\_start, angle\_end, segments):

- *center\_x* and *center\_y* represent the center of the circle
- *radius* represent the radius of the circle
- (optional) *angle\_start* and *angle\_end* are in degree. The default value is 0 and 360.
- (optional) *segments* is the precision of the ellipse. The default value is calculated from the range between angle.

Note that it’s up to you to *close* the circle or not.

For example, for building a simple ellipse, in python:

```

# simple circle
Line(circle=(150, 150, 50))

# only from 90 to 180 degrees
Line(circle=(150, 150, 50, 90, 180))

# only from 90 to 180 degrees, with few segments
Line(circle=(150, 150, 50, 90, 180, 20))

```

New in version 1.4.1.

### **close**

If True, the line will be closed.

New in version 1.4.1.

### **dash\_length**

Property for getting/setting the length of the dashes in the curve

New in version 1.0.8.

### **dash\_offset**

Property for getting/setting the offset between the dashes in the curve

New in version 1.0.8.

### **ellipse**

Use this property to build an ellipse, without calculating the *points*. You can only set this property, not get it.

The argument must be a tuple of (x, y, width, height, angle\_start, angle\_end, segments):

- x and y represent the bottom left of the ellipse
- width and height represent the size of the ellipse
- (optional) angle\_start and angle\_end are in degree. The default value is 0 and 360.
- (optional) segments is the precision of the ellipse. The default value is calculated from the range between angle.

Note that it's up to you to *close* the ellipse or not.

For example, for building a simple ellipse, in python:

```

# simple ellipse
Line(ellipse=(0, 0, 150, 150))

# only from 90 to 180 degrees
Line(ellipse=(0, 0, 150, 150, 90, 180))

# only from 90 to 180 degrees, with few segments
Line(ellipse=(0, 0, 150, 150, 90, 180, 20))

```

New in version 1.4.1.

### **joint**

Determine the join of the line, defaults to 'round'. Can be one of 'none', 'round', 'bevel', 'miter'.

New in version 1.4.1.

### **joint\_precision**

Number of iteration for drawing the "round" joint, defaults to 10. The joint\_precision must be at least 1.

New in version 1.4.1.

### points

Property for getting/settings points of the line

**Warning:** This will always reconstruct the whole graphics from the new points list. It can be very CPU expensive.

### rectangle

Use this property to build a rectangle, without calculating the *points*. You can only set this property, not get it.

The argument must be a tuple of (x, y, width, height):

- x and y represent the bottom-left position of the rectangle
- width and height represent the size

The line is automatically closed.

Usage:

```
Line(rectangle=(0, 0, 200, 200))
```

New in version 1.4.1.

### rounded\_rectangle

Use this property to build a rectangle, without calculating the *points*. You can only set this property, not get it.

The argument must be a tuple of one of the following forms:

- (x, y, width, height, corner\_radius)
- (x, y, width, height, corner\_radius, resolution)
- (x, y, width, height, corner\_radius1, corner\_radius2, corner\_radius3, corner\_radius4)
- (x, y, width, height, corner\_radius1, corner\_radius2, corner\_radius3, corner\_radius4, resolution)
- x and y represent the bottom-left position of the rectangle
- width and height represent the size
- corner\_radius is the number of pixels between two borders and the center of the circle arc joining them
- resolution is the number of line segment that will be used to draw the circle arc at each corner (defaults to 30)

The line is automatically closed.

Usage:

```
Line(rounded_rectangle=(0, 0, 200, 200, 10, 20, 30, 40, 100))
```

New in version 1.9.0.

### width

Determine the width of the line, defaults to 1.0.

New in version 1.4.1.

```
class kivy.graphics.SmoothLine
Bases: kivy.graphics.vertex_instructions.Line
```

Experimental line using over-draw methods to get better anti-aliasing results. It has few drawbacks:

- drawing a line with alpha will probably not have the intended result if the line crosses itself.
- *cap*, *joint* and *dash* properties are not supported.
- it uses a custom texture with a premultiplied alpha.
- lines under 1px in width are not supported: they will look the same.

**Warning:** This is an unfinished work, experimental, and subject to crashes.

New in version 1.9.0.

#### **overdraw\_width**

Determine the overdraw width of the line, defaults to 1.2.

```
class kivy.graphics.MatrixInstruction
Bases: kivy.graphics.instructions.ContextInstruction
```

Base class for Matrix Instruction on the canvas.

#### **matrix**

Matrix property. Matrix from the transformation module. Setting the matrix using this property when a change is made is important because it will notify the context about the update.

#### **stack**

Name of the matrix stack to use. Can be ‘modelview\_mat’, ‘projection\_mat’ or ‘frag\_modelview\_mat’.

New in version 1.6.0.

```
class kivy.graphics.Mesh
Bases: kivy.graphics.instructions.VertexInstruction
```

A 2d mesh.

In OpenGL ES 2.0 and in our graphics implementation, you cannot have more than 65535 indices.

A list of vertices is described as:

```
vertices = [x1, y1, u1, v1, x2, y2, u2, v2, ...]
           |   |   |   |
           +---+ +---+ +---+
```

If you want to draw a triangle, add 3 vertices. You can then make an indices list as follows:

```
indices = [0, 1, 2]
```

New in version 1.1.0.

#### **Parameters**

*vertices*: iterable List of vertices in the format (x1, y1, u1, v1, x2, y2, u2, v2...).

*indices*: iterable List of indices in the format (i1, i2, i3...).

*mode*: str Mode of the vbo. Check *mode* for more information. Defaults to ‘points’.

*fmt*: list The format for vertices, by default, each vertex is described by 2D coordinates (x, y) and 2D texture coordinate (u, v). Each element of the list should be a tuple or list, of the form

(variable\_name, size, type)

which will allow mapping vertex data to the glsl instructions.

[`b'v_pos', 2, b'float')`, `(b'v_tc', 2, b'float')`,]

will allow using

```
attribute vec2 v_pos; attribute vec2 v_tc;
```

in glsl's vertex shader.

Changed in version 1.8.1: Before, *vertices* and *indices* would always be converted to a list, now, they are only converted to a list if they do not implement the buffer interface. So e.g. numpy arrays, python arrays etc. are used in place, without creating any additional copies. However, the buffers cannot be readonly (even though they are not changed, due to a cython limitation) and must be contiguous in memory.

---

**Note:** When passing a memoryview or a instance that implements the buffer interface, *vertices* should be a buffer of floats ('f' code in python array) and *indices* should be a buffer of unsigned short ('H' code in python array). Arrays in other formats will still have to be converted internally, negating any potential gain.

---

### indices

Vertex indices used to specify the order when drawing the mesh.

### mode

VBO Mode used for drawing vertices/indices. Can be one of 'points', 'line\_strip', 'line\_loop', 'lines', 'triangles', 'triangle\_strip' or 'triangle\_fan'.

### vertices

List of x, y, u, v coordinates used to construct the Mesh. Right now, the Mesh instruction doesn't allow you to change the format of the vertices, which means it's only x, y + one texture coordinate.

## class kivy.graphics.Point

Bases: `kivy.graphics.instructions.VertexInstruction`

A list of 2d points. Each point is represented as a square with a width/height of 2 times the *pointsize*.

### Parameters

**points: list** List of points in the format (x1, y1, x2, y2...), where each pair of coordinates specifies the center of a new point.

**pointsize: float, defaults to 1.** The size of the point, measured from the center to the edge. A value of 1.0 therefore means the real size will be 2.0 x 2.0.

**Warning:** Starting from version 1.0.7, vertex instruction have a limit of 65535 vertices (indices of vertex to be accurate). 2 entries in the list (x, y) will be converted to 4 vertices. So the limit inside Point() class is  $2^{15}-2$ .

### add\_point()

Add a point to the current *points* list.

If you intend to add multiple points, prefer to use this method instead of reassigning a new *points* list. Assigning a new *points* list will recalculate and reupload the whole buffer into the GPU. If you use add\_point, it will only upload the changes.

**points**

Property for getting/settings the center points in the points list. Each pair of coordinates specifies the center of a new point.

**pointsize**

Property for getting/setting point size. The size is measured from the center to the edge, so a value of 1.0 means the real size will be  $2.0 \times 2.0$ .

**class kivy.graphics.PopMatrix**

Bases: *kivy.graphics.instructions.ContextInstruction*

Pop the matrix from the context's matrix stack onto the model view.

**stack**

Name of the matrix stack to use. Can be 'modelview\_mat', 'projection\_mat' or 'frag\_modelview\_mat'.

New in version 1.6.0.

**class kivy.graphics.PushMatrix**

Bases: *kivy.graphics.instructions.ContextInstruction*

Push the matrix onto the context's matrix stack.

**stack**

Name of the matrix stack to use. Can be 'modelview\_mat', 'projection\_mat' or 'frag\_modelview\_mat'.

New in version 1.6.0.

**class kivy.graphics.Quad**

Bases: *kivy.graphics.instructions.VertexInstruction*

A 2d quad.

**Parameters**

*points: list* List of point in the format (x1, y1, x2, y2, x3, y3, x4, y4).

**points**

Property for getting/settings points of the quad.

**class kivy.graphics.Rectangle**

Bases: *kivy.graphics.instructions.VertexInstruction*

A 2d rectangle.

**Parameters**

*pos: list* Position of the rectangle, in the format (x, y).

*size: list* Size of the rectangle, in the format (width, height).

**pos**

Property for getting/settings the position of the rectangle.

**size**

Property for getting/settings the size of the rectangle.

**class kivy.graphics.RenderContext**

Bases: *kivy.graphics.instructions.Canvas*

The render context stores all the necessary information for drawing, i.e.:

- The vertex shader
- The fragment shader
- The default texture

- The state stack (color, texture, matrix...)

### **shader**

Return the shader attached to the render context.

### **use\_parent\_frag\_modelview**

If True, the parent fragment modelview matrix will be used.

New in version 1.10.1: `rc = RenderContext(use_parent_frag_modelview=True)`

### **use\_parent\_modelview**

If True, the parent modelview matrix will be used.

New in version 1.7.0.

Before:

```
rc['modelview_mat'] = Window.render_context['modelview_mat']
```

Now:

```
rc = RenderContext(use_parent_modelview=True)
```

### **use\_parent\_projection**

If True, the parent projection matrix will be used.

New in version 1.7.0.

Before:

```
rc['projection_mat'] = Window.render_context['projection_mat']
```

Now:

```
rc = RenderContext(use_parent_projection=True)
```

## **class kivy.graphics.Rotate**

Bases: `kivy.graphics.context_instructions.Transform`

Rotate the coordinate space by applying a rotation transformation on the modelview matrix. You can set the properties of the instructions afterwards with e.g.

```
rot.angle = 90
rot.axis = (0, 0, 1)
```

### **angle**

Property for getting/setting the angle of the rotation.

### **axis**

Property for getting/setting the axis of the rotation.

The format of the axis is (x, y, z).

### **origin**

Origin of the rotation.

New in version 1.7.0.

The format of the origin can be either (x, y) or (x, y, z).

### **set()**

Set the angle and axis of rotation.

```
>>> rotationobject.set(90, 0, 0, 1)
```

Deprecated since version 1.7.0: The set() method doesn't use the new `origin` property.

**class kivy.graphics.Scale**

Bases: `kivy.graphics.context_instructions.Transform`

Instruction to create a non uniform scale transformation.

Create using one or three arguments:

```
Scale(s)      # scale all three axes the same  
Scale(x, y, z) # scale the axes independently
```

Deprecated since version 1.6.0: Deprecated single scale property in favor of x, y, z, xyz axis independent scaled factors.

**origin**

Origin of the scale.

New in version 1.9.0.

The format of the origin can be either (x, y) or (x, y, z).

**scale**

Property for getting/setting the scale.

Deprecated since version 1.6.0: Deprecated in favor of per axis scale properties x,y,z, xyz, etc.

**x**

Property for getting/setting the scale on the X axis.

Changed in version 1.6.0.

**xyz**

3 tuple scale vector in 3D in x, y, and z axis.

Changed in version 1.6.0.

**y**

Property for getting/setting the scale on the Y axis.

Changed in version 1.6.0.

**z**

Property for getting/setting the scale on Z axis.

Changed in version 1.6.0.

**class kivy.graphics.StencilPop**

Bases: `kivy.graphics.instructions.Instruction`

Pop the stencil stack. See the module documentation for more information.

**class kivy.graphics.StencilPush**

Bases: `kivy.graphics.instructions.Instruction`

Push the stencil stack. See the module documentation for more information.

**class kivy.graphics.StencilUse**

Bases: `kivy.graphics.instructions.Instruction`

Use current stencil buffer as a mask. Check the module documentation for more information.

**func\_op**

Determine the stencil operation to use for glStencilFunc(). Can be one of 'never', 'less', 'equal', 'lequal', 'greater', 'notequal', 'gequal' or 'always'.

By default, the operator is set to 'equal'.

New in version 1.5.0.

```
class kivy.graphics.StencilUnUse
    Bases: kivy.graphics.instructions.Instruction
```

Use current stencil buffer to unset the mask.

```
class kivy.graphics.Translate
    Bases: kivy.graphics.context_instructions.Transform
```

Instruction to create a translation of the model view coordinate space.

Construct by either:

```
Translate(x, y)           # translate in just the two axes
Translate(x, y, z)         # translate in all three axes
```

**x**

Property for getting/setting the translation on the X axis.

**xy**

2 tuple with translation vector in 2D for x and y axis.

**xyz**

3 tuple translation vector in 3D in x, y, and z axis.

**y**

Property for getting/setting the translation on the Y axis.

**z**

Property for getting/setting the translation on the Z axis.

```
class kivy.graphics.Triangle
```

```
    Bases: kivy.graphics.instructions.VertexInstruction
```

A 2d triangle.

#### Parameters

**points: list** List of points in the format (x1, y1, x2, y2, x3, y3).

**points**

Property for getting/settings points of the triangle.

```
class kivy.graphics.VertexInstruction
```

```
    Bases: kivy.graphics.instructions.Instruction
```

The VertexInstruction class is the base for all graphics instructions that have a direct visual representation on the canvas, such as Rectangles, Triangles, Lines, Ellipse and so on.

**source**

This property represents the filename to load the texture from. If you want to use an image as source, do it like this:

```
with self.canvas:
    Rectangle(source='mylogo.png', pos=self.pos, size=self.size)
```

Here's the equivalent in Kivy language:

```
<MyWidget>:
    canvas:
        Rectangle:
            source: 'mylogo.png'
            pos: self.pos
            size: self.size
```

---

**Note:** The filename will be searched for using the `kivy.resources.resource_find()` function.

---

### **tex\_coords**

This property represents the texture coordinates used for drawing the vertex instruction. The value must be a list of 8 values.

A texture coordinate has a position (u, v), and a size (w, h). The size can be negative, and would represent the ‘flipped’ texture. By default, the tex\_coords are:

```
[u, v, u + w, v, u + w, v + h, u, v + h]
```

You can pass your own texture coordinates if you want to achieve fancy effects.

**Warning:** The default values just mentioned can be negative. Depending on the image and label providers, the coordinates are flipped vertically because of the order in which the image is internally stored. Instead of flipping the image data, we are just flipping the texture coordinates to be faster.

### **texture**

Property that represents the texture used for drawing this Instruction. You can set a new texture like this:

```
from kivy.core.image import Image

texture = Image('logo.png').texture
with self.canvas:
    Rectangle(texture=texture, pos=self.pos, size=self.size)
```

Usually, you will use the `source` attribute instead of the texture.

**class** `kivy.graphics.ClearColor`  
Bases: `kivy.graphics.instructions.Instruction`

ClearColor Graphics Instruction.

New in version 1.3.0.

Sets the clear color used to clear buffers with the glClear function or `ClearBuffers` graphics instructions.

**a** Alpha component, between 0 and 1.

**b** Blue component, between 0 and 1.

**g** Green component, between 0 and 1.

**r** Red component, between 0 and 1.

**rgb** RGB color, a list of 3 values in 0-1 range where alpha will be 1.

**rgba** RGBA color used for the clear color, a list of 4 values in the 0-1 range.

```
class kivy.graphics.ClearBuffers
    Bases: kivy.graphics.instructions.Instruction
        Clearbuffer Graphics Instruction.

        New in version 1.3.0.

        Clear the buffers specified by the instructions buffer mask property. By default, only the coloc buffer is cleared.

clear_color
    If True, the color buffer will be cleared.

clear_depth
    If True, the depth buffer will be cleared.

clear_stencil
    If True, the stencil buffer will be cleared.

class kivy.graphics.PushState
    Bases: kivy.graphics.instructions.ContextInstruction
        Instruction that pushes arbitrary states/uniforms onto the context state stack.

        New in version 1.6.0.

class kivy.graphics.ChangeState
    Bases: kivy.graphics.instructions.ContextInstruction
        Instruction that changes the values of arbitrary states/uniforms on the current render context.

        New in version 1.6.0.

class kivy.graphics.PopState
    Bases: kivy.graphics.instructions.ContextInstruction
        Instruction that pops arbitrary states/uniforms off the context state stack.

        New in version 1.6.0.

class kivy.graphics.ApplyContextMatrix
    Bases: kivy.graphics.instructions.ContextInstruction
        Pre-multiply the matrix at the top of the stack specified by target_stack by the matrix at the top of the 'source_stack'

        New in version 1.6.0.

source_stack
    Name of the matrix stack to use as a source. Can be 'modelview_mat', 'projection_mat' or 'frag_modelview_mat'.

    New in version 1.6.0.

target_stack
    Name of the matrix stack to use as a target. Can be 'modelview_mat', 'projection_mat' or 'frag_modelview_mat'.

    New in version 1.6.0.

class kivy.graphics.UpdateNormalMatrix
    Bases: kivy.graphics.instructions.ContextInstruction
        Update the normal matrix 'normal_mat' based on the current modelview matrix. This will compute 'normal_mat' uniform as: inverse( transpose( mat3(mvm) ) )

        New in version 1.6.0.
```

```
class kivy.graphics.LoadIdentity
Bases: kivy.graphics.instructions.ContextInstruction
```

Load the identity Matrix into the matrix stack specified by the instructions stack property (default='modelview\_mat')

New in version 1.6.0.

#### **stack**

Name of the matrix stack to use. Can be 'modelview\_mat', 'projection\_mat' or 'frag\_modelview\_mat'.

## 27.3 Canvas

The **Canvas** is the root object used for drawing by a **Widget**. Check the class documentation for more information about the usage of Canvas.

```
class kivy.graphics.instructions.Instruction
Bases: kivy.event.ObjectWithUid
```

Represents the smallest instruction available. This class is for internal usage only, don't use it directly.

#### **proxy\_ref**

Return a proxy reference to the Instruction i.e. without creating a reference of the widget.  
See [weakref.proxy](#) for more information.

New in version 1.7.2.

```
class kivy.graphics.instructions.InstructionGroup
Bases: kivy.graphics.instructions.Instruction
```

Group of **Instructions**. Allows for the adding and removing of graphics instructions. It can be used directly as follows:

```
blue = InstructionGroup()
blue.add(Color(0, 0, 1, 0.2))
blue.add(Rectangle(pos=self.pos, size=(100, 100)))

green = InstructionGroup()
green.add(Color(0, 1, 0, 0.4))
green.add(Rectangle(pos=(100, 100), size=(100, 100)))

# Here, self should be a Widget or subclass
[self.canvas.add(group) for group in [blue, green]]
```

#### **add()**

Add a new **Instruction** to our list.

#### **clear()**

Remove all the **Instructions**.

#### **get\_group()**

Return an iterable for all the **Instructions** with a specific group name.

#### **insert()**

Insert a new **Instruction** into our list at index.

#### **remove()**

Remove an existing **Instruction** from our list.

### `remove_group()`

Remove all *Instructions* with a specific group name.

### `class kivy.graphics.instructions.ContextInstruction`

Bases: *kivy.graphics.instructions.Instruction*

The ContextInstruction class is the base for the creation of instructions that don't have a direct visual representation, but instead modify the current Canvas' state, e.g. texture binding, setting color parameters, matrix manipulation and so on.

### `class kivy.graphics.instructions.VertexInstruction`

Bases: *kivy.graphics.instructions.Instruction*

The VertexInstruction class is the base for all graphics instructions that have a direct visual representation on the canvas, such as Rectangles, Triangles, Lines, Ellipse and so on.

#### **source**

This property represents the filename to load the texture from. If you want to use an image as source, do it like this:

```
with self.canvas:  
    Rectangle(source='mylogo.png', pos=self.pos, size=self.size)
```

Here's the equivalent in Kivy language:

```
<MyWidget>:  
    canvas:  
        Rectangle:  
            source: 'mylogo.png'  
            pos: self.pos  
            size: self.size
```

---

**Note:** The filename will be searched for using the *kivy.resources.resource\_find()* function.

---

#### **tex\_coords**

This property represents the texture coordinates used for drawing the vertex instruction. The value must be a list of 8 values.

A texture coordinate has a position (u, v), and a size (w, h). The size can be negative, and would represent the 'flipped' texture. By default, the tex\_coords are:

```
[u, v, u + w, v, u + w, v + h, u, v + h]
```

You can pass your own texture coordinates if you want to achieve fancy effects.

**Warning:** The default values just mentioned can be negative. Depending on the image and label providers, the coordinates are flipped vertically because of the order in which the image is internally stored. Instead of flipping the image data, we are just flipping the texture coordinates to be faster.

#### **texture**

Property that represents the texture used for drawing this Instruction. You can set a new texture like this:

```
from kivy.core.image import Image  
  
texture = Image('logo.png').texture
```

```
with self.canvas:  
    Rectangle(texture=texture, pos=self.pos, size=self.size)
```

Usually, you will use the *source* attribute instead of the texture.

**class kivy.graphics.instructions.Canvas**  
Bases: *kivy.graphics.instructions.CanvasBase*

The important Canvas class. Use this class to add graphics or context instructions that you want to be used for drawing.

---

**Note:** The Canvas supports Python's `with` statement and its enter & exit semantics.

---

Usage of a canvas without the `with` statement:

```
self.canvas.add(Color(1., 1., 0))  
self.canvas.add(Rectangle(size=(50, 50)))
```

Usage of a canvas with Python's `with` statement:

```
with self.canvas:  
    Color(1., 1., 0)  
    Rectangle(size=(50, 50))
```

#### **after**

Property for getting the 'after' group.

#### **ask\_update()**

Inform the canvas that we'd like it to update on the next frame. This is useful when you need to trigger a redraw due to some value having changed for example.

#### **before**

Property for getting the 'before' group.

#### **clear()**

Clears every *Instruction* in the canvas, leaving it clean.

#### **draw()**

Apply the instruction to our window.

#### **has\_after**

Property to see if the *after* group has already been created.

New in version 1.7.0.

#### **has\_before**

Property to see if the *before* group has already been created.

New in version 1.7.0.

#### **opacity**

Property to get/set the opacity value of the canvas.

New in version 1.4.1.

The opacity attribute controls the opacity of the canvas and its children. Be careful, it's a cumulative attribute: the value is multiplied to the current global opacity and the result is applied to the current context color.

For example: if your parent has an opacity of 0.5 and a child has an opacity of 0.2, the real opacity of the child will be  $0.5 * 0.2 = 0.1$ .

Then, the opacity is applied on the shader as:

```
frag_color = color * vec4(1.0, 1.0, 1.0, opacity);
```

## class kivy.graphics.instructions.CanvasBase

Bases: *kivy.graphics.instructions.InstructionGroup*

CanvasBase provides the context manager methods for the *Canvas*.

## class kivy.graphics.instructions.RenderContext

Bases: *kivy.graphics.instructions.Canvas*

The render context stores all the necessary information for drawing, i.e.:

- The vertex shader
- The fragment shader
- The default texture
- The state stack (color, texture, matrix...)

### shader

Return the shader attached to the render context.

### use\_parent\_frag\_modelview

If True, the parent fragment modelview matrix will be used.

New in version 1.10.1: rc = RenderContext(use\_parent\_frag\_modelview=True)

### use\_parent\_modelview

If True, the parent modelview matrix will be used.

New in version 1.7.0.

Before:

```
rc['modelview_mat'] = Window.render_context['modelview_mat']
```

Now:

```
rc = RenderContext(use_parent_modelview=True)
```

### use\_parent\_projection

If True, the parent projection matrix will be used.

New in version 1.7.0.

Before:

```
rc['projection_mat'] = Window.render_context['projection_mat']
```

Now:

```
rc = RenderContext(use_parent_projection=True)
```

## class kivy.graphics.instructions.Callback

Bases: *kivy.graphics.instructions.Instruction*

New in version 1.0.4.

A Callback is an instruction that will be called when the drawing operation is performed. When adding instructions to a canvas, you can do this:

```
with self.canvas:  
    Color(1, 1, 1)  
    Rectangle(pos=self.pos, size=self.size)  
    Callback(self.my_callback)
```

The definition of the callback must be:

```
def my_callback(self, instr):
    print('I have been called!')
```

**Warning:** Note that if you perform many and/or costly calls to callbacks, you might potentially slow down the rendering performance significantly.

The updating of your canvas does not occur until something new happens. From your callback, you can ask for an update:

```
with self.canvas:
    self.cb = Callback(self.my_callback)
# then later in the code
self.cb.ask_update()
```

If you use the Callback class to call rendering methods of another toolkit, you will have issues with the OpenGL context. The OpenGL state may have been manipulated by the other toolkit, and as soon as program flow returns to Kivy, it will just break. You can have glitches, crashes, black holes might occur, etc. To avoid that, you can activate the `reset_context` option. It will reset the OpenGL context state to make Kivy's rendering correct after the call to your callback.

**Warning:** The `reset_context` is not a full OpenGL reset. If you have issues regarding that, please contact us.

### **ask\_update()**

Inform the parent canvas that we'd like it to update on the next frame. This is useful when you need to trigger a redraw due to some value having changed for example.

New in version 1.0.4.

### **reset\_context**

Set this to True if you want to reset the OpenGL context for Kivy after the callback has been called.

## 27.4 CGL: standard C interface for OpenGL

Kivy uses OpenGL and therefore requires a backend that provides it. The backend used is controlled through the `USE_OPENGL_MOCK` and `USE_SDL2` compile-time variables and through the `KIVY_GL_BACKEND` runtime environmental variable.

Currently, OpenGL is used through direct linking (`gl/glew`), `sdl2`, or by mocking it. Setting `USE_OPENGL_MOCK` disables `gl/glew`. Similarly, setting `USE_SDL2` to `0` will disable `sdl2`. Mocking is always available.

At runtime the following backends are available and can be set using `KIVY_GL_BACKEND`:

- `gl` – Available on unix (the default backend). Unavailable when `USE_OPENGL_MOCK=0`. Requires `gl` be installed.
- `glew` – Available on Windows (the default backend). Unavailable when `USE_OPENGL_MOCK=0`. Requires `glew` be installed.

- `sdl2` – Available on Windows/unix (the default when gl/glew is disabled). Unavailable when `USE SDL2=0`. Requires `kivy.deps.sdl2` be installed.
- `angle_sdl2` – Available on Windows with Python 3.5+. Unavailable when `USE SDL2=0`. Requires `kivy.deps.sdl2` and `kivy.deps.angle` be installed.
- `mock` – Always available. Doesn't actually do anything.

Additionally, the following environmental runtime variables control the graphics system:

- `KIVY_GL_DEBUG` – Logs all gl calls when 1.
- `KIVY_GRAPHICS` – Forces OpenGL ES2 when it is `gles`. OpenGL ES2 is always used on the android, ios, rpi, and mali OSs.

## 27.5 Context instructions

The context instructions represent non graphics elements such as:

- Matrix manipulations (`PushMatrix`, `PopMatrix`, `Rotate`, `Translate`, `Scale`, `MatrixInstruction`)
- Color manipulations (`Color`)
- Texture bindings (`BindTexture`)

Changed in version 1.0.8: The `LineWidth` instruction has been removed. It wasn't working before and we actually have no working implementation. We need to do more experimentation to get it right. Check the bug [#207](#) for more information.

**class kivy.graphics.context\_instructions.Color**  
Bases: `kivy.graphics.instructions.ContextInstruction`

Instruction to set the color state for any vertices being drawn after it.

This represents a color between 0 and 1, but is applied as a *multiplier* to the texture of any vertex instructions following it in a canvas. If no texture is set, the vertex instruction takes the precise color of the `Color` instruction.

For instance, if a `Rectangle` has a texture with uniform color `(0.5, 0.5, 0.5, 1.0)` and the preceding `Color` has `rgba=(1, 0.5, 2, 1)`, the actual visible color will be `(0.5, 0.25, 1.0, 1.0)` since the `Color` instruction is applied as a multiplier to every `rgba` component. In this case, a `Color` component outside the 0-1 range gives a visible result as the intensity of the blue component is doubled.

To declare a `Color` in Python, you can do:

```
from kivy.graphics import Color

# create red v
c = Color(1, 0, 0)
# create blue color
c = Color(0, 1, 0)
# create blue color with 50% alpha
c = Color(0, 1, 0, .5)

# using hsv mode
c = Color(0, 1, 1, mode='hsv')
# using hsv mode + alpha
c = Color(0, 1, 1, .2, mode='hsv')
```

You can also set color components that are available as properties by passing them as keyword arguments:

```
c = Color(b=0.5) # sets the blue component only
```

In kv lang you can set the color properties directly:

```
<Rule>:  
    canvas:  
        # red color  
        Color:  
            rgb: 1, 0, 0  
        # blue color  
        Color:  
            rgb: 0, 1, 0  
        # blue color with 50% alpha  
        Color:  
            rgba: 0, 1, 0, .5  
  
        # using hsv mode  
        Color:  
            hsv: 0, 1, 1  
        # using hsv mode + alpha  
        Color:  
            hsv: 0, 1, 1  
            a: .5
```

**a**

Alpha component, between 0 and 1.

**b**

Blue component, between 0 and 1.

**g**

Green component, between 0 and 1.

**h**

Hue component, between 0 and 1.

**hsv**

HSV color, list of 3 values in 0-1 range, alpha will be 1.

**r**

Red component, between 0 and 1.

**rgb**

RGB color, list of 3 values in 0-1 range. The alpha will be 1.

**rgba**

RGBA color, list of 4 values in 0-1 range.

**s**

Saturation component, between 0 and 1.

**v**

Value component, between 0 and 1.

**class** kivy.graphics.context\_instructions.**BindTexture**  
Bases: *kivy.graphics.instructions.ContextInstruction*

BindTexture Graphic instruction. The BindTexture Instruction will bind a texture and enable GL\_TEXTURE\_2D for subsequent drawing.

#### Parameters

*texture*: Texture Specifies the texture to bind to the given index.

**source**

Set/get the source (filename) to load for the texture.

**class** kivy.graphics.context\_instructions.**PushMatrix**  
Bases: *kivy.graphics.instructions.ContextInstruction*

Push the matrix onto the context's matrix stack.

**stack**

Name of the matrix stack to use. Can be 'modelview\_mat', 'projection\_mat' or 'frag\_modelview\_mat'.

New in version 1.6.0.

**class** kivy.graphics.context\_instructions.**PopMatrix**  
Bases: *kivy.graphics.instructions.ContextInstruction*

Pop the matrix from the context's matrix stack onto the model view.

**stack**

Name of the matrix stack to use. Can be 'modelview\_mat', 'projection\_mat' or 'frag\_modelview\_mat'.

New in version 1.6.0.

**class** kivy.graphics.context\_instructions.**Rotate**  
Bases: *kivy.graphics.context\_instructions.Transform*

Rotate the coordinate space by applying a rotation transformation on the modelview matrix. You can set the properties of the instructions afterwards with e.g.

```
rot.angle = 90  
rot.axis = (0, 0, 1)
```

**angle**

Property for getting/setting the angle of the rotation.

**axis**

Property for getting/setting the axis of the rotation.

The format of the axis is (x, y, z).

**origin**

Origin of the rotation.

New in version 1.7.0.

The format of the origin can be either (x, y) or (x, y, z).

**set()**

Set the angle and axis of rotation.

```
>>> rotationobject.set(90, 0, 0, 1)
```

Deprecated since version 1.7.0: The set() method doesn't use the new *origin* property.

**class** kivy.graphics.context\_instructions.**Scale**  
Bases: *kivy.graphics.context\_instructions.Transform*

Instruction to create a non uniform scale transformation.

Create using one or three arguments:

```
Scale(s)      # scale all three axes the same  
Scale(x, y, z) # scale the axes independently
```

Deprecated since version 1.6.0: Deprecated single scale property in favor of x, y, z, xyz axis independent scaled factors.

### **origin**

Origin of the scale.

New in version 1.9.0.

The format of the origin can be either (x, y) or (x, y, z).

### **scale**

Property for getting/setting the scale.

Deprecated since version 1.6.0: Deprecated in favor of per axis scale properties x,y,z, xyz, etc.

#### **x**

Property for getting/setting the scale on the X axis.

Changed in version 1.6.0.

#### **xyz**

3 tuple scale vector in 3D in x, y, and z axis.

Changed in version 1.6.0.

#### **y**

Property for getting/setting the scale on the Y axis.

Changed in version 1.6.0.

#### **z**

Property for getting/setting the scale on Z axis.

Changed in version 1.6.0.

## **class kivy.graphics.context\_instructions.Translate**

Bases: [kivy.graphics.context\\_instructions.Transform](#)

Instruction to create a translation of the model view coordinate space.

Construct by either:

```
Translate(x, y)          # translate in just the two axes
Translate(x, y, z)        # translate in all three axes
```

#### **x**

Property for getting/setting the translation on the X axis.

#### **xy**

2 tuple with translation vector in 2D for x and y axis.

#### **xyz**

3 tuple translation vector in 3D in x, y, and z axis.

#### **y**

Property for getting/setting the translation on the Y axis.

#### **z**

Property for getting/setting the translation on the Z axis.

## **class kivy.graphics.context\_instructions.MatrixInstruction**

Bases: [kivy.graphics.instructions.ContextInstruction](#)

Base class for Matrix Instruction on the canvas.

### **matrix**

Matrix property. Matrix from the transformation module. Setting the matrix using this property when a change is made is important because it will notify the context about the update.

### **stack**

Name of the matrix stack to use. Can be ‘modelview\_mat’, ‘projection\_mat’ or ‘frag\_modelview\_mat’.

New in version 1.6.0.

## 27.6 Context management

New in version 1.2.0.

This class manages a registry of all created graphics instructions. It has the ability to flush and delete them.

You can read more about Kivy graphics contexts in the [Graphics](#) module documentation. These are based on [OpenGL graphics contexts](#).

### **class kivy.graphics.context.Context**

Bases: object

The Context class manages groups of graphics instructions. It can also be used to manage observer callbacks. See [add\\_reload\\_observer\(\)](#) and [remove\\_reload\\_observer\(\)](#) for more information.

#### **add\_reload\_observer()**

(internal) Add a callback to be called after the whole graphics context has been reloaded.  
This is where you can reupload your custom data into the GPU.

##### Parameters

**callback: func(context) -> return None** The first parameter will be the context itself

**before: boolean, defaults to False** If True, the callback will be executed before all the reloading processes. Use it if you want to clear your cache for example.

Changed in version 1.4.0: *before* parameter added.

#### **remove\_reload\_observer()**

(internal) Remove a callback from the observer list previously added by [add\\_reload\\_observer\(\)](#).

## 27.7 Framebuffer

The Fbo is like an offscreen window. You can activate the fbo for rendering into a texture and use your fbo as a texture for other drawing.

The Fbo acts as a [kivy.graphics.instructions.Canvas](#).

Here is an example of using an fbo for some colored rectangles:

```
from kivy.graphics import Fbo, Color, Rectangle

class FboTest(Widget):
    def __init__(self, **kwargs):
        super(FboTest, self).__init__(**kwargs)

        # first step is to create the fbo and use the fbo texture on other
        # rectangle

        with self.canvas:
```

```

# create the fbo
self.fbo = Fbo(size=(256, 256))

# show our fbo on the widget in different size
Color(1, 1, 1)
Rectangle(size=(32, 32), texture=self.fbo.texture)
Rectangle(pos=(32, 0), size=(64, 64), texture=self.fbo.texture)
Rectangle(pos=(96, 0), size=(128, 128), texture=self.fbo.texture)

# in the second step, you can draw whatever you want on the fbo
with self.fbo:
    Color(1, 0, 0, .8)
    Rectangle(size=(256, 64))
    Color(0, 1, 0, .8)
    Rectangle(size=(64, 256))

```

If you change anything in the `self.fbo` object, it will be automatically updated. The canvas where the fbo is put will be automatically updated as well.

### 27.7.1 Reloading the FBO content

New in version 1.2.0.

If the OpenGL context is lost, then the FBO is lost too. You need to reupload data on it yourself. Use the `Fbo.add_reload_observer()` to add a reloading function that will be automatically called when needed:

```

def __init__(self, **kwargs):
    super(...).__init__(**kwargs)
    self.fbo = Fbo(size=(512, 512))
    self.fbo.add_reload_observer(self.populate_fbo)

    # and load the data now.
    self.populate_fbo(self.fbo)

def populate_fbo(self, fbo):
    with fbo:
        # .. put your Color / Rectangle / ... here

```

This way, you could use the same method for initialization and for reloading. But it's up to you.

**class kivy.graphics.fbo.Fbo**  
Bases: `kivy.graphics.instructions.RenderContext`

Fbo class for wrapping the OpenGL Framebuffer extension. The Fbo support “with” statement.

#### Parameters

`clear_color: tuple, defaults to (0, 0, 0, 0)` Define the default color for clearing the framebuffer

`size: tuple, defaults to (1024, 1024)` Default size of the framebuffer

`push_viewport: bool, defaults to True` If True, the OpenGL viewport will be set to the framebuffer size, and will be automatically restored when the framebuffer released.

`with_depthbuffer: bool, defaults to False` If True, the framebuffer will be allocated with a Z buffer.

**with\_stencilbuffer: bool, defaults to False** New in version 1.9.0.

If True, the framebuffer will be allocated with a stencil buffer.

**texture: Texture, defaults to None** If None, a default texture will be created.

---

**Note:** Using both of `with_stencilbuffer` and `with_depthbuffer` is not supported in kivy 1.9.0

---

### **add\_reload\_observer()**

Add a callback to be called after the whole graphics context has been reloaded. This is where you can reupload your custom data in GPU.

New in version 1.2.0.

#### **Parameters**

**callback: func(context) -> return None** The first parameter will be the context itself

### **bind()**

Bind the FBO to the current opengl context. *Bind* mean that you enable the Framebuffer, and all the drawing operations will act inside the Framebuffer, until `release()` is called.

The bind/release operations are automatically called when you add graphics objects into it. If you want to manipulate a Framebuffer yourself, you can use it like this:

```
self.fbo = FBO()  
self.fbo.bind()  
# do any drawing command  
self.fbo.release()  
  
# then, your fbo texture is available at  
print(self.fbo.texture)
```

### **clear\_buffer()**

Clear the framebuffer with the `clear_color`.

You need to bind the framebuffer yourself before calling this method:

```
fbo.bind()  
fbo.clear_buffer()  
fbo.release()
```

### **clear\_color**

Clear color in (red, green, blue, alpha) format.

### **get\_pixel\_color()**

Get the color of the pixel with specified window coordinates wx, wy. It returns result in RGBA format.

New in version 1.8.0.

### **pixels**

Get the pixels texture, in RGBA format only, unsigned byte. The origin of the image is at bottom left.

New in version 1.7.0.

### **release()**

Release the Framebuffer (unbind).

**`remove_reload_observer()`**

Remove a callback from the observer list, previously added by [`add\_reload\_observer\(\)`](#).

New in version 1.2.0.

**`size`**

Size of the framebuffer, in (width, height) format.

If you change the size, the framebuffer content will be lost.

**`texture`**

Return the framebuffer texture

## 27.8 GL instructions

New in version 1.3.0.

### 27.8.1 Clearing an FBO

To clear an FBO, you can use [`ClearColor`](#) and [`ClearBuffers`](#) instructions like this example:

```
self.fbo = Fbo(size=self.size)
with self.fbo:
    ClearColor(0, 0, 0, 0)
    ClearBuffers()
```

**`class kivy.graphics.gl_instructions.ClearColor`**

Bases: [`kivy.graphics.instructions.Instruction`](#)

ClearColor Graphics Instruction.

New in version 1.3.0.

Sets the clear color used to clear buffers with the glClear function or [`ClearBuffers`](#) graphics instructions.

**`a`**

Alpha component, between 0 and 1.

**`b`**

Blue component, between 0 and 1.

**`g`**

Green component, between 0 and 1.

**`r`**

Red component, between 0 and 1.

**`rgb`**

RGB color, a list of 3 values in 0-1 range where alpha will be 1.

**`rgba`**

RGBA color used for the clear color, a list of 4 values in the 0-1 range.

**`class kivy.graphics.gl_instructions.ClearBuffers`**

Bases: [`kivy.graphics.instructions.Instruction`](#)

Clearbuffer Graphics Instruction.

New in version 1.3.0.

Clear the buffers specified by the instructions buffer mask property. By default, only the coloc buffer is cleared.

**clear\_color**

If True, the color buffer will be cleared.

**clear\_depth**

If True, the depth buffer will be cleared.

**clear\_stencil**

If True, the stencil buffer will be cleared.

## 27.9 Graphics compiler

Before rendering an *InstructionGroup*, we compile the group in order to reduce the number of instructions executed at rendering time.

### 27.9.1 Reducing the context instructions

Imagine that you have a scheme like this:

```
Color(1, 1, 1)
Rectangle(source='button.png', pos=(0, 0), size=(20, 20))
Color(1, 1, 1)
Rectangle(source='button.png', pos=(10, 10), size=(20, 20))
Color(1, 1, 1)
Rectangle(source='button.png', pos=(10, 20), size=(20, 20))
```

The real instructions seen by the graphics canvas would be:

```
Color: change 'color' context to 1, 1, 1
BindTexture: change 'texture0' to `button.png texture`
Rectangle: push vertices (x1, y1...) to vbo & draw
Color: change 'color' context to 1, 1, 1
BindTexture: change 'texture0' to `button.png texture`
Rectangle: push vertices (x1, y1...) to vbo & draw
Color: change 'color' context to 1, 1, 1
BindTexture: change 'texture0' to `button.png texture`
Rectangle: push vertices (x1, y1...) to vbo & draw
```

Only the first *Color* and *BindTexture* are useful and really change the context. We can reduce them to:

```
Color: change 'color' context to 1, 1, 1
BindTexture: change 'texture0' to `button.png texture`
Rectangle: push vertices (x1, y1...) to vbo & draw
Rectangle: push vertices (x1, y1...) to vbo & draw
Rectangle: push vertices (x1, y1...) to vbo & draw
```

This is what the compiler does in the first place, by flagging all the unused instruction with GI\_IGNORE flag. As soon as a Color content changes, the whole InstructionGroup will be recompiled and a previously unused Color might be used for the next compilation.

Note to any Kivy contributor / internal developer:

- All context instructions are checked to see if they change anything in the cache.
- We must ensure that a context instruction is needed for our current Canvas.
- We must ensure that we don't depend of any other canvas.

- We must reset our cache if one of our children is another instruction group because we don't know whether it might do weird things or not.

## 27.10 OpenGL

This module is a Python wrapper for OpenGL commands.

**Warning:** Not every OpenGL command has been wrapped and because we are using the C binding for higher performance, and you should rather stick to the Kivy Graphics API. By using OpenGL commands directly, you might change the OpenGL context and introduce inconsistency between the Kivy state and the OpenGL state.

```
kivy.graphics.opengl.glActiveTexture()
    See: glActiveTexture\(\) on Kronos website
kivy.graphics.opengl.glAttachShader()
    See: glAttachShader\(\) on Kronos website
kivy.graphics.opengl.glBindAttribLocation()
    See: glBindAttribLocation\(\) on Kronos website
kivy.graphics.opengl.glBindBuffer()
    See: glBindBuffer\(\) on Kronos website
kivy.graphics.opengl.glBindFramebuffer()
    See: glBindFramebuffer\(\) on Kronos website
kivy.graphics.opengl.glBindRenderbuffer()
    See: glBindRenderbuffer\(\) on Kronos website
kivy.graphics.opengl.glBindTexture()
    See: glBindTexture\(\) on Kronos website
kivy.graphics.opengl.glBlendColor()
    See: glBlendColor\(\) on Kronos website
kivy.graphics.opengl.glBlendEquation()
    See: glBlendEquation\(\) on Kronos website
kivy.graphics.opengl.glBlendEquationSeparate()
    See: glBlendEquationSeparate\(\) on Kronos website
kivy.graphics.opengl.glBlendFunc()
    See: glBlendFunc\(\) on Kronos website
kivy.graphics.opengl.glBlendFuncSeparate()
    See: glBlendFuncSeparate\(\) on Kronos website
kivy.graphics.opengl.glBufferData()
    See: glBufferData\(\) on Kronos website
kivy.graphics.opengl.glBufferSubData()
    See: glBufferSubData\(\) on Kronos website
kivy.graphics.opengl.glCheckFramebufferStatus()
    See: glCheckFramebufferStatus\(\) on Kronos website
kivy.graphics.opengl.glClear()
    See: glClear\(\) on Kronos website
```

`kivy.graphics.opengl.glClearColor()`  
See: [glClearColor\(\) on Kronos website](#)

`kivy.graphics.opengl.glClearStencil()`  
See: [glClearStencil\(\) on Kronos website](#)

`kivy.graphics.opengl.glColorMask()`  
See: [glColorMask\(\) on Kronos website](#)

`kivy.graphics.opengl.glCompileShader()`  
See: [glCompileShader\(\) on Kronos website](#)

`kivy.graphics.opengl.glCompressedTexImage2D()`  
See: [glCompressedTexImage2D\(\) on Kronos website](#)

`kivy.graphics.opengl.glCompressedTexSubImage2D()`  
See: [glCompressedTexSubImage2D\(\) on Kronos website](#)

`kivy.graphics.opengl.glCopyTexImage2D()`  
See: [glCopyTexImage2D\(\) on Kronos website](#)

`kivy.graphics.opengl.glCopyTexSubImage2D()`  
See: [glCopyTexSubImage2D\(\) on Kronos website](#)

`kivy.graphics.opengl.glCreateProgram()`  
See: [glCreateProgram\(\) on Kronos website](#)

`kivy.graphics.opengl.glCreateShader()`  
See: [glCreateShader\(\) on Kronos website](#)

`kivy.graphics.opengl.glCullFace()`  
See: [glCullFace\(\) on Kronos website](#)

`kivy.graphics.opengl.glDeleteBuffers()`  
See: [glDeleteBuffers\(\) on Kronos website](#)

`kivy.graphics.opengl.glDeleteFramebuffers()`  
See: [glDeleteFramebuffers\(\) on Kronos website](#)

`kivy.graphics.opengl.glDeleteProgram()`  
See: [glDeleteProgram\(\) on Kronos website](#)

`kivy.graphics.opengl.glDeleteRenderbuffers()`  
See: [glDeleteRenderbuffers\(\) on Kronos website](#)

`kivy.graphics.opengl.glDeleteShader()`  
See: [glDeleteShader\(\) on Kronos website](#)

`kivy.graphics.opengl.glDeleteTextures()`  
See: [glDeleteTextures\(\) on Kronos website](#)

`kivy.graphics.opengl.glDepthFunc()`  
See: [glDepthFunc\(\) on Kronos website](#)

`kivy.graphics.opengl.glDepthMask()`  
See: [glDepthMask\(\) on Kronos website](#)

`kivy.graphics.opengl.glDetachShader()`  
See: [glDetachShader\(\) on Kronos website](#)

`kivy.graphics.opengl.glDisable()`  
See: [glDisable\(\) on Kronos website](#)

`kivy.graphics.opengl.glDisableVertexAttribArray()`  
See: [glDisableVertexAttribArray\(\) on Kronos website](#)

`kivy.graphics.opengl.glDrawArrays()`  
See: [glDrawArrays\(\) on Kronos website](#)

`kivy.graphics.opengl.glDrawElements()`  
See: [glDrawElements\(\) on Kronos website](#)

`kivy.graphics.opengl.glEnable()`  
See: [glEnable\(\) on Kronos website](#)

`kivy.graphics.opengl.glEnableVertexAttribArray()`  
See: [glEnableVertexAttribArray\(\) on Kronos website](#)

`kivy.graphics.opengl.glFinish()`  
See: [glFinish\(\) on Kronos website](#)

`kivy.graphics.opengl.glFlush()`  
See: [glFlush\(\) on Kronos website](#)

`kivy.graphics.opengl.glFramebufferRenderbuffer()`  
See: [glFramebufferRenderbuffer\(\) on Kronos website](#)

`kivy.graphics.opengl.glFramebufferTexture2D()`  
See: [glFramebufferTexture2D\(\) on Kronos website](#)

`kivy.graphics.opengl.glFrontFace()`  
See: [glFrontFace\(\) on Kronos website](#)

`kivy.graphics.opengl glGenBuffers()`  
See: [glGenBuffers\(\) on Kronos website](#)

Unlike the C specification, the value will be the result of call.

`kivy.graphics.opengl glGenFramebuffers()`  
See: [glGenFramebuffers\(\) on Kronos website](#)

Unlike the C specification, the value will be the result of call.

`kivy.graphics.opengl glGenRenderbuffers()`  
See: [glGenRenderbuffers\(\) on Kronos website](#)

Unlike the C specification, the value will be the result of call.

`kivy.graphics.opengl glGenTextures()`  
See: [glGenTextures\(\) on Kronos website](#)

Unlike the C specification, the value will be the result of call.

`kivy.graphics.opengl glGenerateMipmap()`  
See: [glGenerateMipmap\(\) on Kronos website](#)

`kivy.graphics.opengl glGetActiveAttrib()`  
See: [glGetActiveAttrib\(\) on Kronos website](#)

Unlike the C specification, the value will be the result of call.

`kivy.graphics.opengl glGetActiveUniform()`  
See: [glGetActiveUniform\(\) on Kronos website](#)

Unlike the C specification, the value will be the result of call.

`kivy.graphics.opengl glGetAttachedShaders()`  
See: [glGetAttachedShaders\(\) on Kronos website](#)

Unlike the C specification, the value will be the result of call.

`kivy.graphics.opengl glGetAttribLocation()`  
See: [glGetAttribLocation\(\) on Kronos website](#)

Unlike the C specification, the value will be the result of call.

**kivy.graphics.opengl.glGetBooleanv()**

See: [glGetBooleanv\(\) on Kronos website](#)

Unlike the C specification, the value will be the result of call.

**kivy.graphics.opengl.glGetBufferParameteriv()**

See: [glGetBufferParameteriv\(\) on Kronos website](#)

Unlike the C specification, the value will be the result of call.

**kivy.graphics.opengl.glGetError()**

See: [glGetError\(\) on Kronos website](#)

Unlike the C specification, the value will be the result of call.

**kivy.graphics.opengl.glGetFloatv()**

See: [glGetFloatv\(\) on Kronos website](#)

Unlike the C specification, the value will be the result of call.

**kivy.graphics.opengl.glGetFramebufferAttachmentParameteriv()**

See: [glGetFramebufferAttachmentParameteriv\(\) on Kronos website](#)

Unlike the C specification, the value will be the result of call.

**kivy.graphics.opengl.glGetIntegerv()**

See: [glGetIntegerv\(\) on Kronos website](#)

Unlike the C specification, the value(s) will be the result of the call

**kivy.graphics.opengl.glGetProgramInfoLog()**

See: [glGetProgramInfoLog\(\) on Kronos website](#)

Unlike the C specification, the source code will be returned as a string.

**kivy.graphics.opengl.glGetProgramiv()**

See: [glGetProgramiv\(\) on Kronos website](#)

Unlike the C specification, the value(s) will be the result of the call

**kivy.graphics.opengl.glGetRenderbufferParameteriv()**

See: [glGetRenderbufferParameteriv\(\) on Kronos website](#)

Unlike the C specification, the value will be the result of call.

**kivy.graphics.opengl.glGetShaderInfoLog()**

See: [glGetShaderInfoLog\(\) on Kronos website](#)

Unlike the C specification, the source code will be returned as a string.

**kivy.graphics.opengl.glGetShaderPrecisionFormat()**

See: [glGetShaderPrecisionFormat\(\) on Kronos website](#)

**Warning:** Not implemented yet.

**kivy.graphics.opengl.glGetShaderSource()**

See: [glGetShaderSource\(\) on Kronos website](#)

Unlike the C specification, the source code will be returned as a string.

**kivy.graphics.opengl.glGetShaderiv()**

See: [glGetShaderiv\(\) on Kronos website](#)

Unlike the C specification, the value will be the result of call.

`kivy.graphics.opengl.glGetString()`

See: [glGetString\(\) on Kronos website](#)

Unlike the C specification, the value will be returned as a string.

`kivy.graphics.opengl.glGetTexParameterfv()`

See: [glGetTexParameterfv\(\) on Kronos website](#)

`kivy.graphics.opengl.glGetTexParameteriv()`

See: [glGetTexParameteriv\(\) on Kronos website](#)

`kivy.graphics.opengl.glGetUniformLocation()`

See: [glGetUniformLocation\(\) on Kronos website](#)

`kivy.graphics.opengl.glGetUniformfv()`

See: [glGetUniformfv\(\) on Kronos website](#)

`kivy.graphics.opengl.glGetUniformiv()`

See: [glGetUniformiv\(\) on Kronos website](#)

`kivy.graphics.opengl.glGetVertexAttribPointerv()`

See: [glGetVertexAttribPointerv\(\) on Kronos website](#)

**Warning:** Not implemented yet.

`kivy.graphics.opengl.glGetVertexAttribfv()`

See: [glGetVertexAttribfv\(\) on Kronos website](#)

`kivy.graphics.opengl.glGetVertexAttribiv()`

See: [glGetVertexAttribiv\(\) on Kronos website](#)

`kivy.graphics.opengl.glHint()`

See: [glHint\(\) on Kronos website](#)

`kivy.graphics.opengl.gllIsBuffer()`

See: [gllIsBuffer\(\) on Kronos website](#)

`kivy.graphics.opengl.gllIsEnabled()`

See: [gllIsEnabled\(\) on Kronos website](#)

`kivy.graphics.opengl.gllIsFramebuffer()`

See: [gllIsFramebuffer\(\) on Kronos website](#)

`kivy.graphics.opengl.gllIsProgram()`

See: [gllIsProgram\(\) on Kronos website](#)

`kivy.graphics.opengl.gllIsRenderbuffer()`

See: [gllIsRenderbuffer\(\) on Kronos website](#)

`kivy.graphics.opengl.gllIsShader()`

See: [gllIsShader\(\) on Kronos website](#)

`kivy.graphics.opengl.gllIsTexture()`

See: [gllIsTexture\(\) on Kronos website](#)

`kivy.graphics.opengl.gllLineWidth()`

See: [gllLineWidth\(\) on Kronos website](#)

`kivy.graphics.opengl.gllLinkProgram()`

See: [gllLinkProgram\(\) on Kronos website](#)

`kivy.graphics.opengl.glpixelStorei()`

See: [glPixelStorei\(\) on Kronos website](#)

`kivy.graphics.opengl.glPolygonOffset()`

See: [glPolygonOffset\(\) on Kronos website](#)

`kivy.graphics.opengl.glReadPixels()`

See: [glReadPixels\(\) on Kronos website](#)

We support only GL\_RGB/GL\_RGBA as a format and GL\_UNSIGNED\_BYTE as a type.

`kivy.graphics.opengl.glReleaseShaderCompiler()`

See: [glReleaseShaderCompiler\(\) on Kronos website](#)

**Warning:** Not implemented yet.

`kivy.graphics.opengl.glRenderbufferStorage()`

See: [glRenderbufferStorage\(\) on Kronos website](#)

`kivy.graphics.opengl.glSampleCoverage()`

See: [glSampleCoverage\(\) on Kronos website](#)

`kivy.graphics.opengl.glScissor()`

See: [glScissor\(\) on Kronos website](#)

`kivy.graphics.opengl.glShaderBinary()`

See: [glShaderBinary\(\) on Kronos website](#)

**Warning:** Not implemented yet.

`kivy.graphics.opengl.glShaderSource()`

See: [glShaderSource\(\) on Kronos website](#)

`kivy.graphics.opengl.glStencilFunc()`

See: [glStencilFunc\(\) on Kronos website](#)

`kivy.graphics.opengl.glStencilFuncSeparate()`

See: [glStencilFuncSeparate\(\) on Kronos website](#)

`kivy.graphics.opengl.glStencilMask()`

See: [glStencilMask\(\) on Kronos website](#)

`kivy.graphics.opengl.glStencilMaskSeparate()`

See: [glStencilMaskSeparate\(\) on Kronos website](#)

`kivy.graphics.opengl.glStencilOp()`

See: [glStencilOp\(\) on Kronos website](#)

`kivy.graphics.opengl.glStencilOpSeparate()`

See: [glStencilOpSeparate\(\) on Kronos website](#)

`kivy.graphics.opengl.glTexImage2D()`

See: [glTexImage2D\(\) on Kronos website](#)

`kivy.graphics.opengl.glTexParameterf()`

See: [glTexParameterf\(\) on Kronos website](#)

`kivy.graphics.opengl.glTexParameterfv()`

See: [glTexParameterfv\(\) on Kronos website](#)

**Warning:** Not implemented yet.

`kivy.graphics.opengl.glTexParameterI()`

See: [glTexParameterI\(\)](#) on Kronos website

`kivy.graphics.opengl.glTexParameterIV()`

See: [glTexParameterIV\(\)](#) on Kronos website

**Warning:** Not implemented yet.

`kivy.graphics.opengl.glTexSubImage2D()`

See: [glTexSubImage2D\(\)](#) on Kronos website

`kivy.graphics.opengl.glUniform1f()`

See: [glUniform1f\(\)](#) on Kronos website

`kivy.graphics.opengl.glUniform1fv()`

See: [glUniform1fv\(\)](#) on Kronos website

**Warning:** Not implemented yet.

`kivy.graphics.opengl.glUniform1i()`

See: [glUniform1i\(\)](#) on Kronos website

`kivy.graphics.opengl.glUniform1iv()`

See: [glUniform1iv\(\)](#) on Kronos website

**Warning:** Not implemented yet.

`kivy.graphics.opengl.glUniform2f()`

See: [glUniform2f\(\)](#) on Kronos website

`kivy.graphics.opengl.glUniform2fv()`

See: [glUniform2fv\(\)](#) on Kronos website

**Warning:** Not implemented yet.

`kivy.graphics.opengl.glUniform2i()`

See: [glUniform2i\(\)](#) on Kronos website

`kivy.graphics.opengl.glUniform2iv()`

See: [glUniform2iv\(\)](#) on Kronos website

**Warning:** Not implemented yet.

`kivy.graphics.opengl.glUniform3f()`

See: [glUniform3f\(\)](#) on Kronos website

`kivy.graphics.opengl.glUniform3fv()`

See: [glUniform3fv\(\)](#) on Kronos website

**Warning:** Not implemented yet.

`kivy.graphics.opengl.glUniform3i()`

See: [glUniform3i\(\) on Kronos website](#)

`kivy.graphics.opengl.glUniform3iv()`

See: [glUniform3iv\(\) on Kronos website](#)

**Warning:** Not implemented yet.

`kivy.graphics.opengl.glUniform4f()`

See: [glUniform4f\(\) on Kronos website](#)

**Warning:** Not implemented yet.

`kivy.graphics.opengl.glUniform4fv()`

See: [glUniform4fv\(\) on Kronos website](#)

**Warning:** Not implemented yet.

`kivy.graphics.opengl.glUniform4i()`

See: [glUniform4i\(\) on Kronos website](#)

`kivy.graphics.opengl.glUniform4iv()`

See: [glUniform4iv\(\) on Kronos website](#)

**Warning:** Not implemented yet.

`kivy.graphics.opengl.glUniformMatrix2fv()`

See: [glUniformMatrix2fv\(\) on Kronos website](#)

**Warning:** Not implemented yet.

`kivy.graphics.opengl.glUniformMatrix3fv()`

See: [glUniformMatrix3fv\(\) on Kronos website](#)

**Warning:** Not implemented yet.

`kivy.graphics.opengl.glUniformMatrix4fv()`

See: [glUniformMatrix4fv\(\) on Kronos website](#)

`kivy.graphics.opengl.glUseProgram()`

See: [glUseProgram\(\) on Kronos website](#)

`kivy.graphics.opengl.glValidateProgram()`

See: [glValidateProgram\(\) on Kronos website](#)

`kivy.graphics.opengl.glVertexAttrib1f()`

See: [glVertexAttrib1f\(\) on Kronos website](#)

`kivy.graphics.opengl.glVertexAttrib1fv()`

See: [glVertexAttrib1fv\(\) on Kronos website](#)

**Warning:** Not implemented yet.

`kivy.graphics.opengl.glVertexAttrib2f()`

See: [glVertexAttrib2f\(\)](#) on Kronos website

`kivy.graphics.opengl.glVertexAttrib2fv()`

See: [glVertexAttrib2fv\(\)](#) on Kronos website

**Warning:** Not implemented yet.

`kivy.graphics.opengl.glVertexAttrib3f()`

See: [glVertexAttrib3f\(\)](#) on Kronos website

`kivy.graphics.opengl.glVertexAttrib3fv()`

See: [glVertexAttrib3fv\(\)](#) on Kronos website

**Warning:** Not implemented yet.

`kivy.graphics.opengl.glVertexAttrib4f()`

See: [glVertexAttrib4f\(\)](#) on Kronos website

`kivy.graphics.opengl.glVertexAttrib4fv()`

See: [glVertexAttrib4fv\(\)](#) on Kronos website

**Warning:** Not implemented yet.

`kivy.graphics.opengl.glVertexAttribPointer()`

See: [glVertexAttribPointer\(\)](#) on Kronos website

`kivy.graphics.opengl.glViewport()`

See: [glViewport\(\)](#) on Kronos website

## 27.11 OpenGL utilities

New in version 1.0.7.

`kivy.graphics.opengl_utils.gl_get_extensions()`

Return a list of OpenGL extensions available. All the names in the list have the *GL\_* stripped at the start (if it exists) and are in lowercase.

```
>>> print(gl_get_extensions())
['arb_blend_func_extended', 'arb_color_buffer_float', 'arb_compatibility',
 'arb_copy_buffer'... ]
```

`kivy.graphics.opengl_utils.gl_has_extension()`

Check if an OpenGL extension is available. If the name starts with *GL\_*, it will be stripped for the test and converted to lowercase.

```
>>> gl_has_extension('NV_get_tex_image')
False
>>> gl_has_extension('OES_texture_npot')
True
```

### `kivy.graphics.opengl_utils.gl_has_capability()`

Return the status of a OpenGL Capability. This is a wrapper that auto-discovers all the capabilities that Kivy might need. The current capabilities tested are:

- GLCAP\_BGRA: Test the support of BGRA texture format
- GLCAP\_NPOT: Test the support of Non Power of Two texture
- GLCAP\_S3TC: Test the support of S3TC texture (DXT1, DXT3, DXT5)
- GLCAP\_DXT1: Test the support of DXT texture (subset of S3TC)
- GLCAP\_ETC1: Test the support of ETC1 texture

### `kivy.graphics.opengl_utils.gl_register_get_size()`

Register an association between an OpenGL Const used in glGet\* to a number of elements.

By example, the GPU\_MEMORY\_INFODEDICATED\_VIDMEM\_NVX is a special pname that will return the integer 1 (nvidia only).

```
>>> GPU_MEMORY_INFODEDICATED_VIDMEM_NVX = 0x9047
>>> gl_register_get_size(GPU_MEMORY_INFODEDICATED_VIDMEM_NVX, 1)
>>> glGetIntegerv(GPU_MEMORY_INFODEDICATED_VIDMEM_NVX)[0]
524288
```

### `kivy.graphics.opengl_utils.gl_has_texture_format()`

Return whether a texture format is supported by your system, natively or by conversion. For example, if your card doesn't support 'bgra', we are able to convert to 'rgba' but only in software mode.

### `kivy.graphics.opengl_utils.gl_has_texture_conversion()`

Return 1 if the texture can be converted to a native format.

### `kivy.graphics.opengl_utils.gl_has_texture_native_format()`

Return 1 if the texture format is handled natively.

```
>>> gl_has_texture_format('azdmok')
0
>>> gl_has_texture_format('rgba')
1
>>> gl_has_texture_format('s3tc_dxt1')
[INFO    ] [GL           ] S3TC texture support is available
[INFO    ] [GL           ] DXT1 texture support is available
1
```

### `kivy.graphics.opengl_utils.gl_get_texture_formats()`

Return a list of texture formats recognized by kivy. The texture list is informative but might not been supported by your hardware. If you want a list of supported textures, you must filter that list as follows:

```
supported_fmts = [gl_has_texture_format(x) for x in gl_get_texture_formats()]
```

### `kivy.graphics.opengl_utils.gl_get_version()`

Return the (major, minor) OpenGL version, parsed from the GL\_VERSION.

New in version 1.2.0.

### `kivy.graphics.opengl_utils.gl_get_version_minor()`

Return the minor component of the OpenGL version.

New in version 1.2.0.

### `kivy.graphics.opengl_utils.gl_get_version_major()`

Return the major component of the OpenGL version.

New in version 1.2.0.

## 27.12 Scissor Instructions

New in version 1.9.1.

Scissor instructions clip your drawing area into a rectangular region.

- **ScissorPush**: Begins clipping, sets the bounds of the clip space
- **ScissorPop**: Ends clipping

The area provided to clip is in screenspace pixels and must be provided as integer values not floats.

The following code will draw a circle ontop of our widget while clipping the circle so it does not expand beyond the widget borders.

```
with self.canvas.after:  
    #If our widget is inside another widget that modified the coordinates  
    #spacing (such as ScrollView) we will want to convert to Window coords  
    x,y = self.to_window(*self.pos)  
    width, height = self.size  
    #We must convert from the possible float values provided by kivy  
    #widgets to an integer screenspace, in python3 round returns an int so  
    #the int cast will be unnecessary.  
    ScissorPush(x=int(round(x)), y=int(round(y)),  
                width=int(round(width)), height=int(round(height)))  
    Color(rgba=(1., 0., 0., .5))  
    Ellipse(size=(width*2., height*2.),  
            pos=self.center)  
    ScissorPop()
```

**class kivy.graphics.scissor\_instructions.Rect**

Bases: object

Rect class used internally by ScissorStack and ScissorPush to determine correct clipping area.

**class kivy.graphics.scissor\_instructions.ScissorPop**

Bases: [kivy.graphics.instructions.Instruction](#)

Pop the scissor stack. Call after ScissorPush, once you have completed the drawing you wish to be clipped.

**class kivy.graphics.scissor\_instructions.ScissorPush**

Bases: [kivy.graphics.instructions.Instruction](#)

Push the scissor stack. Provide kwargs of 'x', 'y', 'width', 'height' to control the area and position of the scissoring region. Defaults to 0, 0, 100, 100

Scissor works by clipping all drawing outside of a rectangle starting at int x, int y position and having sides of int width by int height in Window space coordinates

**class kivy.graphics.scissor\_instructions.ScissorStack**

Bases: object

Class used internally to keep track of the current state of glScissors regions. Do not instantiate, prefer to inspect the module's scissor\_stack.

## 27.13 Shader

The **Shader** class handles the compilation of the vertex and fragment shader as well as the creation of the program in OpenGL.

---

**Todo:** Include more complete documentation about the shader.

---

### 27.13.1 Header inclusion

New in version 1.0.7.

When you are creating a Shader, Kivy will always include default parameters. If you don't want to rewrite this each time you want to customize / write a new shader, you can add the "\$HEADER\$" token and it will be replaced by the corresponding shader header.

Here is the header for the fragment Shader:

```
#ifdef GL_ES
    precision highp float;
#endif

/* Outputs from the vertex shader */
varying vec4 frag_color;
varying vec2 tex_coord0;

/* uniform texture samplers */
uniform sampler2D texture0;

uniform mat4 frag_modelview_mat;
```

And the header for vertex Shader:

```
#ifdef GL_ES
    precision highp float;
#endif

/* Outputs to the fragment shader */
varying vec4 frag_color;
varying vec2 tex_coord0;

/* vertex attributes */
attribute vec2      vPosition;
attribute vec2      vTexCoords0;

/* uniform variables */
uniform mat4      modelview_mat;
uniform mat4      projection_mat;
uniform vec4      color;
uniform float     opacity;
```

### 27.13.2 Single file glsl shader programs

New in version 1.6.0.

To simplify shader management, the vertex and fragment shaders can be loaded automatically from a single glsl source file (plain text). The file should contain sections identified by a line starting with ‘—vertex’ and ‘—fragment’ respectively (case insensitive), e.g.

```
// anything before a meaningful section such as this comment are ignored

---VERTEX SHADER--- // vertex shader starts here
void main(){
    ...
}

---FRAGMENT SHADER--- // fragment shader starts here
void main(){
    ...
}
```

The source property of the Shader should be set to the filename of a glsl shader file (of the above format), e.g. *phong.glsl*

**class kivy.graphics.shader.Shader**

Bases: object

Create a vertex or fragment shader.

**Parameters**

**vs: string, defaults to None** Source code for vertex shader

**fs: string, defaults to None** Source code for fragment shader

**fs**

Fragment shader source code.

If you set a new fragment shader code source, it will be automatically compiled and will replace the current fragment shader.

**source**

glsl source code.

source should be the filename of a glsl shader that contains both the vertex and fragment shader sourcecode, each designated by a section header consisting of one line starting with either “—VERTEX” or “—FRAGMENT” (case insensitive).

New in version 1.6.0.

**success**

Indicate whether the shader loaded successfully and is ready for usage or not.

**vs**

Vertex shader source code.

If you set a new vertex shader code source, it will be automatically compiled and will replace the current vertex shader.

## 27.14 Stencil instructions

New in version 1.0.4.

Changed in version 1.3.0: The stencil operation has been updated to resolve some issues that appeared when nested. You **must** now have a StencilUnUse and repeat the same operation as you did after StencilPush.

Stencil instructions permit you to draw and use the current drawing as a mask. They don't give as much control as pure OpenGL, but you can still do fancy things!

The stencil buffer can be controlled using these 3 instructions:

- **StencilPush**: push a new stencil layer. Any drawing that happens after this will be used as a mask.
- **StencilUse** : now draw the next instructions and use the stencil for masking them.
- **StencilUnUse** : stop using the stencil i.e. remove the mask and draw normally.
- **StencilPop** : pop the current stencil layer.

You should always respect this scheme:

```
StencilPush
# PHASE 1: put any drawing instructions to use as a mask here.

StencilUse
# PHASE 2: all the drawing here will be automatically clipped by the
# mask created in PHASE 1.

StencilUnUse
# PHASE 3: put the same drawing instruction here as you did in PHASE 1

StencilPop
# PHASE 4: the stencil is now removed from the stack and unloaded.
```

#### 27.14.1 Limitations

- Drawing in PHASE 1 and PHASE 3 must not collide or you will get unexpected results
- The stencil is activated as soon as you perform a StencilPush
- The stencil is deactivated as soon as you've correctly popped all the stencil layers
- You must not play with stencils yourself between a StencilPush / StencilPop
- You can push another stencil after a StencilUse / before the StencilPop
- You can push up to 128 layers of stencils (8 for kivy < 1.3.0)

#### 27.14.2 Example of stencil usage

Here is an example, in kv style:

```
StencilPush
# create a rectangular mask with a pos of (100, 100) and a (100, 100) size.
Rectangle:
    pos: 100, 100
    size: 100, 100

StencilUse
# we want to show a big green rectangle, however, the previous stencil
# mask will crop us :)
```

```

Color:
    rgb: 0, 1, 0
Rectangle:
    size: 900, 900

StencilUnUse

# you must redraw the stencil mask to remove it
Rectangle:
    pos: 100, 100
    size: 100, 100

StencilPop

```

**class kivy.graphics.stencil\_instructions.StencilPush**  
Bases: *kivy.graphics.instructions.Instruction*

Push the stencil stack. See the module documentation for more information.

**class kivy.graphics.stencil\_instructions.StencilPop**  
Bases: *kivy.graphics.instructions.Instruction*

Pop the stencil stack. See the module documentation for more information.

**class kivy.graphics.stencil\_instructions.StencilUse**  
Bases: *kivy.graphics.instructions.Instruction*

Use current stencil buffer as a mask. Check the module documentation for more information.

#### func\_op

Determine the stencil operation to use for glStencilFunc(). Can be one of ‘never’, ‘less’, ‘equal’, ‘lequal’, ‘greater’, ‘notequal’, ‘gequal’ or ‘always’.

By default, the operator is set to ‘equal’.

New in version 1.5.0.

**class kivy.graphics.stencil\_instructions.StencilUnUse**  
Bases: *kivy.graphics.instructions.Instruction*

Use current stencil buffer to unset the mask.

## 27.15 SVG

New in version 1.9.0.

**Warning:** This is highly experimental and subject to change. Don’t use it in production.

Load an SVG as a graphics instruction:

```

from kivy.graphics.svg import Svg
with widget.canvas:
    svg = Svg("image.svg")

```

There is no widget that can display Svg directly, you have to make your own for now. Check the *examples/svg* for more informations.

**class kivy.graphics.svg.Svg**  
Bases: *kivy.graphics.instructions.RenderContext*

Svg class. See module for more informations about the usage.

**anchor\_x**

Horizontal anchor position for scaling and rotations. Defaults to 0. The symbolic values 'left', 'center' and 'right' are also accepted.

**anchor\_y**

Vertical anchor position for scaling and rotations. Defaults to 0. The symbolic values 'bottom', 'center' and 'top' are also accepted.


**filename**


Filename to load.

The parsing and rendering is done as soon as you set the filename.

## 27.16 Tesselator

New in version 1.9.0.





**Warning:** This is experimental and subject to change as long as this warning notice is present. Only TYPE\_POLYGONS is currently supported.

Tesselator is a library for tessellating polygons, based on [libtess2](#). It renders concave filled polygons by first tesselating them into convex polygons. It also supports holes.

### 27.16.1 Usage

First, you need to create a [\*Tesselator\*](#) object and add contours. The first one is the external contour of your shape and all of the following ones should be holes:

```
from kivy.graphics.tesselator import Tesselator

tess = Tesselator()
tess.add_contour([0, 0, 200, 0, 200, 200, 0, 200])
tess.add_contour([50, 50, 150, 50, 150, 150, 50, 150])
```

Second, call the [\*Tesselator.tesselate\(\)\*](#) method to compute the points. It is possible that the tesselator won't work. In that case, it can return False:

```
if not tess.tesselate():
    print "Tesselator didn't work :("
    return
```

After the tessellation, you have multiple ways to iterate over the result. The best approach is using [\*Tesselator.meshes\*](#) to get a format directly usable for a [\*Mesh\*](#):

```
for vertices, indices in tess.meshes:
    self.canvas.add(Mesh(
        vertices=vertices,
        indices=indices,
        mode="triangle_fan"
    ))
```

Or, you can get the “raw” result, with just polygons and x/y coordinates with `Tesselator.vertices()`:

```
for vertices in tess.vertices:  
    print "got polygon", vertices
```

## class kivy.graphics.tesselator.Tesselator

Bases: object

Tesselator class. See module for more informations about the usage.

### add\_contour()

Add a contour to the tesselator. It can be:

- a list of  $[x, y, x2, y2, \dots]$  coordinates
- a float array: `array("f", [x, y, x2, y2, \dots])`
- any buffer with floats in it.

### element\_count

Returns the number of convex polygon.

### meshes

Iterate through the result of the `tessellate()` to give a result that can be easily pushed into Kivy’s Mesh object.

It’s a list of:  $[[vertices, indices], [vertices, indices], \dots]$ . The vertices in the format  $[x, y, u, v, x2, y2, u2, v2]$ .

Careful, u/v coordinates are the same as x/y. You are responsible to change them for texture mapping if you need to.

You can create Mesh objects like that:

```
tess = Tesselator()  
# add contours here  
tess.tessellate()  
for vertices, indices in self.meshes:  
    self.canvas.add(Mesh(  
        vertices=vertices,  
        indices=indices,  
        mode="triangle_fan"))
```

### tessellate()

Compute all the contours added with `add_contour()`, and generate polygons.

#### Parameters

`winding_rule: enum` The winding rule classifies a region as inside if its winding number belongs to the chosen category. Can be one of WINDING\_ODD, WINDING\_NONZERO, WINDING\_POSITIVE, WINDING\_NEGATIVE, WINDING\_ABS\_EQ\_TWO. Defaults to WINDING\_ODD.

`element_type: enum` The result type, you can generate the polygons with TYPE\_POLYGONS, or the contours with TYPE\_BOUNDARY\_CONTOURS. Defaults to TYPE\_POLYGONS.

`Returns` 1 if the tessellation happened, 0 otherwise.

`Return type` int

### vertex\_count

Returns the number of vertex generated.

This is the raw result, however, because the Tessellator format the result for you with *meshes* or *vertices* per polygon, you'll have more vertices in the result

### vertices

Iterate through the result of the `tessellate()` in order to give only a list of  $[x, y, x2, y2, \dots]$  polygons.

## 27.17 Texture

Changed in version 1.6.0: Added support for palettes texture on OES: 'palette4\_rgb8', 'palette4\_rgba8', 'palette4\_r5\_g6\_b5', 'palette4\_rgba4', 'palette4\_rgb5\_a1', 'palette8\_rgb8', 'palette8\_rgba8', 'palette8\_r5\_g6\_b5', 'palette8\_rgba4' and 'palette8\_rgb5\_a1'.

*Texture* is a class that handles OpenGL textures. Depending on the hardware, some OpenGL capabilities might not be available (BGRA support, NPOT support, etc.)

You cannot instantiate this class yourself. You must use the function `Texture.create()` to create a new texture:

```
texture = Texture.create(size=(640, 480))
```

When you create a texture, you should be aware of the default color and buffer format:

- the color/pixel format (`Texture.colorfmt`) that can be one of 'rgb', 'rgba', 'luminance', 'luminance\_alpha', 'bgr' or 'bgra'. The default value is 'rgb'
- the buffer format determines how a color component is stored into memory. This can be one of 'ubyte', 'ushort', 'uint', 'byte', 'short', 'int' or 'float'. The default value and the most commonly used is 'ubyte'.

So, if you want to create an RGBA texture:

```
texture = Texture.create(size=(640, 480), colorfmt='rgba')
```

You can use your texture in almost all vertex instructions with the `kivy.graphics.VertexInstruction.texture` parameter. If you want to use your texture in kv lang, you can save it in an *ObjectProperty* inside your widget.

### 27.17.1 Blitting custom data

You can create your own data and blit it to the texture using `Texture.blit_buffer()`.

For example, to blit immutable bytes data:

```
# create a 64x64 texture, defaults to rgba / ubyte
texture = Texture.create(size=(64, 64))

# create 64x64 rgb tab, and fill with values from 0 to 255
# we'll have a gradient from black to white
size = 64 * 64 * 3
buf = [int(x * 255 / size) for x in range(size)]

# then, convert the array to a ubyte string
buf = b''.join(map(chr, buf))

# then blit the buffer
texture.blit_buffer(buf, colorfmt='rgb', bufferfmt='ubyte')

# that's all ! you can use it in your graphics now :)
```

```
# if self is a widget, you can do this
with self.canvas:
    Rectangle(texture=texture, pos=self.pos, size=(64, 64))
```

Since 1.9.0, you can blit data stored in a instance that implements the python buffer interface, or a memoryview thereof, such as numpy arrays, python `array.array`, a `bytearray`, or a cython array. This is beneficial if you expect to blit similar data, with perhaps a few changes in the data.

When using a bytes representation of the data, for every change you have to regenerate the bytes instance, from perhaps a list, which is very inefficient. When using a buffer object, you can simply edit parts of the original data. Similarly, unless starting with a bytes object, converting to bytes requires a full copy, however, when using a buffer instance, no memory is copied, except to upload it to the GPU.

Continuing with the example above:

```
from array import array

size = 64 * 64 * 3
buf = [int(x * 255 / size) for x in range(size)]
# initialize the array with the buffer values
arr = array('B', buf)
# now blit the array
texture.blit_buffer(arr, colorfmt='rgb', bufferfmt='ubyte')

# now change some elements in the original array
arr[24] = arr[50] = 99
# blit again the buffer
texture.blit_buffer(arr, colorfmt='rgb', bufferfmt='ubyte')
```

## 27.17.2 BGR/BGRA support

The first time you try to create a BGR or BGRA texture, we check whether your hardware supports BGR / BGRA textures by checking the extension ‘GL\_EXT\_bgra’.

If the extension is not found, the conversion to RGB / RGBA will be done in software.

## 27.17.3 NPOT texture

Changed in version 1.0.7: If your hardware supports NPOT, no POT is created.

As the OpenGL documentation says, a texture must be power-of-two sized. That means your width and height can be one of 64, 32, 256... but not 3, 68, 42. NPOT means non-power-of-two. OpenGL ES 2 supports NPOT textures natively but with some drawbacks. Another type of NPOT texture is called a rectangle texture. POT, NPOT and textures all have their own pro/cons.

Features	POT	NPOT	Rectangle
OpenGL Target	GL_TEXTURE_2D	GL_TEXTURE_2D	GL_TEXTURE_RECTANGLE_(NV ARB EXT)
Texture coords	0-1 range	0-1 range	width-height range
Mipmapping	Supported	Partially	No
Wrap mode	Supported	Supported	No

If you create a NPOT texture, we first check whether your hardware supports it by checking the extensions `GL_ARB_texture_non_power_of_two` or `OES_texture_npot`. If none of these are available, we

create the nearest POT texture that can contain your NPOT texture. The `Texture.create()` will return a `TextureRegion` instead.

#### 27.17.4 Texture atlas

A texture atlas is a single texture that contains many images. If you want to separate the original texture into many single ones, you don't need to. You can get a region of the original texture. That will return the original texture with custom texture coordinates:

```
# for example, load a 128x128 image that contain 4 64x64 images
from kivy.core.image import Image
texture = Image('mycombinedimage.png').texture

bottomleft = texture.get_region(0, 0, 64, 64)
bottomright = texture.get_region(0, 64, 64, 64)
topleft = texture.get_region(0, 64, 64, 64)
topright = texture.get_region(64, 64, 64, 64)
```

#### 27.17.5 Mipmapping

New in version 1.0.7.

Mipmapping is an OpenGL technique for enhancing the rendering of large textures to small surfaces. Without mipmapping, you might see pixelation when you render to small surfaces. The idea is to precalculate the subtexture and apply some image filter as a linear filter. Then, when you render a small surface, instead of using the biggest texture, it will use a lower filtered texture. The result can look better this way.

To make that happen, you need to specify `mipmap=True` when you create a texture. Some widgets already give you the ability to create mipmapped textures, such as the `Label` and `Image`.

From the OpenGL Wiki : "So a 64x16 2D texture can have 5 mip-maps: 32x8, 16x4, 8x2, 4x1, 2x1, and 1x1". Check <http://www.opengl.org/wiki/Texture> for more information.

---

**Note:** As the table in previous section said, if your texture is NPOT, we create the nearest POT texture and generate a mipmap from it. This might change in the future.

---

#### 27.17.6 Reloading the Texture

New in version 1.2.0.

If the OpenGL context is lost, the Texture must be reloaded. Textures that have a source are automatically reloaded but generated textures must be reloaded by the user.

Use the `Texture.add_reload_observer()` to add a reloading function that will be automatically called when needed:

```
def __init__(self, **kwargs):
    super(...).__init__(**kwargs)
    self.texture = Texture.create(size=(512, 512), colorfmt='RGB',
        bufferfmt='ubyte')
    self.texture.add_reload_observer(self.populate_texture)

    # and load the data now.
    self.cbuffer = '\x00\xf0\xff' * 512 * 512
```

```

    self.populate_texture(self.texture)

def populate_texture(self, texture):
    texture.blit_buffer(self.cbuffer)

```

This way, you can use the same method for initialization and reloading.

---

**Note:** For all text rendering with our core text renderer, the texture is generated but we already bind a method to redo the text rendering and reupload the text to the texture. You don't have to do anything.

---

## `class kivy.graphics.texture.Texture`

Bases: `object`

Handle an OpenGL texture. This class can be used to create simple textures or complex textures based on `ImageData`.

### `add_reload_observer()`

Add a callback to be called after the whole graphics context has been reloaded. This is where you can reupload your custom data into the GPU.

New in version 1.2.0.

#### Parameters

`callback: func(context) -> return None` The first parameter will be the context itself.

### `ask_update()`

Indicate that the content of the texture should be updated and the callback function needs to be called when the texture will be used.

### `bind()`

Bind the texture to the current opengl state.

### `blit_buffer()`

Blit a buffer into the texture.

---

**Note:** Unless the canvas will be updated due to other changes, `ask_update()` should be called in order to update the texture.

---

#### Parameters

`pbuffer: bytes, or a class that implements the buffer interface (including memoryview).`

A buffer containing the image data. It can be either a bytes object or a instance of a class that implements the python buffer interface, e.g. `array.array`, `bytearray`, numpy arrays etc. If it's not a bytes object, the underlying buffer must be contiguous, have only one dimension and must not be readonly, even though the data is not modified, due to a cython limitation. See module description for usage details.

`size: tuple, defaults to texture size` Size of the image (width, height)

`colorfmt: str, defaults to 'rgb'` Image format, can be one of 'rgb', 'rgba', 'bgr', 'bgra', 'luminance' or 'luminance\_alpha'.

`pos: tuple, defaults to (0, 0)` Position to blit in the texture.

`bufferfmt: str, defaults to 'ubyte'` Type of the data buffer, can be one of 'ubyte', 'ushort', 'uint', 'byte', 'short', 'int' or 'float'.

**mipmap\_level: int, defaults to 0** Indicate which mipmap level we are going to update.

**mipmap\_generation: bool, defaults to True** Indicate if we need to regenerate the mipmap from level 0.

Changed in version 1.0.7: added *mipmap\_level* and *mipmap\_generation*

Changed in version 1.9.0: *pbuffer* can now be any class instance that implements the python buffer interface and / or memoryviews thereof.

### **blit\_data()**

Replace a whole texture with image data.

### **bufferfmt**

Return the buffer format used in this texture (readonly).

New in version 1.2.0.

### **colorfmt**

Return the color format used in this texture (readonly).

New in version 1.0.7.

### **static create()**

Create a texture based on size.

#### **Parameters**

**size: tuple, defaults to (128, 128)** Size of the texture.

**colorfmt: str, defaults to 'rgba'** Color format of the texture. Can be 'rgba' or 'rgb', 'luminance' or 'luminance\_alpha'. On desktop, additional values are available: 'red', 'rg'.

**icolorfmt: str, defaults to the value of colorfmt** Internal format storage of the texture. Can be 'rgba' or 'rgb', 'luminance' or 'luminance\_alpha'. On desktop, additional values are available: 'r8', 'rg8', 'rgba8'.

**bufferfmt: str, defaults to 'ubyte'** Internal buffer format of the texture. Can be 'ubyte', 'ushort', 'uint', 'bute', 'short', 'int' or 'float'.

**mipmap: bool, defaults to False** If True, it will automatically generate the mipmap texture.

**callback: callable(), defaults to False** If a function is provided, it will be called when data is needed in the texture.

Changed in version 1.7.0: *callback* has been added

### **static create\_from\_data()**

Create a texture from an *ImageData* class.

### **flip\_horizontal()**

Flip *tex\_coords* for horizontal display.

New in version 1.9.0.

### **flip\_vertical()**

Flip *tex\_coords* for vertical display.

### **get\_region()**

Return a part of the texture defined by the rectangular arguments (x, y, width, height). Returns a *TextureRegion* instance.

### **height**

Return the height of the texture (readonly).

**id**

Return the OpenGL ID of the texture (readonly).

**mag\_filter**

Get/set the mag filter texture. Available values:

- linear
- nearest

Check the opengl documentation for more information about the behavior of these values :

<http://www.khronos.org/opengles/sdk/docs/man/xhtml/glTexParameter.xml>.

**min\_filter**

Get/set the min filter texture. Available values:

- linear
- nearest
- linear\_mipmap\_linear
- linear\_mipmap\_nearest
- nearest\_mipmap\_nearest
- nearest\_mipmap\_linear

Check the opengl documentation for more information about the behavior of these values :

<http://www.khronos.org/opengles/sdk/docs/man/xhtml/glTexParameter.xml>.

**mipmap**

Return True if the texture has mipmap enabled (readonly).

**pixels**

Get the pixels texture, in RGBA format only, unsigned byte. The origin of the image is at bottom left.

New in version 1.7.0.

**remove\_reload\_observer()**

Remove a callback from the observer list, previously added by [add\\_reload\\_observer\(\)](#).

New in version 1.2.0.

**save()**

Save the texture content to a file. Check [kivy.core.image.Image.save\(\)](#) for more information.

The flipped parameter flips the saved image vertically, and defaults to True.

New in version 1.7.0.

Changed in version 1.8.0: Parameter *flipped* added, defaults to True. All the OpenGL Texture are readed from bottom / left, it need to be flipped before saving. If you don't want to flip the image, set flipped to False.

**size**

Return the (width, height) of the texture (readonly).

**target**

Return the OpenGL target of the texture (readonly).

**tex\_coords**

Return the list of tex\_coords (opengl).

**uvpos**

Get/set the UV position inside the texture.

### **uvsize**

Get/set the UV size inside the texture.

**Warning:** The size can be negative if the texture is flipped.

### **width**

Return the width of the texture (readonly).

### **wrap**

Get/set the wrap texture. Available values:

- repeat
- mirrored\_repeat
- clamp\_to\_edge

Check the opengl documentation for more information about the behavior of these values :  
<http://www.khronos.org/opengles/sdk/docs/man/xhtml/glTexParameter.xml>.

## **class kivy.graphics.texture.TextureRegion**

Bases: *kivy.graphics.texture.Texture*

Handle a region of a Texture class. Useful for non power-of-2 texture handling.

## 27.18 Transformation

This module contains a Matrix class used for our Graphics calculations. We currently support:

- rotation, translation and scaling matrices
- multiplication matrix
- clip matrix (with or without perspective)
- transformation matrix for 3d touch

For more information on transformation matrices, please see the [OpenGL Matrices Tutorial](#).

Changed in version 1.6.0: Added *Matrix.perspective()*, *Matrix.look\_at()* and *Matrix.transpose()*.

## **class kivy.graphics.transformation.Matrix**

Bases: *object*

Optimized matrix class for OpenGL:

```
>>> from kivy.graphics.transformation import Matrix
>>> m = Matrix()
>>> print(m)
[[ 1.000000 0.000000 0.000000 0.000000 ]
 [ 0.000000 1.000000 0.000000 0.000000 ]
 [ 0.000000 0.000000 1.000000 0.000000 ]
 [ 0.000000 0.000000 0.000000 1.000000 ]]

[ 0   1   2   3]
[ 4   5   6   7]
[ 8   9   10  11]
[ 12  13  14  15]
```

**get()**

Retrieve the value of the current as a flat list.

New in version 1.9.1.

**identity()**

Reset the matrix to the identity matrix (inplace).

**inverse()**

Return the inverse of the matrix as a new Matrix.

**look\_at()**

Returns a new lookat Matrix (similar to [gluLookAt](#)).

**Parameters**

*eyex: float* Eyes X co-ordinate  
*eyey: float* Eyes Y co-ordinate  
*eyez: float* Eyes Z co-ordinate  
*centerx: float* The X position of the reference point  
*centery: float* The Y position of the reference point  
*centerz: float* The Z position of the reference point  
*upx: float* The X value up vector.  
*upy: float* The Y value up vector.  
*upz: float* The Z value up vector.

New in version 1.6.0.

**multiply()**

Multiply the given matrix with self (from the left) i.e. we premultiply the given matrix by the current matrix and return the result (not inplace):

```
m.multiply(n) -> n * m
```

**Parameters**

*ma: Matrix* The matrix to multiply by

**normal\_matrix()**

Computes the normal matrix, which is the inverse transpose of the top left 3x3 modelview matrix used to transform normals into eye/camera space.

New in version 1.6.0.

**perspective()**

Creates a perspective matrix (inplace).

**Parameters**

*fovy: float* "Field Of View" angle  
*aspect: float* Aspect ratio  
*zNear: float* Near clipping plane  
*zFar: float* Far clippin plane

New in version 1.6.0.

**project()**

Project a point from 3d space into a 2d viewport.

### Parameters

**objx: float** Points X co-ordinate  
**objy: float** Points Y co-ordinate  
**objz: float** Points Z co-ordinate  
**model: Matrix** The model matrix  
**proj: Matrix** The projection matrix  
**vx: float** Viewports X co-ordinate  
**vy: float** Viewports y co-ordinate  
**vw: float** Viewports width  
**vh: float** Viewports height

New in version 1.7.0.

### **rotate()**

Rotate the matrix through the angle around the axis (x, y, z) (inplace).

### Parameters

**angle: float** The angle through which to rotate the matrix  
**x: float** X position of the point  
**y: float** Y position of the point  
**z: float** Z position of the point

### **scale()**

Scale the current matrix by the specified factors over each dimension (inplace).

### Parameters

**x: float** The scale factor along the X axis  
**y: float** The scale factor along the Y axis  
**z: float** The scale factor along the Z axis

### **set()**

Insert custom values into the matrix in a flat list format or 4x4 array format like below:

```
m.set(array=[  
    [1.0, 0.0, 0.0, 0.0],  
    [0.0, 1.0, 0.0, 0.0],  
    [0.0, 0.0, 1.0, 0.0],  
    [0.0, 0.0, 0.0, 1.0]]  
)
```

New in version 1.9.0.

### **tolist()**

Retrieve the value of the current matrix in numpy format. for example m.tolist() will return:

```
[[1.0, 0.0, 0.0, 0.0],  
 [0.0, 1.0, 0.0, 0.0],  
 [0.0, 0.0, 1.0, 0.0],  
 [0.0, 0.0, 0.0, 1.0]]
```

you can use this format to plug the result straight into numpy in this way  
numpy.array(m.tolist())

New in version 1.9.0.

### **translate()**

Translate the matrix.

#### **Parameters**

**x: float** The translation factor along the X axis

**y: float** The translation factor along the Y axis

**z: float** The translation factor along the Z axis

### **transpose()**

Return the transposed matrix as a new Matrix.

New in version 1.6.0.

### **view\_clip()**

Create a clip matrix (inplace).

#### **Parameters**

**left: float** Co-ordinate

**right: float** Co-ordinate

**bottom: float** Co-ordinate

**top: float** Co-ordinate

**near: float** Co-ordinate

**far: float** Co-ordinate

**perspective: int** Co-ordinate

Changed in version 1.6.0: Enable support for perspective parameter.

## 27.19 Vertex Instructions

This module includes all the classes for drawing simple vertex objects.

### 27.19.1 Updating properties

The list attributes of the graphics instruction classes (e.g. `Triangle.points`, `Mesh.indices` etc.) are not Kivy properties but Python properties. As a consequence, the graphics will only be updated when the list object itself is changed and not when list values are modified.

For example in python:

```
class MyWidget(Button):

    triangle = ObjectProperty(None)
    def __init__(self, **kwargs):
        super(MyWidget, self).__init__(**kwargs)
        with self.canvas:
            self.triangle = Triangle(points=[0,0, 100,100, 200,0])
```

and in kv:

```
<MyWidget>:
    text: 'Update'
    on_press:
        self.triangle.points[3] = 400
```

Although pressing the button will change the triangle coordinates, the graphics will not be updated because the list itself has not changed. Similarly, no updates will occur using any syntax that changes only elements of the list e.g. `self.triangle.points[0:2] = [10,10]` or `self.triangle.points.insert(10)` etc. To force an update after a change, the list variable itself must be changed, which in this case can be achieved with:

```
<MyWidget>:
    text: 'Update'
    on_press:
        self.triangle.points[3] = 400
        self.triangle.points = self.triangle.points
```

**class kivy.graphics.vertex\_instructions.Triangle**  
Bases: *kivy.graphics.instructions.VertexInstruction*

A 2d triangle.

#### Parameters

**points: list** List of points in the format (x1, y1, x2, y2, x3, y3).

#### points

Property for getting/settings points of the triangle.

**class kivy.graphics.vertex\_instructions.Quad**  
Bases: *kivy.graphics.instructions.VertexInstruction*

A 2d quad.

#### Parameters

**points: list** List of point in the format (x1, y1, x2, y2, x3, y3, x4, y4).

#### points

Property for getting/settings points of the quad.

**class kivy.graphics.vertex\_instructions.Rectangle**  
Bases: *kivy.graphics.instructions.VertexInstruction*

A 2d rectangle.

#### Parameters

**pos: list** Position of the rectangle, in the format (x, y).

**size: list** Size of the rectangle, in the format (width, height).

#### pos

Property for getting/settings the position of the rectangle.

#### size

Property for getting/settings the size of the rectangle.

**class kivy.graphics.vertex\_instructions.RoundedRectangle**  
Bases: *kivy.graphics.vertex\_instructions.Rectangle*

A 2D rounded rectangle.

New in version 1.9.1.

#### Parameters

**segments: int, defaults to 10** Define how many segments are needed for drawing the rounded corner. The drawing will be smoother if you have many segments.

**radius: list, defaults to [(10.0, 10.0), (10.0, 10.0), (10.0, 10.0), (10.0, 10.0)]** Specifies the radii used for the rounded corners clockwise: top-left, top-right, bottom-right, bottom-left. Elements of the list can be numbers or tuples of two numbers to specify different x,y dimensions. One value will define all corner radii to be of this value. Four values will define each corner radius separately. Higher numbers of values will be truncated to four. The first value will be used for all corners if there are fewer than four values.

### **radius**

Corner radii of the rounded rectangle, defaults to [10,].

### **segments**

Property for getting/setting the number of segments for each corner.

**class kivy.graphics.vertex\_instructions.BorderImage**  
Bases: *kivy.graphics.vertex\_instructions.Rectangle*

A 2d border image. The behavior of the border image is similar to the concept of a CSS3 border-image.

#### **Parameters**

**border: list** Border information in the format (bottom, right, top, left). Each value is in pixels.

**auto\_scale: string** New in version 1.9.1.

Changed in version 1.9.2: This used to be a bool and has been changed to be a string state.

Can be one of 'off', 'both', 'x\_only', 'y\_only', 'y\_full\_x\_lower', 'x\_full\_y\_lower', 'both\_lower'.

Autoscale controls the behavior of the 9-slice.

By default the border values are preserved exactly, meaning that if the total size of the object is smaller than the border values you will have some 'rendering errors' where your texture appears inside out. This also makes it impossible to achieve a rounded button that scales larger than the size of its source texture. The various options for auto\_scale will let you achieve some mixes of the 2 types of rendering.

'off': is the default and behaves as BorderImage did when auto\_scale was False before.

'both': Scales both x and y dimension borders according to the size of the BorderImage, this disables the BorderImage making it render the same as a regular Image.

'x\_only': The Y dimension functions as the default, and the X scales to the size of the BorderImage's width.

'y\_only': The X dimension functions as the default, and the Y scales to the size of the BorderImage's height.

'y\_full\_x\_lower': Y scales as in 'y\_only', Y scales if the size of the scaled version would be smaller than the provided border only.

'x\_full\_y\_lower': X scales as in 'x\_only', Y scales if the size of the scaled version would be smaller than the provided border only.

'both\_lower': This is what auto\_scale did when it was True in 1.9.1 Both X and Y dimensions will be scaled if the BorderImage is smaller than the source.

If the BorderImage's size is less than the sum of its borders, horizontally or vertically, and this property is set to True, the borders will be rescaled to accommodate for the smaller size.

### auto\_scale

Property for setting if the corners are automatically scaled when the BorderImage is too small.

### border

Property for getting/setting the border of the class.

### display\_border

Property for getting/setting the border display size.

## class kivy.graphics.vertex\_instructions.Ellipse

Bases: *kivy.graphics.vertex\_instructions.Rectangle*

A 2D ellipse.

Changed in version 1.0.7: Added angle\_start and angle\_end.

#### Parameters

**segments: int, defaults to 180** Define how many segments are needed for drawing the ellipse. The drawing will be smoother if you have many segments.

**angle\_start: int, defaults to 0** Specifies the starting angle, in degrees, of the disk portion.

**angle\_end: int, defaults to 360** Specifies the ending angle, in degrees, of the disk portion.

#### angle\_end

End angle of the ellipse in degrees, defaults to 360.

#### angle\_start

Start angle of the ellipse in degrees, defaults to 0.

#### segments

Property for getting/setting the number of segments of the ellipse.

## class kivy.graphics.vertex\_instructions.Line

Bases: *kivy.graphics.instructions.VertexInstruction*


A 2d line.

Drawing a line can be done easily:

```
with self.canvas:  
    Line(points=[100, 100, 200, 100, 100, 200], width=10)
```

The line has 3 internal drawing modes that you should be aware of for optimal results:

1. If the **width** is 1.0, then the standard GL\_LINE drawing from OpenGL will be used. **dash\_length** and **dash\_offset** will work, while properties for cap and joint have no meaning here.
2. If the **width** is greater than 1.0, then a custom drawing method, based on triangulation, will be used. **dash\_length** and **dash\_offset** do not work in this mode. Additionally, if the current color has an alpha less than 1.0, a stencil will be used internally to draw the line.



## Parameters

**points: list** List of points in the format (x1, y1, x2, y2...)

**dash\_length: int** Length of a segment (if dashed), defaults to 1.

**dash\_offset: int** Offset between the end of a segment and the beginning of the next one, defaults to 0. Changing this makes it dashed.

**width: float** Width of the line, defaults to 1.0.

**cap: str, defaults to 'round'** See [cap](#) for more information.

**joint: str, defaults to 'round'** See [joint](#) for more information.

**cap\_precision: int, defaults to 10** See [cap\\_precision](#) for more information

**joint\_precision: int, defaults to 10** See [joint\\_precision](#) for more information  
See [cap\\_precision](#) for more information.

**joint\_precision: int, defaults to 10** See [joint\\_precision](#) for more information.

**close: bool, defaults to False** If True, the line will be closed.

**circle: list** If set, the [points](#) will be set to build a circle. See [circle](#) for more information.

**ellipse: list** If set, the [points](#) will be set to build an ellipse. See [ellipse](#) for more information.

**rectangle: list** If set, the *points* will be set to build a rectangle. See [rectangle](#) for more information.

**bezier: list** If set, the *points* will be set to build a bezier line. See [bezier](#) for more information.

**bezier\_precision: int, defaults to 180** Precision of the Bezier drawing.

Changed in version 1.0.8: *dash\_offset* and *dash\_length* have been added.

Changed in version 1.4.1: *width*, *cap*, *joint*, *cap\_precision*, *joint\_precision*, *close*, *ellipse*, *rectangle* have been added.

Changed in version 1.4.1: *bezier*, *bezier\_precision* have been added.

### **bezier**

Use this property to build a bezier line, without calculating the *points*. You can only set this property, not get it.

The argument must be a tuple of 2n elements, n being the number of points.

Usage:

```
Line(bezier=(x1, y1, x2, y2, x3, y3))
```

New in version 1.4.2.

---

**Note:** Bezier lines calculations are inexpensive for a low number of points, but complexity is quadratic, so lines with a lot of points can be very expensive to build, use with care!

---

### **bezier\_precision**

Number of iteration for drawing the bezier between 2 segments, defaults to 180. The *bezier\_precision* must be at least 1.

New in version 1.4.2.

### **cap**

Determine the cap of the line, defaults to 'round'. Can be one of 'none', 'square' or 'round'

New in version 1.4.1.

### **cap\_precision**

Number of iteration for drawing the "round" cap, defaults to 10. The *cap\_precision* must be at least 1.

New in version 1.4.1.

### **circle**

Use this property to build a circle, without calculating the *points*. You can only set this property, not get it.

The argument must be a tuple of (center\_x, center\_y, radius, angle\_start, angle\_end, segments):

- *center\_x* and *center\_y* represent the center of the circle
- *radius* represent the radius of the circle
- (optional) *angle\_start* and *angle\_end* are in degree. The default value is 0 and 360.
- (optional) *segments* is the precision of the ellipse. The default value is calculated from the range between angle.

Note that it's up to you to [close](#) the circle or not.

For example, for building a simple ellipse, in python:

```

# simple circle
Line(circle=(150, 150, 50))

# only from 90 to 180 degrees
Line(circle=(150, 150, 50, 90, 180))

# only from 90 to 180 degrees, with few segments
Line(circle=(150, 150, 50, 90, 180, 20))

```

New in version 1.4.1.

### **close**

If True, the line will be closed.

New in version 1.4.1.

### **dash\_length**

Property for getting/setting the length of the dashes in the curve

New in version 1.0.8.

### **dash\_offset**

Property for getting/setting the offset between the dashes in the curve

New in version 1.0.8.

### **ellipse**

Use this property to build an ellipse, without calculating the *points*. You can only set this property, not get it.

The argument must be a tuple of (x, y, width, height, angle\_start, angle\_end, segments):

- x and y represent the bottom left of the ellipse
- width and height represent the size of the ellipse
- (optional) angle\_start and angle\_end are in degree. The default value is 0 and 360.
- (optional) segments is the precision of the ellipse. The default value is calculated from the range between angle.

Note that it's up to you to *close* the ellipse or not.

For example, for building a simple ellipse, in python:

```

# simple ellipse
Line(ellipse=(0, 0, 150, 150))

# only from 90 to 180 degrees
Line(ellipse=(0, 0, 150, 150, 90, 180))

# only from 90 to 180 degrees, with few segments
Line(ellipse=(0, 0, 150, 150, 90, 180, 20))

```

New in version 1.4.1.

### **joint**

Determine the join of the line, defaults to 'round'. Can be one of 'none', 'round', 'bevel', 'miter'.

New in version 1.4.1.

### **joint\_precision**

Number of iteration for drawing the "round" joint, defaults to 10. The joint\_precision must be at least 1.

New in version 1.4.1.

### points

Property for getting/settings points of the line

**Warning:** This will always reconstruct the whole graphics from the new points list. It can be very CPU expensive.

### rectangle

Use this property to build a rectangle, without calculating the *points*. You can only set this property, not get it.

The argument must be a tuple of (x, y, width, height):

- x and y represent the bottom-left position of the rectangle
- width and height represent the size

The line is automatically closed.

Usage:

```
Line(rectangle=(0, 0, 200, 200))
```

New in version 1.4.1.

### rounded\_rectangle

Use this property to build a rectangle, without calculating the *points*. You can only set this property, not get it.

The argument must be a tuple of one of the following forms:

- (x, y, width, height, corner\_radius)
- (x, y, width, height, corner\_radius, resolution)
- (x, y, width, height, corner\_radius1, corner\_radius2, corner\_radius3, corner\_radius4)
- (x, y, width, height, corner\_radius1, corner\_radius2, corner\_radius3, corner\_radius4, resolution)
- x and y represent the bottom-left position of the rectangle
- width and height represent the size
- corner\_radius is the number of pixels between two borders and the center of the circle arc joining them
- resolution is the number of line segment that will be used to draw the circle arc at each corner (defaults to 30)

The line is automatically closed.

Usage:

```
Line(rounded_rectangle=(0, 0, 200, 200, 10, 20, 30, 40, 100))
```

New in version 1.9.0.

### width

Determine the width of the line, defaults to 1.0.

New in version 1.4.1.

```
class kivy.graphics.vertex_instructions.Point
Bases: kivy.graphics.instructions.VertexInstruction
```

A list of 2d points. Each point is represented as a square with a width/height of 2 times the *pointsize*.

#### Parameters

**points: list** List of points in the format (x1, y1, x2, y2...), where each pair of coordinates specifies the center of a new point.

**pointsize: float, defaults to 1.** The size of the point, measured from the center to the edge. A value of 1.0 therefore means the real size will be 2.0 x 2.0.

**Warning:** Starting from version 1.0.7, vertex instruction have a limit of 65535 vertices (indices of vertex to be accurate). 2 entries in the list (x, y) will be converted to 4 vertices. So the limit inside Point() class is  $2^{15}-2$ .

#### add\_point()

Add a point to the current *points* list.

If you intend to add multiple points, prefer to use this method instead of reassigning a new *points* list. Assigning a new *points* list will recalculate and reupload the whole buffer into the GPU. If you use add\_point, it will only upload the changes.

#### points

Property for getting/settings the center points in the points list. Each pair of coordinates specifies the center of a new point.

#### pointsize

Property for getting/setting point size. The size is measured from the center to the edge, so a value of 1.0 means the real size will be 2.0 x 2.0.

```
class kivy.graphics.vertex_instructions.Mesh
```

```
Bases: kivy.graphics.instructions.VertexInstruction
```

A 2d mesh.

In OpenGL ES 2.0 and in our graphics implementation, you cannot have more than 65535 indices.

A list of vertices is described as:

```
vertices = [x1, y1, u1, v1, x2, y2, u2, v2, ...]
           |   |   |   |
           +---+ i1 +---+ i2 +---+
```

If you want to draw a triangle, add 3 vertices. You can then make an indices list as follows:

```
indices = [0, 1, 2]
```

New in version 1.1.0.

#### Parameters

**vertices: iterable** List of vertices in the format (x1, y1, u1, v1, x2, y2, u2, v2...).

**indices: iterable** List of indices in the format (i1, i2, i3...).

**mode: str** Mode of the vbo. Check *mode* for more information. Defaults to 'points'.

**fmt: list** The format for vertices, by default, each vertex is described by 2D coordinates (x, y) and 2D texture coordinate (u, v). Each element of the list should be a tuple or list, of the form

(variable\_name, size, type)

which will allow mapping vertex data to the glsl instructions.

[`b'v_pos', 2, b'float')`, `(b'v_tc', 2, b'float')`,]

will allow using

```
attribute vec2 v_pos; attribute vec2 v_tc;
```

in glsl's vertex shader.

Changed in version 1.8.1: Before, *vertices* and *indices* would always be converted to a list, now, they are only converted to a list if they do not implement the buffer interface. So e.g. numpy arrays, python arrays etc. are used in place, without creating any additional copies. However, the buffers cannot be readonly (even though they are not changed, due to a cython limitation) and must be contiguous in memory.

---

**Note:** When passing a memoryview or a instance that implements the buffer interface, *vertices* should be a buffer of floats ('f' code in python array) and *indices* should be a buffer of unsigned short ('H' code in python array). Arrays in other formats will still have to be converted internally, negating any potential gain.

---

### **indices**

Vertex indices used to specify the order when drawing the mesh.

### **mode**

VBO Mode used for drawing vertices/indices. Can be one of 'points', 'line\_strip', 'line\_loop', 'lines', 'triangles', 'triangle\_strip' or 'triangle\_fan'.

### **vertices**

List of x, y, u, v coordinates used to construct the Mesh. Right now, the Mesh instruction doesn't allow you to change the format of the vertices, which means it's only x, y + one texture coordinate.

## **class kivy.graphics.vertex\_instructions.GraphicException**

Bases: exceptions.Exception

Exception raised when a graphics error is fired.

## **class kivy.graphics.vertex\_instructions.Bezier**

Bases: [kivy.graphics.instructions.VertexInstruction](#)

A 2d Bezier curve.

New in version 1.0.8.

### **Parameters**

**points: list** List of points in the format (x1, y1, x2, y2...)

**segments: int, defaults to 180** Define how many segments are needed for drawing the curve. The drawing will be smoother if you have many segments.

**loop: bool, defaults to False** Set the bezier curve to join the last point to the first.

**dash\_length: int** Length of a segment (if dashed), defaults to 1.

**dash\_offset: int** Distance between the end of a segment and the start of the next one, defaults to 0. Changing this makes it dashed.

### **dash\_length**

Property for getting/setting the length of the dashes in the curve.

**dash\_offset**

Property for getting/setting the offset between the dashes in the curve.

**points**

Property for getting/settings the points of the triangle.

**Warning:** This will always reconstruct the whole graphic from the new points list. It can be very CPU intensive.

**segments**

Property for getting/setting the number of segments of the curve.

**class kivy.graphics.vertex\_instructions.SmoothLine**

Bases: *kivy.graphics.vertex\_instructions.Line*

Experimental line using over-draw methods to get better anti-aliasing results. It has few draw-backs:

- drawing a line with alpha will probably not have the intended result if the line crosses itself.
- *cap*, *joint* and *dash* properties are not supported.
- it uses a custom texture with a premultiplied alpha.
- lines under 1px in width are not supported: they will look the same.

**Warning:** This is an unfinished work, experimental, and subject to crashes.

New in version 1.9.0.

**overdraw\_width**

Determine the overdraw width of the line, defaults to 1.2.

---

# Input management

---

Our input system is wide and simple at the same time. We are currently able to natively support :

- Windows multitouch events (pencil and finger)
- OS X touchpads
- Linux multitouch events (kernel and mtdev)
- Linux wacom drivers (pencil and finger)
- TUIO

All the input management is configurable in the Kivy [config](#). You can easily use many multitouch devices in one Kivy application.

When the events have been read from the devices, they are dispatched through a post processing module before being sent to your application. We also have several default modules for :

- Double tap detection
- Decreasing jittering
- Decreasing the inaccuracy of touch on “bad” DIY hardware
- Ignoring regions

**class kivy.input.MotionEvent(device, id, args)**  
Bases: [kivy.input.motionevent.MotionEvent](#)

Abstract class that represents an input event (touch or non-touch).

#### Parameters

*id*: str unique ID of the MotionEvent

*args*: list list of parameters, passed to the depack() function

**apply\_transform\_2d(transform)**

Apply a transformation on x, y, z, px, py, pz, ox, oy, oz, dx, dy, dz

**copy\_to(to)**

Copy some attribute to another touch object.

**depack(args)**

Depack *args* into attributes of the class

**distance(other\_touch)**

Return the distance between the current touch and another touch.

**dpos**

Return delta between last position and current position, in the screen coordinate system (self.dx, self.dy)

**grab(class\_instance, exclusive=False)**

Grab this motion event. You can grab a touch if you want to receive subsequent *on\_touch\_move()* and *on\_touch\_up()* events, even if the touch is not dispatched by the parent:

```
def on_touch_down(self, touch):
    touch.grab(self)

def on_touch_move(self, touch):
    if touch.grab_current is self:
        # I received my grabbed touch
    else:
        # it's a normal touch

def on_touch_up(self, touch):
    if touch.grab_current is self:
        # I receive my grabbed touch, I must ungrab it!
        touch.ungrab(self)
    else:
        # it's a normal touch
    pass
```

**is\_mouse\_scrolling**

Returns True if the touch is a mousewheel scrolling

New in version 1.6.0.

**move(args)**

Move the touch to another position

**opos**

Return the initial position of the touch in the screen coordinate system (self.ox, self.oy)

**pop()**

Pop attributes values from the stack

**ppos**

Return the previous position of the touch in the screen coordinate system (self.px, self.py)

**push(attrs=None)**

Push attribute values in *attrs* onto the stack

**scale\_for\_screen(w, h, p=None, rotation=0, smode='None', kheight=0)**

Scale position for the screen

**spos**

Return the position in the 0-1 coordinate system (self.sx, self.sy)

**ungrab(class\_instance)**

Ungrab a previously grabbed touch

**class kivy.input.MotionEventProvider(device, args)**

Bases: object

Base class for a provider.

**start()**

Start the provider. This method is automatically called when the application is started and if the configuration uses the current provider.

**stop()**

Stop the provider.

**update(*dispatch\_fn*)**

Update the provider and dispatch all the new touch events though the *dispatch\_fn* argument.

**class kivy.input.MotionEventFactory**

MotionEvent factory is a class that registers all availables input factories. If you create a new input factory, you need to register it here:

```
MotionEventFactory.register('myproviderid', MyInputProvider)
```

**static get(*name*)**

Get a provider class from the provider id

**static list()**

Get a list of all available providers

**static register(*name, classname*)**

Register a input provider in the database

## 28.1 Input Postprocessing

### 28.1.1 Calibration

New in version 1.9.0.

Recalibrate input device to a specific range / offset.

Let's say you have 3 1080p displays, the 2 firsts are multitouch. By default, both will have mixed touch, the range will conflict with each others: the 0-1 range will goes to 0-5760 px (remember,  $3 * 1920 = 5760$ .)

To fix it, you need to manually reference them. For example:

```
[input]
left = mtdev,/dev/input/event17
middle = mtdev,/dev/input/event15
# the right screen is just a display.
```

Then, you can use the calibration postproc module:

```
[postproc:calibration]
left = xratio=0.3333
middle = xratio=0.3333,xoffset=0.3333
```

Now, the touches from the left screen will be within 0-0.3333 range, and the touches from the middle screen will be within 0.3333-0.6666 range.

**class kivy.input.postproc.calibration.InputPostprocCalibration**

Bases: object

Recalibrate the inputs.

The configuration must go within a section named *postproc:calibration*. Within the section, you must have line like:

```
devicename = param=value, param=value
```

#### Parameters

**xratio: float** Value to multiply X  
**yratio: float** Value to multiply Y  
**xoffset: float** Value to add to X  
**yoffset: float** Value to add to Y

### 28.1.2 Dejitter

Prevent blob jittering.

A problem that is often faced (esp. in optical MT setups) is that of jitterish BLOBs caused by bad camera characteristics. With this module you can get rid of that jitter. You just define a threshold *jitter\_distance* in your config, and all touch movements that move the touch by less than the jitter distance are considered ‘bad’ movements caused by jitter and will be discarded.

**class kivy.input.postproc.dejitter.InputPostprocDejitter**  
Bases: object

Get rid of jitterish BLOBs. Example:

```
[postproc]
jitter_distance = 0.004
jitter_ignore_devices = mouse,mactouch
```

#### Configuration

**jitter\_distance: float** A float in range 0-1.  
**jitter\_ignore\_devices: string** A comma-separated list of device identifiers that should not be processed by dejitter (because they’re very precise already).

### 28.1.3 Double Tap

Search touch for a double tap

**class kivy.input.postproc.doubletap.InputPostprocDoubleTap**  
Bases: object

InputPostProcDoubleTap is a post-processor to check if a touch is a double tap or not. Double tap can be configured in the Kivy config file:

```
[postproc]
double_tap_time = 250
double_tap_distance = 20
```

Distance parameter is in the range 0-1000 and time is in milliseconds.

**find\_double\_tap(ref)**

Find a double tap touch within self.touches. The touch must be not a previous double tap and the distance must be within the specified threshold. Additionally, the touch profiles must be the same kind of touch.

#### 28.1.4 Ignore list

Ignore touch on some areas of the screen

**class** kivy.input.postproc.ignorelist.**InputPostprocIgnoreList**  
Bases: object

InputPostprocIgnoreList is a post-processor which removes touches in the Ignore list. The Ignore list can be configured in the Kivy config file:

```
[postproc]
# Format: [(xmin, ymin, xmax, ymax), ...]
ignore = [(0.1, 0.1, 0.15, 0.15)]
```

The Ignore list coordinates are in the range 0-1, not in screen pixels.

#### 28.1.5 Retain Touch

Reuse touch to counter lost finger behavior

**class** kivy.input.postproc.retaintouch.**InputPostprocRetainTouch**  
Bases: object

InputPostprocRetainTouch is a post-processor to delay the ‘up’ event of a touch, to reuse it under certains conditions. This module is designed to prevent lost finger touches on some hardware/setups.

Retain touch can be configured in the Kivy config file:

```
[postproc]
retain_time = 100
retain_distance = 50
```

The distance parameter is in the range 0-1000 and time is in milliseconds.

#### 28.1.6 Triple Tap

New in version 1.7.0.

Search touch for a triple tap

**class** kivy.input.postproc.tripletap.**InputPostprocTripleTap**  
Bases: object

InputPostProcTripleTap is a post-processor to check if a touch is a triple tap or not. Triple tap can be configured in the Kivy config file:

```
[postproc]
triple_tap_time = 250
triple_tap_distance = 20
```

The distance parameter is in the range 0-1000 and time is in milliseconds.

**find\_triple\_tap(ref)**

Find a triple tap touch within *self.touches*. The touch must be not be a previous triple tap and the distance must be be within the bounds specified. Additionally, the touch profile must be the same kind of touch.

## 28.2 Providers

### 28.2.1 Android Joystick Input Provider

This module is based on the PyGame JoyStick Input Provider. For more information, please refer to <http://www.pygame.org/docs/ref/joystick.html>

### 28.2.2 Auto Create Input Provider Config Entry for Available MT Hardware (linux only).

Thanks to Marc Tardif for the probing code, taken from scan-for-mt-device.

The device discovery is done by this provider. However, the reading of input can be performed by other providers like: hidinput, mtdev and linuxwacom. mtdev is used prior to other providers. For more information about mtdev, check [mtdev](#).

Here is an example of auto creation:

```
[input]
# using mtdev
device_(name)s = probesysfs,provider=mtdev
# using hidinput
device_(name)s = probesysfs,provider=hidinput
# using mtdev with a match on name
device_(name)s = probesysfs,provider=mtdev,match=acer

# using hidinput with custom parameters to hidinput (all on one line)
%(name)s = probesysfs,
    provider=hidinput,param=min_pressure=1,param=max_pressure=99

# you can also match your wacom touchscreen
touch = probesysfs,match=E3_Finger,provider=linuxwacom,
    select_all=1,param=mode=touch
# and your wacom pen
pen = probesysfs,match=E3_Pen,provider=linuxwacom,
    select_all=1,param=mode=pen
```

By default, ProbeSysfs module will enumerate hardware from the /sys/class/input device, and configure hardware with ABS\_MT\_POSITION\_X capability. But for example, the wacom screen doesn't support this capability. You can prevent this behavior by putting select\_all=1 in your config line. Add use\_mouse=1 to also include touchscreen hardware that offers core pointer functionality.

### 28.2.3 Common definitions for a Windows provider

This file provides common definitions for constants used by WM\_Touch / WM\_Pen.

### 28.2.4 Leap Motion - finger only

### 28.2.5 Mouse provider implementation

On linux systems, the mouse provider can be annoying when used with another multitouch provider (hidinput or mtdev). The Mouse can conflict with them: a single touch can generate one event from the mouse provider and another from the multitouch provider.

To avoid this behavior, you can activate the “disable\_on\_activity” token in the mouse configuration. Then, if any touches are created by another provider, the mouse event will be discarded. Add this to your configuration:

```
[input]
mouse = mouse, disable_on_activity
```

### Using multitouch interaction with the mouse

New in version 1.3.0.

By default, the middle and right mouse buttons, as well as a combination of ctrl + left mouse button are used for multitouch emulation. If you want to use them for other purposes, you can disable this behavior by activating the “disable\_multitouch” token:

```
[input]
mouse = mouse, disable_multitouch
```

Changed in version 1.9.0.

You can now selectively control whether a click initiated as described above will emulate multi-touch. If the touch has been initiated in the above manner (e.g. right mouse button), a *multitouch\_sim* value will be added to the touch’s profile, and a *multitouch\_sim* property will be added to the touch. By default, *multitouch\_sim* is True and multitouch will be emulated for that touch. If, however, *multitouch\_on\_demand* is added to the config:

```
[input]
mouse = mouse, multitouch_on_demand
```

then *multitouch\_sim* defaults to *False*. In that case, if *multitouch\_sim* is set to *True* before the mouse is released (e.g. in *on\_touch\_down/move*), the touch will simulate a multi-touch event. For example:

```
if 'multitouch_sim' in touch.profile:
    touch.multitouch_sim = True
```

Following is a list of the supported values for the *profile* property list.

Profile value	Description
button	Mouse button (one of <i>left</i> , <i>right</i> , <i>middle</i> , <i>scrollup</i> or <i>scrolldown</i> ). Accessed via the ‘button’ property.
pos	2D position. Also reflected in the <i>x</i> , <i>y</i> and <i>pos</i> properties.
multi-touch_sim	Specifies whether multitouch is simulated or not. Accessed via the ‘multitouch_sim’ property.

### 28.2.6 Native support for HID input from the linux kernel

Support starts from 2.6.32-ubuntu, or 2.6.34.

To configure HIDInput, add this to your configuration:

```
[input]
# devicename = hidinput,/dev/input/eventXX
# example with Stantum MTP4.3" screen
stantum = hidinput,/dev/input/event2
```

---

**Note:** You must have read access to the input event.

---

You can use a custom range for the X, Y and pressure values. For some drivers, the range reported is invalid. To fix that, you can add these options to the argument line:

- invert\_x : 1 to invert X axis
- invert\_y : 1 to invert Y axis
- min\_position\_x : X minimum
- max\_position\_x : X maximum
- min\_position\_y : Y minimum
- max\_position\_y : Y maximum
- min\_pressure : pressure minimum
- max\_pressure : pressure maximum
- rotation : rotate the input coordinate (0, 90, 180, 270)

For example, on the Asus T101M, the touchscreen reports a range from 0-4095 for the X and Y values, but the real values are in a range from 0-32768. To correct this, you can add the following to the configuration:

```
[input]
t101m = hidinput,/dev/input/event7,max_position_x=32768,max_position_y=32768
```

New in version 1.9.1: *rotation* configuration token added.

### 28.2.7 Native support for Multitouch devices on Linux, using libmtdev.

The Mtdev project is a part of the Ubuntu Maverick multitouch architecture. You can read more on <http://wiki.ubuntu.com/Multitouch>

To configure MTDev, it's preferable to use probesysfs providers. Check [probesysfs](#) for more information.

Otherwise, add this to your configuration:

```
[input]
# devicename = hidinput,/dev/input/eventXX
acert230h = mtdev,/dev/input/event2
```

---

**Note:** You must have read access to the input event.

---

You can use a custom range for the X, Y and pressure values. On some drivers, the range reported is invalid. To fix that, you can add these options to the argument line:

- invert\_x : 1 to invert X axis
- invert\_y : 1 to invert Y axis
- min\_position\_x : X minimum
- max\_position\_x : X maximum
- min\_position\_y : Y minimum
- max\_position\_y : Y maximum

- min\_pressure : pressure minimum
- max\_pressure : pressure maximum
- min\_touch\_major : width shape minimum
- max\_touch\_major : width shape maximum
- min\_touch\_minor : width shape minimum
- max\_touch\_minor : height shape maximum
- rotation : 0,90,180 or 270 to rotate

## 28.2.8 Native support of MultitouchSupport framework for MacBook (MaxOSX platform)

### 28.2.9 Native support of Wacom tablet from linuxwacom driver

To configure LinuxWacom, add this to your configuration:

```
[input]
pen = linuxwacom,/dev/input/event2,mode=pen
finger = linuxwacom,/dev/input/event3,mode=touch
```

---

**Note:** You must have read access to the input event.

---

You can use a custom range for the X, Y and pressure values. On some drivers, the range reported is invalid. To fix that, you can add these options to the argument line:

- invert\_x : 1 to invert X axis
- invert\_y : 1 to invert Y axis
- min\_position\_x : X minimum
- max\_position\_x : X maximum
- min\_position\_y : Y minimum
- max\_position\_y : Y maximum
- min\_pressure : pressure minimum
- max\_pressure : pressure maximum

## 28.2.10 Support for WM\_PEN messages (Windows platform)

**class** `kivy.input.providers.wm_pen.WM_Pen(device, id, args)`  
 Bases: `kivy.input.motionevent.MotionEvent`

MotionEvent representing the WM\_Pen event. Supports the pos profile.

## 28.2.11 Support for WM\_TOUCH messages (Windows platform)

**class** `kivy.input.providers.wm_touch.WM_MotionEvent(device, id, args)`  
 Bases: `kivy.input.motionevent.MotionEvent`

MotionEvent representing the WM\_MotionEvent event. Supports pos, shape and size profiles.

## 28.2.12 TUIO Input Provider

TUIO is the de facto standard network protocol for the transmission of touch and fiducial information between a server and a client. To learn more about TUIO (which is itself based on the OSC protocol), please refer to <http://tuio.org> – The specification should be of special interest.

Configure a TUIO provider in the config.ini

The TUIO provider can be configured in the configuration file in the [input] section:

```
[input]
# name = tuio,<ip>:<port>
multitouchtable = tuio,192.168.0.1:3333
```

Configure a TUIO provider in the App

You must add the provider before your application is run, like this:

```
from kivy.app import App
from kivy.config import Config

class TestApp(App):
    def build(self):
        Config.set('input', 'multitouchscreen1', 'tuio,0.0.0.0:3333')
        # You can also add a second TUIO listener
        # Config.set('input', 'source2', 'tuio,0.0.0.0:3334')
        # Then do the usual things
        #
        return
```

```
class kivy.input.providers.tuio.TuioMotionEventProvider(device, args)
Bases: kivy.input.provider.MotionEventProvider
```

The TUIO provider listens to a socket and handles some of the incoming OSC messages:

- /tuio/2Dcur
- /tuio/2Dobj

You can easily extend the provider to handle new TUIO paths like so:

```
# Create a class to handle the new TUIO type/path
# Replace NEWPATH with the pathname you want to handle
class TuioNEWPATHMotionEvent(MotionEvent):
    def __init__(self, id, args):
        super(TuioNEWPATHMotionEvent, self).__init__(id, args)

    def depack(self, args):
        # In this method, implement 'unpacking' for the received
        # arguments. you basically translate from TUIO args to Kivy
        # MotionEvent variables. If all you receive are x and y
        # values, you can do it like this:
        if len(args) == 2:
            self.sx, self.sy = args
            self.profile = ('pos', )
            self.sy = 1 - self.sy
        super(TuioNEWPATHMotionEvent, self).depack(args)

    # Register it with the TUIO MotionEvent provider.
```

```
# You obviously need to replace the PATH placeholders appropriately.  
TuioMotionEventProvider.register('/tuio/PATH', TuioNEWPATHMotionEvent)
```

---

**Note:** The class name is of no technical importance. Your class will be associated with the path that you pass to the `register()` function. To keep things simple, you should name your class after the path that it handles, though.

---

```
static create(oscpath, **kwargs)  
    Create a touch event from a TUIO path  
static register(oscpath, classname)  
    Register a new path to handle in TUIO provider  
start()  
    Start the TUIO provider  
stop()  
    Stop the TUIO provider  
static unregister(oscpath, classname)  
    Unregister a path to stop handling it in the TUIO provider  
update(dispatch_fn)  
    Update the TUIO provider (pop events from the queue)  
class kivy.input.providers.tuio.Tuio2dCurMotionEvent(device, id, args)  
    Bases: kivy.input.providers.tuio.TuioMotionEvent  
    A 2dCur TUIO touch.  
class kivy.input.providers.tuio.Tuio2dObjMotionEvent(device, id, args)  
    Bases: kivy.input.providers.tuio.TuioMotionEvent  
    A 2dObj TUIO object.
```

## 28.3 Input recorder

New in version 1.1.0.

**Warning:** This part of Kivy is still experimental and this API is subject to change in a future version.

This is a class that can record and replay some input events. This can be used for test cases, screen savers etc.

Once activated, the recorder will listen for any input event and save its properties in a file with the delta time. Later, you can play the input file: it will generate fake touch events with the saved properties and dispatch it to the event loop.

By default, only the position is saved ('pos' profile and 'sx', 'sy', attributes). Change it only if you understand how input handling works.

### 28.3.1 Recording events

The best way is to use the “recorder” module. Check the [Modules](#) documentation to see how to activate a module.

Once activated, you can press F8 to start the recording. By default, events will be written to `<current-path>/recorder.kvi`. When you want to stop recording, press F8 again.

You can replay the file by pressing F7.

Check the [Recorder module](#) module for more information.

### 28.3.2 Manual play

You can manually open a recorder file, and play it by doing:

```
from kivy.input.recorder import Recorder

rec = Recorder(filename='myrecorder.kvi')
rec.play = True
```

If you want to loop over that file, you can do:

```
from kivy.input.recorder import Recorder

def recorder_loop(instance, value):
    if value is False:
        instance.play = True

rec = Recorder(filename='myrecorder.kvi')
rec.bind(play=recorder_loop)
rec.play = True
```

### 28.3.3 Recording more attributes

You can extend the attributes to save on one condition: attributes values must be simple values, not instances of complex classes.

Let's say you want to save the angle and pressure of the touch, if available:

```
from kivy.input.recorder import Recorder

rec = Recorder(filename='myrecorder.kvi',
               record_attrs=['is_touch', 'sx', 'sy', 'angle', 'pressure'],
               record_profile_mask=['pos', 'angle', 'pressure'])
rec.record = True
```

Or with modules variables:

```
$ python main.py -m recorder,attrs=is_touch:sx:sy:angle:pressure,
  ↪profile_mask=pos:angle:pressure
```

### 28.3.4 Known limitations

- Unable to save attributes with instances of complex classes.
- Values that represent time will not be adjusted.
- Can replay only complete records. If a begin/update/end event is missing, this could lead to ghost touches.
- Stopping the replay before the end can lead to ghost touches.

```
class kivy.input.recorder.Recorder(**kwargs)
Bases: kivy.event.EventDispatcher
```

Recorder class. Please check module documentation for more information.

#### Events

*on\_stop*: Fired when the playing stops.

Changed in version 1.10.0: Event *on\_stop* added.

#### counter

Number of events recorded in the last session.

*counter* is a *NumericProperty* and defaults to 0, read-only.

#### filename

Filename to save the output of the recorder.

*filename* is a *StringProperty* and defaults to ‘recorder.kvi’.

#### play

Boolean to start/stop the replay of the current file (if it exists).

*play* is a *BooleanProperty* and defaults to False.

#### record

Boolean to start/stop the recording of input events.

*record* is a *BooleanProperty* and defaults to False.

#### recordAttrs

Attributes to record from the motion event.

*recordAttrs* is a *ListProperty* and defaults to [‘is\_touch’, ‘sx’, ‘sy’].

#### recordProfileMask

Profile to save in the fake motion event when replayed.

*recordProfileMask* is a *ListProperty* and defaults to [‘pos’].

#### window

Window instance to attach the recorder. If None, it will use the default instance.

*window* is a *ObjectProperty* and defaults to None.

## 28.4 Motion Event

The *MotionEvent* is the base class used for events provided by pointing devices (touch and non-touch). This class defines all the properties and methods needed to handle 2D and 3D movements but has many more capabilities.

---

**Note:** You never create the *MotionEvent* yourself: this is the role of the *providers*.

---

### 28.4.1 Motion Event and Touch

We differentiate between a Motion Event and Touch event. A Touch event is a *MotionEvent* with the *pos* profile. Only these events are dispatched throughout the widget tree.

1. The *MotionEvent*’s are gathered from input providers.
2. All the *MotionEvent*’s are dispatched from *on\_motion()*.

3. If a **MotionEvent** has a *pos* profile, we dispatch it through `on_touch_down()`, `on_touch_move()` and `on_touch_up()`.

#### 28.4.2 Listening to a Motion Event

If you want to receive all MotionEvents, Touch or not, you can bind the MotionEvent from the Window to your own callback:

```
def on_motion(self, etype, motionevent):
    # will receive all motion events.
    pass

Window.bind(on_motion=on_motion)
```

You can also listen to changes of the mouse position by watching `mouse_pos`.

#### 28.4.3 Profiles

The **MotionEvent** stores device specific information in various properties listed in the **profile**. For example, you can receive a MotionEvent that has an angle, a fiducial ID, or even a shape. You can check the **profile** attribute to see what is currently supported by the MotionEvent provider.

This is a short list of the profile values supported by default. Please check the `MotionEvent.profile` property to see what profile values are available.

Profile value	Description
angle	2D angle. Accessed via the <i>a</i> property.
button	Mouse button ('left', 'right', 'middle', 'scrollup' or 'scrolldown'). Accessed via the <i>button</i> property.
markerid	Marker or Fiducial ID. Accessed via the <i>fid</i> property.
pos	2D position. Accessed via the <i>x</i> , <i>y</i> or <i>pos</i> properties.
pos3d	3D position. Accessed via the <i>x</i> , <i>y</i> or <i>z</i> properties.
pressure	Pressure of the contact. Accessed via the <i>pressure</i> property.
shape	Contact shape. Accessed via the <i>shape</i> property .

If you want to know whether the current **MotionEvent** has an angle:

```
def on_touch_move(self, touch):
    if 'angle' in touch.profile:
        print('The touch angle is', touch.a)
```

If you want to select only the fiducials:

```
def on_touch_move(self, touch):
    if 'markerid' not in touch.profile:
        return
```

**class kivy.input.motionevent.MotionEvent(device, id, args)**  
Bases: `kivy.input.motionevent.MotionEvent`

Abstract class that represents an input event (touch or non-touch).

##### Parameters

***id*: str** unique ID of the MotionEvent

***args*: list** list of parameters, passed to the depack() function

**apply\_transform\_2d(*transform*)**  
 Apply a transformation on x, y, z, px, py, pz, ox, oy, oz, dx, dy, dz

**copy\_to(*to*)**  
 Copy some attribute to another touch object.

**depack(*args*)**  
 Dpack *args* into attributes of the class

**device = None**  
 Device used for creating this touch

**distance(*other\_touch*)**  
 Return the distance between the current touch and another touch.

**double\_tap\_time = None**  
 If the touch is a *is\_double\_tap*, this is the time between the previous tap and the current touch.

**dpos**  
 Return delta between last position and current position, in the screen coordinate system (self.dx, self.dy)

**dsx = None**  
 Delta between self.sx and self.psx, in 0-1 range.

**dsy = None**  
 Delta between self.sy and self.psy, in 0-1 range.

**dsz = None**  
 Delta between self.sz and self.psz, in 0-1 range.

**dx = None**  
 Delta between self.x and self.px, in window range

**dy = None**  
 Delta between self.y and self.py, in window range

**dz = None**  
 Delta between self.z and self.pz, in window range

**grab(*class\_instance*, *exclusive=False*)**  
 Grab this motion event. You can grab a touch if you want to receive subsequent *on\_touch\_move()* and *on\_touch\_up()* events, even if the touch is not dispatched by the parent:

```
def on_touch_down(self, touch):
    touch.grab(self)

def on_touch_move(self, touch):
    if touch.grab_current is self:
        # I received my grabbed touch
    else:
        # it's a normal touch

def on_touch_up(self, touch):
    if touch.grab_current is self:
        # I receive my grabbed touch, I must ungrab it!
        touch.ungrab(self)
    else:
        # it's a normal touch
        pass
```

**grab\_current = None**

Used to determine which widget the touch is being dispatched to. Check the [grab\(\)](#) function for more information.

**id = None**

Id of the touch, not uniq. This is generally the Id set by the input provider, like ID in TUO. If you have multiple TUO source, the same id can be used. Prefer to use [uid](#) attribute instead.

**is\_double\_tap = None**

Indicate if the touch is a double tap or not

**is\_mouse\_scrolling**

Returns True if the touch is a mousewheel scrolling

New in version 1.6.0.

**is\_touch = None**

True if the Motion Event is a Touch. Can be also verified is *pos* is [profile](#).

**is\_triple\_tap = None**

Indicate if the touch is a triple tap or not

New in version 1.7.0.

**move(args)**

Move the touch to another position

**opos**

Return the initial position of the touch in the screen coordinate system (self.ox, self.oy)

**osx = None**

Origin X position, in 0-1 range.

**osy = None**

Origin Y position, in 0-1 range.

**osz = None**

Origin Z position, in 0-1 range.

**ox = None**

Origin X position, in window range

**oy = None**

Origin Y position, in window range

**oz = None**

Origin Z position, in window range

**pop()**

Pop attributes values from the stack

**pos = None**

Position (X, Y), in window range

**ppos**

Return the previous position of the touch in the screen coordinate system (self.px, self.py)

**profile = None**

Profiles currently used in the touch

**psx = None**

Previous X position, in 0-1 range.

**psy = None**

Previous Y position, in 0-1 range.

**psz = None**  
 Previous Z position, in 0-1 range.

**push(attrs=None)**  
 Push attribute values in *attrs* onto the stack

**push\_attrs\_stack = None**  
 Attributes to push by default, when we use *push()* : x, y, z, dx, dy, dz, ox, oy, oz, px, py, pz.

**px = None**  
 Previous X position, in window range

**py = None**  
 Previous Y position, in window range

**pz = None**  
 Previous Z position, in window range

**scale\_for\_screen(w, h, p=None, rotation=0, smode='None', kheight=0)**  
 Scale position for the screen

**shape = None**  
 Shape of the touch, subclass of *Shape*. By default, the property is set to None

**spos**  
 Return the position in the 0-1 coordinate system (self.sx, self.sy)

**sx = None**  
 X position, in 0-1 range

**sy = None**  
 Y position, in 0-1 range

**sz = None**  
 Z position, in 0-1 range

**time\_end = None**  
 Time of the end event (last touch usage)

**time\_start = None**  
 Initial time of the touch creation

**time\_update = None**  
 Time of the last update

**triple\_tap\_time = None**  
 If the touch is a *is\_triple\_tap*, this is the time between the first tap and the current touch.  
 New in version 1.7.0.

**ud = None**  
 User data dictionary. Use this dictionary to save your own data on the touch.

**uid = None**  
 Uniq ID of the touch. You can safely use this property, it will be never the same accross all existing touches.

**ungrab(class\_instance)**  
 Ungrab a previously grabbed touch

**x = None**  
 X position, in window range

**y = None**  
 Y position, in window range

**z = None**  
Z position, in window range

## 28.5 Motion Event Factory

Factory of *MotionEvent* providers.

**class kivy.input.factory.MotionEventFactory**

MotionEvent factory is a class that registers all available input factories. If you create a new input factory, you need to register it here:

```
TouchListenerFactory.register('myproviderid', MyInputProvider)
```

**static get(name)**  
Get a provider class from the provider id  
**static list()**  
Get a list of all available providers  
**static register(name, classname)**  
Register a input provider in the database

## 28.6 Motion Event Provider

Abstract class for the implementation of a *MotionEvent* provider. The implementation must support the *start()*, *stop()* and *update()* methods.

**class kivy.input.provider.MotionEventProvider(device, args)**

Bases: object

Base class for a provider.

**start()**

Start the provider. This method is automatically called when the application is started and if the configuration uses the current provider.

**stop()**

Stop the provider.

**update(dispatch\_fn)**

Update the provider and dispatch all the new touch events through the *dispatch\_fn* argument.

## 28.7 Motion Event Shape

Represent the shape of the *MotionEvent*

**class kivy.input.shape.Shape**

Bases: object

Abstract class for all implementations of a shape

**class kivy.input.shape.ShapeRect**

Bases: *kivy.input.shape.Shape*

Class for the representation of a rectangle.

**height**

Height of the rect

**width**

Width fo the rect



# Kivy Language

---

The Kivy language is a language dedicated to describing user interface and interactions. You could compare this language to Qt's QML (<http://qt.nokia.com>), but we included new concepts such as rule definitions (which are somewhat akin to what you may know from CSS), templating and so on.

Changed in version 1.7.0: The Builder doesn't execute canvas expressions in realtime anymore. It will pack all the expressions that need to be executed first and execute them after dispatching input, just before drawing the frame. If you want to force the execution of canvas drawing, just call *Builder.sync*.

An experimental profiling tool for the kv lang is also included. You can activate it by setting the environment variable *KIVY\_PROFILE\_LANG=1*. It will then generate an html file named *builder\_stats.html*.

## 29.1 Overview

The language consists of several constructs that you can use:

**Rules** A rule is similar to a CSS rule. A rule applies to specific widgets (or classes thereof) in your widget tree and modifies them in a certain way. You can use rules to specify interactive behaviour or use them to add graphical representations of the widgets they apply to. You can target a specific class of widgets (similar to the CSS concept of a *class*) by using the `cls` attribute (e.g. `cls=MyTestWidget`).

**A Root Widget** You can use the language to create your entire user interface. A kv file must contain only one root widget at most.

**Dynamic Classes** (*introduced in version 1.7.0*) Dynamic classes let you create new widgets and rules on-the-fly, without any Python declaration.

**Templates (deprecated)** (*introduced in version 1.0.5, deprecated from version 1.7.0*) Templates were used to populate parts of an application, such as styling the content of a list (e.g. icon on the left, text on the right). They are now deprecated by dynamic classes.

## 29.2 Syntax of a kv File

A Kivy language file must have `.kv` as filename extension.

The content of the file should always start with the Kivy header, where *version* must be replaced with the Kivy language version you're using. For now, use 1.0:

```
#:kivy `1.0`  
  
# content here
```

The *content* can contain rule definitions, a root widget, dynamic class definitions and templates:

```
# Syntax of a rule definition. Note that several Rules can share the same  
# definition (as in CSS). Note the braces: they are part of the definition.  
<Rule1,Rule2>:  
    # .. definitions ..  
  
<Rule3>:  
    # .. definitions ..  
  
# Syntax for creating a root widget  
RootClassName:  
    # .. definitions ..  
  
# Syntax for creating a dynamic class  
<NewWidget@BaseClass>:  
    # .. definitions ..  
  
# Syntax for create a template  
[TemplateName@BaseClass1,BaseClass2]:  
    # .. definitions ..
```

Regardless of whether it's a rule, root widget, dynamic class or template you're defining, the definition should look like this:

```
# With the braces it's a rule. Without them, it's a root widget.  
<ClassName>:  
    prop1: value1  
    prop2: value2  
  
    canvas:  
        CanvasInstruction1:  
            canvasprop1: value1  
        CanvasInstruction2:  
            canvasprop2: value2  
  
    AnotherClass:  
        prop3: value1
```

Here *prop1* and *prop2* are the properties of *ClassName* and *prop3* is the property of *AnotherClass*. If the widget doesn't have a property with the given name, an **ObjectProperty** will be automatically created and added to the widget.

*AnotherClass* will be created and added as a child of the *ClassName* instance.

- The indentation is important and must be consistent. The spacing must be a multiple of the number of spaces used on the first indented line. Spaces are encouraged: mixing tabs and spaces is not recommended.
- The value of a property must be given on a single line (for now at least).

- The `canvas` property is special: you can put graphics instructions in it to create a graphical representation of the current class.

Here is a simple example of a kv file that contains a root widget:

```
#:kivy 1.0

Button:
    text: 'Hello world'
```

Changed in version 1.7.0: The indentation is not limited to 4 spaces anymore. The spacing must be a multiple of the number of spaces used on the first indented line.

Both the `load_file()` and the `load_string()` methods return the root widget defined in your kv file/string. They will also add any class and template definitions to the `Factory` for later usage.

## 29.3 Value Expressions, on\_property Expressions, ids, and Reserved Keywords

When you specify a property's value, the value is evaluated as a Python expression. This expression can be static or dynamic, which means that the value can use the values of other properties using reserved keywords.

**self** The keyword `self` references the “current widget instance”:

```
Button:
    text: 'My state is %s' % self.state
```

**root** This keyword is available only in rule definitions and represents the root widget of the rule (the first instance of the rule):

```
<MyWidget>:
    custom: 'Hello world'
    Button:
        text: root.custom
```

**app** This keyword always refers to your app instance. It's equivalent to a call to `kivy.app.App.get_running_app()` in Python.

```
Label:
    text: app.name
```

**args** This keyword is available in `on_<action>` callbacks. It refers to the arguments passed to the callback.

```
TextInput:
    on_focus: self.insert_text("Focus" if args[1] else "No focus")
```

### 29.3.1 ids

Class definitions may contain `ids` which can be used as a keywords::

```
<MyWidget>
    Button:
        id: btn1
    Button:
        text: 'The state of the other button is %s' % btn1.state
```

Please note that the *id* will not be available in the widget instance: it is used exclusively for external references. *id* is a weakref to the widget, and not the widget itself. The widget itself can be accessed with `<id>.__self__` (`btn1.__self__` in this case).

When the kv file is processed, weakrefs to all the widgets tagged with ids are added to the root widget's *ids* dictionary. In other words, following on from the example above, the buttons state could also be accessed as follows:

```
widget = MyWidget()
state = widget.ids["btn1"].state

# Or, as an alternative syntax,
state = widget.ids.btn1.state
```

Note that the outermost widget applies the kv rules to all its inner widgets before any other rules are applied. This means if an inner widget contains ids, these ids may not be available during the inner widget's `__init__` function.

### 29.3.2 Valid expressions

There are two places that accept python statements in a kv file: after a property, which assigns to the property the result of the expression (such as the text of a button as shown above) and after a `on_property`, which executes the statement when the property is updated (such as `on_state`).

In the former case, the `expression` can only span a single line, cannot be extended to multiple lines using newline escaping, and must return a value. An example of a valid expression is `text: self.state` and `('up' if self.state == 'normal' else 'down')`.

In the latter case, multiple single line statements are valid, including those that escape their newline, as long as they don't add an indentation level.

Examples of valid statements are:

```
on_press: if self.state == 'normal': print('normal')
on_state:
    if self.state == 'normal': print('normal')
    else: print('down')
    if self.state == 'normal': \
        print('multiline normal')
    for i in range(10): print(i)
    print([1,2,3,4,
      5,6,7])
```

An example of an invalid statement:

```
on_state:
    if self.state == 'normal':
        print('normal')
```

## 29.4 Relation Between Values and Properties

When you use the Kivy language, you might notice that we do some work behind the scenes to automatically make things work properly. You should know that *Properties* implement the *Observer Design Pattern*. That means that you can bind your own function to be called when the value of a property changes (i.e. you passively *observe* the property for potential changes).

The Kivy language detects properties in your *value* expression and will create callbacks to automatically update the property via your expression when changes occur.

Here's a simple example that demonstrates this behaviour:

```
Button:  
    text: str(self.state)
```

In this example, the parser detects that *self.state* is a dynamic value (a property). The *state* property of the button can change at any moment (when the user touches it). We now want this button to display its own state as text, even as the state changes. To do this, we use the *state* property of the Button and use it in the value expression for the button's *text* property, which controls what text is displayed on the button (We also convert the state to a string representation). Now, whenever the button state changes, the text property will be updated automatically.

Remember: The value is a python expression! That means that you can do something more interesting like:

```
Button:  
    text: 'Plop world' if self.state == 'normal' else 'Release me!'
```

The Button text changes with the state of the button. By default, the button text will be 'Plop world', but when the button is being pressed, the text will change to 'Release me!'.

More precisely, the kivy language parser detects all substrings of the form *X.a.b* where *X* is *self* or *root* or *app* or a known id, and *a* and *b* are properties: it then adds the appropriate dependencies to cause the constraint to be reevaluated whenever something changes. For example, this works exactly as expected:

```
<IndexedExample>:  
    beta: self.a.b[self.c.d]
```

However, due to limitations in the parser which hopefully may be lifted in the future, the following doesn't work:

```
<BadExample>:  
    beta: self.a.b[self.c.d].e.f
```

indeed the *.f* part is not recognized because it doesn't follow the expected pattern, and so, does not result in an appropriate dependency being setup. Instead, an intermediate property should be introduced to allow the following constraint:

```
<GoodExample>:  
    alpha: self.a.b[self.c.d]  
    beta: self.alpha.e.f
```

## 29.5 Graphical Instructions

The graphical instructions are a special part of the Kivy language. They are handled by the 'canvas' property definition:

```
Widget:  
    canvas:  
        Color:  
            rgb: (1, 1, 1)  
        Rectangle:  
            size: self.size  
            pos: self.pos
```

All the classes added inside the canvas property must be derived from the *Instruction* class. You cannot put any Widget class inside the canvas property (as that would not make sense because a widget is not a graphics instruction).

If you want to do theming, you'll have the same question as in CSS: which rules have been executed first? In our case, the rules are executed in processing order (i.e. top-down).

If you want to change how Buttons are rendered, you can create your own kv file and add something like this:

```
<Button>:  
    canvas:  
        Color:  
            rgb: (1, 0, 0)  
        Rectangle:  
            pos: self.pos  
            size: self.size  
        Rectangle:  
            pos: self.pos  
            size: self.texture_size  
            texture: self.texture
```

This will result in buttons having a red background with the label in the bottom left, in addition to all the preceding rules. You can clear all the previous instructions by using the *Clear* command:

```
<Button>:  
    canvas:  
        Clear  
        Color:  
            rgb: (1, 0, 0)  
        Rectangle:  
            pos: self.pos  
            size: self.size  
        Rectangle:  
            pos: self.pos  
            size: self.texture_size  
            texture: self.texture
```

Then, only your rules that follow the *Clear* command will be taken into consideration.

## 29.6 Dynamic classes

Dynamic classes allow you to create new widgets on-the-fly, without any python declaration in the first place. The syntax of the dynamic classes is similar to the Rules, but you need to specify the base classes you want to subclass.

The syntax looks like:

```
# Simple inheritance  
<NewWidget@Button>:  
    # kv code here ...  
  
# Multiple inheritance  
<NewWidget@ButtonBehavior+Label>:  
    # kv code here ...
```

The @ character is used to separate your class name from the classes you want to subclass. The Python equivalent would have been:

```

# Simple inheritance
class NewWidget(Button):
    pass

# Multiple inheritance
class NewWidget(ButtonBehavior, Label):
    pass

```

Any new properties, usually added in python code, should be declared first. If the property doesn't exist in the dynamic class, it will be automatically created as an *ObjectProperty* (pre 1.8.0) or as an appropriate typed property (from version 1.8.0).

Changed in version 1.8.0: If the property value is an expression that can be evaluated right away (no external binding), then the value will be used as default value of the property, and the type of the value will be used for the specialization of the Property class. In other terms: if you declare `hello: "world"`, a new *StringProperty* will be instantiated, with the default value `"world"`. Lists, tuples, dictionaries and strings are supported.

Let's illustrate the usage of these dynamic classes with an implementation of a basic Image button. We could derive our classes from the Button and just add a property for the image filename:

```

<ImageButton@Button>:
    source: None

    Image:
        source: root.source
        pos: root.pos
        size: root.size

# let's use the new classes in another rule:
<MainUI>:
    BoxLayout:
        ImageButton:
            source: 'hello.png'
            on_press: root.do_something()
        ImageButton:
            source: 'world.png'
            on_press: root.do_something_else()

```

In Python, you can create an instance of the dynamic class as follows:

```

from kivy.factory import Factory
button_inst = Factory.ImageButton()

```

---

**Note:** Using dynamic classes, a child class can be declared before its parent. This however, leads to the unintuitive situation where the parent properties/methods override those of the child. Be careful if you choose to do this.

---

## 29.7 Templates

Changed in version 1.7.0: Template usage is now deprecated. Please use Dynamic classes instead.

### 29.7.1 Syntax of templates

Using a template in Kivy requires 2 things :

1. a context to pass for the context (will be ctx inside template).
2. a kv definition of the template.

Syntax of a template:

```
# With only one base class
[ClassName@BaseClass]:
    # .. definitions ..

# With more than one base class
[ClassName@BaseClass1,BaseClass2]:
    # .. definitions ..
```

For example, for a list, you'll need to create a entry with a image on the left, and a label on the right. You can create a template for making that definition easier to use. So, we'll create a template that uses 2 entries in the context: an image filename and a title:

```
[IconItem@BoxLayout]:
    Image:
        source: ctx.image
    Label:
        text: ctx.title
```

Then in Python, you can instantiate the template using:

```
from kivy.lang import Builder

# create a template with hello world + an image
# the context values should be passed as kwargs to the Builder.template
# function
icon1 = Builder.template('IconItem', title='Hello world',
    image='myimage.png')

# create a second template with other information
ctx = {'title': 'Another hello world',
    'image': 'myimage2.png'}
icon2 = Builder.template('IconItem', **ctx)
# and use icon1 and icon2 as other widget.
```

### 29.7.2 Template example

Most of time, when you are creating a screen in the kv lang, you use a lot of redefinitions. In our example, we'll create a Toolbar, based on a BoxLayout, and put in a few *Image* widgets that will react to the *on\_touch\_down* event.

```
<MyToolbar>:
    BoxLayout:
        Image:
            source: 'data/text.png'
            size: self.texture_size
            size_hint: None, None
            on_touch_down: self.collide_point(*args[1].pos) and root.create_text()

        Image:
```

```

        source: 'data/image.png'
        size: self.texture_size
        size_hint: None, None
        on_touch_down: self.collide_point(*args[1].pos) and root.create_image()

    Image:
        source: 'data/video.png'
        size: self.texture_size
        size_hint: None, None
        on_touch_down: self.collide_point(*args[1].pos) and root.create_video()

```

We can see that the size and size\_hint attribute are exactly the same. More than that, the callback in on\_touch\_down and the image are changing. These can be the variable part of the template that we can put into a context. Let's try to create a template for the Image:

```

[ToolbarButton@Image]:
    # This is the same as before
    size: self.texture_size
    size_hint: None, None

    # Now, we are using the ctx for the variable part of the template
    source: 'data/%s.png' % ctx.image
    on_touch_down: self.collide_point(*args[1].pos) and ctx.callback()

```

The template can be used directly in the MyToolbar rule:

```

<MyToolbar>:
    BoxLayout:
        ToolbarButton:
            image: 'text'
            callback: root.create_text
        ToolbarButton:
            image: 'image'
            callback: root.create_image
        ToolbarButton:
            image: 'video'
            callback: root.create_video

```

That's all :)

### 29.7.3 Template limitations

When you are creating a context:

1. you cannot use references other than “root”:

```

<MyRule>:
    Widget:
        id: mywidget
        value: 'bleh'
    Template:
        ctxkey: mywidget.value # << fail, this references the id
        # mywidget

```

2. not all of the dynamic parts will be understood:

```

<MyRule>
    Template:

```

```

ctxkey: 'value 1' if root.prop1 else 'value2' # << even if
# root.prop1 is a property, if it changes value, ctxkey
# will not be updated

```

Template definitions also replace any similarly named definitions in their entirety and thus do not support inheritance.

## 29.8 Redefining a widget's style

Sometimes we would like to inherit from a widget in order to use its Python properties without also using its .kv defined style. For example, we would like to inherit from a Label, but we would also like to define our own canvas instructions instead of automatically using the canvas instructions inherited from the Label. We can achieve this by prepending a dash (-) before the class name in the .kv style definition.

In myapp.py:

```

class MyWidget(Label):
    pass

```

and in my.kv:

```

<-MyWidget>:
    canvas:
        Color:
            rgb: 1, 1, 1
        Rectangle:
            size: (32, 32)

```

MyWidget will now have a Color and Rectangle instruction in its canvas without any of the instructions inherited from the Label.

## 29.9 Redefining a widget's property style

Similar to *redefining style*, sometimes we would like to inherit from a widget, keep all its KV defined styles, except for the style applied to a specific property. For example, we would like to inherit from a **Button**, but we would also like to set our own *state\_image*, rather than relying on the *background\_normal* and *background\_down* values. We can achieve this by prepending a dash (-) before the *state\_image* property name in the .kv style definition.

In myapp.py:

```

class MyWidget(Button):
    new_background = StringProperty('my_background.png')

```

and in my.kv:

```

<MyWidget>:
    -state_image: self.new_background

```

MyWidget will now have a *state\_image* background set only by *new\_background*, and not by any previous styles that may have set *state\_image*.

---

**Note:** Although the previous rules are cleared, they are still applied during widget construction and are only removed when the new rule with the dash is reached. This means that initially, previous rules

could be used to set the property.

---

## 29.10 Order of kwargs and KV rule application

Properties can be initialized in KV as well as in python. For example, in KV:

```
<MyRule@Widget>:  
    text: 'Hello'  
    ramp: 45.  
    order: self.x + 10
```

Then *MyRule()* would initialize all three kivy properties to the given KV values. Separately in python, if the properties already exist as kivy properties one can do for example *MyRule(line='Bye', side=55)*.

However, what will be the final values of the properties when *MyRule(text='Bye', order=55)* is executed? The quick rule is that python initialization is stronger than KV initialization only for constant rules.

Specifically, the *kwargs* provided to the python initializer are always applied first. So in the above example, *text* is set to 'Bye' and *order* is set to 55. Then, all the KV rules are applied, except those constant rules that overwrite a python initializer provided value.

That is, the KV rules that do not creates bindings such as *text: 'Hello'* and *ramp: 45.*, if a value for that property has been provided in python, then that rule will not be applied.

So in the *MyRule(text='Bye', order=55)* example, *text* will be 'Bye', *ramp* will be 45., and *order*, which creates a binding, will first be set to 55, but then when KV rules are applied will end up being whatever *self.x + 10* is.

Changed in version 1.9.1: Before, KV rules always overwrote the python values, now, python values are not overwritten by constant rules.

## 29.11 Lang Directives

You can use directives to add declarative commands, such as imports or constant definitions, to the lang files. Directives are added as comments in the following format:

```
#:<directivename> <options>
```

### 29.11.1 import <package>

New in version 1.0.5.

Syntax:

```
#:import <alias> <package>
```

You can import a package by writing:

```
#:import os os  
  
<Rule>:  
    Button:  
        text: os.getcwd()
```

Or more complex:

```
#:import ut kivy.utils

<Rule>:
    canvas:
        Color:
            rgba: ut.get_random_color()
```

New in version 1.0.7.

You can directly import classes from a module:

```
#: import Animation kivy.animation.Animation
<Rule>
    on_prop: Animation(x=.5).start(self)
```

## 29.11.2 set <key> <expr>

New in version 1.0.6.

Syntax:

```
#:set <key> <expr>
```

Set a key that will be available anywhere in the kv. For example:

```
#:set my_color (.4, .3, .4)
#:set my_color_hl (.5, .4, .5)

<Rule>:
    state: 'normal'
    canvas:
        Color:
            rgb: my_color if self.state == 'normal' else my_color_hl
```

## 29.11.3 include <file>

New in version 1.9.0.

Syntax:

```
#:include [force] <file>
```

Includes an external kivy file. This allows you to split complex widgets into their own files. If the include is forced, the file will first be unloaded and then reloaded again. For example:

```
# Test.kv
#:include mycomponent.kv
#:include force mybutton.kv

<Rule>:
    state: 'normal'
    MyButton:
        MyComponent:
```

```
# mycomponent.kv
#:include mybutton.kv
```

```
<MyComponent>:
```

```
    MyButton:
```

```
# mybutton.kv
```

```
<MyButton>:
```

```
    canvas:
```

```
        Color:
```

```
            rgb: (1.0, 0.0, 0.0)
```

```
        Rectangle:
```

```
            pos: self.pos
```

```
            size: (self.size[0]/4, self.size[1]/4)
```

```
class kivy.lang.Observable
```

```
Bases: kivy.event.ObjectWithUid
```

**Observable** is a stub class defining the methods required for binding. `EventDispatcher` is (the) one example of a class that implements the binding interface. See `EventDispatcher` for details.

New in version 1.9.0.

```
fbind()
```

```
See EventDispatcher.fbind().
```

---

**Note:** To keep backward compatibility with derived classes which may have inherited from `Observable` before, the `fbind()` method was added. The default implementation of `fbind()` is to create a partial function that it passes to bind while saving the uid and largs/kwargs. However, `funbind()` (and `unbind_uid()`) are fairly inefficient since we have to first lookup this partial function using the largs/kwargs or uid and then call `unbind()` on the returned function. It is recommended to overwrite these methods in derived classes to bind directly for better performance.

Similarly to `EventDispatcher.fbind()`, this method returns 0 on failure and a positive unique uid on success. This uid can be used with `unbind_uid()`.

---

```
funbind()
```

```
See fbind() and EventDispatcher.funbind().
```

```
unbind_uid()
```

```
See fbind() and EventDispatcher.unbind_uid().
```

```
class kivy.lang.BuilderBase
```

```
Bases: object
```

The Builder is responsible for creating a `Parser` for parsing a kv file, merging the results into its internal rules, templates, etc.

By default, `Builder` is a global Kivy instance used in widgets that you can use to load other kv files in addition to the default ones.

```
apply(widget, ignored_consts=set([]))
```

```
Search all the rules that match the widget and apply them.
```

`ignored_consts` is a set or list type whose elements are property names for which constant KV rules (i.e. those that don't create bindings) of that widget will not be applied. This allows e.g. skipping constant rules that overwrite a value initialized in python.

```
apply_rules(widget, rule_name, ignored_consts=set([]))
```

```
Search all the rules that match rule_name widget and apply them to widget.
```

New in version 1.10.0.

`ignored_consts` is a set or list type whose elements are property names for which constant KV rules (i.e. those that don't create bindings) of that widget will not be applied. This allows e.g. skipping constant rules that overwrite a value initialized in python.

**load\_file**(*filename*, \*\**kwargs*)

Insert a file into the language builder and return the root widget (if defined) of the kv file.

## Parameters

**rulesonly: bool, defaults to False** If True, the Builder will raise an exception if you have a root widget inside the definition.

**load\_string**(*string*, \*\**kwargs*)

Insert a string into the Language Builder and return the root widget (if defined) of the kv string.

## Parameters

**rulesonly: bool, defaults to False** If True, the Builder will raise an exception if you have a root widget inside the definition.

**match**(*widget*)

Return a list of **ParserRule** objects matching the widget.

**match\_rule\_name**(*rule name*)

**get\_parser\_rules(widget\_name)**  
Return a list of ParserRule objects matching the widget.

**sync()**

Execute all the waiting operations, such as the execution of all the expressions related to the canvas.

New in version 1.7.0.

**template**(\*args, \*\*ctx)

Create a specialized template using a specific context.

New in version 1.0.5.

With templates, you can construct custom widgets from a kv lang definition by giving them a context. Check [Template usage](#).

**unbind\_property**(*widget, name*)

Unbind the handlers created by all the rules of the widget that set the name.

This effectively clears all the rules of widget that take the form:

**name:** rule

```
>>> w = Builder.load_
... Widget:
...     height: self.
...     x: self.y + 5
...     ''')
>>> w.size
[100, 100]
>>> w.pos
[50, 0]
>>> w.width = 500
>>> w.size
[500, 500]
>>> Builder.unbind pr
```

```
>>> w.width = 222
>>> w.size
[222, 500]
>>> w.y = 500
>>> w.pos
[550, 500]
```

New in version 1.9.1.

### **unbind\_widget(*uid*)**

Unbind all the handlers created by the KV rules of the widget. The `kivy.uix.widget.Widget.uid` is passed here instead of the widget itself, because Builder is using it in the widget destructor.

This effectively clears all the KV rules associated with this widget. For example:

```
>>> w = Builder.load_string('''
... Widget:
...     height: self.width / 2. if self.disabled else self.width
...     x: self.y + 50
...
...
>>> w.size
[100, 100]
>>> w.pos
[50, 0]
>>> w.width = 500
>>> w.size
[500, 500]
>>> Builder.unbind_widget(w.uid)
>>> w.width = 222
>>> w.y = 500
>>> w.size
[222, 500]
>>> w.pos
[50, 500]
```

New in version 1.7.2.

### **unload\_file(*filename*)**

Unload all rules associated with a previously imported file.

New in version 1.0.8.

**Warning:** This will not remove rules or templates already applied/used on current widgets. It will only effect the next widgets creation or template invocation.

**class kivy.lang.BuilderException(*context, line, message, cause=None*)**  
Bases: `kivy.lang.parser.ParserException`

Exception raised when the Builder failed to apply a rule on a widget.

**class kivy.lang.Parser(\*\*kwargs)**  
Bases: `object`

Create a Parser object to parse a Kivy language file or Kivy content.

**parse(*content*)**  
Parse the contents of a Parser file and return a list of root objects.

**parse\_level(*level, lines, spaces=0*)**  
Parse the current level (*level \* spaces*) indentation.

**strip\_comments(*lines*)**

Remove all comments from all lines in-place. Comments need to be on a single line and not at the end of a line. i.e. a comment line's first non-whitespace character must be a #.

**class kivy.lang.ParserException(*context, line, message, cause=None*)**

Bases: exceptions.Exception

Exception raised when something wrong happened in a kv file.

## 29.12 Builder

Class used for the registering and application of rules for specific widgets.

**class kivy.lang.builder.Observable**

Bases: *kivy.event.ObjectWithUid*

**Observable** is a stub class defining the methods required for binding. EventDispatcher is (the) one example of a class that implements the binding interface. See EventDispatcher for details.

New in version 1.9.0.

**fbind()**

See EventDispatcher.fbind().

---

**Note:** To keep backward compatibility with derived classes which may have inherited from **Observable** before, the **fbind()** method was added. The default implementation of **fbind()** is to create a partial function that it passes to bind while saving the uid and largs/kwargs. However, **funbind()** (and **unbind\_uid()**) are fairly inefficient since we have to first lookup this partial function using the largs/kwargs or uid and then call **unbind()** on the returned function. It is recommended to overwrite these methods in derived classes to bind directly for better performance.

Similarly to EventDispatcher.fbind(), this method returns 0 on failure and a positive unique uid on success. This uid can be used with **unbind\_uid()**.

---

**funbind()**

See **fbind()** and EventDispatcher.funbind().

**unbind\_uid()**

See **fbind()** and EventDispatcher.unbind\_uid().

**kivy.lang.builder.Builder = <kivy.lang.builder.BuilderBase object>**

Main instance of a **BuilderBase**.

**class kivy.lang.builder.BuilderBase**

Bases: object

The Builder is responsible for creating a Parser for parsing a kv file, merging the results into its internal rules, templates, etc.

By default, **Builder** is a global Kivy instance used in widgets that you can use to load other kv files in addition to the default ones.

**apply(*widget, ignored\_consts=set([])*)**

Search all the rules that match the widget and apply them.

*ignored\_consts* is a set or list type whose elements are property names for which constant KV rules (i.e. those that don't create bindings) of that widget will not be applied. This allows e.g. skipping constant rules that overwrite a value initialized in python.

**apply\_rules(widget, rule\_name, ignored\_consts=set([]))**

Search all the rules that match *rule\_name* widget and apply them to *widget*.

New in version 1.10.0.

*ignored\_consts* is a set or list type whose elements are property names for which constant KV rules (i.e. those that don't create bindings) of that widget will not be applied. This allows e.g. skipping constant rules that overwrite a value initialized in python.

**load\_file(filename, \*\*kwargs)**

Insert a file into the language builder and return the root widget (if defined) of the kv file.

**Parameters**

**rulesonly: bool, defaults to False** If True, the Builder will raise an exception if you have a root widget inside the definition.

**load\_string(string, \*\*kwargs)**

Insert a string into the Language Builder and return the root widget (if defined) of the kv string.

**Parameters**

**rulesonly: bool, defaults to False** If True, the Builder will raise an exception if you have a root widget inside the definition.

**match(widget)**

Return a list of ParserRule objects matching the widget.

**match\_rule\_name(rule\_name)**

Return a list of ParserRule objects matching the widget.

**sync()**

Execute all the waiting operations, such as the execution of all the expressions related to the canvas.

New in version 1.7.0.

**template(\*args, \*\*ctx)**

Create a specialized template using a specific context.

New in version 1.0.5.

With templates, you can construct custom widgets from a kv lang definition by giving them a context. Check [Template usage](#).

**unbind\_property(widget, name)**

Unbind the handlers created by all the rules of the widget that set the name.

This effectively clears all the rules of widget that take the form:

```
name: rule
```

For example:

```
>>> w = Builder.load_string('''
... Widget:
...     height: self.width / 2. if self.disabled else self.width
...     x: self.y + 50
...
...
>>> w.size
[100, 100]
>>> w.pos
[50, 0]
>>> w.width = 500
```

```

>>> w.size
[500, 500]
>>> Builder.unbind_property(w, 'height')
>>> w.width = 222
>>> w.size
[222, 500]
>>> w.y = 500
>>> w.pos
[550, 500]

```

New in version 1.9.1.

### **unbind\_widget(*uid*)**

Unbind all the handlers created by the KV rules of the widget. The `kivy.uix.widget.Widget.uid` is passed here instead of the widget itself, because Builder is using it in the widget destructor.

This effectively clears all the KV rules associated with this widget. For example:

```

>>> w = Builder.load_string('''
... Widget:
...     height: self.width / 2. if self.disabled else self.width
...     x: self.y + 50
...
...
>>> w.size
[100, 100]
>>> w.pos
[50, 0]
>>> w.width = 500
>>> w.size
[500, 500]
>>> Builder.unbind_widget(w.uid)
>>> w.width = 222
>>> w.y = 500
>>> w.size
[222, 500]
>>> w.pos
[50, 500]

```

New in version 1.7.2.

### **unload\_file(*filename*)**

Unload all rules associated with a previously imported file.

New in version 1.0.8.

**Warning:** This will not remove rules or templates already applied/used on current widgets. It will only effect the next widgets creation or template invocation.

**class kivy.lang.builder.BuilderException(*context, line, message, cause=None*)**

Bases: `kivy.lang.parser.ParserException`

Exception raised when the Builder failed to apply a rule on a widget.

## 29.13 Parser

Class used for the parsing of .kv files into rules.

```
class kivy.lang.parser.Parser(**kwargs)
Bases: object

Create a Parser object to parse a Kivy language file or Kivy content.

parse(content)
    Parse the contents of a Parser file and return a list of root objects.

parse_level(level, lines, spaces=0)
    Parse the current level (level * spaces) indentation.

strip_comments(lines)
    Remove all comments from all lines in-place. Comments need to be on a single line and not
    at the end of a line. i.e. a comment line's first non-whitespace character must be a #.

class kivy.lang.parser.ParserException(context, line, message, cause=None)
Bases: exceptions.Exception

Exception raised when something wrong happened in a kv file.
```



# External libraries

---

Kivy comes with other python/C libraries:

- *ddsfile* - used for parsing and saving DDS files.
- *osc* - a modified/optimized version of PyOSC for using the Open Sound Control protocol.
- *mtdev* - provides support for the Kernel multi-touch transformation library.

**Warning:** Even though Kivy comes with these external libraries, we do not provide any support for them and they might change in the future. Don't rely on them in your code.

## 30.1 GstPlayer

New in version 1.8.0.

*GstPlayer* is a media player implemented specifically for Kivy with Gstreamer 1.0. It doesn't use Gi at all and is focused on what we want: the ability to read video and stream the image in a callback, or read an audio file. Don't use it directly but use our Core providers instead.

This player is automatically compiled if you have `pkg-config --libs --cflags gstreamer-1.0` working.

**Warning:** This is an external library and Kivy does not provide any support for it. It might change in the future and we advise you don't rely on it in your code.

## 30.2 OSC

This is an heavy modified version of PyOSC used to access the Open Sound Control protocol. It is used by Kivy internally for TUIO providers, but can also be used by applications to interact with devices or processes using the OSC API.

**Warning:** This is an external library and Kivy does not provide any support for it. It might change in the future and we advise you don't rely on it in your code.

### 30.2.1 NO DOCUMENTATION (module kivy.lib.osc)

#### **class** kivy.lib.osc.OSC.CallbackManager

This utility class maps OSC addresses to callables.

The CallbackManager calls its callbacks with a list of decoded OSC arguments, including the address and the typetags as the first two arguments.

##### **add**(callback, name)

Adds a callback to our set of callbacks, or removes the callback with name if callback is None.

##### **dispatch**(message, source=None)

Sends decoded OSC data to an appropriate callback

##### **handle**(data, source=None)

Given OSC data, tries to call the callback with the right address.

##### **unbundler**(messages)

Dispatch the messages in a decoded bundle.

#### **kivy.lib.osc.OSC.OSCArgument**(data)

Convert some Python types to their OSC binary representations, returning a (typetag, data) tuple.

#### **kivy.lib.osc.OSC.OSCBlob**(next)

Convert a string into an OSC Blob, returning a (typetag, data) tuple.

#### **class** kivy.lib.osc.OSC.OSCMessage

Builds typetagged OSC messages.

##### **append**(argument, typehint=None)

Appends data to the message, updating the typetags based on the argument's type. If the argument is a blob (counted string) pass in 'b' as typehint.

##### **getBinary()**

Returns the binary message (so far) with typetags.

##### **rawAppend**(data)

Appends raw data to the message. Use append().

#### **kivy.lib.osc.OSC.hexDump**(data)

Useful utility; prints the string in hexadecimal

#### **kivy.lib.osc.OSC.parseArgs**(args)

Given a list of strings, produces a list where those strings have been parsed (where possible) as floats or integers.

#### **kivy.lib.osc.OSC.readDouble**(data)

Tries to interpret the next 8 bytes of the data as a 64-bit double float.

#### **kivy.lib.osc.OSC.readLong**(data)

Tries to interpret the next 8 bytes of the data as a 64-bit signed integer.

### 30.2.2 simpleOSC 0.2

ixi software - July, 2006 [www.ixi-software.net](http://www.ixi-software.net)

simple API for the Open SoundControl for Python (by Daniel Holth, Clinton McChesney -> pyKit.tar.gz file at <http://wiretap.stetson.edu>) Documentation at <http://wiretap.stetson.edu/docs/pyKit/>

The main aim of this implementation is to provide with a simple way to deal with the OSC implementation that makes life easier to those who don't have understanding of sockets or programming. This would not be on your screen without the help of Daniel Holth.

This library is free software; you can redistribute it and/or modify it under the terms of the GNU Lesser General Public License as published by the Free Software Foundation; either version 2.1 of the License, or (at your option) any later version.

This library is distributed in the hope that it will be useful, but WITHOUT ANY WARRANTY; without even the implied warranty of MERCHANTABILITY or FITNESS FOR A PARTICULAR PURPOSE. See the GNU Lesser General Public License for more details.

You should have received a copy of the GNU Lesser General Public License along with this library; if not, write to the Free Software Foundation, Inc., 59 Temple Place, Suite 330, Boston, MA 02111-1307 USA

Thanks for the support to Buchsenhausen, Innsbruck, Austria.

```
kivy.lib.osc.oscAPI.appendToBundle(bundle, oscAddress, dataArray)
    create OSC message and append it to a given bundle

kivy.lib.osc.oscAPI.bind(oscid, func, oscaddress)
    bind given oscaddresses with given functions in address manager

kivy.lib.osc.oscAPI.createBinaryMsg(oscAddress, dataArray, typehint=None)
    create and return general type binary OSC msg

kivy.lib.osc.oscAPI.createBundle()
    create bundled type of OSC messages

kivy.lib.osc.oscAPI.dontListen(thread_id=None)
    closes the socket and kills the thread

kivy.lib.osc.oscAPI.init()
    instantiates address manager and outsocket as globals

kivy.lib.osc.oscAPI.listen(ipAddr='127.0.0.1', port=9001)
    Creates a new thread listening to that port defaults to ipAddr='127.0.0.1', port 9001

kivy.lib.osc.oscAPI.readQueue(thread_id=None)
    Read queues from all threads, and dispatch message. This must be call in the main thread.
    You can pass the thread id to deque message from a specific thread. This id is returned from the
    listen() function

kivy.lib.osc.oscAPI.sendBundle(bundle, ipAddr='127.0.0.1', port=9000)
    convert bundle to a binary and send it

kivy.lib.osc.oscAPI.sendMsg(oscAddress, dataArray=[], ipAddr='127.0.0.1', port=9000, type-
    hint=None)
    create and send normal OSC msgs defaults to '127.0.0.1', port 9000
```

### 30.3 DDS File library

This library can be used to parse and save DDS (*DirectDraw Surface* <[https://en.wikipedia.org/wiki/DirectDraw\\_Surface](https://en.wikipedia.org/wiki/DirectDraw_Surface)>) files.

The initial version was written by:

Alexey Borzenkov ( <a href="mailto:snaury@gmail.com">snaury@gmail.com</a> )
-----------------------------------------------------------------------------

All the initial work credits go to him! Thank you :)

This version uses structs instead of ctypes.

### 30.3.1 DDS Format

```
[DDS ][SurfaceDesc][Data]

[SurfaceDesc]:: (everything is uint32)
    Size
    Flags
    Height
    Width
    PitchOrLinearSize
    Depth
    MipmapCount
    Reserved1 * 11
    [PixelFormat]::
        Size
        Flags
        FourCC
        RGBBitCount
        RBitMask
        GBitMask
        BBitMask
        ABitMask
    [Caps]::
        Caps1
        Caps2
        Reserved1 * 2
    Reserved2
```

**Warning:** This is an external library and Kivy does not provide any support for it. It might change in the future and we advise you don't rely on it in your code.

## 30.4 Python mtdev

The mtdev module provides Python bindings to the [Kernel multi-touch transformation library](#), also known as mtdev (MIT license).

The mtdev library transforms all variants of kernel MT events to the slotted type B protocol. The events put into mtdev may be from any MT device, specifically type A without contact tracking, type A with contact tracking, or type B with contact tracking. See the kernel documentation for further details.

**Warning:** This is an external library and Kivy does not provide any support for it. It might change in the future and we advise you don't rely on it in your code.

# Modules

---

Modules are classes that can be loaded when a Kivy application is starting. The loading of modules is managed by the config file. Currently, we include:

- *touchring*: Draw a circle around each touch.
- *monitor*: Add a red topbar that indicates the FPS and a small graph indicating input activity.
- *keybinding*: Bind some keys to actions, such as a screenshot.
- *recorder*: Record and playback a sequence of events.
- *screen*: Emulate the characteristics (dpi/density/ resolution) of different screens.
- *inspector*: Examines your widget hierarchy and widget properties.
- *webdebugger*: Realtime examination of your app internals via a web browser.
- *joycursor*: Navigate in your app with a joystick.

Modules are automatically loaded from the Kivy path and User path:

- *PATH\_TO\_KIVY/kivy/modules*
- *HOME/.kivy/mods*

## 31.1 Activating a module

There are various ways in which you can activate a kivy module.

### 31.1.1 Activate a module in the config

To activate a module this way, you can edit your configuration file (in your *HOME/.kivy/config.ini*):

```
[modules]
# uncomment to activate
touchring =
```

```
# monitor =
# keybinding =
```

Only the name of the module followed by “=” is sufficient to activate the module.

### 31.1.2 Activate a module in Python

Before starting your application, preferably at the start of your import, you can do something like this:

```
import kivy
kivy.require('1.0.8')

# Activate the touchring module
from kivy.config import Config
Config.set('modules', 'touchring', '')
```

### 31.1.3 Activate a module via the commandline

When starting your application from the commandline, you can add a `-m <modulename>` to the arguments. For example:

```
python main.py -m webdebugger
```

---

**Note:** Some modules, such as the screen, may require additional parameters. They will, however, print these parameters to the console when launched without them.

---

## 31.2 Create your own module

Create a file in your `HOME/.kivy/mods`, and create 2 functions:

```
def start(win, ctx):
    pass

def stop(win, ctx):
    pass
```

Start/stop are functions that will be called for every window opened in Kivy. When you are starting a module, you can use these to store and manage the module state. Use the `ctx` variable as a dictionary. This context is unique for each instance/start() call of the module, and will be passed to stop() too.

## 31.3 Console

New in version 1.9.1.

Reboot of the old inspector, designed to be modular and keep concerns separated. It also have a addons architecture that allow you to add a button, panel, or more in the Console itself.

**Warning:** This module works, but might fail in some cases. Please contribute!

### 31.3.1 Usage

For normal module usage, please see the [modules](#) documentation:

```
python main.py -m console
```

### 31.3.2 Mouse navigation

When “Select” button is activated, you can:

- tap once on a widget to select it without leaving inspect mode
- double tap on a widget to select and leave inspect mode (then you can manipulate the widget again)

### 31.3.3 Keyboard navigation

- “Ctrl + e”: toggle console
- “Escape”: cancel widget lookup, then hide inspector view
- “Top”: select the parent widget
- “Down”: select the first children of the current selected widget
- “Left”: select the previous following sibling
- “Right”: select the next following sibling

### 31.3.4 Additional informations

Some properties can be edited live. However, due to the delayed usage of some properties, it might crash if you don’t handle all the cases.

### 31.3.5 Addons

Addons must be added to `Console.addons` before the first Clock tick of the application, or before the `create_console` is called. You cannot add addons on the fly currently. Addons are quite cheap until the Console is activated. Panel are even cheaper, nothing is done until the user select it.

By default, we provide multiple addons activated by default:

- `ConsoleAddonFps`: display the FPS at the top-right
- `ConsoleAddonSelect`: activate the selection mode
- `ConsoleAddonBreadcrumb`: display the hierarchy of the current widget at the bottom
- `ConsoleAddonWidgetTree`: panel to display the widget tree of the application
- `ConsoleAddonWidgetPanel`: panel to display the properties of the selected widget

If you need to add custom widget in the Console, please use either `ConsoleButton`, `ConsoleToggleButton` or `ConsoleLabel`

An addon must inherit from the `ConsoleAddon` class.

For example, here is a simple addon for displaying the FPS at the top/right of the Console:

```

from kivy.modules.console import Console, ConsoleAddon

class ConsoleAddonFps(ConsoleAddon):
    def __init__(self):
        self.lbl = ConsoleLabel(text="0 Fps")
        self.console.add_toolbar_widget(self.lbl, right=True)

    def activate(self):
        self.event = Clock.schedule_interval(self.update_fps, 1 / 2.)

    def deactivated(self):
        self.event.cancel()

    def update_fps(self, *args):
        fps = Clock.get_fps()
        self.lbl.text = "{} Fps".format(int(fps))

Console.register_addon(ConsoleAddonFps)

```

You can create addon that adds panels. Panel activation/deactivation are not tied to the addon activation/deactivation, but on some cases, you can use the same callback for deactivating the addon and the panel. Here is a simple About panel addon:

```

from kivy.modules.console import Console, ConsoleAddon, ConsoleLabel

class ConsoleAddonAbout(ConsoleAddon):
    def __init__(self):
        self.console.add_panel("About", self.panel_activate,
                              self.panel_deactivate)

    def panel_activate(self):
        self.console.bind(widget=self.update_content)
        self.update_content()

    def panel_deactivate(self):
        self.console.unbind(widget=self.update_content)

    def deactivate(self):
        self.panel_deactivate()

    def update_content(self, *args):
        widget = self.console.widget
        if not widget:
            return
        text = "Selected widget is: {!r}".format(widget)
        lbl = ConsoleLabel(text=text)
        self.console.set_content(lbl)

Console.register_addon(ConsoleAddonAbout)

```

### kivy.modules.console.start(*win, ctx*)

Create an Console instance attached to the *ctx* and bound to the Window's *on\_keyboard()* event for capturing the keyboard shortcut.

#### Parameters

*win*: A [Window](#) The application Window to bind to.

*ctx*: A [Widget](#) or subclass The Widget to be inspected.

### kivy.modules.console.stop(*win, ctx*)

Stop and unload any active Inspectors for the given *ctx*.

```
class kivy.modules.console.Console(**kwargs)
Bases: kivy.uix.relativelayout.RelativeLayout
```

Console interface

This widget is created by `create_console()`, when the module is loaded. During that time, you can add addons on the console to extend the functionalities, or add your own application stats / debugging module.

#### **activated**

True if the Console is activated (showed)

```
add_panel(name, cb_activate, cb_deactivate, cb_refresh=None)
```

Add a new panel in the Console.

- *cb\_activate* is a callable that will be called when the panel is activated by the user.
- *cb\_deactivate* is a callable that will be called when the panel is deactivated or when the console will hide.
- *cb\_refresh* is an optional callable that is called if the user click again on the button for display the panel

When activated, it's up to the panel to display a content in the Console by using `set_content()`.

```
add_toolbar_widget(widget, right=False)
```

Add a widget in the top left toolbar of the Console. Use *right=True* if you wanna add the widget at the right instead.

```
addons = [<class 'kivy.modules.console.ConsoleAddonSelect'>, <class 'kivy.modules.co
```

Array of addons that will be created at Console creation

```
highlight_at(x, y)
```

Select a widget from a x/y window coordinate. This is mostly used internally when Select mode is activated

```
inspect_enabled
```

Indicate if the inspector inspection is enabled. If yes, the next touch down will select a the widget under the touch

```
mode
```

Display mode of the Console, either docked at the bottom, or as a floating window.

```
pick(widget, x, y)
```

Pick a widget at x/y, given a root *widget*

```
remove_toolbar_widget(widget)
```

Remove a widget from the toolbar

```
set_content(content)
```

Replace the Console content with a new one.

```
widget
```

Current widget being selected

```
class kivy.modules.console.ConsoleAddon(console)
```

Bases: object

Base class for implementing addons

```
activate()
```

Method called when the addon is activated by the console (when the console is displayed)

```

console = None
    Console instance

deactivate()
    Method called when the addon is deactivated by the console (when the console is hidden)

init()
    Method called when the addon is instantiated by the Console

class kivy.modules.console.ConsoleButton(**kwargs)
    Bases: kivy.uix.button.Button
        Button specialized for the Console

class kivy.modules.console.ConsoleToggleButton(**kwargs)
    Bases: kivy.uix.togglebutton.ToggleButton
        ToggleButton specialized for the Console

class kivy.modules.console.ConsoleLabel(**kwargs)
    Bases: kivy.uix.label.Label
        LabelButton specialized for the Console

```

## 31.4 Inspector

New in version 1.0.9.

**Warning:** This module is highly experimental, use it with care.

The Inspector is a tool for finding a widget in the widget tree by clicking or tapping on it. Some keyboard shortcuts are activated:

- “Ctrl + e”: activate / deactivate the inspector view
- “Escape”: cancel widget lookup first, then hide the inspector view

Available inspector interactions:

- tap once on a widget to select it without leaving inspect mode
- double tap on a widget to select and leave inspect mode (then you can manipulate the widget again)

Some properties can be edited live. However, due to the delayed usage of some properties, it might crash if you don’t handle all the cases.

### 31.4.1 Usage

For normal module usage, please see the [modules](#) documentation.

The Inspector, however, can also be imported and used just like a normal python module. This has the added advantage of being able to activate and deactivate the module programmatically:

```

from kivy.core.window import Window
from kivy.app import App
from kivy.uix.button import Button
from kivy.modules import inspector

class Demo(App):

```

```
def build(self):
    button = Button(text="Test")
    inspector.create_inspector(Window, button)
    return button

Demo().run()
```

To remove the Inspector, you can do the following:

```
inspector.stop(Window, button)
```

`kivy.modules.inspector.stop(win, ctx)`

Stop and unload any active Inspectors for the given *ctx*.

`kivy.modules.inspector.create_inspector(win, ctx, *l)`

Create an Inspector instance attached to the *ctx* and bound to the Window's `on_keyboard()` event for capturing the keyboard shortcut.

#### Parameters

*win*: A `Window` The application Window to bind to.

*ctx*: A `Widget` or subclass The Widget to be inspected.

## 31.5 JoyCursor

New in version 1.10.0.

The JoyCursor is a tool for navigating with a joystick as if using a mouse or touch. Most of the actions that are possible for a mouse user are available in this module.

For example:

- left click
- right click
- double click (two clicks)
- moving the cursor
- holding the button (+ moving at the same time)
- selecting
- scrolling

There are some properties that can be edited live, such as intensity of the JoyCursor movement and toggling mouse button holding.

### 31.5.1 Usage

For normal module usage, please see the `modules` documentation and these bindings:

Event	Joystick
cursor move	Axis 3, Axis 4
cursor intensity	Button 0, Button 1
left click	Button 2
right click	Button 3
scroll up	Button 4
scroll down	Button 5
hold button	Button 6
joycursor on/off	Button 7

The JoyCursor, like Inspector, can also be imported and used as a normal python module. This has the added advantage of being able to activate and deactivate the module programmatically:

```
from kivy.lang import Builder
from kivy.base import runTouchApp
runTouchApp(Builder.load_string("""
#:import jc kivy.modules.joycursor
BoxLayout:
    Button:
        text: 'Press & activate with Ctrl+E or Button 7'
        on_release: jc.create_joycursor(root.parent, root)
    Button:
        text: 'Disable'
        on_release: jc.stop(root.parent, root)
"""))
```

**kivy.modules.joycursor.stop(*win, ctx*)**

Stop and unload any active JoyCursors for the given *ctx*.

**kivy.modules.joycursor.create\_joycursor(*win, ctx, \*args*)**

Create a JoyCursor instance attached to the *ctx* and bound to the Window's *on\_keyboard()* event for capturing the keyboard shortcuts.

#### Parameters

*win*: A **Window** The application Window to bind to.

*ctx*: A **Widget** or subclass The Widget for JoyCursor to attach to.

## 31.6 Keybinding

This module forces the mapping of some keys to functions:

- F11: Rotate the Window through 0, 90, 180 and 270 degrees
- Shift + F11: Switches between portrait and landscape on desktops
- F12: Take a screenshot

Note: this doesn't work if the application requests the keyboard beforehand.

### 31.6.1 Usage

For normal module usage, please see the **modules** documentation.

The Keybinding module, however, can also be imported and used just like a normal python module. This has the added advantage of being able to activate and deactivate the module programmatically:

```

from kivy.app import App
from kivy.uix.button import Button
from kivy.modules import keybinding
from kivy.core.window import Window

class Demo(App):

    def build(self):
        button = Button(text="Hello")
        keybinding.start(Window, button)
        return button

Demo().run()

```

To remove the Keybinding, you can do the following:

```
Keybinding.stop(Window, button)
```

## 31.7 Monitor module

The Monitor module is a toolbar that shows the activity of your current application :

- FPS
- Graph of input events

### 31.7.1 Usage

For normal module usage, please see the [modules](#) documentation.

## 31.8 Recorder module

New in version 1.1.0.

Create an instance of [\*Recorder\*](#), attach to the class, and bind some keys to record / play sequences:

- F6: play the last record in a loop
- F7: read the latest recording
- F8: record input events

### 31.8.1 Configuration

#### Parameters

*attrs*: str, defaults to [\*record\\_attrs\*](#) value. Attributes to record from the motion event

*profile\_mask*: str, defaults to [\*record\\_profile\\_mask\*](#) value. Mask for motion event profile. Used to filter which profile will appear in the fake motion event when replayed.

*filename*: str, defaults to ‘recorder.kvi’ Name of the file to record / play with

## 31.8.2 Usage

For normal module usage, please see the [modules](#) documentation.

## 31.9 Screen

This module changes some environment and configuration variables to match the density / dpi / screensize of a specific device.

To see a list of the available screenid's, just run:

```
python main.py -m screen
```

To simulate a medium-density screen such as the Motorola Droid 2:

```
python main.py -m screen:droid2
```

To simulate a high-density screen such as HTC One X, in portrait:

```
python main.py -m screen:onex,portrait
```

To simulate the iPad 2 screen:

```
python main.py -m screen:ipad
```

If the generated window is too large, you can specify a scale:

```
python main.py -m screen:note2,portrait,scale=.75
```

Note that to display your contents correctly on a scaled window you must consistently use units 'dp' and 'sp' throughout your app. See [metrics](#) for more details.

## 31.10 Touchring

Shows rings around every touch on the surface / screen. You can use this module to check that you don't have any calibration issues with touches.

### 31.10.1 Configuration

#### Parameters

**image: str, defaults to '<kivy>/data/images/ring.png'** Filename of the image to use.

**scale: float, defaults to 1.** Scale of the image.

**alpha: float, defaults to 1.** Opacity of the image.

### 31.10.2 Example

In your configuration (`~/kivy/config.ini`), you can add something like this:

```
[modules]
touchring = image=mypointer.png,scale=.3,alpha=.7
```

## 31.11 Web Debugger

New in version 1.2.0.

**Warning:** This module is highly experimental, use it with care.

This module will start a webserver and run in the background. You can see how your application evolves during runtime, examine the internal cache etc.

Run with:

```
python main.py -m webdebugger
```

Then open your webbrowser on <http://localhost:5000/>



---

# Network support

---

Kivy currently supports basic, asynchronous network requests. Please refer to [kivy.network.urlrequest.UrlRequest](#).

## 32.1 UrlRequest

New in version 1.0.8.

You can use the [UrlRequest](#) to make asynchronous requests on the web and get the result when the request is completed. The spirit is the same as the XHR object in Javascript.

The content is also decoded if the Content-Type is application/json and the result automatically passed through json.loads.

The syntax to create a request:

```
from kivy.network.urlrequest import UrlRequest
req = UrlRequest(url, on_success, on_redirect, on_failure, on_error,
                  on_progress, req_body, req_headers, chunk_size,
                  timeout, method, decode, debug, file_path, ca_file,
                  verify)
```

Only the first argument is mandatory: the rest are optional. By default, a “GET” request will be sent. If the [UrlRequest.req\\_body](#) is not None, a “POST” request will be sent. It’s up to you to adjust [UrlRequest.req\\_headers](#) to suit your requirements and the response to the request will be accessible as the parameter called “result” on the callback function of the on\_success event.

Example of fetching JSON:

```
def got_json(req, result):
    for key, value in result['headers'].items():
        print('{}: {}'.format(key, value))

req = UrlRequest('https://httpbin.org/headers', got_json)
```

Example of Posting data (adapted from `httplib` example):

```
import urllib

def bug_posted(req, result):
    print('Our bug is posted!')
    print(result)

params = urllib.urlencode({'@number': 12524, '@type': 'issue',
                           '@action': 'show'})
headers = {'Content-type': 'application/x-www-form-urlencoded',
           'Accept': 'text/plain'}
req = UrlRequest('bugs.python.org', on_success=bug_posted, req_body=params,
                 req_headers=headers)
```

If you want a synchronous request, you can call the `wait()` method.

```
class kivy.network.urlrequest.UrlRequest(url, on_success=None, on_redirect=None,
                                            on_failure=None, on_error=None,
                                            on_progress=None, req_body=None,
                                            req_headers=None, chunk_size=8192,
                                            timeout=None, method=None, decode=True,
                                            debug=False, file_path=None, ca_file=None,
                                            verify=True, proxy_host=None,
                                            proxy_port=None, proxy_headers=None)
```

Bases: `threading.Thread`

A `UrlRequest`. See module documentation for usage.

Changed in version 1.5.1: Add `debug` parameter

Changed in version 1.0.10: Add `method` parameter

Changed in version 1.8.0: Parameter `decode` added. Parameter `file_path` added. Parameter `on_redirect` added. Parameter `on_failure` added.

Changed in version 1.9.1: Parameter `ca_file` added. Parameter `verify` added.

Changed in version 1.10.0: Parameters `proxy_host`, `proxy_port` and `proxy_headers` added.

#### Parameters

`url: str` Complete url string to call.

`on_success: callback(request, result)` Callback function to call when the result has been fetched.

`on_redirect: callback(request, result)` Callback function to call if the server returns a Redirect.

`on_failure: callback(request, result)` Callback function to call if the server returns a Client or Server Error.

`on_error: callback(request, error)` Callback function to call if an error occurs.

`on_progress: callback(request, current_size, total_size)` Callback function that will be called to report progression of the download. `total_size` might be -1 if no Content-Length has been reported in the http response. This callback will be called after each `chunk_size` is read.

`req_body: str, defaults to None` Data to sent in the request. If it's not None, a POST will be done instead of a GET.

`req_headers: dict, defaults to None` Custom headers to add to the request.

**chunk\_size: int, defaults to 8192** Size of each chunk to read, used only when *on\_progress* callback has been set. If you decrease it too much, a lot of *on\_progress* callbacks will be fired and will slow down your download. If you want to have the maximum download speed, increase the *chunk\_size* or don't use *on\_progress*.

**timeout: int, defaults to None** If set, blocking operations will timeout after this many seconds.

**method: str, defaults to 'GET' (or 'POST' if body is specified)** The HTTP method to use.

**decode: bool, defaults to True** If False, skip decoding of the response.

**debug: bool, defaults to False** If True, it will use the `Logger.debug` to print information about url access/progression/errors.

**file\_path: str, defaults to None** If set, the result of the `URLRequest` will be written to this path instead of in memory.

**ca\_file: str, defaults to None** Indicates a SSL CA certificate file path to validate HTTPS certificates against

**verify: bool, defaults to True** If False, disables SSL CA certificate verification

**proxy\_host: str, defaults to None** If set, the proxy host to use for this connection.

**proxy\_port: int, defaults to None** If set, and *proxy\_host* is also set, the port to use for connecting to the proxy server.

**proxy\_headers: dict, defaults to None** If set, and *proxy\_host* is also set, the headers to send to the proxy server in the CONNECT request.

### **chunk\_size**

Return the size of a chunk, used only in "progress" mode (when *on\_progress* callback is set.)

### **decode\_result(result, resp)**

Decode the result fetched from url according to his Content-Type. Currently supports only application/json.

### **error**

Return the error of the request. This value is not determined until the request is completed.

### **get\_connection\_for\_scheme(scheme)**

Return the Connection class for a particular scheme. This is an internal function that can be expanded to support custom schemes.

Actual supported schemes: http, https.

### **is\_finished**

Return True if the request has finished, whether it's a success or a failure.

### **req\_body = None**

Request body passed in `__init__`

### **req\_headers = None**

Request headers passed in `__init__`

### **resp\_headers**

If the request has been completed, return a dictionary containing the headers of the response. Otherwise, it will return None.

### **resp\_status**

Return the status code of the response if the request is complete, otherwise return None.

**result**

Return the result of the request. This value is not determined until the request is finished.

**url = None**

Url of the request

**wait(*delay=0.5*)**

Wait for the request to finish (until *resp\_status* is not None)

---

**Note:** This method is intended to be used in the main thread, and the callback will be dispatched from the same thread from which you're calling.

---

New in version 1.1.0.

# Storage

---

New in version 1.7.0.

**Warning:** This module is still experimental, and the API is subject to change in a future version.

## 33.1 Usage

The idea behind the Storage module is to be able to load/store any number of key-value pairs via an indexed key. The default model is abstract so you cannot use it directly. We provide some implementations such as:

- `kivy.storage.dictstore.DictStore`: use a python dict as a store
- `kivy.storage.jsonstore.JsonStore`: use a JSON file as a store
- `kivy.storage.redisstore.RedisStore`: use a Redis database with redis-py

## 33.2 Examples

For example, let's use a JsonStore:

```
from kivy.storage.jsonstore import JsonStore

store = JsonStore('hello.json')

# put some values
store.put('tito', name='Mathieu', org='kivy')
store.put('tshirtman', name='Gabriel', age=27)

# using the same index key erases all previously added key-value pairs
store.put('tito', name='Mathieu', age=30)
```

```
# get a value using a index key and key
print('tito is', store.get('tito')['age'])

# or guess the key/entry for a part of the key
for item in store.find(name='Gabriel'):
    print('tshirtmans index key is', item[0])
    print('his key value pairs are', str(item[1]))
```

Because the data is persistent, you can check later to see if the key exists:

```
from kivy.storage.jsonstore import JsonStore

store = JsonStore('hello.json')
if store.exists('tito'):
    print('tite exists:', store.get('tito'))
    store.delete('tito')
```

### 33.3 Synchronous / Asynchronous API

All the standard methods (`get()`, `put()`, `exists()`, `delete()`, `find()`) have an asynchronous version.

For example, the `get` method has a `callback` parameter. If set, the `callback` will be used to return the result to the user when available: the request will be asynchronous. If the `callback` is None, then the request will be synchronous and the result will be returned directly.

Without callback (Synchronous API):

```
entry = mystore.get('tito')
print('tito =', entry)
```

With callback (Asynchronous API):

```
def my_callback(store, key, result):
    print('the key', key, 'has a value of', result)
mystore.get('plop', callback=my_callback)
```

The callback signature (for almost all methods) is:

```
def callback(store, key, result):
    """
    store: the `Store` instance currently used.
    key: the key sought for.
    result: the result of the lookup for the key.
    """
```

### 33.4 Synchronous container type

The storage API emulates the container type for the synchronous API:

```
store = JsonStore('hello.json')

# original: store.get('tito')
store['tito']
```

```

# original: store.put('tito', name='Mathieu')
store['tito'] = {'name': 'Mathieu'}

# original: store.delete('tito')
del store['tito']

# original: store.count()
len(store)

# original: store.exists('tito')
'tito' in store

# original: for key in store.keys()
for key in store:
    pass

```

**class kivy.storage.AbstractStore(\*\*kwargs)**

Bases: *kivy.event.EventDispatcher*

Abstract class used to implement a Store

**async\_clear(callback)**

Asynchronous version of *clear()*.

**async\_count(callback)**

Asynchronously return the number of entries in the storage.

**async\_delete(callback, key)**

Asynchronous version of *delete()*.

**Callback arguments**

*store: AbstractStore instance* Store instance

*key: string* Name of the key to search for

*result: bool* Indicate True if the storage has been updated, or False if nothing has been done (no changes). None if any error.

**async\_exists(callback, key)**

Asynchronous version of *exists()*.

**Callback arguments**

*store: AbstractStore instance* Store instance

*key: string* Name of the key to search for

*result: bool* Result of the query, None if any error

**async\_find(callback, \*\*filters)**

Asynchronous version of *find()*.

The callback will be called for each entry in the result.

**Callback arguments**

*store: AbstractStore instance* Store instance

*key: string* Name of the key to search for, or None if we reach the end of the results

*result: bool* Indicate True if the storage has been updated, or False if nothing has been done (no changes). None if any error.

**async\_get(callback, key)**  
Asynchronous version of [get\(\)](#).

**Callback arguments**

**store: AbstractStore instance** Store instance

**key: string** Name of the key to search for

**result: dict** Result of the query, None if any error

**async\_keys(callback)**

Asynchronously return all the keys in the storage.

**async\_put(callback, key, \*\*values)**

Asynchronous version of [put\(\)](#).

**Callback arguments**

**store: AbstractStore instance** Store instance

**key: string** Name of the key to search for

**result: bool** Indicate True if the storage has been updated, or False if nothing has been done (no changes). None if any error.

**clear()**

Wipe the whole storage.

**count()**

Return the number of entries in the storage.

**delete(key)**

Delete a key from the storage. If the key is not found, a *KeyError* exception will be thrown.

**exists(key)**

Check if a key exists in the store.

**find(\*\*filters)**

Return all the entries matching the filters. The entries are returned through a generator as a list of (key, entry) pairs where *entry* is a dict of key-value pairs

```
for key, entry in store.find(name='Mathieu'):
    print('key:', key, ', entry:', entry)
```

Because it's a generator, you cannot directly use it as a list. You can do:

```
# get all the (key, entry) availables
entries = list(store.find(name='Mathieu'))
# get only the entry from (key, entry)
entries = list((x[1] for x in store.find(name='Mathieu')))
```

**get(key)**

Get the key-value pairs stored at *key*. If the key is not found, a *KeyError* exception will be thrown.

**keys()**

Return a list of all the keys in the storage.

**put(key, \*\*values)**

Put new key-value pairs (given in *values*) into the storage. Any existing key-value pairs will be removed.

## 33.5 Dictionary store

Use a Python dictionary as a store.

```
class kivy.storage.dictstore.DictStore(filename, data=None, **kwargs)
Bases: kivy.storage.AbstractStore
```

Store implementation using a pickled *dict*. See the [kivy.storage](#) module documentation for more information.

## 33.6 JSON store

A *Storage* module used to save/load key-value pairs from a json file.

```
class kivy.storage.jsonstore.JsonStore(filename, indent=None, sort_keys=False,
                                         **kwargs)
Bases: kivy.storage.AbstractStore
```

Store implementation using a json file for storing the key-value pairs. See the [kivy.storage](#) module documentation for more information.

## 33.7 Redis Store

Store implementation using Redis. You must have redis-py installed.

Usage example:

```
from kivy.storage.redisstore import RedisStore
params = dict(host='localhost', port=6379, db=14)
store = RedisStore(params)
```

All the key-value pairs will be stored with a prefix 'store' by default. You can instantiate the storage with another prefix like this:

```
from kivy.storage.redisstore import RedisStore
params = dict(host='localhost', port=6379, db=14)
store = RedisStore(params, prefix='mystore2')
```

The params dictionary will be passed to the redis.StrictRedis class.

See [redis-py](#).

```
class kivy.storage.redisstore.RedisStore(redis_params, **kwargs)
Bases: kivy.storage.AbstractStore
```

Store implementation using a Redis database. See the [kivy.storage](#) module documentation for more informations.



# Tools

---

The tools module provides various utility scripts, modules and examples.

## 34.1 Scripts

Some useful scripts include:

- `kviewer.py`: for viewing kv files with automatic updating
- `benchmark.py`: provides detailed OpenGL hardware information as well as some benchmarks measuring kivy specific performance
- `reports.py`: provides a comprehensive report covering your systems providers, libraries, configuration, environment, input devices and options
- `texturecompress.py`: a command line utility for compressing images into PVRTC or ETC1 formats
- `generate-icons.py`: generates set of icons suitable for the various store and package formats
- `gles_compat/subset_gles.py`: examines compatibility between GLEXT and GLES2 headers for finding compatible subsets

## 34.2 Modules

Tool modules provide various resources for:

- *packaging*
- *text editor highlighting*

## 34.3 Other

Other miscellaneous resources include

- `pep8checker`: pep8 checking scripts and git hook
- `theming`: demonstrates an alternative theme for kivy
- `travis`: travis continuous integration

This help document is a work-in-progress and currently under construction.

## 34.4 Packaging

This module contains [PyInstaller](#) hooks in order to assist in the process of building binary packages. PyInstaller allows you to produce stand-alone, self-contained executables of your Kivy app for Windows, Linux and Mac.

For more information, please see the [PyInstaller website](#)

### 34.4.1 Pyinstaller hooks

Module that exports pyinstaller related methods and parameters.

#### Hooks

PyInstaller comes with a default hook for kivy that lists the indirectly imported modules that pyinstaller would not find on its own using `get_deps_all()`. `hookspath()` returns the path to an alternate kivy hook, `kivy/tools/packaging/pyinstaller_hooks/kivy-hook.py` that does not add these dependencies to its list of hidden imports and they have to be explicitly included instead.

One can overwrite the default hook by providing on the command line the `--additional-hooks-dir=HOOKSPATH` option. Because although the default hook will still run, the [important global variables](#), e.g. `excludedimports` and `hiddenimports` will be overwritten by the new hook, if set there.

Additionally, one can add a hook to be run after the default hook by passing e.g. `hookspath=[HOOKSPATH]` to the `Analysis` class. In both cases, `HOOKSPATH` is the path to a directory containing a file named `hook-kivy.py` that is the pyinstaller hook for kivy to be processed after the default hook.

#### hiddenimports

When a module is imported indirectly, e.g. with `__import__`, pyinstaller won't know about it and the module has to be added through `hiddenimports`.

`hiddenimports` and other hook variables can be specified within a hook as described above. Also, these variable can be passed to `Analysis` and their values are then appended to the hook's values for these variables.

Most of kivy's core modules, e.g. `video` are imported indirectly and therefore need to be added in `hiddenimports`. The default PyInstaller hook adds all the providers. To overwrite, a modified kivy-hook similar to the default hook, such as `hookspath()` that only imports the desired modules can be added. One then uses `get_deps_minimal()` or `get_deps_all()` to get the list of modules and adds them manually in a modified hook or passes them to `Analysis` in the spec file.

## Hook generator

`pyinstaller_hooks` includes a tool to generate a hook which lists all the provider modules in a list so that one can manually comment out the providers not to be included. To use, do:

```
python -m kivy.tools.packaging.pyinstaller_hooks hook filename
```

`filename` is the name and path of the hook file to create. If `filename` is not provided the hook is printed to the terminal.

`kivy.tools.packaging.pyinstaller_hooks.add_dep_paths()`

Should be called by the hook. It adds the paths with the binary dependencies to the system path so that pyinstaller can find the binaries during its crawling stage.

`kivy.tools.packaging.pyinstaller_hooks.get_deps_all()`

Similar to `get_deps_minimal()`, but this returns all the kivy modules that can indirectly imported. Which includes all the possible kivy providers.

This can be used to get a list of all the possible providers which can then manually be included/excluded by commenting out elements in the list instead of passing on all the items. See module description.

### Returns

A dict with two keys, `hiddenimports` and `excludes`. Their values are a list of the corresponding modules to include/exclude. This can be passed directly to `Analysis'` with e.g.

```
a = Analysis(['..\kivy\examples\demo\touchtracer\main.py'],
             ...
             **get_deps_all())
```

`kivy.tools.packaging.pyinstaller_hooks.get_deps_minimal(exclude_ignored=True,`  
`**kwargs)`

Returns Kivy hidden modules as well as excluded modules to be used with `Analysis`.

The function takes core modules as keyword arguments and their value indicates which of the providers to include/exclude from the compiled app.

The possible keyword names are `audio`, `camera`, `clipboard`, `image`, `spelling`, `text`, `video`, and `window`. Their values can be:

**True: Include current provider** The providers imported when the core module is loaded on this system are added to hidden imports. This is the default if the keyword name is not specified.

**None: Exclude** Don't return this core module at all.

**A string or list of strings: Providers to include** Each string is the name of a provider for this module to be included.

For example, `get_deps_minimal(video=None, window=True, audio=['gstplayer', 'ffpyplayer'], spelling='enchant')` will exclude all the video providers, will include the gstreamer and ffpyplayer providers for audio, will include the enchant provider for spelling, and will use the current default provider for `window`.

`exclude_ignored`, if `True` (the default), if the value for a core library is `None`, then if `exclude_ignored` is `True`, not only will the library not be included in the `hiddenimports` but it'll also be added to the `excludedimports` to prevent it being included accidentally by pyinstaller.

### Returns

A dict with two keys, `hiddenimports` and `excludes`. Their values are a list of the corresponding modules to include/exclude. This can be passed directly to `Analysis`' with e.g.

```
a = Analysis(['..\\kivy\\examples\\demo\\touchtracer\\main.py'],
    ...
    hookspath=hookspath(),
    runtime_hooks=[],
    win_no_prefer_redirects=False,
    win_private_assemblies=False,
    cipher=block_cipher,
    **get_deps_minimal(video=None, audio=None))
```

`kivy.tools.packaging.pyinstaller_hooks.get_factory_modules()`

Returns a list of all the modules registered in the kivy factory.

`kivy.tools.packaging.pyinstaller_hooks.get_hooks()`

Returns the dict for the spec `hookspath` and `runtime_hooks` values.

`kivy.tools.packaging.pyinstaller_hooks.hookspath()`

Returns a list with the directory that contains the alternate (not the default included with pyinstaller) pyinstaller hook for kivy, `kivy/tools/packaging/pyinstaller_hooks/kivy-hook.py`. It is typically used with `hookspath=hookspath()` in the spec file.

The default pyinstaller hook returns all the core providers used using `get_deps_minimal()` to add to its list of hidden imports. This alternate hook only included the essential modules and leaves the core providers to be included additionally with `get_deps_minimal()` or `get_deps_all()`.

`kivy.tools.packaging.pyinstaller_hooks.runtime_hooks()`

Returns a list with the runtime hooks for kivy. It can be used with `runtime_hooks=runtime_hooks()` in the spec file. Pyinstaller comes preinstalled with this hook.

---

# Widgets

---

Widgets are elements of a graphical user interface that form part of the [User Experience](#). The `kivy.uix` module contains classes for creating and managing Widgets. Please refer to the [Widget class](#) documentation for further information.

Kivy widgets can be categorized as follows:

- **UX widgets:** Classical user interface widgets, ready to be assembled to create more complex widgets.  
*Label, Button, CheckBox, Image, Slider, Progress Bar, Text Input, Toggle button, Switch, Video*
  - **Layouts:** A layout widget does no rendering but just acts as a trigger that arranges its children in a specific way. Read more on [Layouts here](#).  
*Anchor Layout, Box Layout, Float Layout, GridLayout, PageLayout, RelativeLayout, Scatter Layout, Stack Layout*
  - **Complex UX widgets:** Non-atomic widgets that are the result of combining multiple classic widgets. We call them complex because their assembly and usage are not as generic as the classical widgets.  
*Bubble, Drop-Down List, FileChooser, Popup, Spinner, ListView, TabbedPanel, Video player, VKeyboard,*
  - **Behaviors widgets:** These widgets do no rendering but act on the graphics instructions or interaction (touch) behavior of their children.  
*Scatter, Stencil View*
  - **Screen manager:** Manages screens and transitions when switching from one to another.  
*Screen Manager*
- 

## 35.1 Behaviors

New in version 1.8.0.

### 35.1.1 Behavior mixin classes

This module implements behaviors that can be [mixed in](#) with existing base widgets. The idea behind these classes is to encapsulate properties and events associated with certain types of widgets.

Isolating these properties and events in a mixin class allows you to define your own implementation for standard kivy widgets that can act as drop-in replacements. This means you can re-style and re-define widgets as desired without breaking compatibility: as long as they implement the behaviors correctly, they can simply replace the standard widgets.

### 35.1.2 Adding behaviors

Say you want to add [Button](#) capabilities to an [Image](#), you could do:

```
class IconButton(ButtonBehavior, Image):  
    pass
```

This would give you an [Image](#) with the events and properties inherited from [ButtonBehavior](#). For example, the `on_press` and `on_release` events would be fired when appropriate:

```
class IconButton(ButtonBehavior, Image):  
    def on_press(self):  
        print("on_press")
```

Or in kv:

```
IconButton:  
    on_press: print('on_press')
```

Naturally, you could also bind to any property changes the behavior class offers:

```
def state_changed(*args):  
    print('state changed')  
  
button = IconButton()  
button.bind(state=state_changed)
```

---

**Note:** The behavior class must always be `_before_` the widget class. If you don't specify the inheritance in this order, the behavior will not work because the behavior methods are overwritten by the class method listed first.

Similarly, if you combine a behavior class with a class which requires the use of the methods also defined by the behavior class, the resulting class may not function properly. For example, when combining the [ButtonBehavior](#) with a [Slider](#), both of which use the `on_touch_up()` method, the resulting class may not work properly.

---

Changed in version 1.9.1: The individual behavior classes, previously in one big `behaviors.py` file, has been split into a single file for each class under the [behaviors](#) module. All the behaviors are still imported in the [behaviors](#) module so they are accessible as before (e.g. both `from kivy.uix.behaviors import ButtonBehavior` and `from kivy.uix.behaviors.button import ButtonBehavior` work).

```
class kivy.uix.behaviors.ButtonBehavior(**kwargs)  
Bases: object
```

This [mixin](#) class provides [Button](#) behavior. Please see the [button behaviors module](#) documentation for more information.

#### Events

`on_press` Fired when the button is pressed.

`on_release` Fired when the button is released (i.e. the touch/click that pressed the button goes away).

#### **trigger\_action(duration=0.1)**

Trigger whatever action(s) have been bound to the button by calling both the `on_press` and `on_release` callbacks.

This simulates a quick button press without using any touch events.

Duration is the length of the press in seconds. Pass 0 if you want the action to happen instantly.

New in version 1.8.0.

### **class kivy.uix.behaviors.ToggleButtonBehavior(\*\*kwargs)**

Bases: `kivy.uix.behaviors.button.ButtonBehavior`

This `mixin` class provides `togglebutton` behavior. Please see the [togglebutton behaviors module](#) documentation for more information.

New in version 1.8.0.

#### **static get\_widgets(groupname)**

Return a list of the widgets contained in a specific group. If the group doesn't exist, an empty list will be returned.

---

**Note:** Always release the result of this method! Holding a reference to any of these widgets can prevent them from being garbage collected. If in doubt, do:

```
l = ToggleButtonBehavior.get_widgets('mygroup')
# do your job
del l
```

---

**Warning:** It's possible that some widgets that you have previously deleted are still in the list. The garbage collector might need to release other objects before flushing them.

---

### **class kivy.uix.behaviors.DragBehavior(\*\*kwargs)**

Bases: `object`

The `DragBehavior` `mixin` provides Drag behavior. When combined with a widget, dragging in the rectangle defined by `drag_rectangle` will drag the widget. Please see the [drag behaviors module](#) documentation for more information.

New in version 1.8.0.

### **class kivy.uix.behaviors.FocusBehavior(\*\*kwargs)**

Bases: `object`

Provides keyboard focus behavior. When combined with other `FocusBehavior` widgets it allows one to cycle focus among them by pressing tab. Please see the [focus behavior module documentation](#) for more information.

New in version 1.9.0.

#### **get\_focus\_next()**

Returns the next focusable widget using either `focus_next` or the `children` similar to the order when tabbing forwards with the `tab` key.

**get\_focus\_previous()**

Returns the previous focusable widget using either `focus_previous` or the `children` similar to the order when `tab + shift` key are triggered together.

**hide\_keyboard()**

Convenience function to hide the keyboard in managed mode.

**keyboard\_on\_key\_down(*window, keycode, text, modifiers*)**

The method bound to the keyboard when the instance has focus.

When the instance becomes focused, this method is bound to the keyboard and will be called for every input press. The parameters are the same as `kivy.core.window.WindowBase.on_key_down()`.

When overwriting the method in the derived widget, super should be called to enable tab cycling. If the derived widget wishes to use tab for its own purposes, it can call super after it has processed the character (if it does not wish to consume the tab).

Similar to other keyboard functions, it should return True if the key was consumed.

**keyboard\_on\_key\_up(*window, keycode*)**

The method bound to the keyboard when the instance has focus.

When the instance becomes focused, this method is bound to the keyboard and will be called for every input release. The parameters are the same as `kivy.core.window.WindowBase.on_key_up()`.

When overwriting the method in the derived widget, super should be called to enable defocusing on escape. If the derived widget wishes to use escape for its own purposes, it can call super after it has processed the character (if it does not wish to consume the escape).

See `keyboard_on_key_down()`

**show\_keyboard()**

Convenience function to show the keyboard in managed mode.

**class kivy.uix.behaviors.CompoundSelectionBehavior(\*\*kwargs)**

Bases: `object`

The Selection behavior `mixin` implements the logic behind keyboard and touch selection of selectable widgets managed by the derived widget. Please see the [compound selection behaviors module](#) documentation for more information.

New in version 1.9.0.

**clear\_selection()**

Deselects all the currently selected nodes.

**deselect\_node(*node*)**

Deselects a possibly selected node.

It is called by the controller when it deselects a node and can also be called from the outside to deselect a node directly. The derived widget should overwrite this method and change the node to its unselected state when this is called

**Parameters**

*node* The node to be deselected.

**Warning:** This method must be called by the derived widget using super if it is overwritten.

**get\_index\_of\_node(*node*, *selectable\_nodes*)**

(internal) Returns the index of the *node* within the *selectable\_nodes* returned by [get\\_selectable\\_nodes\(\)](#).

**get\_selectable\_nodes()**

(internal) Returns a list of the nodes that can be selected. It can be overwritten by the derived widget to return the correct list.

This list is used to determine which nodes to select with group selection. E.g. the last element in the list will be selected when home is pressed, pagedown will move (or add to, if shift is held) the selection from the current position by negative `page_count` nodes starting from the position of the currently selected node in this list and so on. Still, nodes can be selected even if they are not in this list.

---

**Note:** It is safe to dynamically change this list including removing, adding, or re-arranging its elements. Nodes can be selected even if they are not on this list. And selected nodes removed from the list will remain selected until [deselect\\_node\(\)](#) is called.

---

**Warning:** Layouts display their children in the reverse order. That is, the contents of [children](#) is displayed from right to left, bottom to top. Therefore, internally, the indices of the elements returned by this function are reversed to make it work by default for most layouts so that the final result is consistent e.g. home, although it will select the last element in this list visually, will select the first element when counting from top to bottom and left to right. If this behavior is not desired, a reversed list should be returned instead.

Defaults to returning [children](#).

**goto\_node(*key*, *last\_node*, *last\_node\_idx*)**

(internal) Used by the controller to get the node at the position indicated by *key*. The *key* can be keyboard inputs, e.g. pageup, or scroll inputs from the mouse scroll wheel, e.g. scrollup. '*last\_node*' is the last node selected and is used to find the resulting node. For example, if the key is up, the returned node is one node up from the last node.

It can be overwritten by the derived widget.

**Parameters**

*key* str, the string used to find the desired node. It can be any of the keyboard keys, as well as the mouse scrollup, scrolldown, scrollright, and scrollleft strings. If letters are typed in quick succession, the letters will be combined before it's passed in as *key* and can be used to find nodes that have an associated string that starts with those letters.

*last\_node* The last node that was selected.

*last\_node\_idx* The cached index of the last node selected in the [get\\_selectable\\_nodes\(\)](#) list. If the list hasn't changed it saves having to look up the index of *last\_node* in that list.

**Returns** tuple, the node targeted by *key* and its index in the [get\\_selectable\\_nodes\(\)](#) list. Returning (*last\_node*, *last\_node\_idx*) indicates a node wasn't found.

**select\_node(*node*)**

Selects a node.

It is called by the controller when it selects a node and can be called from the outside to select a node directly. The derived widget should overwrite this method and change the node state

to selected when called.

#### Parameters

*node* The node to be selected.

**Returns** bool, True if the node was selected, False otherwise.

**Warning:** This method must be called by the derived widget using super if it is overwritten.

**select\_with\_key\_down**(*keyboard*, *scancode*, *codepoint*, *modifiers*, *\*\*kwargs*)

Processes a key press. This is called when a key press is to be used for selection. Depending on the keyboard keys pressed and the configuration, it could select or deselect nodes or node ranges from the selectable nodes list, [get\\_selectable\\_nodes\(\)](#).

The parameters are such that it could be bound directly to the on\_key\_down event of a keyboard. Therefore, it is safe to be called repeatedly when the key is held down as is done by the keyboard.

**Returns** bool, True if the keypress was used, False otherwise.

**select\_with\_key\_up**(*keyboard*, *scancode*, *\*\*kwargs*)

(internal) Processes a key release. This must be called by the derived widget when a key that [select\\_with\\_key\\_down\(\)](#) returned True is released.

The parameters are such that it could be bound directly to the on\_key\_up event of a keyboard.

**Returns** bool, True if the key release was used, False otherwise.

**select\_with\_touch**(*node*, *touch=None*)

(internal) Processes a touch on the node. This should be called by the derived widget when a node is touched and is to be used for selection. Depending on the keyboard keys pressed and the configuration, it could select or deselect this and other nodes in the selectable nodes list, [get\\_selectable\\_nodes\(\)](#).

#### Parameters

*node* The node that received the touch. Can be None for a scroll type touch.

*touch* Optionally, the touch. Defaults to None.

**Returns** bool, True if the touch was used, False otherwise.

**class kivy.ux.behaviors.CodeNavigationBehavior**

Bases: [kivy.event.EventDispatcher](#)

Code navigation behavior. Modifies the navigation behavior in TextInput to work like an IDE instead of a word processor. Please see the [code navigation behaviors module](#) documentation for more information.

New in version 1.9.1.

**class kivy.ux.behaviors.EmacsBehavior(\*\*kwargs)**

Bases: object

A mixin that enables Emacs-style keyboard shortcuts for the [TextInput](#) widget. Please see the [Emacs behaviors module](#) documentation for more information.

New in version 1.9.1.

**delete\_word\_left()**

Delete text left of the cursor to the beginning of word

### `delete_word_right()`

Delete text right of the cursor to the end of the word

## `class kivy.uix.behaviors.CoverBehavior(**kwargs)`

Bases: `object`

The CoverBehavior `mixin` provides rendering a texture covering full widget size keeping aspect ratio of the original texture.

New in version 1.10.0.

## `class kivy.uix.behaviors.TouchRippleBehavior(**kwargs)`

Bases: `object`

Touch ripple behavior.

Supposed to be used as mixin on widget classes.

Ripple behavior does not trigger automatically, concrete implementation needs to call `ripple_show()` respective `ripple_fade()` manually.

Here we create a Label which renders the touch ripple animation on interaction:

```
class RippleLabel(TouchRippleBehavior, Label):

    def __init__(self, **kwargs):
        super(RippleLabel, self).__init__(**kwargs)

    def on_touch_down(self, touch):
        collide_point = self.collide_point(touch.x, touch.y)
        if collide_point:
            touch.grab(self)
            self.ripple_show(touch)
            return True
        return False

    def on_touch_up(self, touch):
        if touch.grab_current is self:
            touch.ungrab(self)
            self.ripple_fade()
            return True
        return False
```

### `ripple_fade()`

Finish ripple animation on current widget.

### `ripple_show(touch)`

Begin ripple animation on current widget.

Expects touch event as argument.

## `class kivy.uix.behaviors.TouchRippleButtonBehavior(**kwargs)`

Bases: `kivy.uix.behaviors.touchripple.TouchRippleBehavior`

This `mixin` class provides a similar behavior to `ButtonBehavior` but provides touch ripple animation instead of button pressed/released as visual effect.

### Events

`on_press` Fired when the button is pressed.

`on_release` Fired when the button is released (i.e. the touch/click that pressed the button goes away).

### 35.1.3 Button Behavior

The `ButtonBehavior` mixin class provides `Button` behavior. You can combine this class with other widgets, such as an `Image`, to provide alternative buttons that preserve Kivy button behavior.

For an overview of behaviors, please refer to the [behaviors](#) documentation.

#### Example

The following example adds button behavior to an image to make a checkbox that behaves like a button:

```
from kivy.app import App
from kivy.uix.image import Image
from kivy.uix.behaviors import ButtonBehavior

class MyButton(ButtonBehavior, Image):
    def __init__(self, **kwargs):
        super(MyButton, self).__init__(**kwargs)
        self.source = 'atlas://data/images/defaulttheme/checkbox_off'

    def on_press(self):
        self.source = 'atlas://data/images/defaulttheme/checkbox_on'

    def on_release(self):
        self.source = 'atlas://data/images/defaulttheme/checkbox_off'

class SampleApp(App):
    def build(self):
        return MyButton()

SampleApp().run()
```

See [ButtonBehavior](#) for details.

```
class kivy.uix.behaviors.button.ButtonBehavior(**kwargs)
Bases: object
```

This mixin class provides `Button` behavior. Please see the [button behaviors module](#) documentation for more information.

#### Events

`on_press` Fired when the button is pressed.

`on_release` Fired when the button is released (i.e. the touch/click that pressed the button goes away).

#### always\_release

This determines whether or not the widget fires an `on_release` event if the touch\_up is outside the widget.

New in version 1.9.0.

Changed in version 1.10.0: The default value is now False.

`always_release` is a `BooleanProperty` and defaults to `False`.

#### last\_touch

Contains the last relevant touch received by the Button. This can be used in `on_press` or `on_release` in order to know which touch dispatched the event.

New in version 1.8.0.

`last_touch` is a *ObjectProperty* and defaults to *None*.

#### **min\_state\_time**

The minimum period of time which the widget must remain in the ‘down’ state.

New in version 1.9.1.

`min_state_time` is a float and defaults to 0.035. This value is taken from *Config*.

#### **state**

The state of the button, must be one of ‘normal’ or ‘down’. The state is ‘down’ only when the button is currently touched(clicked, otherwise its ‘normal’).

`state` is an *OptionProperty* and defaults to ‘normal’.

#### **trigger\_action(duration=0.1)**

Trigger whatever action(s) have been bound to the button by calling both the `on_press` and `on_release` callbacks.

This simulates a quick button press without using any touch events.

Duration is the length of the press in seconds. Pass 0 if you want the action to happen instantly.

New in version 1.8.0.

### 35.1.4 Code Navigation Behavior

The `CodeNavigationBehavior` modifies navigation behavior in the `TextInput`, making it work like an IDE instead of a word processor.

Using this mixin gives the `TextInput` the ability to recognize whitespace, punctuation and case variations (e.g. CamelCase) when moving over text. It is currently used by the `CodeInput` widget.

#### **class kivy.ux.behaviors.codenavigation.CodeNavigationBehavior**

Bases: `kivy.event.EventDispatcher`

Code navigation behavior. Modifies the navigation behavior in `TextInput` to work like an IDE instead of a word processor. Please see the `code navigation behaviors module` documentation for more information.

New in version 1.9.1.

### 35.1.5 Compound Selection Behavior

The `CompoundSelectionBehavior` mixin class implements the logic behind keyboard and touch selection of selectable widgets managed by the derived widget. For example, it can be combined with a `GridLayout` to add selection to the layout.

#### Compound selection concepts

At its core, it keeps a dynamic list of widgets that can be selected. Then, as the touches and keyboard input are passed in, it selects one or more of the widgets based on these inputs. For example, it uses the mouse scroll and keyboard up/down buttons to scroll through the list of widgets. Multiselection can also be achieved using the keyboard shift and ctrl keys.

Finally, in addition to the up/down type keyboard inputs, compound selection can also accept letters from the keyboard to be used to select nodes with associated strings that start with those letters, similar to how files are selected by a file browser.

## Selection mechanics

When the controller needs to select a node, it calls `select_node()` and `deselect_node()`. Therefore, they must be overwritten in order alter node selection. By default, the class doesn't listen for keyboard or touch events, so the derived widget must call `select_with_touch()`, `select_with_key_down()`, and `select_with_key_up()` on events that it wants to pass on for selection purposes.

### Example

To add selection to a grid layout which will contain Button widgets. For each button added to the layout, you need to bind the `on_touch_down` of the button to `select_with_touch()` to pass on the touch events:

```
from kivy.uix.behaviors.compoundselection import CompoundSelectionBehavior
from kivy.uix.button import Button
from kivy.uix.gridlayout import GridLayout
from kivy.uix.behaviors import FocusBehavior
from kivy.core.window import Window
from kivy.app import App

class SelectableGrid(FocusBehavior, CompoundSelectionBehavior, GridLayout):

    def keyboard_on_key_down(self, window, keycode, text, modifiers):
        """Based on FocusBehavior that provides automatic keyboard
        access, key presses will be used to select children.
        """
        if super>SelectableGrid, self).keyboard_on_key_down(
            window, keycode, text, modifiers):
            return True
        if self.select_with_key_down(window, keycode, text, modifiers):
            return True
        return False

    def keyboard_on_key_up(self, window, keycode):
        """Based on FocusBehavior that provides automatic keyboard
        access, key release will be used to select children.
        """
        if super>SelectableGrid, self).keyboard_on_key_up(window, keycode):
            return True
        if self.select_with_key_up(window, keycode):
            return True
        return False

    def add_widget(self, widget):
        """Override the adding of widgets so we can bind and catch their
        *on_touch_down* events. """
        widget.bind(on_touch_down=self.button_touch_down,
                   on_touch_up=self.button_touch_up)
        return super>SelectableGrid, self).add_widget(widget)

    def button_touch_down(self, button, touch):
        """Use collision detection to select buttons when the touch occurs
        within their area. """
        if button.collide_point(*touch.pos):
            self.select_with_touch(button, touch)

    def button_touch_up(self, button, touch):
```

```

""" Use collision detection to de-select buttons when the touch
occurs outside their area and *touch_multiselect* is not True. """
if not (button.collide_point(*touch.pos) or
        self.touch_multiselect):
    self.deselect_node(button)

def select_node(self, node):
    node.background_color = (1, 0, 0, 1)
    return super(SelectableGrid, self).select_node(node)

def deselect_node(self, node):
    node.background_color = (1, 1, 1, 1)
    super(SelectableGrid, self).deselect_node(node)

def on_selected_nodes(self, grid, nodes):
    print("Selected nodes = {}".format(nodes))

class TestApp(App):
    def build(self):
        grid = SelectableGrid(cols=3, rows=2, touch_multiselect=True,
                              multiselect=True)
        for i in range(0, 6):
            grid.add_widget(Button(text="Button {}".format(i)))
        return grid

TestApp().run()

```

**Warning:** This code is still experimental, and its API is subject to change in a future version.

**class kivy.uix.behaviors.compoundselection.CompoundSelectionBehavior(\*\*kwargs)**  
Bases: object

The Selection behavior `mixin` implements the logic behind keyboard and touch selection of selectable widgets managed by the derived widget. Please see the [compound selection behaviors module](#) documentation for more information.

New in version 1.9.0.

**clear\_selection()**

Deselects all the currently selected nodes.

**deselect\_node(node)**

Deselects a possibly selected node.

It is called by the controller when it deselects a node and can also be called from the outside to deselect a node directly. The derived widget should overwrite this method and change the node to its unselected state when this is called

#### Parameters

*node* The node to be deselected.

**Warning:** This method must be called by the derived widget using `super` if it is overwritten.

**get\_index\_of\_node(*node*, *selectable\_nodes*)**

(internal) Returns the index of the *node* within the *selectable\_nodes* returned by [get\\_selectable\\_nodes\(\)](#).

**get\_selectable\_nodes()**

(internal) Returns a list of the nodes that can be selected. It can be overwritten by the derived widget to return the correct list.

This list is used to determine which nodes to select with group selection. E.g. the last element in the list will be selected when home is pressed, pagedown will move (or add to, if shift is held) the selection from the current position by negative [page\\_count](#) nodes starting from the position of the currently selected node in this list and so on. Still, nodes can be selected even if they are not in this list.

---

**Note:** It is safe to dynamically change this list including removing, adding, or re-arranging its elements. Nodes can be selected even if they are not on this list. And selected nodes removed from the list will remain selected until [deselect\\_node\(\)](#) is called.

---

**Warning:** Layouts display their children in the reverse order. That is, the contents of [children](#) is displayed from right to left, bottom to top. Therefore, internally, the indices of the elements returned by this function are reversed to make it work by default for most layouts so that the final result is consistent e.g. home, although it will select the last element in this list visually, will select the first element when counting from top to bottom and left to right. If this behavior is not desired, a reversed list should be returned instead.

Defaults to returning [children](#).

**goto\_node(*key*, *last\_node*, *last\_node\_idx*)**

(internal) Used by the controller to get the node at the position indicated by *key*. The *key* can be keyboard inputs, e.g. pageup, or scroll inputs from the mouse scroll wheel, e.g. scrollup. '*last\_node*' is the last node selected and is used to find the resulting node. For example, if the key is up, the returned node is one node up from the last node.

It can be overwritten by the derived widget.

**Parameters**

*key* str, the string used to find the desired node. It can be any of the keyboard keys, as well as the mouse scrollup, scrolldown, scrollright, and scrollleft strings. If letters are typed in quick succession, the letters will be combined before it's passed in as *key* and can be used to find nodes that have an associated string that starts with those letters.

*last\_node* The last node that was selected.

*last\_node\_idx* The cached index of the last node selected in the [get\\_selectable\\_nodes\(\)](#) list. If the list hasn't changed it saves having to look up the index of *last\_node* in that list.

**Returns** tuple, the node targeted by *key* and its index in the [get\\_selectable\\_nodes\(\)](#) list. Returning (*last\_node*, *last\_node\_idx*) indicates a node wasn't found.

**keyboard\_select**

Determines whether the keyboard can be used for selection. If False, keyboard inputs will be ignored.

[keyboard\\_select](#) is a [BooleanProperty](#) and defaults to True.

### **multiselect**

Determines whether multiple nodes can be selected. If enabled, keyboard shift and ctrl selection, optionally combined with touch, for example, will be able to select multiple widgets in the normally expected manner. This dominates `touch_multiselect` when False.

`multiselect` is a *BooleanProperty* and defaults to False.

### **nodes\_order\_reversed**

(Internal) Indicates whether the order of the nodes as displayed top- down is reversed compared to their order in `get_selectable_nodes()` (e.g. how the children property is reversed compared to how it's displayed).

### **page\_count**

Determines by how much the selected node is moved up or down, relative to the position of the last selected node, when pageup (or pagedown) is pressed.

`page_count` is a *NumericProperty* and defaults to 10.

### **right\_count**

Determines by how much the selected node is moved up or down, relative to the position of the last selected node, when the right (or left) arrow on the keyboard is pressed.

`right_count` is a *NumericProperty* and defaults to 1.

### **scroll\_count**

Determines by how much the selected node is moved up or down, relative to the position of the last selected node, when the mouse scroll wheel is scrolled.

`right_count` is a *NumericProperty* and defaults to 0.

### **select\_node(node)**

Selects a node.

It is called by the controller when it selects a node and can be called from the outside to select a node directly. The derived widget should overwrite this method and change the node state to selected when called.

#### **Parameters**

`node` The node to be selected.

**Returns** bool, True if the node was selected, False otherwise.

**Warning:** This method must be called by the derived widget using super if it is overwritten.

### **select\_with\_key\_down(keyboard, scancode, codepoint, modifiers, \*\*kwargs)**

Processes a key press. This is called when a key press is to be used for selection. Depending on the keyboard keys pressed and the configuration, it could select or deselect nodes or node ranges from the selectable nodes list, `get_selectable_nodes()`.

The parameters are such that it could be bound directly to the on\_key\_down event of a keyboard. Therefore, it is safe to be called repeatedly when the key is held down as is done by the keyboard.

**Returns** bool, True if the keypress was used, False otherwise.

### **select\_with\_key\_up(keyboard, scancode, \*\*kwargs)**

(internal) Processes a key release. This must be called by the derived widget when a key that `select_with_key_down()` returned True is released.

The parameters are such that it could be bound directly to the on\_key\_up event of a keyboard.

**Returns** bool, True if the key release was used, False otherwise.

#### **select\_with\_touch(node, touch=None)**

(internal) Processes a touch on the node. This should be called by the derived widget when a node is touched and is to be used for selection. Depending on the keyboard keys pressed and the configuration, it could select or deselect this and other nodes in the selectable nodes list, [get\\_selectable\\_nodes\(\)](#).

#### **Parameters**

*node* The node that received the touch. Can be None for a scroll type touch.

*touch* Optionally, the touch. Defaults to None.

**Returns** bool, True if the touch was used, False otherwise.

#### **selected\_nodes**

The list of selected nodes.

---

**Note:** Multiple nodes can be selected right after one another e.g. using the keyboard. When listening to [selected\\_nodes](#), one should be aware of this.

---

[selected\\_nodes](#) is a *ListProperty* and defaults to the empty list, []. It is read-only and should not be modified.

#### **text\_entry\_timeout**

When typing characters in rapid succession (i.e. the time difference since the last character is less than [text\\_entry\\_timeout](#)), the keys get concatenated and the combined text is passed as the key argument of [goto\\_node\(\)](#).

New in version 1.10.0.

#### **touch\_deselect\_last**

Determines whether the last selected node can be deselected when [multiselect](#) or [touch\\_multiselect](#) is False.

New in version 1.10.0.

[touch\\_deselect\\_last](#) is a *BooleanProperty* and defaults to True on mobile, False on desktop platforms.

#### **touch\_multiselect**

A special touch mode which determines whether touch events, as processed by [select\\_with\\_touch\(\)](#), will add the currently touched node to the selection, or if it will clear the selection before adding the node. This allows the selection of multiple nodes by simply touching them.

This is different from [multiselect](#) because when it is True, simply touching an unselected node will select it, even if ctrl is not pressed. If it is False, however, ctrl must be pressed in order to add to the selection when [multiselect](#) is True.

---

**Note:** [multiselect](#), when False, will disable [touch\\_multiselect](#).

---

[touch\\_multiselect](#) is a *BooleanProperty* and defaults to False.

#### **up\_count**

Determines by how much the selected node is moved up or down, relative to the position of the last selected node, when the up (or down) arrow on the keyboard is pressed.

[up\\_count](#) is a *NumericProperty* and defaults to 1.

### 35.1.6 Cover Behavior

The `CoverBehavior` mixin is intended for rendering textures to full widget size keeping the aspect ratio of the original texture.

Use cases are i.e. rendering full size background images or video content in a dynamic layout.

For an overview of behaviors, please refer to the [behaviors](#) documentation.

#### Example

The following examples add cover behavior to an image:

In python:

```
from kivy.app import App
from kivy.uix.behaviors import CoverBehavior
from kivy.uix.image import Image

class CoverImage(CoverBehavior, Image):

    def __init__(self, **kwargs):
        super(CoverImage, self).__init__(**kwargs)
        texture = self._coreimage.texture
        self.reference_size = texture.size
        self.texture = texture

class MainApp(App):

    def build(self):
        return CoverImage(source='image.jpg')

MainApp().run()
```

In Kivy Language:

```
CoverImage:
    source: 'image.png'

<CoverImage@CoverBehavior+Image>:
    reference_size: self.texture_size
```

See `CoverBehavior` for details.

```
class kivy.uix.behaviors.cover.CoverBehavior(**kwargs)
Bases: object
```

The CoverBehavior mixin provides rendering a texture covering full widget size keeping aspect ratio of the original texture.

New in version 1.10.0.

#### cover\_pos

Position of the aspect ratio aware texture. Gets calculated in `CoverBehavior.calculate_cover`.

`cover_pos` is a [ListProperty](#) and defaults to [0, 0].

**cover\_size**

Size of the aspect ratio aware texture. Gets calculated in CoverBehavior.  
calculate\_cover.

*cover\_size* is a *ListProperty* and defaults to [0, 0].

**reference\_size**

Reference size used for aspect ratio approximation calculation.

*reference\_size* is a *ListProperty* and defaults to [].

### 35.1.7 Drag Behavior

The *DragBehavior* mixin class provides Drag behavior. When combined with a widget, dragging in the rectangle defined by the *drag\_rectangle* will drag the widget.

#### Example

The following example creates a draggable label:

```
from kivy.uix.label import Label
from kivy.app import App
from kivy.uix.behaviors import DragBehavior
from kivy.lang import Builder

# You could also put the following in your kv file...
kv = '''
<DragLabel>:
    # Define the properties for the DragLabel
    drag_rectangle: self.x, self.y, self.width, self.height
    drag_timeout: 10000000
    drag_distance: 0

FloatLayout:
    # Define the root widget
    DragLabel:
        size_hint: 0.25, 0.2
        text: 'Drag me'
    ...

class DragLabel(DragBehavior, Label):
    pass

class TestApp(App):
    def build(self):
        return Builder.load_string(kv)

TestApp().run()
```

```
class kivy.uix.behaviors.drag.DragBehavior(**kwargs)
Bases: object
```

The DragBehavior mixin provides Drag behavior. When combined with a widget, dragging in the rectangle defined by *drag\_rectangle* will drag the widget. Please see the *drag behaviors module* documentation for more information.

New in version 1.8.0.

### **drag\_distance**

Distance to move before dragging the *DragBehavior*, in pixels. As soon as the distance has been traveled, the *DragBehavior* will start to drag, and no touch event will be dispatched to the children. It is advisable that you base this value on the dpi of your target device's screen.

*drag\_distance* is a *NumericProperty* and defaults to the *scroll\_distance* as defined in the user *Config* (20 pixels by default).

### **drag\_rect\_height**

Height of the axis aligned bounding rectangle where dragging is allowed.

*drag\_rect\_height* is a *NumericProperty* and defaults to 100.

### **drag\_rect\_width**

Width of the axis aligned bounding rectangle where dragging is allowed.

*drag\_rect\_width* is a *NumericProperty* and defaults to 100.

### **drag\_rect\_x**

X position of the axis aligned bounding rectangle where dragging is allowed (in window coordinates).

*drag\_rect\_x* is a *NumericProperty* and defaults to 0.

### **drag\_rect\_y**

Y position of the axis aligned bounding rectangle where dragging is allowed (in window coordinates).

*drag\_rect\_y* is a *NumericProperty* and defaults to 0.

### **drag\_rectangle**

Position and size of the axis aligned bounding rectangle where dragging is allowed.

*drag\_rectangle* is a *ReferenceListProperty* of (*drag\_rect\_x*, *drag\_rect\_y*, *drag\_rect\_width*, *drag\_rect\_height*) properties.

### **drag\_timeout**

Timeout allowed to trigger the *drag\_distance*, in milliseconds. If the user has not moved *drag\_distance* within the timeout, dragging will be disabled, and the touch event will be dispatched to the children.

*drag\_timeout* is a *NumericProperty* and defaults to the *scroll\_timeout* as defined in the user *Config* (55 milliseconds by default).

## 35.1.8 Emacs Behavior

The *EmacsBehavior* mixin allows you to add *Emacs* keyboard shortcuts for basic movement and editing to the *TextInput* widget. The shortcuts currently available are listed below:

## Emacs shortcuts

Shortcut	Description
Control + a	Move cursor to the beginning of the line
Control + e	Move cursor to the end of the line
Control + f	Move cursor one character to the right
Control + b	Move cursor one character to the left
Alt + f	Move cursor to the end of the word to the right
Alt + b	Move cursor to the start of the word to the left
Alt + Backspace	Delete text left of the cursor to the beginning of word
Alt + d	Delete text right of the cursor to the end of the word
Alt + w	Copy selection
Control + w	Cut selection
Control + y	Paste selection

**Warning:** If you have the `inspector` module enabled, the shortcut for opening the inspector (Control + e) conflicts with the Emacs shortcut to move to the end of the line (it will still move the cursor to the end of the line, but the inspector will open as well).

`class kivy.uix.behaviors.emacs.EmacsBehavior(**kwargs)`  
Bases: `object`

A `mixin` that enables Emacs-style keyboard shortcuts for the `TextInput` widget. Please see the [Emacs behaviors module](#) documentation for more information.

New in version 1.9.1.

`delete_word_left()`

Delete text left of the cursor to the beginning of word

`delete_word_right()`

Delete text right of the cursor to the end of the word

`key_bindings`

String name which determines the type of key bindings to use with the `TextInput`. This allows Emacs key bindings to be enabled/disabled programmatically for widgets that inherit from `EmacsBehavior`. If the value is not 'emacs', Emacs bindings will be disabled. Use 'default' for switching to the default key bindings of `TextInput`.

`key_bindings` is a `StringProperty` and defaults to 'emacs'.

New in version 1.10.0.

### 35.1.9 Focus Behavior

The `FocusBehavior` mixin class provides keyboard focus behavior. When combined with other FocusBehavior widgets it allows one to cycle focus among them by pressing tab. In addition, upon gaining focus, the instance will automatically receive keyboard input.

Focus, very different from selection, is intimately tied with the keyboard; each keyboard can focus on zero or one widgets, and each widget can only have the focus of one keyboard. However, multiple keyboards can focus simultaneously on different widgets. When escape is hit, the widget having the focus of that keyboard will de-focus.

## Managing focus

In essence, focus is implemented as a doubly linked list, where each node holds a (weak) reference to the instance before it and after it, as visualized when cycling through the nodes using tab (forward) or shift+tab (backward). If a previous or next widget is not specified, `focus_next` and `focus_previous` defaults to `None`. This means that the `children` list and `parents` are walked to find the next focusable widget, unless `focus_next` or `focus_previous` is set to the `StopIteration` class, in which case focus stops there.

For example, to cycle focus between `Button` elements of a `GridLayout`:

```
class FocusButton(FocusBehavior, Button):
    pass

grid = GridLayout(cols=4)
for i in range(40):
    grid.add_widget(FocusButton(text=str(i)))
# clicking on a widget will activate focus, and tab can now be used
# to cycle through
```

When using a software keyboard, typical on mobile and touch devices, the keyboard display behavior is determined by the `softinput_mode` property. You can use this property to ensure the focused widget is not covered or obscured by the keyboard.

## Initializing focus

Widgets needs to be visible before they can receive the focus. This means that setting their `focus` property to True before they are visible will have no effect. To initialize focus, you can use the 'on\_parent' event:

```
from kivy.app import App
from kivy.uix.textinput import TextInput

class MyTextInput(TextInput):
    def on_parent(self, widget, parent):
        self.focus = True

class SampleApp(App):
    def build(self):
        return MyTextInput()

SampleApp().run()
```

If you are using a `popup`, you can use the 'on\_open' event.

For an overview of behaviors, please refer to the [behaviors](#) documentation.

**Warning:** This code is still experimental, and its API is subject to change in a future version.

```
class kivy.uix.behaviors.focus.FocusBehavior(**kwargs)
Bases: object
```

Provides keyboard focus behavior. When combined with other FocusBehavior widgets it allows one to cycle focus among them by pressing tab. Please see the [focus behavior module documentation](#) for more information.

New in version 1.9.0.

## **focus**

Whether the instance currently has focus.

Setting it to True will bind to and/or request the keyboard, and input will be forwarded to the instance. Setting it to False will unbind and/or release the keyboard. For a given keyboard, only one widget can have its focus, so focusing one will automatically unfocus the other instance holding its focus.

When using a software keyboard, please refer to the *softinput\_mode* property to determine how the keyboard display is handled.

*focus* is a *BooleanProperty* and defaults to False.

## **focus\_next**

The *FocusBehavior* instance to acquire focus when tab is pressed and this instance has focus, if not *None* or *StopIteration*.

When tab is pressed, focus cycles through all the *FocusBehavior* widgets that are linked through *focus\_next* and are focusable. If *focus\_next* is *None*, it instead walks the children lists to find the next focusable widget. Finally, if *focus\_next* is the *StopIteration* class, focus won't move forward, but end here.

*focus\_next* is an *ObjectProperty* and defaults to *None*.

## **focus\_previous**

The *FocusBehavior* instance to acquire focus when shift+tab is pressed on this instance, if not *None* or *StopIteration*.

When shift+tab is pressed, focus cycles through all the *FocusBehavior* widgets that are linked through *focus\_previous* and are focusable. If *focus\_previous* is *None*, it instead walks the children tree to find the previous focusable widget. Finally, if *focus\_previous* is the *StopIteration* class, focus won't move backward, but end here.

*focus\_previous* is an *ObjectProperty* and defaults to *None*.

## **focused**

An alias of *focus*.

*focused* is a *BooleanProperty* and defaults to False.

**Warning:** *focused* is an alias of *focus* and will be removed in 2.0.0.

## **get\_focus\_next()**

Returns the next focusable widget using either *focus\_next* or the *children* similar to the order when tabbing forwards with the *tab* key.

## **get\_focus\_previous()**

Returns the previous focusable widget using either *focus\_previous* or the *children* similar to the order when *tab + shift* key are triggered together.

## **hide\_keyboard()**

Convenience function to hide the keyboard in managed mode.

## **ignored\_touch = []**

A list of touches that should not be used to defocus. After *on\_touch\_up*, every touch that is not in *ignored\_touch* will defocus all the focused widgets if the config keyboard mode is not multi. Touches on focusable widgets that were used to focus are automatically added here.

Example usage:

```

class Unfocusable(Widget):
    def on_touch_down(self, touch):
        if self.collide_point(*touch.pos):
            FocusBehavior.ignored_touch.append(touch)

```

Notice that you need to access this as a class, not an instance variable.

### **input\_type**

The kind of input keyboard to request.

New in version 1.8.0.

*input\_type* is an **OptionsProperty** and defaults to ‘text’. Can be one of ‘text’, ‘number’, ‘url’, ‘mail’, ‘datetime’, ‘tel’ or ‘address’.

### **is\_focusable**

Whether the instance can become focused. If focused, it’ll lose focus when set to False.

*is\_focusable* is a **BooleanProperty** and defaults to True on a desktop (i.e. *desktop* is True in *config*), False otherwise.

### **keyboard**

The keyboard to bind to (or bound to the widget) when focused.

When None, a keyboard is requested and released whenever the widget comes into and out of focus. If not None, it must be a keyboard, which gets bound and unbound from the widget whenever it’s in or out of focus. It is useful only when more than one keyboard is available, so it is recommended to be set to None when only one keyboard is available.

If more than one keyboard is available, whenever an instance gets focused a new keyboard will be requested if None. Unless the other instances lose focus (e.g. if tab was used), a new keyboard will appear. When this is undesired, the keyboard property can be used. For example, if there are two users with two keyboards, then each keyboard can be assigned to different groups of instances of FocusBehavior, ensuring that within each group, only one FocusBehavior will have focus, and will receive input from the correct keyboard. See *keyboard\_mode* in *config* for more information on the keyboard modes.

### Keyboard and focus behavior

When using the keyboard, there are some important default behaviors you should keep in mind.

- When Config’s *keyboard\_mode* is multi, each new touch is considered a touch by a different user and will set the focus (if clicked on a focusable) with a new keyboard. Already focused elements will not lose their focus (even if an unfocusable widget is touched).
- If the keyboard property is set, that keyboard will be used when the instance gets focused. If widgets with different keyboards are linked through *focus\_next* and *focus\_previous*, then as they are tabbed through, different keyboards will become active. Therefore, typically it’s undesirable to link instances which are assigned different keyboards.
- When a widget has focus, setting its keyboard to None will remove its keyboard, but the widget will then immediately try to get another keyboard. In order to remove its keyboard, rather set its *focus* to False.
- When using a software keyboard, typical on mobile and touch devices, the keyboard display behavior is determined by the *softinput\_mode* property. You can use this property to ensure the focused widget is not covered or obscured.

*keyboard* is an **AliasProperty** and defaults to None.

### **keyboard\_mode**

Determines how the keyboard visibility should be managed. ‘auto’ will result in the standard behaviour of showing/hiding on focus. ‘managed’ requires setting the keyboard visibility manually, or calling the helper functions `show_keyboard()` and `hide_keyboard()`.

`keyboard_mode` is an `OptionsProperty` and defaults to ‘auto’. Can be one of ‘auto’ or ‘managed’.

### **keyboard\_on\_key\_down** (*window, keycode, text, modifiers*)

The method bound to the keyboard when the instance has focus.

When the instance becomes focused, this method is bound to the keyboard and will be called for every input press. The parameters are the same as `kivy.core.window.WindowBase.on_key_down()`.

When overwriting the method in the derived widget, super should be called to enable tab cycling. If the derived widget wishes to use tab for its own purposes, it can call super after it has processed the character (if it does not wish to consume the tab).

Similar to other keyboard functions, it should return True if the key was consumed.

### **keyboard\_on\_key\_up** (*window, keycode*)

The method bound to the keyboard when the instance has focus.

When the instance becomes focused, this method is bound to the keyboard and will be called for every input release. The parameters are the same as `kivy.core.window.WindowBase.on_key_up()`.

When overwriting the method in the derived widget, super should be called to enable defocusing on escape. If the derived widget wishes to use escape for its own purposes, it can call super after it has processed the character (if it does not wish to consume the escape).

See `Keyboard_on_key_down()`

### **show\_keyboard()**

Convenience function to show the keyboard in managed mode.

### **unfocus\_on\_touch**

Whether a instance should lose focus when clicked outside the instance.

When a user clicks on a widget that is focus aware and shares the same keyboard as this widget (which in the case of only one keyboard, are all focus aware widgets), then as the other widgets gains focus, this widget loses focus. In addition to that, if this property is `True`, clicking on any widget other than this widget, will remove focus from this widget.

`unfocus_on_touch` is a `BooleanProperty` and defaults to `False` if the `keyboard_mode` in `Config` is ‘multi’ or ‘systemandmulti’, otherwise it defaults to `True`.

## 35.1.10 Kivy Namespaces

New in version 1.9.1.

**Warning:** This code is still experimental, and its API is subject to change in a future version.

The `KNSpaceBehavior` mixin class provides namespace functionality for Kivy objects. It allows kivy objects to be named and then accessed using namespaces.

`KNSpace` instances are the namespaces that store the named objects in Kivy `ObjectProperty` instances. In addition, when inheriting from `KNSpaceBehavior`, if the derived object is named, the name will automatically be added to the associated namespace and will point to a `proxy_ref` of the derived object.

## Basic examples

By default, there's only a single namespace: the `knspace` namespace. The simplest example is adding a widget to the namespace:

```
from kivy.uix.behaviors.knspace import knspace
widget = Widget()
knspace.my_widget = widget
```

This adds a kivy `ObjectProperty` with `rebind=True` and `allownone=True` to the `knspace` namespace with a property name `my_widget`. And the property now also points to this widget.

This can be done automatically with:

```
class MyWidget(KNSpaceBehavior, Widget):
    pass

widget = MyWidget(knsname='my_widget')
```

Or in kv:

```
<MyWidget@KNSpaceBehavior+Widget>

MyWidget:
    knsname: 'my_widget'
```

Now, `knspace.my_widget` will point to that widget.

When one creates a second widget with the same name, the namespace will also change to point to the new widget. E.g.:

```
widget = MyWidget(knsname='my_widget')
# knspace.my_widget now points to widget
widget2 = MyWidget(knsname='my_widget')
# knspace.my_widget now points to widget2
```

## Setting the namespace

One can also create ones own namespace rather than using the default `knspace` by directly setting `KNSpaceBehavior.knspace`:

```
class MyWidget(KNSpaceBehavior, Widget):
    pass

widget = MyWidget(knsname='my_widget')
my_new_namespace = KNSpace()
widget.knspace = my_new_namespace
```

Initially, `my_widget` is added to the default namespace, but when the widget's namespace is changed to `my_new_namespace`, the reference to `my_widget` is moved to that namespace. We could have also of course first set the namespace to `my_new_namespace` and then have named the widget `my_widget`, thereby avoiding the initial assignment to the default namespace.

Similarly, in kv:

```
<MyWidget@KNSpaceBehavior+Widget>

MyWidget:
```

```
knspace: KNSpace()  
knsname: 'my_widget'
```

### Inheriting the namespace

In the previous example, we directly set the namespace we wished to use. In the following example, we inherit it from the parent, so we only have to set it once:

```
<MyWidget@KNSpaceBehavior+Widget>  
<MyLabel@KNSpaceBehavior+Label>  
  
<MyComplexWidget@MyWidget>:  
    knsname: 'my_complex'  
    MyLabel:  
        knsname: 'label1'  
    MyLabel:  
        knsname: 'label2'
```

Then, we do:

```
widget = MyComplexWidget()  
new_knspace = KNSpace()  
widget.knspace = new_knspace
```

The rule is that if no knspace has been assigned to a widget, it looks for a namespace in its parent and parent's parent and so on until it finds one to use. If none are found, it uses the default `knspace`.

When `MyComplexWidget` is created, it still used the default namespace. However, when we assigned the root widget its new namespace, all its children switched to using that new namespace as well. So `new_knspace` now contains `label1` and `label2` as well as `my_complex`.

If we had first done:

```
widget = MyComplexWidget()  
new_knspace = KNSpace()  
knspace.label1.knspace = knspace  
widget.knspace = new_knspace
```

Then `label1` would remain stored in the default `knspace` since it was directly set, but `label2` and `my_complex` would still be added to the new namespace.

One can customize the attribute used to search the parent tree by changing `KNSpaceBehavior.knspace_key`. If the desired knspace is not reachable through a widget's parent tree, e.g. in a popup that is not a widget's child, `KNSpaceBehavior.knspace_key` can be used to establish a different search order.

### Accessing the namespace

As seen in the previous example, if not directly assigned, the namespace is found by searching the parent tree. Consequently, if a namespace was assigned further up the parent tree, all its children and below could access that namespace through their `KNSpaceBehavior.knspace` property.

This allows the creation of multiple widgets with identically given names if each root widget instance is assigned a new namespace. For example:

```
<MyComplexWidget@KNSpaceBehavior+Widget>:  
    Label:  
        text: root.knspace.pretty.text if root.knspace.pretty else ''
```

```

<MyPrettyWidget@KNSpaceBehavior+TextInput>:
    knsname: 'pretty'
    text: 'Hello'

<MyCompositeWidget@KNSpaceBehavior+BoxLayout>:
    MyComplexWidget
    MyPrettyWidget

```

Now, when we do:

```

knspace1, knspace2 = KNSpace(), KNSpace()
composite1 = MyCompositeWidget()
composite1.knspace = knspace1

composite2 = MyCompositeWidget()
composite2.knspace = knspace2

knspace1.pretty = "Here's the ladder, now fix the roof!"
knspace2.pretty = "Get that raccoon off me!"

```

Because each of the *MyCompositeWidget* instances have a different namespace their children also use different namespaces. Consequently, the pretty and complex widgets of each instance will have different text.

Further, because both the namespace *ObjectProperty* references, and *KNSpaceBehavior.knspace* have *rebind=True*, the text of the *MyComplexWidget* label is rebound to match the text of *MyPrettyWidget* when either the root's namespace changes or when the *root.knspace.pretty* property changes, as expected.

### Forking a namespace

Forking a namespace provides the opportunity to create a new namespace from a parent namespace so that the forked namespace will contain everything in the origin namespace, but the origin namespace will not have access to anything added to the forked namespace.

For example:

```

child = knspace.fork()
grandchild = child.fork()

child.label = Label()
grandchild.button = Button()

```

Now label is accessible by both child and grandchild, but not by knspace. And button is only accessible by the grandchild but not by the child or by knspace. Finally, doing *grandchild.label = Label()* will leave *grandchild.label* and *child.label* pointing to different labels.

A motivating example is the example from above:

```

<MyComplexWidget@KNSpaceBehavior+Widget>:
    Label:
        text: root.knspace.pretty.text if root.knspace.pretty else ''

<MyPrettyWidget@KNSpaceBehavior+TextInput>:
    knsname: 'pretty'
    text: 'Hello'

<MyCompositeWidget@KNSpaceBehavior+BoxLayout>:

```

```
knspace: 'fork'  
MyComplexWidget  
MyPrettyWidget
```

Notice the addition of `knspace: 'fork'`. This is identical to doing `knspace: self.knspace.fork()`. However, doing that would lead to infinite recursion as that kv rule would be executed recursively because `self.knspace` will keep on changing. However, allowing `knspace: 'fork'` circumvents that. See [KNSpaceBehavior.knspace](#).

Now, having forked, we just need to do:

```
composite1 = MyCompositeWidget()  
composite2 = MyCompositeWidget()  
  
composite1.knspace.pretty = "Here's the ladder, now fix the roof!"  
composite2.knspace.pretty = "Get that raccoon off me!"
```

Since by forking we automatically created a unique namespace for each `MyCompositeWidget` instance.

**class kivy.uix.behaviors.knspace.KNSpace(`parent=None, keep_ref=False, **kwargs`)**  
Bases: [kivy.event.EventDispatcher](#)

Each `KNSpace` instance is a namespace that stores the named Kivy objects associated with this namespace. Each named object is stored as the value of a Kivy `ObjectProperty` of this instance whose property name is the object's given name. Both `rebind` and `allownone` are set to `True` for the property.

See [KNSpaceBehavior.knspace](#) for details on how a namespace is associated with a named object.

When storing an object in the namespace, the object's `proxy_ref` is stored if the object has such an attribute.

#### Parameters

**`parent: (internal) A KNSpace instance or None.`** If specified, it's a parent namespace, in which case, the current namespace will have in its namespace all its named objects as well as the named objects of its parent and parent's parent etc. See `fork()` for more details.

#### **fork()**

Returns a new `KNSpace` instance which will have access to all the named objects in the current namespace but will also have a namespace of its own that is unique to it.

For example:

```
forked_knspace1 = knspace.fork()  
forked_knspace2 = knspace.fork()
```

Now, any names added to `knspace` will be accessible by the `forked_knspace1` and `forked_knspace2` namespaces by the normal means. However, any names added to `forked_knspace1` will not be accessible from `knspace` or `forked_knspace2`. Similar for `forked_knspace2`.

#### **`keep_ref = False`**

Whether a direct reference should be kept to the stored objects. If `True`, we use the direct object, otherwise we use `proxy_ref` when present.

Defaults to `False`.

#### **`parent = None`**

(internal) The parent namespace instance, `KNSpace`, or `None`. See [fork\(\)](#).

```
class kivy.uix.behaviors.knspace.KNSpaceBehavior(knspace=None, **kwargs)
Bases: object
```

Inheriting from this class allows naming of the inherited objects, which are then added to the associated namespace *knspace* and accessible through it.

Please see the [knspace behaviors module](#) documentation for more information.

#### **knsname**

The name given to this instance. If named, the name will be added to the associated *knspace* namespace, which will then point to the *proxy\_ref* of this instance.

When named, one can access this object by e.g. `self.knspace.name`, where *name* is the given name of this instance. See *knspace* and the module description for more details.

#### **knspace**

The namespace instance, *KNSpace*, associated with this widget. The *knspace* namespace stores this widget when naming this widget with *knsname*.

If the namespace has been set with a *KNSpace* instance, e.g. with `self.knspace = KNSpace()`, then that instance is returned (setting with *None* doesn't count). Otherwise, if *knspace\_key* is not *None*, we look for a namespace to use in the object that is stored in the property named *knspace\_key*, of this instance. I.e. `object = getattr(self, self.knspace_key)`.

If that object has a *knspace* property, then we return its value. Otherwise, we go further up, e.g. with `getattr(object, self.knspace_key)` and look for its *knspace* property.

Finally, if we reach a value of *None*, or *knspace\_key* was *None*, the default *knspace* namespace is returned.

If *knspace* is set to the string '*fork*', the current namespace in *knspace* will be forked with *KNSpace.fork()* and the resulting namespace will be assigned to this instance's *knspace*. See the module examples for a motivating example.

Both *rebind* and *allownone* are *True*.

#### **knspace\_key**

The name of the property of this instance, to use to search upwards for a namespace to use by this instance. Defaults to '*parent*' so that we'll search the parent tree. See *knspace*.

When *None*, we won't search the parent tree for the namespace. *allownone* is *True*.

```
kivy.uix.behaviors.knspace.knspace = <kivy.uix.behaviors.knspace.KNSpace object>
```

The default *KNSpace* namespace. See *KNSpaceBehavior.knspace* for more details.

### 35.1.11 ToggleButton Behavior

The *ToggleButtonBehavior* mixin class provides *ToggleButton* behavior. You can combine this class with other widgets, such as an *Image*, to provide alternative togglebuttons that preserve Kivy togglebutton behavior.

For an overview of behaviors, please refer to the [behaviors](#) documentation.

#### Example

The following example adds togglebutton behavior to an image to make a checkbox that behaves like a togglebutton:

```
from kivy.app import App
from kivy.uix.image import Image
from kivy.uix.behaviors import ToggleButtonBehavior
```

```

class MyButton(ToggleButtonBehavior, Image):
    def __init__(self, **kwargs):
        super(MyButton, self).__init__(**kwargs)
        self.source = 'atlas://data/images/defaulttheme/checkbox_off'

    def on_state(self, widget, value):
        if value == 'down':
            self.source = 'atlas://data/images/defaulttheme/checkbox_on'
        else:
            self.source = 'atlas://data/images/defaulttheme/checkbox_off'

class SampleApp(App):
    def build(self):
        return MyButton()

SampleApp().run()

```

**class kivy.uix.behaviors.togglebutton.ToggleButtonBehavior(\*\*kwargs)**  
Bases: *kivy.uix.behaviors.button.ButtonBehavior*

This *mixin* class provides *togglebutton* behavior. Please see the *togglebutton behaviors module* documentation for more information.

New in version 1.8.0.

#### **allow\_no\_selection**

This specifies whether the widgets in a group allow no selection i.e. everything to be deselected.

New in version 1.9.0.

*allow\_no\_selection* is a BooleanProperty and defaults to *True*

#### **static get\_widgets(groupname)**

Return a list of the widgets contained in a specific group. If the group doesn't exist, an empty list will be returned.

---

**Note:** Always release the result of this method! Holding a reference to any of these widgets can prevent them from being garbage collected. If in doubt, do:

```

l = ToggleButtonBehavior.get_widgets('mygroup')
# do your job
del l

```

---

**Warning:** It's possible that some widgets that you have previously deleted are still in the list. The garbage collector might need to release other objects before flushing them.

#### **group**

Group of the button. If *None*, no group will be used (the button will be independent). If specified, *group* must be a hashable object, like a string. Only one button in a group can be in a 'down' state.

*group* is a *ObjectProperty* and defaults to *None*.

### 35.1.12 Touch Ripple

New in version 1.10.1.

**Warning:** This code is still experimental, and its API is subject to change in a future version.

This module contains `mixin` classes to add a touch ripple visual effect known from *Google Material Design* <[https://en.wikipedia.org/wiki/Material\\_Design](https://en.wikipedia.org/wiki/Material_Design)>\_ to widgets.

For an overview of behaviors, please refer to the [behaviors](#) documentation.

The class `TouchRippleBehavior` provides rendering the ripple animation.

The class `TouchRippleButtonBehavior` basically provides the same functionality as `ButtonBehavior` but rendering the ripple animation instead of default press/release visualization.

```
class kivy.uix.behaviors.touchripple.TouchRippleBehavior(**kwargs)
Bases: object
```

Touch ripple behavior.

Supposed to be used as mixin on widget classes.

Ripple behavior does not trigger automatically, concrete implementation needs to call `ripple_show()` respective `ripple_fade()` manually.

Here we create a Label which renders the touch ripple animation on interaction:

```
class RippleLabel(TouchRippleBehavior, Label):

    def __init__(self, **kwargs):
        super(RippleLabel, self).__init__(**kwargs)

    def on_touch_down(self, touch):
        collide_point = self.collide_point(touch.x, touch.y)
        if collide_point:
            touch.grab(self)
            self.ripple_show(touch)
            return True
        return False

    def on_touch_up(self, touch):
        if touch.grab_current is self:
            touch.ungrab(self)
            self.ripple_fade()
            return True
        return False
```

#### `ripple_duration_in`

Animation duration taken to show the overlay.

`ripple_duration_in` is a [NumericProperty](#) and defaults to 0.5.

#### `ripple_duration_out`

Animation duration taken to fade the overlay.

`ripple_duration_out` is a [NumericProperty](#) and defaults to 0.2.

#### `ripple_fade()`

Finish ripple animation on current widget.

**ripple\_fade\_from\_alpha**

Alpha channel for ripple color the animation starts with.

*ripple\_fade\_from\_alpha* is a *NumericProperty* and defaults to 0.5.

**ripple\_fade\_to\_alpha**

Alpha channel for ripple color the animation targets to.

*ripple\_fade\_to\_alpha* is a *NumericProperty* and defaults to 0.8.

**ripple\_func\_in**

Animation callback for showing the overlay.

*ripple\_func\_in* is a *StringProperty* and defaults to *in\_cubic*.

**ripple\_func\_out**

Animation callback for hiding the overlay.

*ripple\_func\_out* is a *StringProperty* and defaults to *out\_quad*.

**ripple\_rad\_default**

Default radius the animation starts from.

*ripple\_rad\_default* is a *NumericProperty* and defaults to 10.

**ripple\_scale**

Max scale of the animation overlay calculated from max(width/height) of the decorated widget.

*ripple\_scale* is a *NumericProperty* and defaults to 2.0.

**ripple\_show(touch)**

Begin ripple animation on current widget.

Expects touch event as argument.

**class kivy.uix.behaviors.touchripple.TouchRippleButtonBehavior(\*\*kwargs)**

Bases: *kivy.uix.behaviors.touchripple.TouchRippleBehavior*

This *mixin* class provides a similar behavior to *ButtonBehavior* but provides touch ripple animation instead of button pressed/released as visual effect.

**Events**

*on\_press* Fired when the button is pressed.

*on\_release* Fired when the button is released (i.e. the touch/click that pressed the button goes away).

**always\_release**

This determines whether or not the widget fires an *on\_release* event if the *touch\_up* is outside the widget.

*always\_release* is a *BooleanProperty* and defaults to *False*.

**last\_touch**

Contains the last relevant touch received by the Button. This can be used in *on\_press* or *on\_release* in order to know which touch dispatched the event.

*last\_touch* is a *ObjectProperty* and defaults to *None*.

## 35.2 RecycleView

New in version 1.10.0.

The RecycleView provides a flexible model for viewing selected sections of large data sets. It aims to prevent the performance degradation that can occur when generating large numbers of widgets in order to display many data items.

The view is generated by processing the *data*, essentially a list of dicts, and uses these dicts to generate instances of the *viewclass* as required. Its design is based on the MVC ([Model-view-controller](#)) pattern.

- Model: The model is formed by *data* you pass in via a list of dicts.
- View: The View is split across layout and views and implemented using adapters.
- Controller: The controller determines the logical interaction and is implemented by *RecycleViewBehavior*.

These are abstract classes and cannot be used directly. The default concrete implementations are the *RecycleDataModel* for the model, the *RecycleLayout* for the view, and the *RecycleView* for the controller.

When a RecycleView is instantiated, it automatically creates the views and data classes. However, one must manually create the layout classes and add them to the RecycleView.

A layout manager is automatically created as a *layout\_manager* when added as the child of the RecycleView. Similarly when removed. A requirement is that the layout manager must be contained as a child somewhere within the RecycleView's widget tree so the view port can be found.

A minimal example might look something like this:

```
from kivy.app import App
from kivy.lang import Builder
from kivy.uix.recycleview import RecycleView

Builder.load_string('''
<RV>:
    viewclass: 'Label'
    RecycleBoxLayout:
        default_size: None, dp(56)
        default_size_hint: 1, None
        size_hint_y: None
        height: self.minimum_height
        orientation: 'vertical'
''')

class RV(RecycleView):
    def __init__(self, **kwargs):
        super(RV, self).__init__(**kwargs)
        self.data = [{'text': str(x)} for x in range(100)]


class TestApp(App):
    def build(self):
        return RV()

if __name__ == '__main__':
    TestApp().run()
```

In order to support selection in the view, you can add the required behaviours as follows:

```
from kivy.app import App
from kivy.lang import Builder
from kivy.uix.recycleview import RecycleView
```

```

from kivy.uix.recycleview.views import RecycleDataViewBehavior
from kivy.uix.label import Label
from kivy.properties import BooleanProperty
from kivy.uix.recycleboxlayout import RecycleBoxLayout
from kivy.uix.behaviors import FocusBehavior
from kivy.uix.recycleview.layout import LayoutSelectionBehavior

Builder.load_string('''
<SelectableLabel>:
    # Draw a background to indicate selection
    canvas.before:
        Color:
            rgba: (.0, .9, .1, .3) if self.selected else (0, 0, 0, 1)
        Rectangle:
            pos: self.pos
            size: self.size
<RV>:
    viewclass: 'SelectableLabel'
    SelectableRecycleBoxLayout:
        default_size: None, dp(56)
        default_size_hint: 1, None
        size_hint_y: None
        height: self.minimum_height
        orientation: 'vertical'
        multiselect: True
        touch_multiselect: True
''')

class SelectableRecycleBoxLayout(FocusBehavior, LayoutSelectionBehavior,
                                RecycleBoxLayout):
    ''' Adds selection and focus behaviour to the view. '''

class SelectableLabel(RecycleDataViewBehavior, Label):
    ''' Add selection support to the Label '''
    index = None
    selected = BooleanProperty(False)
    selectable = BooleanProperty(True)

    def refresh_view_attrs(self, rv, index, data):
        ''' Catch and handle the view changes '''
        self.index = index
        return super(SelectableLabel, self).refresh_view_attrs(
            rv, index, data)

    def on_touch_down(self, touch):
        ''' Add selection on touch down '''
        if super(SelectableLabel, self).on_touch_down(touch):
            return True
        if self.collide_point(*touch.pos) and self.selectable:
            return self.parent.select_with_touch(self.index, touch)

    def apply_selection(self, rv, index, is_selected):
        ''' Respond to the selection of items in the view. '''
        self.selected = is_selected
        if is_selected:
            print("selection changed to {0}".format(rv.data[index]))
        else:
            print("selection removed for {0}".format(rv.data[index]))

```

```

class RV(RecycleView):
    def __init__(self, **kwargs):
        super(RV, self).__init__(**kwargs)
        self.data = [{text: str(x)} for x in range(100)]

class TestApp(App):
    def build(self):
        return RV()

if __name__ == '__main__':
    TestApp().run()

```

Please see the `examples/widgets/recycleview/basic_data.py` file for a more complete example.

#### TODO:

- Method to clear cached class instances.
- Test when views cannot be found (e.g. viewclass is None).
- Fix selection goto.

**Warning:** When views are re-used they may not trigger if the data remains the same.

**class kivy.uix.recycleview.RecycleViewBehavior(\*\*kwargs)**  
Bases: object

RecycleViewBehavior provides a behavioral model upon which the `RecycleView` is built. Together, they offer an extensible and flexible way to produce views with limited windows over large data sets.

See the module documentation for more information.

#### **data\_model**

The Data model responsible for maintaining the data set.

`data_model` is an *AliasProperty* that gets and sets the current data model.

#### **layout\_manager**

The Layout manager responsible for positioning views within the `RecycleView`.

`layout_manager` is an *AliasProperty* that gets and sets the layout\_manger.

#### **refresh\_from\_data(\*largs, \*\*kwargs)**

This should be called when data changes. Data changes typically indicate that everything should be recomputed since the source data changed.

This method is automatically bound to the `on_data_changed` method of the `RecycleDataModelBehavior` class and therefore responds to and accepts the keyword arguments of that event.

It can be called manually to trigger an update.

#### **refresh\_from\_layout(\*largs, \*\*kwargs)**

This should be called when the layout changes or needs to change. It is typically called when a layout parameter has changed and therefore the layout needs to be recomputed.

**refresh\_from\_viewport(\*args)**

This should be called when the viewport changes and the displayed data must be updated. Neither the data nor the layout will be recomputed.

**view\_adapter**

The adapter responsible for providing views that represent items in a data set.

view\_adapter is an *AliasProperty* that gets and sets the current view adapter.

**class kivy.uix.recycleview.RecycleView(\*\*kwargs)**

Bases: *kivy.uix.recycleview.RecycleViewBehavior*, *kivy.uix.scrollview.ScrollView*

RecycleView is a flexible view for providing a limited window into a large data set.

See the module documentation for more information.

**data**

The data used by the current view adapter. This is a list of dicts whose keys map to the corresponding property names of the *viewclass*.

data is an *AliasProperty* that gets and sets the data used to generate the views.

**key\_viewclass**

key\_viewclass is an *AliasProperty* that gets and sets the key viewclass for the current layout\_manager.

**viewclass**

The viewclass used by the current layout\_manager.

viewclass is an *AliasProperty* that gets and sets the class used to generate the individual items presented in the view.

### 35.2.1 RecycleView Data Model

New in version 1.10.0.

The data model part of the RecycleView model-view-controller pattern.

It defines the models (classes) that store the data associated with a *RecycleViewBehavior*. Each model (class) determines how the data is stored and emits requests to the controller (*RecycleViewBehavior*) when the data is modified.

**class kivy.uix.recycleview.datamodel.RecycleDataModelBehavior**

Bases: object

*RecycleDataModelBehavior* is the base class for the models that describes and provides the data for the *RecycleViewBehavior*.

**Events**

*on\_data\_changed*: Fired when the data changes. The event may dispatch keyword arguments specific to each implementation of the data model. When dispatched, the event and keyword arguments are forwarded to *refresh\_from\_data()*.

**attach\_recycleview(rv)**

Associates a *RecycleViewBehavior* with this data model.

**detach\_recycleview()**

Removes the *RecycleViewBehavior* associated with this data model.

**recycleview**

The *RecycleViewBehavior* instance associated with this data model.

```
class kivy.uix.recycleview.datamodel.RecycleDataModel(**kwargs)
Bases: kivy.uix.recycleview.datamodel.RecycleDataModelBehavior, kivy.event.EventDispatcher
```

A implementation of *RecycleDataModelBehavior* that keeps the data in a indexable list. See *data*.

When data changes this class currently dispatches *on\_data\_changed* with one of the following additional keyword arguments.

**none: no keyword argument** With no additional argument it means a generic data change.

**removed: a slice or integer** The value is a slice or integer indicating the indices removed.

**appended: a slice** The slice in *data* indicating the first and last new items (i.e. the slice pointing to the new items added at the end).

**inserted: a integer** The index in *data* where a new data item was inserted.

**modified: a slice** The slice with the indices where the data has been modified. This currently does not allow changing of size etc.

#### **data**

Stores the model's data using a list.

The data for a item at index *i* can also be accessed with *RecycleDataModel[i]*.

#### **observable\_dict**

A dictionary instance, which when modified will trigger a *data* and consequently an *on\_data\_changed* dispatch.

### 35.2.2 RecycleView Layouts

New in version 1.10.0.

The Layouts handle the presentation of views for the *RecycleView*.

**Warning:** This module is highly experimental, its API may change in the future and the documentation is not complete at this time.

```
class kivy.uix.recycleview.layout.LayoutSelectionBehavior(**kwargs)
Bases: kivy.uix.behaviors.compoundselection.CompoundSelectionBehavior
```

The *LayoutSelectionBehavior* can be combined with *RecycleLayoutManagerBehavior* to allow its derived classes selection behaviors similarly to how *CompoundSelectionBehavior* can be used to add selection behaviors to normal layout.

*RecycleLayoutManagerBehavior* manages its children differently than normal layouts or widgets so this class adapts *CompoundSelectionBehavior* based selection to work with *RecycleLayoutManagerBehavior* as well.

Similarly to *CompoundSelectionBehavior*, one can select using the keyboard or touch, which calls *select\_node()* or *deselect\_node()*, or one can call these methods directly. When a item is selected or deselected *apply\_selection()* is called. See *apply\_selection()*.

#### **apply\_selection(index, view, is\_selected)**

Applies the selection to the view. This is called internally when a view is displayed and it needs to be shown as selected or as not selected.

It is called when *select\_node()* or *deselect\_node()* is called or when a view needs to be refreshed. Its function is purely to update the view to reflect the selection state. So the function may be called multiple times even if the selection state may not have changed.

If the view is a instance of `RecycleDataViewBehavior`, its `apply_selection()` method will be called every time the view needs to refresh the selection state. Otherwise, this method is responsible for applying the selection.

#### Parameters

`index: int` The index of the data item that is associated with the view.

`view: widget` The widget that is the view of this data item.

`is_selected: bool` Whether the item is selected.

#### key\_selection

The key used to check whether a view of a data item can be selected with touch or the keyboard.

`key_selection` is the key in data, which if present and `True` will enable selection for this item from the keyboard or with a touch. When `None`, the default, no item will be selectable.

`key_selection` is a `StringProperty` and defaults to `None`.

---

**Note:** All data items can be selected directly using `select_node()` or `deselect_node()`, even if `key_selection` is `False`.

---

## `class kivy.uix.recycleview.layout.RecycleLayoutManagerBehavior`

Bases: `object`

A RecycleLayoutManagerBehavior is responsible for positioning views into the `RecycleView`. `data` within a `RecycleView`. It adds new views into the data when it becomes visible to the user, and removes them when they leave the visible area.

#### `compute_visible_views(data, viewport)`

`viewport` is in coordinates of the layout manager.

#### `get_view_index_at(pos)`

Return the view `index` on which position, `pos`, falls.

`pos` is in coordinates of the layout manager.

#### `goto_view(index)`

Moves the views so that the view corresponding to `index` is visible.

#### `key_viewclass`

See `RecyclerView.key_viewclass`.

#### `refresh_view_layout(index, layout, view, viewport)`

See :meth:`~kivy.uix.recycleview.views.RecycleDataAdapter.refresh\_view\_layout`.

#### `set_visible_views(indices, data, viewport)`

`viewport` is in coordinates of the layout manager.

#### `viewclass`

See `RecyclerView.viewclass`.

### 35.2.3 RecycleView Views

New in version 1.10.0.

The adapter part of the `RecycleView` which together with the layout is the view part of the model-view-controller pattern.

The view module handles converting the data to a view using the adapter class which is then displayed by the layout. A view can be any Widget based class. However, inheriting from RecycleDataAdapterBehavior adds methods for converting the data to a view.

#### TODO:

- Make view caches specific to each view class type.

**class** `kivy.uix.recycleview.views.RecycleDataAdapter`  
Bases: `kivy.event.EventDispatcher`

The class that converts data to a view.

— Internal details — A view can have 3 states.

- It can be completely in sync with the data, which occurs when the view is displayed. These are stored in `views`.
- It can be dirty, which occurs when the view is in sync with the data, except for the size/pos parameters which is controlled by the layout. This occurs when the view is not currently displayed but the data has not changed. These views are stored in `dirty_views`.
- Finally the view can be dead which occurs when the data changes and the view was not updated or when a view is just created. Such views are typically added to the internal cache.

Typically what happens is that the layout manager lays out the data and then asks for views, using `set_visible_views, ()` for some specific data items that it displays.

These views are gotten from the current views, dirty or global cache. Then depending on the view state `refresh_view_attrs()` is called to bring the view up to date with the data (except for sizing parameters). Finally, the layout manager gets these views, updates their size and displays them.

**attach\_recycleview(rv)**

Associates a `RecycleViewBehavior` with this instance. It is stored in `recycleview`.

**create\_view(index, data\_item, viewclass)**

(internal) Creates and initializes the view for the data at `index`.

The returned view is synced with the data, except for the pos/size information.

**detach\_recycleview()**

Removes the `RecycleViewBehavior` associated with this instance and clears `recycleview`.

**get\_view(index, data\_item, viewclass)**

(internal) Returns a view instance for the data at `index`

It looks through the various caches and finally creates a view if it doesn't exist. The returned view is synced with the data, except for the pos/size information.

If found in the cache it's removed from the source before returning. It doesn't check the current views.

**get\_visible\_view(index)**

Returns the currently visible view associated with `index`.

If no view is currently displayed for `index` it returns `None`.

**invalidate()**

Moves all the current views into the global cache.

As opposed to making a view dirty where the view is in sync with the data except for sizing information, this will completely disconnect the view from the data, as it is assumed the data has gone out of sync with the view.

This is typically called when the data changes.

**make\_view\_dirty**(*view, index*)  
(internal) Used to flag this view as dirty, ready to be used for others. See [make\\_views\\_dirty\(\)](#).

### **make\_views\_dirty()**

Makes all the current views dirty.

Dirty views are still in sync with the corresponding data. However, the size information may go out of sync. Therefore a dirty view can be reused by the same index by just updating the sizing information.

Once the underlying data of this index changes, the view should be removed from the dirty views and moved to the global cache with [invalidate\(\)](#).

This is typically called when the layout manager needs to re-layout all the data.

### **recycleview**

The [RecycleViewBehavior](#) associated with this instance.

### **refresh\_view\_attrs**(*index, data\_item, view*)

(internal) Syncs the view and brings it up to date with the data.

This method calls [RecycleDataViewBehavior.refresh\\_view\\_attrs\(\)](#) if the view inherits from [RecycleDataViewBehavior](#). See that method for more details.

---

**Note:** Any sizing and position info is skipped when syncing with the data.

---

### **refresh\_view\_layout**(*index, layout, view, viewport*)

Updates the sizing information of the view.

viewport is in coordinates of the layout manager.

This method calls [RecycleDataViewBehavior.refresh\\_view\\_attrs\(\)](#) if the view inherits from [RecycleDataViewBehavior](#). See that method for more details.

---

**Note:** Any sizing and position info is skipped when syncing with the data.

---

### **set\_visible\_views**(*indices, data, viewclasses*)

Gets a 3-tuple of the new, remaining, and old views for the current viewport.

The new views are synced to the data except for the size/pos properties. The old views need to be removed from the layout, and the new views added.

The new views are not necessarily *new*, but are all the currently visible views.

## **class kivy.uix.recycleview.views.RecycleDataViewBehavior**

Bases: `object`

A optional base class for data views (`RecycleView.viewclass`). If a view inherits from this class, the class's functions will be called when the view needs to be updated due to a data change or layout update.

### **refresh\_view\_attrs**(*rv, index, data*)

Called by the `RecycleAdapter` when the view is initially populated with the values from the *data* dictionary for this item.

Any pos or size info should be removed because they are set subsequently with [refresh\\_view\\_layout](#).

#### **Parameters**

*rv*: `RecycleView` instance The `RecycleView` that caused the update.

**data: dict** The data dict used to populate this view.

**refresh\_view\_layout(rv, index, layout, viewport)**

Called when the view's size is updated by the layout manager, RecycleLayoutManagerBehavior.

#### Parameters

**rv: RecycleView instance** The RecycleView that caused the update.

**viewport: 4-tuple** The coordinates of the bottom left and width height in layout manager coordinates. This may be larger than this view item.

**Raises LayoutChangeException:** If the sizing or data changed during a call to this method, raising a *LayoutChangeException* exception will force a refresh. Useful when data changed and we don't want to layout further since it'll be overwritten again soon.

## 35.3 Abstract View

New in version 1.5.

Deprecated since version 1.10.0: The feature has been deprecated.

**Warning:** This code is still experimental, and its API is subject to change in a future version.

The **AbstractView** widget has an adapter property for an adapter that mediates to data. The adapter manages an item\_view\_instance dict property that holds views for each data item, operating as a cache.

**class kivy.uix.abstractview.AbstractView(\*args, \*\*kwargs)**  
Bases: **kivy.uix.floatlayout.FloatLayout**


View using an **Adapter** as a data provider.

#### adapter

The adapter can be one of several kinds of **adapters**. The most common example is the **ListAdapter** used for managing data items in a list.

## 35.4 Accordion

New in version 1.0.8.



The Accordion widget is a form of menu where the options are stacked either vertically or horizontally and the item in focus (when touched) opens up to display its content.

The `Accordion` should contain one or many `AccordionItem` instances, each of which should contain one root content widget. You'll end up with a Tree something like this:

- Accordion
  - AccordionItem
    - \* YourContent
  - AccordionItem
    - \* BoxLayout
      - Another user content 1
      - Another user content 2
  - AccordionItem
    - \* Another user content

The current implementation divides the `AccordionItem` into two parts:

1. One container for the title bar
2. One container for the content

The title bar is made from a Kv template. We'll see how to create a new template to customize the design of the title bar.

**Warning:** If you see message like:

```
[WARNING] [Accordion] not have enough space for displaying all children
[WARNING] [Accordion] need 440px, got 100px
[WARNING] [Accordion] layout aborted.
```

That means you have too many children and there is no more space to display the content. This is "normal" and nothing will be done. Try to increase the space for the accordion or reduce the number of children. You can also reduce the `Accordion.min_space`.

### 35.4.1 Simple example

```
from kivy.uix.accordion import Accordion, AccordionItem
from kivy.uix.label import Label
from kivy.app import App

class AccordionApp(App):
    def build(self):
        root = Accordion()
        for x in range(5):
            item = AccordionItem(title='Title %d' % x)
            item.add_widget(Label(text='Very big content\n' * 10))
            root.add_widget(item)
        return root

if __name__ == '__main__':
    AccordionApp().run()
```

### 35.4.2 Customize the accordion

You can increase the default size of the title bar:

```
root = Accordion(min_space=60)
```

Or change the orientation to vertical:

```
root = Accordion(orientation='vertical')
```

The AccordionItem is more configurable and you can set your own title background when the item is collapsed or opened:

```
item = AccordionItem(background_normal='image_when_collapsed.png',
                      background_selected='image_when_selected.png')
```

**class kivy.uix.accordion.Accordion(\*\*kwargs)**  
Bases: *kivy.uix.widget.Widget*

Accordion class. See module documentation for more information.

#### **anim\_duration**

Duration of the animation in seconds when a new accordion item is selected.

*anim\_duration* is a *NumericProperty* and defaults to .25 (250ms).

#### **anim\_func**

Easing function to use for the animation. Check *kivy.animation.AnimationTransition* for more information about available animation functions.

*anim\_func* is an *ObjectProperty* and defaults to 'out\_expo'. You can set a string or a function to use as an easing function.

#### **min\_space**

Minimum space to use for the title of each item. This value is automatically set for each child every time the layout event occurs.

*min\_space* is a *NumericProperty* and defaults to 44 (px).

#### **orientation**

Orientation of the layout.

*orientation* is an *OptionProperty* and defaults to 'horizontal'. Can take a value of 'vertical' or 'horizontal'.

**class kivy.uix.accordion.AccordionItem(\*\*kwargs)**

Bases: *kivy.uix.floatlayout.FloatLayout*

AccordionItem class that must be used in conjunction with the *Accordion* class. See the module documentation for more information.

#### **accordion**

Instance of the *Accordion* that the item belongs to.

*accordion* is an *ObjectProperty* and defaults to None.

#### **background\_disabled\_normal**

Background image of the accordion item used for the default graphical representation when the item is collapsed and disabled.

New in version 1.8.0.

*background\_\_disabled\_normal* is a *StringProperty* and defaults to 'atlas://data/images/defaulttheme/button\_disabled'.

**background\_disabled\_selected**

Background image of the accordion item used for the default graphical representation when the item is selected (not collapsed) and disabled.

New in version 1.8.0.

*background\_disabled\_selected* is a *StringProperty* and defaults to ‘atlas://data/images/defaulttheme/button\_disabled\_pressed’.

**background\_normal**

Background image of the accordion item used for the default graphical representation when the item is collapsed.

*background\_normal* is a *StringProperty* and defaults to ‘atlas://data/images/defaulttheme/button’.

**background\_selected**

Background image of the accordion item used for the default graphical representation when the item is selected (not collapsed).

*background\_normal* is a *StringProperty* and defaults to ‘atlas://data/images/defaulttheme/button\_pressed’.

**collapse**

Boolean to indicate if the current item is collapsed or not.

*collapse* is a *BooleanProperty* and defaults to True.

**collapse\_alpha**

Value between 0 and 1 to indicate how much the item is collapsed (1) or whether it is selected (0). It’s mostly used for animation.

*collapse\_alpha* is a *NumericProperty* and defaults to 1.

**container**

(internal) Property that will be set to the container of children inside the AccordionItem representation.

**container\_title**

(internal) Property that will be set to the container of title inside the AccordionItem representation.

**content\_size**

(internal) Set by the *Accordion* to the size allocated for the content.

**min\_space**

Link to the *Accordion.min\_space* property.

**orientation**

Link to the *Accordion.orientation* property.

**title**

Title string of the item. The title might be used in conjunction with the *AccordionItemTitle* template. If you are using a custom template, you can use that property as a text entry, or not. By default, it’s used for the title text. See *title\_template* and the example below.

*title* is a *StringProperty* and defaults to “”.

**title\_args**

Default arguments that will be passed to the *kivy.lang.Builder.template()* method.

*title\_args* is a *DictProperty* and defaults to {}.

**title\_template**

Template to use for creating the title part of the accordion item. The default template is a sim-

ple Label, not customizable (except the text) that supports vertical and horizontal orientation and different backgrounds for collapse and selected mode.

It's better to create and use your own template if the default template does not suffice.

`title` is a *StringProperty* and defaults to 'AccordionItemTitle'. The current default template lives in the *kivy/data/style.kv* file.

Here is the code if you want to build your own template:

```
[AccordionItemTitle@Label]:
    text: ctx.title
    canvas.before:
        Color:
            rgb: 1, 1, 1
        BorderImage:
            source:
                ctx.item.background_normal \
                if ctx.item.collapse \
                else ctx.item.background_selected
            pos: self.pos
            size: self.size
        PushMatrix
        Translate:
            xy: self.center_x, self.center_y
        Rotate:
            angle: 90 if ctx.item.orientation == 'horizontal' else 0
            axis: 0, 0, 1
        Translate:
            xy: -self.center_x, -self.center_y
    canvas.after:
        PopMatrix
```


### `class kivy.uix.accordion.AccordionException`

Bases: `exceptions.Exception`

AccordionException class.

## 35.5 Action Bar

New in version 1.8.0.



The ActionBar widget is like Android's *ActionBar*, where items are stacked horizontally. When the area becomes too small, widgets are moved into the *ActionOverflow* area.

An *ActionBar* contains an *ActionView* with various *ContextualActionViews*. An *ActionView* will contain an *ActionPrevious* having title, app\_icon and previous\_icon properties. An *ActionView* will contain subclasses of *ActionItems*. Some predefined ones include an *ActionButton*, an *ActionToggleButton*, an *ActionCheck*, an *ActionSeparator* and an *ActionGroup*.

An *ActionGroup* is used to display *ActionItems* in a group. An *ActionView* will always display an *ActionGroup* after other *ActionItems*. An *ActionView* contains an *ActionOverflow*, but this is only made visible when required i.e. the available area is too small to fit all the widgets. A *ContextualActionView* is a subclass of `an:layout:ActionView`.

Changed in version 1.10.1: `ActionGroup` core rewritten from `Spinner` to pure `DropDown`

## `class kivy.uix.actionbar.ActionBarException`

Bases: `exceptions.Exception`

ActionBarException class

## `class kivy.uix.actionbar.ActionItem`

Bases: `object`

ActionItem class, an abstract class for all ActionBar widgets. To create a custom widget for an ActionBar, inherit from this class. See module documentation for more information.

### `background_down`

Background image of the ActionItem used for the default graphical representation when an ActionItem is pressed.

`background_down` is a `StringProperty` and defaults to 'atlas://data/images/defaulttheme/action\_item\_down'.

### `background_normal`

Background image of the ActionItem used for the default graphical representation when the ActionItem is not pressed.

`background_normal` is a `StringProperty` and defaults to 'atlas://data/images/defaulttheme/action\_item'.

### `important`

Determines if an ActionItem is important or not. If an item is important and space is limited, this item will be displayed in preference to others.

`important` is a `BooleanProperty` and defaults to False.

### `inside_group`

(internal) Determines if an ActionItem is displayed inside an ActionGroup or not.

`inside_group` is a `BooleanProperty` and defaults to False.

### `minimum_width`

Minimum Width required by an ActionItem.

`minimum_width` is a `NumericProperty` and defaults to '90sp'.

### `mipmap`

Defines whether the image/icon displayed on top of the button uses a mipmap or not.

`mipmap` is a `BooleanProperty` and defaults to `True`.

### `pack_width`

(read-only) The actual width to use when packing the item. Equal to the greater of `minimum_width` and `width`.

`pack_width` is an `AliasProperty`.

## `class kivy.uix.actionbarActionButton(**kwargs)`

Bases: `kivy.uix.button.Button, kivy.uix.actionbar.ActionItem`

ActionButton class, see module documentation for more information.

The text color, width and size\_hint\_x are set manually via the Kv language file. It covers a lot of cases: with/without an icon, with/without a group and takes care of the padding between elements.

You don't have much control over these properties, so if you want to customize it's appearance, we suggest you create your own button representation. You can do this by creating a class that subclasses an existing widget and an `ActionItem`:

```
class MyOwnActionButton(Button, ActionItem):  
    pass
```

You can then create your own style using the Kv language.

#### **icon**

Source image to use when the Button is part of the ActionBar. If the Button is in a group, the text will be preferred.

*icon* is a *StringProperty* and defaults to None.

```
class kivy.uix.actionbar.ActionToggleButton(**kwargs)  
Bases: kivy.uix.actionbar.ActionItem, kivy.uix.togglebutton.ToggleButton
```

ActionToggleButton class, see module documentation for more information.

#### **icon**

Source image to use when the Button is part of the ActionBar. If the Button is in a group, the text will be preferred.

```
class kivy.uix.actionbar.ActionCheck(**kwargs)  
Bases: kivy.uix.actionbar.ActionItem, kivy.uix.checkbox.CheckBox
```

ActionCheck class, see module documentation for more information.

```
class kivy.uix.actionbar.ActionSeparator(**kwargs)  
Bases: kivy.uix.actionbar.ActionItem, kivy.uix.widget.Widget
```

ActionSeparator class, see module documentation for more information.

#### **background\_image**

Background image for the separators default graphical representation.

*background\_image* is a *StringProperty* and defaults to 'atlas://data/images/defaulttheme/separator'.

```
class kivy.uix.actionbar.ActionDropDown(**kwargs)  
Bases: kivy.uix.dropdown.DropDown
```

ActionDropDown class, see module documentation for more information.

```
class kivy.uix.actionbar.ActionGroup(**kwargs)  
Bases: kivy.uix.actionbar.ActionItem, kivy.uix.button.Button
```

ActionGroup class, see module documentation for more information.

#### **dropdown\_width**

If non zero, provides the width for the associated DropDown. This is useful when some items in the ActionGroup's DropDown are wider than usual and you don't want to make the ActionGroup widget itself wider.

*dropdown\_width* is a *NumericProperty* and defaults to 0.

New in version 1.10.0.

#### **is\_open**

By default, the DropDown is not open. Set to True to open it.

*is\_open* is a *BooleanProperty* and defaults to False.

#### **mode**

Sets the current mode of an ActionGroup. If mode is 'normal', the ActionGroups children will be displayed normally if there is enough space, otherwise they will be displayed in a spinner. If mode is 'spinner', then the children will always be displayed in a spinner.

*mode* is an *OptionProperty* and defaults to 'normal'.

**separator\_image**

Background Image for an ActionSeparator in an ActionView.

*separator\_image* is a *StringProperty* and defaults to 'atlas://data/images/defaulttheme/separator'.

**separator\_width**

Width of the ActionSeparator in an ActionView.

*separator\_width* is a *NumericProperty* and defaults to 0.

**use\_separator**

Specifies whether to use a separator after/before this group or not.

*use\_separator* is a *BooleanProperty* and defaults to False.

**class kivy.uix.actionbar.ActionOverflow(\*\*kwargs)**

Bases: *kivy.uix.actionbar.ActionGroup*

ActionOverflow class, see module documentation for more information.

**overflow\_image**

Image to be used as an Overflow Image.

*overflow\_image* is a *StringProperty* and defaults to 'atlas://data/images/defaulttheme/overflow'.

**class kivy.uix.actionbar.ActionView(\*\*kwargs)**

Bases: *kivy.uix.boxlayout.BoxLayout*

ActionView class, see module documentation for more information.

**action\_previous**

Previous button for an ActionView.

*action\_previous* is an *ObjectProperty* and defaults to None.

**background\_color**

Background color in the format (r, g, b, a).

*background\_color* is a *ListProperty* and defaults to [1, 1, 1, 1].

**background\_image**

Background image of an ActionViews default graphical representation.

*background\_image* is a *StringProperty* and defaults to 'atlas://data/images/defaulttheme/action\_view'.

**overflow\_group**

Widget to be used for the overflow.

*overflow\_group* is an *ObjectProperty* and defaults to an instance of *ActionOverflow*.

**use\_separator**

Specify whether to use a separator before every ActionGroup or not.

*use\_separator* is a *BooleanProperty* and defaults to False.

**class kivy.uix.actionbar.ContextualActionView(\*\*kwargs)**

Bases: *kivy.uix.actionbar.ActionView*

ContextualActionView class, see the module documentation for more information.

**class kivy.uix.actionbar.ActionPrevious(\*\*kwargs)**

Bases: *kivy.uix.boxlayout.BoxLayout, kivy.uix.actionbar.ActionItem*

ActionPrevious class, see module documentation for more information.

**app\_icon**

Application icon for the ActionView.

*app\_icon* is a *StringProperty* and defaults to the window icon if set, otherwise 'data/logo/kivy-icon-32.png'.

**app\_icon\_height**

Height of app\_icon image.

*app\_icon\_height* is a *NumericProperty* and defaults to 0.

**app\_icon\_width**

Width of app\_icon image.

*app\_icon\_width* is a *NumericProperty* and defaults to 0.

**color**

Text color, in the format (r, g, b, a)

*color* is a *ListProperty* and defaults to [1, 1, 1, 1].

**markup**

If True, the text will be rendered using the *MarkupLabel*: you can change the style of the text using tags. Check the *Text Markup* documentation for more information.

*markup* is a *BooleanProperty* and defaults to False.

**previous\_image**

Image for the 'previous' ActionButtons default graphical representation.

*previous\_image* is a *StringProperty* and defaults to 'atlas://data/images/defaulttheme/previous\_normal'.

**previous\_image\_height**

Height of previous\_image image.

*app\_icon\_width* is a *NumericProperty* and defaults to 0.

**previous\_image\_width**

Width of previous\_image image.

*width* is a *NumericProperty* and defaults to 0.

**title**

Title for ActionView.

*title* is a *StringProperty* and defaults to ''.

**with\_previous**

Specifies whether clicking on ActionPrevious will load the previous screen or not. If True, the previous\_icon will be shown otherwise it will not.

*with\_previous* is a *BooleanProperty* and defaults to True.

**class** `kivy.uix.actionbar.ActionBar(**kwargs)`

Bases: `kivy.uix.boxlayoutBoxLayout`

ActionBar class, which acts as the main container for an *ActionView* instance. The ActionBar determines the overall styling aspects of the bar. *ActionItems* are not added to this class directly, but to the contained *ActionView* instance.

**Events**

*on\_previous* Fired when action\_previous of action\_view is pressed.

Please see the module documentation for more information.

**action\_view**

action\_view of the ActionBar.

*action\_view* is an *ObjectProperty* and defaults to an instance of ActionView.

**background\_color**

Background color, in the format (r, g, b, a).

*background\_color* is a *ListProperty* and defaults to [1, 1, 1, 1].

**background\_image**

Background image of the ActionBars default graphical representation.


*background\_image* is a *StringProperty* and defaults to 'atlas://data/images/defaulttheme/action\_bar'.

**border**

The border to be applied to the *background\_image*.

*border* is a *ListProperty* and defaults to [2, 2, 2, 2]

## 35.6 Anchor Layout



The *AnchorLayout* aligns its children to a border (top, bottom, left, right) or center:

```
layout = AnchorLayout(  
    anchor_x='right', anchor_y='bottom')  
btn = Button(text='Hello World')  
layout.add_widget(btn)
```

```
class kivy.uix.anchorlayout.AnchorLayout(**kwargs)
```

Bases: *kivy.uix.layout.Layout*

Anchor layout class. See the module documentation for more information.

#### **anchor\_x**

Horizontal anchor.

*anchor\_x* is an *OptionProperty* and defaults to ‘center’. It accepts values of ‘left’, ‘center’ or ‘right’.

#### **anchor\_y**

Vertical anchor.

*anchor\_y* is an *OptionProperty* and defaults to ‘center’. It accepts values of ‘top’, ‘center’ or ‘bottom’.


#### **padding**

Padding between the widget box and its children, in pixels: [padding\_left, padding\_top, padding\_right, padding\_bottom].

padding also accepts a two argument form [padding\_horizontal, padding\_vertical] and a one argument form [padding].

*padding* is a *VariableListProperty* and defaults to [0, 0, 0, 0].

## 35.7 Box Layout



*BoxLayout* arranges children in a vertical or horizontal box.

To position widgets above/below each other, use a vertical BoxLayout:

```
layout = BoxLayout(orientation='vertical')
btn1 = Button(text='Hello')
btn2 = Button(text='World')
```

```
layout.add_widget(btn1)
layout.add_widget(btn2)
```

To position widgets next to each other, use a horizontal BoxLayout. In this example, we use 10 pixel spacing between children; the first button covers 70% of the horizontal space, the second covers 30%:

```
layout = BoxLayout(spacing=10)
btn1 = Button(text='Hello', size_hint=(.7, 1))
btn2 = Button(text='World', size_hint=(.3, 1))
layout.add_widget(btn1)
layout.add_widget(btn2)
```

Position hints are partially working, depending on the orientation:

- If the orientation is *vertical*: *x*, *right* and *center\_x* will be used.
- If the orientation is *horizontal*: *y*, *top* and *center\_y* will be used.

You can check the *examples/widgets/boxlayout\_poshint.py* for a live example.

---

**Note:** The *size\_hint* uses the available space after subtracting all the fixed-size widgets. For example, if you have a layout that is 800px wide, and add three buttons like this:

```
btn1 = Button(text='Hello', size=(200, 100), size_hint=(None, None))
btn2 = Button(text='Kivy', size_hint=(.5, 1))
btn3 = Button(text='World', size_hint=(.5, 1))
```

The first button will be 200px wide as specified, the second and third will be 300px each, e.g. (800-200) \* 0.5

---

Changed in version 1.4.1: Added support for *pos\_hint*.

**class kivy.uix.boxlayout.BoxLayout(\*\*kwargs)**  
Bases: *kivy.uix.layout.Layout*

Box layout class. See module documentation for more information.

#### **minimum\_height**

Automatically computed minimum height needed to contain all children.

New in version 1.10.0.

*minimum\_height* is a *NumericProperty* and defaults to 0. It is read only.

#### **minimum\_size**

Automatically computed minimum size needed to contain all children.

New in version 1.10.0.

*minimum\_size* is a *ReferenceListProperty* of (*minimum\_width*, *minimum\_height*) properties. It is read only.

#### **minimum\_width**

Automatically computed minimum width needed to contain all children.

New in version 1.10.0.

*minimum\_width* is a *NumericProperty* and defaults to 0. It is read only.

#### **orientation**

Orientation of the layout.

*orientation* is an *OptionProperty* and defaults to 'horizontal'. Can be 'vertical' or 'horizontal'.

### **padding**

Padding between layout box and children: [padding\_left, padding\_top, padding\_right, padding\_bottom].

padding also accepts a two argument form [padding\_horizontal, padding\_vertical] and a one argument form [padding].

Changed in version 1.7.0: Replaced NumericProperty with VariableListProperty.

*padding* is a *VariableListProperty* and defaults to [0, 0, 0, 0].


### **spacing**

Spacing between children, in pixels.

*spacing* is a *NumericProperty* and defaults to 0.

## 35.8 Bubble

New in version 1.1.0.



The Bubble widget is a form of menu or a small popup where the menu options are stacked either vertically or horizontally.

The *Bubble* contains an arrow pointing in the direction you choose.

### 35.8.1 Simple example

```
...
Bubble
=====

Test of the widget Bubble.
'''

from kivy.app import App
from kivy.uix.floatlayout import FloatLayout
from kivy.uix.button import Button
from kivy.lang import Builder
from kivy.uix.bubble import Bubble

Builder.load_string('''
<cut_copy_paste>
    size_hint: (None, None)
    size: (160, 120)
    pos_hint: {'center_x': .5, 'y': .6}
    BubbleButton:
        text: 'Cut'
    BubbleButton:
        text: 'Copy'
    BubbleButton:
        text: 'Paste'
''')
```

```

class cut_copy_paste(Bubble):
    pass

class BubbleShowcase(FloatLayout):

    def __init__(self, **kwargs):
        super(BubbleShowcase, self).__init__(**kwargs)
        self.but_bubble = Button(text='Press to show bubble')
        self.but_bubble.bind(on_release=self.show_bubble)
        self.add_widget(self.but_bubble)

    def show_bubble(self, *l):
        if not hasattr(self, 'bubb'):
            self.bubb = bubb = cut_copy_paste()
            self.add_widget(bubb)
        else:
            values = ('left_top', 'left_mid', 'left_bottom', 'top_left',
                      'top_mid', 'top_right', 'right_top', 'right_mid',
                      'right_bottom', 'bottom_left', 'bottom_mid', 'bottom_right')
            index = values.index(self.bubb.arrow_pos)
            self.bubb.arrow_pos = values[(index + 1) % len(values)]


class TestBubbleApp(App):

    def build(self):
        return BubbleShowcase()

if __name__ == '__main__':
    TestBubbleApp().run()

```

### 35.8.2 Customize the Bubble

You can choose the direction in which the arrow points:

```
Bubble(arrow_pos='top_mid')
```

The widgets added to the Bubble are ordered horizontally by default, like a Boxlayout. You can change that by:

```
orientation = 'vertical'
```

To add items to the bubble:

```
bubble = Bubble(orientation = 'vertical')
bubble.add_widget(your_widget_instance)
```

To remove items:

```
bubble.remove_widget(widget)
or
bubble.clear_widgets()
```

To access the list of children, use content.children:

```
bubble.content.children
```

**Warning:** This is important! Do not use bubble.children

To change the appearance of the bubble:

```
bubble.background_color = (1, 0, 0, .5) #50% translucent red
bubble.border = [0, 0, 0, 0]
background_image = 'path/to/background/image'
arrow_image = 'path/to/arrow/image'
```

**class kivy.uix.bubble.Bubble(\*\*kwargs)**  
Bases: *kivy.uix.gridlayout.GridLayout*

Bubble class. See module documentation for more information.

#### **arrow\_image**

Image of the arrow pointing to the bubble.

*arrow\_image* is a *StringProperty* and defaults to 'atlas://data/images/defaulttheme/bubble\_arrow'.

#### **arrow\_pos**

Specifies the position of the arrow relative to the bubble. Can be one of: left\_top, left\_mid, left\_bottom top\_left, top\_mid, top\_right right\_top, right\_mid, right\_bottom bottom\_left, bottom\_mid, bottom\_right.

*arrow\_pos* is a *OptionProperty* and defaults to 'bottom\_mid'.

#### **background\_color**

Background color, in the format (r, g, b, a). To use it you have to set either *background\_image* or *arrow\_image* first.

*background\_color* is a *ListProperty* and defaults to [1, 1, 1, 1].

#### **background\_image**

Background image of the bubble.

*background\_image* is a *StringProperty* and defaults to 'atlas://data/images/defaulttheme/bubble'.

#### **border**

Border used for *BorderImage* graphics instruction. Used with the *background\_image*. It should be used when using custom backgrounds.

It must be a list of 4 values: (bottom, right, top, left). Read the BorderImage instructions for more information about how to use it.

*border* is a *ListProperty* and defaults to (16, 16, 16, 16)

#### **content**

This is the object where the main content of the bubble is held.

*content* is a *ObjectProperty* and defaults to 'None'.

#### **limit\_to**

Specifies the widget to which the bubbles position is restricted.

New in version 1.6.0.

*limit\_to* is a *ObjectProperty* and defaults to 'None'.

### **orientation**

This specifies the manner in which the children inside bubble are arranged. Can be one of ‘vertical’ or ‘horizontal’.

*orientation* is a *OptionProperty* and defaults to ‘horizontal’.

### **show\_arrow**

Indicates whether to show arrow.

New in version 1.8.0.

*show\_arrow* is a *BooleanProperty* and defaults to *True*.

**class** kivy.uix.bubble.BubbleButton(\*\*kwargs)

Bases: *kivy.uix.button.Button*

A button intended for use in a Bubble widget. You can use a “normal” button class, but it will not look good unless the background is changed.

Rather use this BubbleButton widget that is already defined and provides a suitable background for you.

## 35.9 Button



The *Button* is a *Label* with associated actions that are triggered when the button is pressed (or released after a click/touch). To configure the button, the same properties (padding, font\_size, etc) and *sizing system* are used as for the *Label* class:

```
button = Button(text='Hello world', font_size=14)
```

To attach a callback when the button is pressed (clicked/touched), use `bind`:

```
def callback(instance):
    print('The button <%s> is being pressed' % instance.text)

btn1 = Button(text='Hello world 1')
btn1.bind(on_press=callback)
btn2 = Button(text='Hello world 2')
btn2.bind(on_press=callback)
```

If you want to be notified every time the button state changes, you can bind to the `Button.state` property:

```
def callback(instance, value):
    print('My button <%s> state is <%s>' % (instance, value))
btn1 = Button(text='Hello world 1')
btn1.bind(state=callback)
```

**class** kivy.uix.button.Button(\*\*kwargs)

Bases: *kivy.uix.behaviors.button.ButtonBehavior, kivy.uix.label.Label*

Button class, see module documentation for more information.

Changed in version 1.8.0: The behavior / logic of the button has been moved to `ButtonBehaviors`.

### **background\_color**

Background color, in the format (r, g, b, a).

This acts as a *multiplier* to the texture colour. The default texture is grey, so just setting the background color will give a darker result. To set a plain color, set the `background_normal` to ''.

New in version 1.0.8.

The `background_color` is a `ListProperty` and defaults to [1, 1, 1, 1].

### **background\_disabled\_down**

Background image of the button used for the default graphical representation when the button is disabled and pressed.

New in version 1.8.0.

`background_disabled_down` is a `StringProperty` and defaults to 'atlas://data/images/defaulttheme/button\_disabled\_pressed'.

### **background\_disabled\_normal**

Background image of the button used for the default graphical representation when the button is disabled and not pressed.

New in version 1.8.0.

`background_disabled_normal` is a `StringProperty` and defaults to 'atlas://data/images/defaulttheme/button\_disabled'.

### **background\_down**

Background image of the button used for the default graphical representation when the button is pressed.

New in version 1.0.4.

`background_down` is a `StringProperty` and defaults to 'atlas://data/images/defaulttheme/button\_pressed'.

### **background\_normal**

Background image of the button used for the default graphical representation when the button is not pressed.

New in version 1.0.4.

`background_normal` is a `StringProperty` and defaults to 'atlas://data/images/defaulttheme/button'.

### **border**

Border used for `BorderImage` graphics instruction. Used with `background_normal` and `background_down`. Can be used for custom backgrounds.

It must be a list of four values: (bottom, right, top, left). Read the `BorderImage` instruction for more information about how to use it.

`border` is a `ListProperty` and defaults to (16, 16, 16, 16)

## 35.10 Camera

The `Camera` widget is used to capture and display video from a camera. Once the widget is created, the texture inside the widget will be automatically updated. Our `CameraBase` implementation is used under the hood:

```
cam = Camera()
```

By default, the first camera found on your system is used. To use a different camera, set the index property:

```
cam = Camera(index=1)
```

You can also select the camera resolution:

```
cam = Camera(resolution=(320, 240))
```

**Warning:** The camera texture is not updated as soon as you have created the object. The camera initialization is asynchronous, so there may be a delay before the requested texture is created.

**class** `kivy.uix.camera.Camera(**kwargs)`  
Bases: `kivy.uix.image.Image`

Camera class. See module documentation for more information.

### **index**

Index of the used camera, starting from 0.

`index` is a `NumericProperty` and defaults to -1 to allow auto selection.

### **play**

Boolean indicating whether the camera is playing or not. You can start/stop the camera by setting this property:

```
# start the camera playing at creation (default)
cam = Camera(play=True)

# create the camera, and start later
cam = Camera(play=False)
# and later
cam.play = True
```

`play` is a `BooleanProperty` and defaults to True.

### **resolution**

Preferred resolution to use when invoking the camera. If you are using [-1, -1], the resolution will be the default one:

```
# create a camera object with the best image available
cam = Camera()

# create a camera object with an image of 320x240 if possible
cam = Camera(resolution=(320, 240))
```

**Warning:** Depending on the implementation, the camera may not respect this property.

*resolution* is a *ListProperty* and defaults to [-1, -1].

## 35.11 Carousel

New in version 1.4.0.

The *Carousel* widget provides the classic mobile-friendly carousel view where you can swipe between slides. You can add any content to the carousel and have it move horizontally or vertically. The carousel can display pages in a sequence or a loop.

Example:

```
from kivy.app import App
from kivy.uix.carousel import Carousel
from kivy.uix.image import AsyncImage

class CarouselApp(App):
    def build(self):
        carousel = Carousel(direction='right')
        for i in range(10):
            src = "http://placehold.it/480x270.png&text=slide-%d&.png" % i
            image = AsyncImage(source=src, allow_stretch=True)
            carousel.add_widget(image)
        return carousel

CarouselApp().run()
```

Changed in version 1.5.0: The carousel now supports active children, like the *ScrollView*. It will detect a swipe gesture according to the *Carousel.scroll\_timeout* and *Carousel.scroll\_distance* properties.

In addition, the slide container is no longer exposed by the API. The impacted properties are *Carousel.slides*, *Carousel.current\_slide*, *Carousel.previous\_slide* and *Carousel.next\_slide*.

**class kivy.uix.carousel.Carousel(\*\*kwargs)**  
Bases: *kivy.uix.stencilview.StencilView*

Carousel class. See module documentation for more information.

### **anim\_cancel\_duration**

Defines the duration of the animation when a swipe movement is not accepted. This is generally when the user does not make a large enough swipe. See *min\_move*.

*anim\_cancel\_duration* is a *NumericProperty* and defaults to 0.3.

### **anim\_move\_duration**

Defines the duration of the Carousel animation between pages.

*anim\_move\_duration* is a *NumericProperty* and defaults to 0.5.

### **anim\_type**

Type of animation to use while animating to the next/previous slide. This should be the name of an *AnimationTransition* function.

*anim\_type* is a *StringProperty* and defaults to 'out\_quad'.

New in version 1.8.0.

**current\_slide**

The currently shown slide.

*current\_slide* is an *AliasProperty*.

Changed in version 1.5.0: The property no longer exposes the slides container. It returns the widget you have added.

**direction**

Specifies the direction in which the slides are ordered. This corresponds to the direction from which the user swipes to go from one slide to the next. It can be *right*, *left*, *top*, or *bottom*. For example, with the default value of *right*, the second slide is to the right of the first and the user would swipe from the right towards the left to get to the second slide.

*direction* is an *OptionProperty* and defaults to 'right'.

**ignore\_perpendicular\_swipes**

Ignore swipes on axis perpendicular to direction.

*ignore\_perpendicular\_swipes* is a *BooleanProperty* and defaults to False.

New in version 1.10.0.

**index**

Get/Set the current slide based on the index.

*index* is an *AliasProperty* and defaults to 0 (the first item).

**load\_next(mode='next')**

Animate to the next slide.

New in version 1.7.0.

**load\_previous()**

Animate to the previous slide.

New in version 1.7.0.

**load\_slide(slid)**

Animate to the slide that is passed as the argument.

Changed in version 1.8.0.

**loop**

Allow the Carousel to loop infinitely. If True, when the user tries to swipe beyond last page, it will return to the first. If False, it will remain on the last page.

*loop* is a *BooleanProperty* and defaults to False.

**min\_move**

Defines the minimum distance to be covered before the touch is considered a swipe gesture and the Carousel content changed. This is expressed as a fraction of the Carousel's width. If the movement doesn't reach this minimum value, the movement is cancelled and the content is restored to its original position.

*min\_move* is a *NumericProperty* and defaults to 0.2.

**next\_slide**

The next slide in the Carousel. It is None if the current slide is the last slide in the Carousel. This ordering reflects the order in which the slides are added: their presentation varies according to the *direction* property.

*next\_slide* is an *AliasProperty*.

Changed in version 1.5.0: The property no longer exposes the slides container. It returns the widget you have added.

### **previous\_slide**

The previous slide in the Carousel. It is None if the current slide is the first slide in the Carousel. This ordering reflects the order in which the slides are added: their presentation varies according to the *direction* property.

*previous\_slide* is an *AliasProperty*.

Changed in version 1.5.0: This property no longer exposes the slides container. It returns the widget you have added.

### **scroll\_distance**

Distance to move before scrolling the *Carousel* in pixels. As soon as the distance has been traveled, the *Carousel* will start to scroll, and no touch event will go to children. It is advisable that you base this value on the dpi of your target device's screen.

*scroll\_distance* is a *NumericProperty* and defaults to 20dp.

New in version 1.5.0.

### **scroll\_timeout**

Timeout allowed to trigger the *scroll\_distance*, in milliseconds. If the user has not moved *scroll\_distance* within the timeout, no scrolling will occur and the touch event will go to the children.

*scroll\_timeout* is a *NumericProperty* and defaults to 200 (milliseconds)

New in version 1.5.0.


### **slides**

List of slides inside the Carousel. The slides are the widgets added to the Carousel using the *add\_widget* method.

*slides* is a *ListProperty* and is read-only.

## 35.12 CheckBox

New in version 1.4.0.



*CheckBox* is a specific two-state button that can be either checked or unchecked. If the CheckBox is in a Group, it becomes a Radio button. As with the *ToggleButton*, only one Radio button at a time can be selected when the *CheckBox.group* is set.

An example usage:

```

from kivy.uix.checkbox import CheckBox

# ...

def on_checkbox_active(checkbox, value):
    if value:
        print('The checkbox', checkbox, 'is active')
    else:
        print('The checkbox', checkbox, 'is inactive')

checkbox = CheckBox()
checkbox.bind(active=on_checkbox_active)

```

**class kivy.uix.checkbox.CheckBox(\*\*kwargs)**  
Bases: *kivy.uix.behaviors.togglebutton.ToggleButtonBehavior, kivy.uix.widget.Widget*

CheckBox class, see module documentation for more information.

#### **active**

Indicates if the switch is active or inactive.

*active* is a *BooleanProperty* and defaults to False.

#### **background\_checkbox\_disabled\_down**

Background image of the checkbox used for the default graphical representation when the checkbox is disabled and active.

New in version 1.9.0.

*background\_checkbox\_disabled\_down* is a *StringProperty* and defaults to ‘atlas://data/images/defaulttheme/checkbox\_disabled\_on’.

#### **background\_checkbox\_disabled\_normal**

Background image of the checkbox used for the default graphical representation when the checkbox is disabled and not active.

New in version 1.9.0.

*background\_checkbox\_disabled\_normal* is a *StringProperty* and defaults to ‘atlas://data/images/defaulttheme/checkbox\_disabled\_off’.

#### **background\_checkbox\_down**

Background image of the checkbox used for the default graphical representation when the checkbox is active.

New in version 1.9.0.

*background\_checkbox\_down* is a *StringProperty* and defaults to ‘atlas://data/images/defaulttheme/checkbox\_on’.

#### **background\_checkbox\_normal**

Background image of the checkbox used for the default graphical representation when the checkbox is not active.

New in version 1.9.0.

*background\_checkbox\_normal* is a *StringProperty* and defaults to ‘atlas://data/images/defaulttheme/checkbox\_off’.

#### **background\_radio\_disabled\_down**

Background image of the radio button used for the default graphical representation when the radio button is disabled and active.

New in version 1.9.0.

*background\_radio\_disabled\_down* is a *StringProperty* and defaults to ‘atlas://data/images/defaulttheme/checkbox\_radio\_disabled\_on’.

#### **background\_radio\_disabled\_normal**

Background image of the radio button used for the default graphical representation when the radio button is disabled and not active.

New in version 1.9.0.

*background\_radio\_disabled\_normal* is a *StringProperty* and defaults to ‘atlas://data/images/defaulttheme/checkbox\_radio\_disabled\_off’.

#### **background\_radio\_down**

Background image of the radio button used for the default graphical representation when the radio button is active.

New in version 1.9.0.

*background\_radio\_down* is a *StringProperty* and defaults to ‘atlas://data/images/defaulttheme/checkbox\_radio\_on’.

#### **background\_radio\_normal**

Background image of the radio button used for the default graphical representation when the radio button is not active.

New in version 1.9.0.

*background\_radio\_normal* is a *StringProperty* and defaults to ‘atlas://data/images/defaulttheme/checkbox\_radio\_off’.

#### **color**

Color is used for tinting the default graphical representation of checkbox and radio button (images).

Color is in the format (r, g, b, a). Use alpha greater than 1 for brighter colors. Alpha greater than 4 causes blending border and check mark together.

New in version 1.10.0.

*color* is a *ListProperty* and defaults to ‘[1, 1, 1, 1]’.

## 35.13 Code Input

New in version 1.5.0.

```
if __name__ == '__main__':
    from kivy.app import App
    from kivy.uix.boxlayout import BoxLayout

    class TextInputApp(App):

        def build(self):
            root = BoxLayout(orientation='vertical')
            textinput = TextInput(multiline=True)
            textinput.text = __doc__
            root.add_widget(textinput)
            textinput2 = TextInput(text='monoline textinput',
                                  size_hint=(1, None), height=30)
            root.add_widget(textinput2)
            return root

    TextInputApp().run()
```

**BoxLayout:**  
# Double as a Tabbed Panel Demo!

**TabbedPanel:**  
tab\_pos: "top\_right"  
default\_tab\_text: "List View"  
default\_tab\_content: list\_view\_tab

**TabbedPanelHeader:**  
text: 'Icon View'  
content: icon\_view\_tab

**FileChooserListView:**  
id: list\_view\_tab

**FileChooserIconView:**  
id: icon\_view\_tab  
show\_hidden: True

---

**Note:** This widget requires `pygments` package to run. Install it with `pip`.

---

The `CodeInput` provides a box of editable highlighted text like the one shown in the image.

It supports all the features provided by the `TextInput` as well as code highlighting for `languages supported by pygments` along with `KivyLexer` for `kivy.lang` highlighting.

### 35.13.1 Usage example

To create a `CodeInput` with highlighting for *KV language*:

```
from kivy.uix.codeinput import CodeInput
from kivy.extras.highlight import KivyLexer
codeinput = CodeInput(lexer=KivyLexer())
```

To create a `CodeInput` with highlighting for *Cython*:

```
from kivy.uix.codeinput import CodeInput
from pygments.lexers import CythonLexer
codeinput = CodeInput(lexer=CythonLexer())
```

**class** `kivy.uix.codeinput.CodeInput(**kwargs)`  
Bases: `kivy.uix.behaviors.codenavigation.CodeNavigationBehavior, kivy.uix.TextInput`

`CodeInput` class, used for displaying highlighted code.

**lexer**

This holds the selected Lexer used by `pygments` to highlight the code.

`lexer` is an *ObjectProperty* and defaults to `PythonLexer`.

**style**

The `pygments` style object to use for formatting.

When `style_name` is set, this will be changed to the corresponding style object.

`style` is a *ObjectProperty* and defaults to `None`

**style\_name**


Name of the `pygments` style to use for formatting.

`style_name` is an *OptionProperty* and defaults to '`default`'.

## 35.14 Color Picker

New in version 1.7.0.

**Warning:** This widget is experimental. Its use and API can change at any time until this warning is removed.



The ColorPicker widget allows a user to select a color from a chromatic wheel where pinch and zoom can be used to change the wheel's saturation. Sliders and TextInput are also provided for entering the RGBA/HSV/HEX values directly.

Usage:

```
clr_picker = ColorPicker()
parent.add_widget(clr_picker)

# To monitor changes, we can bind to color property changes
def on_color(instance, value):
    print "RGBA = ", str(value) # or instance.color
    print "HSV = ", str(instance.hsv)
    print "HEX = ", str(instance.hex_color)

clr_picker.bind(color=on_color)
```

**class kivy.uix.colorpicker.ColorPicker(\*\*kwargs)**  
Bases: [kivy.uix.relativelayout.RelativeLayout](#)

See module documentation.

#### color

The **color** holds the color currently selected in rgba format.

**color** is a [ListProperty](#) and defaults to (1, 1, 1, 1).

#### font\_name

Specifies the font used on the ColorPicker.

**font\_name** is a [StringProperty](#) and defaults to 'data/fonts/RobotoMono-Regular.ttf'.

#### hex\_color

The **hex\_color** holds the currently selected color in hex.

**hex\_color** is an [AliasProperty](#) and defaults to #ffffffff.

#### hsv

The **hsv** holds the color currently selected in hsv format.

**hsv** is a [ListProperty](#) and defaults to (1, 1, 1).

#### wheel

The **wheel** holds the color wheel.

**wheel** is an [ObjectProperty](#) and defaults to None.

```

class kivy.uix.colorpicker.ColorWheel(**kwargs)
    Bases: kivy.uix.widget.Widget

    Chromatic wheel for the ColorPicker.

    Changed in version 1.7.1: font_size, font_name and foreground_color have been removed. The sizing is now the same as others widget, based on 'sp'. Orientation is also automatically determined according to the width/height ratio.

a
    The Alpha value of the color currently selected.

    a is a BoundedNumericProperty and can be a value from 0 to 1.

b
    The Blue value of the color currently selected.

    b is a BoundedNumericProperty and can be a value from 0 to 1.

color
    The holds the color currently selected.

    color is a ReferenceListProperty and contains a list of r, g, b, a values.

g
    The Green value of the color currently selected.

    g is a BoundedNumericProperty and can be a value from 0 to 1.

r
    The Red value of the color currently selected.

    r is a BoundedNumericProperty and can be a value from 0 to 1. It defaults to 0.

```

## 35.15 Drop-Down List

New in version 1.4.0.

A versatile drop-down list that can be used with custom widgets. It allows you to display a list of widgets under a displayed widget. Unlike other toolkits, the list of widgets can contain any type of widget: simple buttons, images etc.

The positioning of the drop-down list is fully automatic: we will always try to place the dropdown list in a way that the user can select an item in the list.

### 35.15.1 Basic example

A button with a dropdown list of 10 possible values. All the buttons within the dropdown list will trigger the dropdown [DropDown.select\(\)](#) method. After being called, the main button text will display the selection of the dropdown.

```

from kivy.uix.dropdown import DropDown
from kivy.uix.button import Button
from kivy.base import runTouchApp

# create a dropdown with 10 buttons
dropdown = DropDown()
for index in range(10):
    # When adding widgets, we need to specify the height manually
    # (disabling the size_hint_y) so the dropdown can calculate

```

```

# the area it needs.

btn = Button(text='Value %d' % index, size_hint_y=None, height=44)

# for each button, attach a callback that will call the select() method
# on the dropdown. We'll pass the text of the button as the data of the
# selection.
btn.bind(on_release=lambda btn: dropdown.select(btn.text))

# then add the button inside the dropdown
dropdown.add_widget(btn)

# create a big main button
mainbutton = Button(text='Hello', size_hint=(None, None))

# show the dropdown menu when the main button is released
# note: all the bind() calls pass the instance of the caller (here, the
# mainbutton instance) as the first argument of the callback (here,
# dropdown.open.).
mainbutton.bind(on_release=dropdown.open)

# one last thing, listen for the selection in the dropdown list and
# assign the data to the button text.
dropdown.bind(on_select=lambda instance, x: setattr(mainbutton, 'text', x))

runTouchApp(mainbutton)

```

### 35.15.2 Extending dropdown in Kv

You could create a dropdown directly from your kv:

```

#:kivy 1.4.0
<CustomDropDown>:
    Button:
        text: 'My first Item'
        size_hint_y: None
        height: 44
        on_release: root.select('item1')
    Label:
        text: 'Unselectable item'
        size_hint_y: None
        height: 44
    Button:
        text: 'My second Item'
        size_hint_y: None
        height: 44
        on_release: root.select('item2')

```

And then, create the associated python class and use it:

```

class CustomDropDown(DropDown):
    pass

dropdown = CustomDropDown()
mainbutton = Button(text='Hello', size_hint=(None, None))
mainbutton.bind(on_release=dropdown.open)
dropdown.bind(on_select=lambda instance, x: setattr(mainbutton, 'text', x))

```

```
class kivy.uix.dropdown.DropDown(**kwargs)
Bases: kivy.uix.scrollview.ScrollView
```

DropDown class. See module documentation for more information.

#### Events

**on\_select: data** Fired when a selection is done. The data of the selection is passed in as the first argument and is what you pass in the **select()** method as the first argument.

**on\_dismiss:** New in version 1.8.0.

Fired when the DropDown is dismissed, either on selection or on touching outside the widget.

#### attach\_to

(internal) Property that will be set to the widget to which the drop down list is attached.

The **open()** method will automatically set this property whilst **dismiss()** will set it back to None.

#### auto\_dismiss

By default, the dropdown will be automatically dismissed when a touch happens outside of it, this option allows to disable this feature

**auto\_dismiss** is a *BooleanProperty* and defaults to True.

New in version 1.8.0.

#### auto\_width

By default, the width of the dropdown will be the same as the width of the attached widget. Set to False if you want to provide your own width.

**auto\_width** is a *BooleanProperty* and defaults to True.

#### container

(internal) Property that will be set to the container of the dropdown list. It is a *GridLayout* by default.

#### dismiss(\*args)

Remove the dropdown widget from the window and detach it from the attached widget.

#### dismiss\_on\_select

By default, the dropdown will be automatically dismissed when a selection has been done. Set to False to prevent the dismiss.

**dismiss\_on\_select** is a *BooleanProperty* and defaults to True.

#### max\_height

Indicate the maximum height that the dropdown can take. If None, it will take the maximum height available until the top or bottom of the screen is reached.

**max\_height** is a *NumericProperty* and defaults to None.

#### min\_state\_time

Minimum time before the DropDown is dismissed. This is used to allow for the widget inside the dropdown to display a down state or for the DropDown itself to display a animation for closing.

**min\_state\_time** is a *NumericProperty* and defaults to the Config value *min\_state\_time*.

New in version 1.10.0.

#### open(widget)

Open the dropdown list and attach it to a specific widget. Depending on the position of the

widget within the window and the height of the dropdown, the dropdown might be above or below that widget.

### **select(*data*)**

Call this method to trigger the *on\_select* event with the *data* selection. The *data* can be anything you want.

## 35.16 EffectWidget

New in version 1.9.0.

The **EffectWidget** is able to apply a variety of fancy graphical effects to its children. It works by rendering to a series of **Fbo** instances with custom opengl fragment shaders. As such, effects can freely do almost anything, from inverting the colors of the widget, to anti-aliasing, to emulating the appearance of a crt monitor!

**Warning:** This code is still experimental, and its API is subject to change in a future version.

The basic usage is as follows:

```
w = EffectWidget()
w.add_widget(Button(text='Hello!'))
w.effects = [InvertEffect(), HorizontalBlurEffect(size=2.0)]
```

The equivalent in kv would be:

```
#: import ew.kivy.uix.effectwidget
EffectWidget:
    effects: ew.InvertEffect(), ew.HorizontalBlurEffect(size=2.0)
    Button:
        text: 'Hello!'
```

The effects can be a list of effects of any length, and they will be applied sequentially.

The module comes with a range of prebuilt effects, but the interface is designed to make it easy to create your own. Instead of writing a full glsl shader, you provide a single function that takes some inputs based on the screen (current pixel color, current widget texture etc.). See the sections below for more information.

### 35.16.1 Usage Guidelines

It is not efficient to resize an **EffectWidget**, as the **Fbo** is recreated on each resize event. If you need to resize frequently, consider doing things a different way.

Although some effects have adjustable parameters, it is *not* efficient to animate these, as the entire shader is reconstructed every time. You should use glsl uniform variables instead. The **AdvancedEffectBase** may make this easier.

---

**Note:** The **EffectWidget** cannot draw outside its own widget area (pos -> pos + size). Any child widgets overlapping the boundary will be cut off at this point.

---

## 35.16.2 Provided Effects

The module comes with several pre-written effects. Some have adjustable properties (e.g. blur radius). Please see the individual effect documentation for more details.

- *MonochromeEffect* - makes the widget grayscale.
- *InvertEffect* - inverts the widget colors.
- *ChannelMixEffect* - swaps color channels.
- *ScanlinesEffect* - displays flickering scanlines.
- *PixelateEffect* - pixelates the image.
- *HorizontalBlurEffect* - Gaussuan blurs horizontally.
- *VerticalBlurEffect* - Gaussuan blurs vertically.
- *FXAAEffect* - applies a very basic anti-aliasing.

## 35.16.3 Creating Effects

Effects are designed to make it easy to create and use your own transformations. You do this by creating and using an instance of *EffectBase* with your own custom *EffectBase.gsl* property.

The *gsl* property is a string representing part of a *gsl* fragment shader. You can include as many functions as you like (the string is simply spliced into the whole shader), but it must implement a function *effect* as below:

```
vec4 effect(vec4 color, sampler2D texture, vec2 tex_coords, vec2 coords)
{
    // ... your code here
    return something; // must be a vec4 representing the new color
}
```

The full shader will calculate the normal pixel color at each point, then call your *effect* function to transform it. The parameters are:

- **color**: The normal color of the current pixel (i.e. texture sampled at *tex\_coords*).
- **texture**: The texture containing the widget's normal background.
- **tex\_coords**: The normal *texture\_coords* used to access texture.
- **coords**: The pixel indices of the current pixel.

The shader code also has access to two useful uniform variables, *time* containing the time (in seconds) since the program start, and *resolution* containing the shape (x pixels, y pixels) of the widget.

For instance, the following simple string (taken from the *InvertEffect*) would invert the input color but set alpha to 1.0:

```
vec4 effect(vec4 color, sampler2D texture, vec2 tex_coords, vec2 coords)
{
    return vec4(1.0 - color.xyz, 1.0);
}
```

You can also set the *gsl* by automatically loading the string from a file, simply set the *EffectBase.source* property of an effect.

```
class kivy.uix.effectwidget.EffectWidget(**kwargs)
Bases: kivy.uix.relativelayout.RelativeLayout
```

Widget with the ability to apply a series of graphical effects to its children. See the module documentation for more information on setting effects and creating your own.

### **background\_color**

This defines the background color to be used for the fbo in the EffectWidget.

*background\_color* is a `ListProperty` defaults to (0, 0, 0, 0)

### **effects**

List of all the effects to be applied. These should all be instances or subclasses of `EffectBase`.

`effects` is a `ListProperty` and defaults to [].

### **fbo\_list**

(internal) List of all the fbos that are being used to apply the effects.

`fbo_list` is a `ListProperty` and defaults to [].

### **refresh\_fbo\_setup(\*args)**

(internal) Creates and assigns one `Fbo` per effect, and makes sure all sizes etc. are correct and consistent.

### **texture**

The output texture of the final `Fbo` after all effects have been applied.

`texture` is an `ObjectProperty` and defaults to None.

**class** `kivy.uix.effectwidget.EffectBase(*args, **kwargs)`

Bases: `kivy.event.EventDispatcher`

The base class for GLSL effects. It simply returns its input.

See the module documentation for more details.

### **fbo**

The fbo currently using this effect. The `EffectBase` automatically handles this.

`fbo` is an `ObjectProperty` and defaults to None.

### **glsl**

The glsl string defining your effect function. See the module documentation for more details.

`glsl` is a `StringProperty` and defaults to a trivial effect that returns its input.

### **set\_fbo\_shader(\*args)**

Sets the `Fbo`'s shader by splicing the `glsl` string into a full fragment shader.

The full shader is made up of `shader_header + shader_uniforms + self.glsl + shader_footer_effect`.

### **source**

The (optional) filename from which to load the `glsl` string.

`source` is a `StringProperty` and defaults to "".

**class** `kivy.uix.effectwidget.AdvancedEffectBase(*args, **kwargs)`

Bases: `kivy.uix.effectwidget.EffectBase`

An `EffectBase` with additional behavior to easily set and update uniform variables in your shader.

This class is provided for convenience when implementing your own effects: it is not used by any of those provided with Kivy.

In addition to your base glsl string that must be provided as normal, the `AdvancedEffectBase` has an extra property `uniforms`, a dictionary of name-value pairs. Whenever a value is changed, the new value for the uniform variable is uploaded to the shader.

You must still manually declare your uniform variables at the top of your glsl string.

### uniforms

A dictionary of uniform variable names and their values. These are automatically uploaded to the fbo shader if appropriate.

uniforms is a *DictProperty* and defaults to {}.

**class** `kivy.uix.effectwidget.MonochromeEffect(*args, **kwargs)`  
Bases: `kivy.uix.effectwidget.EffectBase`

Returns its input colors in monochrome.

**class** `kivy.uix.effectwidget.InvertEffect(*args, **kwargs)`  
Bases: `kivy.uix.effectwidget.EffectBase`

Inverts the colors in the input.

**class** `kivy.uix.effectwidget.ChannelMixEffect(*args, **kwargs)`  
Bases: `kivy.uix.effectwidget.EffectBase`

Mixes the color channels of the input according to the order property. Channels may be arbitrarily rearranged or repeated.

### order

The new sorted order of the rgb channels.

order is a *ListProperty* and defaults to [1, 2, 0], corresponding to (g, b, r).

**class** `kivy.uix.effectwidget.ScanlinesEffect(*args, **kwargs)`  
Bases: `kivy.uix.effectwidget.EffectBase`

Adds scanlines to the input.

**class** `kivy.uix.effectwidget.PixelateEffect(*args, **kwargs)`  
Bases: `kivy.uix.effectwidget.EffectBase`

Pixelates the input according to its *pixel\_size*

### pixel\_size

Sets the size of a new ‘pixel’ in the effect, in terms of number of ‘real’ pixels.

*pixel\_size* is a *NumericProperty* and defaults to 10.

**class** `kivy.uix.effectwidget.HorizontalBlurEffect(*args, **kwargs)`  
Bases: `kivy.uix.effectwidget.EffectBase`

Blurs the input horizontally, with the width given by *size*.

### size

The blur width in pixels.

*size* is a *NumericProperty* and defaults to 4.0.

**class** `kivy.uix.effectwidget.VerticalBlurEffect(*args, **kwargs)`  
Bases: `kivy.uix.effectwidget.EffectBase`

Blurs the input vertically, with the width given by *size*.

### size

The blur width in pixels.

*size* is a *NumericProperty* and defaults to 4.0.

**class** `kivy.uix.effectwidget.FXAAEffect(*args, **kwargs)`  
Bases: `kivy.uix.effectwidget.EffectBase`

Applies very simple anti-aliasing via fxaa.

## 35.17 FileChooser

The FileChooser module provides various classes for describing, displaying and browsing file systems.


### 35.17.1 Simple widgets

There are two ready-to-use widgets that provide views of the file system. Each of these present the files and folders in a different style.

The *FileChooserListView* displays file entries as text items in a vertical list, where folders can be collapsed and expanded.

Name	Size
.. /	
> build	
> doc	
> examples	
> kivy	
AUTHORS	2 KB
CONTRIBUTING.md	3 KB
LICENSE	1 KB
MANIFEST.in	319 B
Makefile	4 KB
README.md	4 KB
setup.cfg	69 B
setup.py	35 KB

The *FileChooserIconView* presents icons and text from left to right, wrapping them as required.



They both provide for scrolling, selection and basic user interaction. Please refer to the [FileChooserController](#) for details on supported events and properties.

### 35.17.2 Widget composition

FileChooser classes adopt a [MVC](#) design. They are exposed so that you can extend and customize your file chooser according to your needs.

The FileChooser classes can be categorized as follows:

- Models are represented by concrete implementations of the [FileSystemAbstract](#) class, such as the [FileSystemLocal](#).
- Views are represented by the [FileChooserListLayout](#) and [FileChooserIconLayout](#) classes. These are used by the [FileChooserListView](#) and [FileChooserIconView](#) widgets respectively.
- Controllers are represented by concrete implementations of the [FileChooserController](#), namely the [FileChooser](#), [FileChooserIconView](#) and [FileChooserListView](#) classes.

This means you can define your own views or provide [FileSystemAbstract](#) implementations for alternative file systems for use with these widgets. The [FileChooser](#) can be used as a controller for handling multiple, synchronized views of the same path. By combining these elements, you can add your own views and file systems and have them easily interact with the existing components.

### 35.17.3 Usage example

main.py

```
from kivy.app import App
from kivy.uix.floatlayout import FloatLayout
from kivy.factory import Factory
from kivy.properties import ObjectProperty
from kivy.uix.popup import Popup
```

```

import os

class LoadDialog(FloatLayout):
    load = ObjectProperty(None)
    cancel = ObjectProperty(None)

class SaveDialog(FloatLayout):
    save = ObjectProperty(None)
    text_input = ObjectProperty(None)
    cancel = ObjectProperty(None)

class Root(FloatLayout):
    loadfile = ObjectProperty(None)
    savefile = ObjectProperty(None)
    text_input = ObjectProperty(None)

    def dismiss_popup(self):
        self._popup.dismiss()

    def show_load(self):
        content = LoadDialog(load=self.load, cancel=self.dismiss_popup)
        self._popup = Popup(title="Load file", content=content,
                            size_hint=(0.9, 0.9))
        self._popup.open()

    def show_save(self):
        content = SaveDialog(save=self.save, cancel=self.dismiss_popup)
        self._popup = Popup(title="Save file", content=content,
                            size_hint=(0.9, 0.9))
        self._popup.open()

    def load(self, path, filename):
        with open(os.path.join(path, filename[0])) as stream:
            self.text_input.text = stream.read()

        self.dismiss_popup()

    def save(self, path, filename):
        with open(os.path.join(path, filename), 'w') as stream:
            stream.write(self.text_input.text)

        self.dismiss_popup()

class Editor(App):
    pass

Factory.register('Root', cls=Root)
Factory.register('LoadDialog', cls=LoadDialog)
Factory.register('SaveDialog', cls=SaveDialog)

if __name__ == '__main__':
    Editor().run()

```

editor.kv

```
#:kivy 1.1.0

Root:
    text_input: text_input

BoxLayout:
    orientation: 'vertical'
    BoxLayout:
        size_hint_y: None
        height: 30
        Button:
            text: 'Load'
            on_release: root.show_load()
        Button:
            text: 'Save'
            on_release: root.show_save()

    BoxLayout:
        TextInput:
            id: text_input
            text: ''

        RstDocument:
            text: text_input.text
            show_errors: True

<LoadDialog>:
    BoxLayout:
        size: root.size
        pos: root.pos
        orientation: "vertical"
        FileChooserListView:
            id: filechooser

    BoxLayout:
        size_hint_y: None
        height: 30
        Button:
            text: "Cancel"
            on_release: root.cancel()

        Button:
            text: "Load"
            on_release: root.load(filechooser.path, filechooser.selection)

<SaveDialog>:
    text_input: text_input
    BoxLayout:
        size: root.size
        pos: root.pos
        orientation: "vertical"
        FileChooserListView:
            id: filechooser
            on_selection: text_input.text = self.selection and self.selection[0]_
            or ''
            or '''

    TextInput:
        id: text_input
        size_hint_y: None
        height: 30
```

```

        multiline: False

BoxLayout:
    size_hint_y: None
    height: 30
    Button:
        text: "Cancel"
        on_release: root.cancel()

    Button:
        text: "Save"
        on_release: root.save(filechooser.path, text_input.text)

```

New in version 1.0.5.

Changed in version 1.2.0: In the chooser template, the *controller* is no longer a direct reference but a weak-reference. If you are upgrading, you should change the notation *root.controller.xxx* to *root.controller().xxx*.

**class kivy.uix.filechooser.FileChooserListView(\*\*kwargs)**  
Bases: *kivy.uix.filechooser.FileChooserController*

Implementation of a *FileChooserController* using a list view.

New in version 1.9.0.

**class kivy.uix.filechooser.FileChooserIconView(\*\*kwargs)**  
Bases: *kivy.uix.filechooser.FileChooserController*

Implementation of a *FileChooserController* using an icon view.

New in version 1.9.0.

**class kivy.uix.filechooser.FileChooserListLayout(\*\*kwargs)**  
Bases: *kivy.uix.filechooser.FileChooserLayout*

File chooser layout using a list view.

New in version 1.9.0.

**class kivy.uix.filechooser.FileChooserIconLayout(\*\*kwargs)**  
Bases: *kivy.uix.filechooser.FileChooserLayout*

File chooser layout using an icon view.

New in version 1.9.0.

**class kivy.uix.filechooser.FileChooser(\*\*kwargs)**  
Bases: *kivy.uix.filechooser.FileChooserController*

Implementation of a *FileChooserController* which supports switching between multiple, synced layout views.

The FileChooser can be used as follows:

```

BoxLayout:
    orientation: 'vertical'

    BoxLayout:
        size_hint_y: None
        height: sp(52)

        Button:
            text: 'Icon View'
            on_press: fc.view_mode = 'icon'

```

```
Button:  
    text: 'List View'  
    on_press: fc.view_mode = 'list'  
  
FileChooser:  
    id: fc  
    FileChooserIconLayout  
    FileChooserListView
```

New in version 1.9.0.

### manager

Reference to the [ScreenManager](#) instance.

manager is an [ObjectProperty](#).

### view\_list

List of views added to this FileChooser.

view\_list is an [AliasProperty](#) of type `list`.

### view\_mode

Current layout view mode.

view\_mode is an [AliasProperty](#) of type `str`.

**class** `kivy.uix.filechooser.FileChooserController(**kwargs)`

Bases: [kivy.uix.relativelayout.RelativeLayout](#)

Base for implementing a FileChooser. Don't use this class directly, but prefer using an implementation such as the [FileChooser](#), [FileChooserListView](#) or [FileChooserIconView](#).

### Events

**on\_entry\_added: entry, parent** Fired when a root-level entry is added to the file list.

If you return True from this event, the entry is not added to FileChooser.

**on\_entries\_cleared** Fired when the entries list is cleared, usually when the root is refreshed.

**on\_subentry\_to\_entry: entry, parent** Fired when a sub-entry is added to an existing entry or when entries are removed from an entry e.g. when a node is closed.

**on\_submit: selection, touch** Fired when a file has been selected with a double-tap.

### cancel(\*args)

Cancel any background action started by filechooser, such as loading a new directory.

New in version 1.2.0.

### dirselect

Determines whether directories are valid selections or not.

dirselect is a [BooleanProperty](#) and defaults to False.

New in version 1.1.0.

### entry\_released(entry, touch)

(internal) This method must be called by the template when an entry is touched by the user.

New in version 1.1.0.

### entry\_touched(entry, touch)

(internal) This method must be called by the template when an entry is touched by the user.

## **file\_encodings**

Possible encodings for decoding a filename to unicode. In the case that the user has a non-ascii filename, undecodable without knowing it's initial encoding, we have no other choice than to guess it.

Please note that if you encounter an issue because of a missing encoding here, we'll be glad to add it to this list.

file\_encodings is a *ListProperty* and defaults to ['utf-8', 'latin1', 'cp1252'].

New in version 1.3.0.

Deprecated since version 1.8.0: This property is no longer used as the filechooser no longer decodes the file names.

## **file\_system**

The file system object used to access the file system. This should be a subclass of *FileSystemAbstract*.

file\_system is an *ObjectProperty* and defaults to *FileSystemLocal()*

New in version 1.8.0.

## **files**

The list of files in the directory specified by path after applying the filters.

files is a read-only *ListProperty*.

## **filter\_dirs**

Indicates whether filters should also apply to directories. filter\_dirs is a *BooleanProperty* and defaults to False.

## **filters**

filters specifies the filters to be applied to the files in the directory. filters is a *ListProperty* and defaults to []. This is equivalent to '\*' i.e. nothing is filtered.

The filters are not reset when the path changes. You need to do that yourself if desired.

There are two kinds of filters: patterns and callbacks.

### 1. Patterns

e.g. ['\*.png']. You can use the following patterns:

Pattern	Meaning
*	matches everything
?	matches any single character
[seq]	matches any character in seq
[!seq]	matches any character not in seq

### 2. Callbacks

You can specify a function that will be called for each file. The callback will be passed the folder and file name as the first and second parameters respectively. It should return True to indicate a match and False otherwise.

Changed in version 1.4.0: Added the option to specify the filter as a callback.

## **get\_nice\_size(*fn*)**

Pass the filepath. Returns the size in the best human readable format or '' if it is a directory (Don't recursively calculate size).

## **layout**

Reference to the layout widget instance.

layout is an *ObjectProperty*.

New in version 1.9.0.

#### **multiselect**

Determines whether the user is able to select multiple files or not.

`multiselect` is a *BooleanProperty* and defaults to False.

#### **path**

`path` is a *StringProperty* and defaults to the current working directory as a unicode string. It specifies the path on the filesystem that this controller should refer to.

**Warning:** If a unicode path is specified, all the files returned will be in unicode, allowing the display of unicode files and paths. If a bytes path is specified, only files and paths with ascii names will be displayed properly: non-ascii filenames will be displayed and listed with question marks (?) instead of their unicode characters.

#### **progress\_cls**

Class to use for displaying a progress indicator for filechooser loading.

`progress_cls` is an *ObjectProperty* and defaults to `FileChooserProgress`.

New in version 1.2.0.

Changed in version 1.8.0: If set to a string, the *Factory* will be used to resolve the class name.

#### **rootpath**

Root path to use instead of the system root path. If set, it will not show a “..” directory to go up to the root path. For example, if you set `rootpath` to `/users/foo`, the user will be unable to go to `/users` or to any other directory not starting with `/users/foo`.

`rootpath` is a *StringProperty* and defaults to None.

New in version 1.2.0.

---

**Note:** Similarly to `path`, whether `rootpath` is specified as bytes or a unicode string determines the type of the filenames and paths read.

---

#### **selection**

Contains the list of files that are currently selected.

`selection` is a read-only *ListProperty* and defaults to `[]`.

#### **show\_hidden**

Determines whether hidden files and folders should be shown.

`show_hidden` is a *BooleanProperty* and defaults to False.

#### **sort\_func**

Provides a function to be called with a list of filenames as the first argument and the filesystem implementation as the second argument. It returns a list of filenames sorted for display in the view.

`sort_func` is an *ObjectProperty* and defaults to a function returning alphanumerically named folders first.

Changed in version 1.8.0: The signature needs now 2 arguments: first the list of files, second the filesystem class to use.

```
class kivy.uix.filechooser.FileChooserProgressBase(**kwargs)
Bases: kivy.uix.floatlayout.FloatLayout
```

Base for implementing a progress view. This view is used when too many entries need to be created and are delayed over multiple frames.

New in version 1.2.0.

**cancel(\*args)**

Cancel any action from the FileChooserController.

**index**

Current index of *total* entries to be loaded.

**path**

Current path of the FileChooser, read-only.

**total**

Total number of entries to load.

```
class kivy.uix.filechooser.FileSystemAbstract
```

Bases: *object*

Class for implementing a File System view that can be used with the *FileChooser*.

New in version 1.8.0.

**getsize(fn)**

Return the size in bytes of a file

**is\_dir(fn)**

Return True if the argument passed to this method is a directory

**is\_hidden(fn)**

Return True if the file is hidden

**listdir(fn)**

Return the list of files in the directory *fn*

```
class kivy.uix.filechooser.FileSystemLocal
```

Bases: *kivy.uix.filechooser.FileSystemAbstract*

Implementation of *FileSystemAbstract* for local files.

New in version 1.8.0.

## 35.18 Float Layout

*FloatLayout* honors the *pos\_hint* and the *size\_hint* properties of its children.



For example, a `FloatLayout` with a size of (300, 300) is created:

```
layout = FloatLayout(size=(300, 300))
```

By default, all widgets have their `size_hint=(1, 1)`, so this button will adopt the same size as the layout:

```
button = Button(text='Hello world')
layout.add_widget(button)
```

To create a button 50% of the width and 25% of the height of the layout and positioned at (20, 20), you can do:

```
button = Button(
    text='Hello world',
    size_hint=(.5, .25),
    pos=(20, 20))
```

If you want to create a button that will always be the size of layout minus 20% on each side:

```
button = Button(text='Hello world', size_hint=(.6, .6),
    pos_hint={'x':.2, 'y':.2})
```

---

**Note:** This layout can be used for an application. Most of the time, you will use the size of Window.

---

**Warning:** If you are not using `pos_hint`, you must handle the positioning of the children: if the float layout is moving, you must handle moving the children too.

```
class kivy.uix.floatlayout.FloatLayout(**kwargs)
    Bases: kivy.uix.layout.Layout
```

Float layout class. See module documentation for more information.

## 35.19 Gesture Surface

New in version 1.9.0.

**Warning:** This is experimental and subject to change as long as this warning notice is present.

See `kivy/examples/demo/multistroke/main.py` for a complete application example.

```
class kivy.uix.gesturesurface.GestureSurface(**kwargs)
    Bases: kivy.uix.floatlayout.FloatLayout
```

Simple gesture surface to track/draw touch movements. Typically used to gather user input suitable for `kivy.multistroke.Recognizer`.

### Properties

`temporal_window` Time to wait from the last touch\_up event before attempting to recognize the gesture. If you set this to 0, the `on_gesture_complete` event is not fired unless the `max_strokes` condition is met.

`temporal_window` is a `NumericProperty` and defaults to 2.0

`max_strokes` Max number of strokes in a single gesture; if this is reached, recognition will start immediately on the final touch\_up event. If this is set to 0, the `on_gesture_complete` event is not fired unless the `temporal_window` expires.

`max_strokes` is a `NumericProperty` and defaults to 2.0

`bbox_margin` Bounding box margin for detecting gesture collisions, in pixels.

`bbox_margin` is a `NumericProperty` and defaults to 30

`draw_timeout` Number of seconds to keep lines/bbox on canvas after the `on_gesture_complete` event is fired. If this is set to 0, gestures are immediately removed from the surface when complete.

`draw_timeout` is a `NumericProperty` and defaults to 3.0

`color` Color used to draw the gesture, in RGB. This option does not have an effect if `use_random_color` is True.

`draw_timeout` is a `ListProperty` and defaults to [1, 1, 1] (white)

`use_random_color` Set to True to pick a random color for each gesture, if you do this then `color` is ignored. Defaults to False.

`use_random_color` is a `BooleanProperty` and defaults to False

`line_width` Line width used for tracing touches on the surface. Set to 0 if you only want to detect gestures without drawing anything. If you use 1.0, OpenGL GL\_LINE is used for drawing; values > 1 will use an internal drawing method based on triangles (less efficient), see `kivy.graphics`.

`line_width` is a `NumericProperty` and defaults to 2

`draw_bbox` Set to True if you want to draw bounding box behind gestures. This only works if `line_width` >= 1. Default is False.

`draw_bbox` is a `BooleanProperty` and defaults to True

**`bbox_alpha`** Opacity for bounding box if `draw_bbox` is True. Default 0.1

`bbox_alpha` is a [NumericProperty](#) and defaults to 0.1

## Events

**`on_gesture_start GestureContainer`** Fired when a new gesture is initiated on the surface, i.e. the first `on_touch_down` that does not collide with an existing gesture on the surface.

**`on_gesture_extend GestureContainer`** Fired when a `touch_down` event occurs within an existing gesture.

**`on_gesture_merge GestureContainer, GestureContainer`** Fired when two gestures collide and get merged to one gesture. The first argument is the gesture that has been merged (no longer valid); the second is the combined (resulting) gesture.

**`on_gesture_complete GestureContainer`** Fired when a set of strokes is considered a complete gesture, this happens when `temporal_window` expires or `max_strokes` is reached. Typically you will bind to this event and use the provided `GestureContainer get_vectors()` method to match against your gesture database.

**`on_gesture_cleanup GestureContainer`** Fired `draw_timeout` seconds after `on_gesture_complete`, The gesture will be removed from the canvas (if `line_width > 0` or `draw_bbox` is True) and the internal gesture list before this.

**`on_gesture_discard GestureContainer`** Fired when a gesture does not meet the minimum size requirements for recognition (`width/height < 5`, or consists only of single-point strokes).

## **`find_colliding_gesture(touch)`**

Checks if a touch x/y collides with the bounding box of an existing gesture. If so, return it (otherwise returns None)

## **`get_gesture(touch)`**

Returns `GestureContainer` associated with given touch

## **`init_gesture(touch)`**

Create a new gesture from touch, i.e. it's the first on surface, or was not close enough to any existing gesture (yet)

## **`merge_gestures(g, other)`**

Merges two gestures together, the oldest one is retained and the newer one gets the `GestureContainer.was_merged` flag raised.

## **`on_touch_down(touch)`**

When a new touch is registered, the first thing we do is to test if it collides with the bounding box of another known gesture. If so, it is assumed to be part of that gesture.

## **`on_touch_move(touch)`**

When a touch moves, we add a point to the line on the canvas so the path is updated. We must also check if the new point collides with the bounding box of another gesture - if so, they should be merged.

**`class kivy.uix.gesturesurface.GestureContainer(touch, **kwargs)`**  
Bases: [kivy.event.EventDispatcher](#)

Container object that stores information about a gesture. It has various properties that are updated by `GestureSurface` as drawing progresses.

## Arguments

**touch** Touch object (as received by `on_touch_down`) used to initialize the gesture container. Required.

## Properties

**active** Set to False once the gesture is complete (meets `max_stroke` setting or `GestureSurface.temporal_window`)

`active` is a *BooleanProperty*

**active\_strokes** Number of strokes currently active in the gesture, ie concurrent touches associated with this gesture.

`active_strokes` is a *NumericProperty*

**max\_strokes** Max number of strokes allowed in the gesture. This is set by `GestureSurface.max_strokes` but can be overridden for example from `on_gesture_start`.

`max_strokes` is a *NumericProperty*

**was\_merged** Indicates that this gesture has been merged with another gesture and should be considered discarded.

`was_merged` is a *BooleanProperty*

**bbox** Dictionary with keys minx, miny, maxx, maxy. Represents the size of the gesture bounding box.

`bbox` is a *DictProperty*

**width** Represents the width of the gesture.

`width` is a *NumericProperty*

**height** Represents the height of the gesture.

`height` is a *NumericProperty*

### **accept\_stroke(*count*=1)**

Returns True if this container can accept *count* new strokes

### **add\_stroke(*touch, line*)**

Associate a list of points with a `touch.uid`; the line itself is created by the caller, but subsequent move/up events look it up via us. This is done to avoid problems during merge.

### **complete\_stroke()**

Called on touch up events to keep track of how many strokes are active in the gesture (we only want to dispatch event when the *last* stroke in the gesture is released)

### **get\_vectors(\*\*kwargs)**

Return strokes in a format that is acceptable for `kivy.multistroke.Recognizer` as a gesture candidate or template. The result is cached automatically; the cache is invalidated at the start and end of a stroke and if `update_bbox` is called. If you are going to analyze a gesture mid-stroke, you may need to set the `no_cache` argument to True.

### **handles(*touch*)**

Returns True if this container handles the given touch

### **single\_points\_test()**

Returns True if the gesture consists only of single-point strokes, we must discard it in this case, or an exception will be raised

### **update\_bbox(*touch*)**

Update gesture bbox from a touch coordinate

## 35.20 Grid Layout



New in version 1.0.4.

The [GridLayout](#) arranges children in a matrix. It takes the available space and divides it into columns and rows, then adds widgets to the resulting “cells”.

Changed in version 1.0.7: The implementation has changed to use the widget `size_hint` for calculating column/row sizes. `uniform_width` and `uniform_height` have been removed and other properties have added to give you more control.

### 35.20.1 Background

Unlike many other toolkits, you cannot explicitly place a widget in a specific column/row. Each child is automatically assigned a position determined by the layout configuration and the child’s index in the children list.

A GridLayout must always have at least one input constraint: `GridLayout.cols` or `GridLayout.rows`. If you do not specify cols or rows, the Layout will throw an exception.

### 35.20.2 Column Width and Row Height


The column width/row height are determined in 3 steps:

- The initial size is given by the `col_default_width` and `row_default_height` properties. To customize the size of a single column or row, use `cols_minimum` or `rows_minimum`.
- The `size_hint_x`/`size_hint_y` of the children are taken into account. If no widgets have a size hint, the maximum size is used for all children.
- You can force the default size by setting the `col_force_default` or `row_force_default` property. This will force the layout to ignore the `width` and `size_hint` properties of children and use the default size.

### 35.20.3 Using a GridLayout

In the example below, all widgets will have an equal size. By default, the `size_hint` is `(1, 1)`, so a Widget will take the full size of the parent:

```
layout = GridLayout(cols=2)
layout.add_widget(Button(text='Hello 1'))
layout.add_widget(Button(text='World 1'))
layout.add_widget(Button(text='Hello 2'))
layout.add_widget(Button(text='World 2'))
```



Now, let's fix the size of Hello buttons to 100px instead of using `size_hint_x=1`:

```
layout = GridLayout(cols=2)
layout.add_widget(Button(text='Hello 1', size_hint_x=None, width=100))
layout.add_widget(Button(text='World 1'))
layout.add_widget(Button(text='Hello 2', size_hint_x=None, width=100))
layout.add_widget(Button(text='World 2'))
```



Next, let's fix the row height to a specific size:

```
layout = GridLayout(cols=2, row_force_default=True, row_default_height=40)
layout.add_widget(Button(text='Hello 1', size_hint_x=None, width=100))
layout.add_widget(Button(text='World 1'))
layout.add_widget(Button(text='Hello 2', size_hint_x=None, width=100))
```

```
layout.add_widget(Button(text='World 2'))
```

Hello 1	World 1
Hello 2	World 2

**class kivy.uix.gridlayout.GridLayout(\*\*kwargs)**  
Bases: *kivy.uix.layout.Layout*

Grid layout class. See module documentation for more information.

#### **col\_default\_width**

Default minimum size to use for a column.

New in version 1.0.7.

*col\_default\_width* is a *NumericProperty* and defaults to 0.

#### **col\_force\_default**

If True, ignore the width and size\_hint\_x of the child and use the default column width.

New in version 1.0.7.

*col\_force\_default* is a *BooleanProperty* and defaults to False.

#### **cols**

Number of columns in the grid.

Changed in version 1.0.8: Changed from a NumericProperty to BoundedNumericProperty.  
You can no longer set this to a negative value.

*cols* is a *NumericProperty* and defaults to 0.

#### **cols\_minimum**

Dict of minimum width for each column. The dictionary keys are the column numbers, e.g. 0, 1, 2...

New in version 1.0.7.

*cols\_minimum* is a *DictProperty* and defaults to {}.

#### **minimum\_height**

Automatically computed minimum height needed to contain all children.

New in version 1.0.8.

*minimum\_height* is a *NumericProperty* and defaults to 0. It is read only.

#### **minimum\_size**

Automatically computed minimum size needed to contain all children.

New in version 1.0.8.

*minimum\_size* is a *ReferenceListProperty* of (*minimum\_width*, *minimum\_height*) properties. It is read only.

#### **minimum\_width**

Automatically computed minimum width needed to contain all children.

New in version 1.0.8.

*minimum\_width* is a *NumericProperty* and defaults to 0. It is read only.

#### **padding**

Padding between the layout box and its children: [padding\_left, padding\_top, padding\_right, padding\_bottom].

padding also accepts a two argument form [padding\_horizontal, padding\_vertical] and a one argument form [padding].

Changed in version 1.7.0: Replaced NumericProperty with VariableListProperty.

*padding* is a *VariableListProperty* and defaults to [0, 0, 0, 0].

#### **row\_default\_height**

Default minimum size to use for row.

New in version 1.0.7.

*row\_default\_height* is a *NumericProperty* and defaults to 0.

#### **row\_force\_default**

If True, ignore the height and size\_hint\_y of the child and use the default row height.

New in version 1.0.7.

*row\_force\_default* is a *BooleanProperty* and defaults to False.

#### **rows**

Number of rows in the grid.

Changed in version 1.0.8: Changed from a NumericProperty to a BoundedNumericProperty. You can no longer set this to a negative value.

*rows* is a *NumericProperty* and defaults to 0.

#### **rows\_minimum**

Dict of minimum height for each row. The dictionary keys are the row numbers, e.g. 0, 1, 2...

New in version 1.0.7.

*rows\_minimum* is a *DictProperty* and defaults to {}.

#### **spacing**

Spacing between children: [spacing\_horizontal, spacing\_vertical].

spacing also accepts a one argument form [spacing].

*spacing* is a *VariableListProperty* and defaults to [0, 0].

### **class kivy.uix.gridlayout.GridLayoutException**

Bases: exceptions.Exception

Exception for errors if the grid layout manipulation fails.

## 35.21 Image

The *Image* widget is used to display an image:

```
wimg = Image(source='mylogo.png')
```

### 35.21.1 Asynchronous Loading

To load an image asynchronously (for example from an external webserver), use the *AsyncImage* subclass:

```
aimg = AsyncImage(source='http://mywebsite.com/logo.png')
```

This can be useful as it prevents your application from waiting until the image is loaded. If you want to display large images or retrieve them from URL's, using `AsyncImage` will allow these resources to be retrieved on a background thread without blocking your application.

### 35.21.2 Alignment

By default, the image is centered and fits inside the widget bounding box. If you don't want that, you can set `allow_stretch` to True and `keep_ratio` to False.

You can also inherit from Image and create your own style. For example, if you want your image to be greater than the size of your widget, you could do:

```
class FullImage(Image):
    pass
```

And in your kivy language file:

```
<-FullImage>:
    canvas:
        Color:
            rgb: (1, 1, 1)
        Rectangle:
            texture: self.texture
            size: self.width + 20, self.height + 20
            pos: self.x - 10, self.y - 10
```

**class kivy.uix.image.Image(\*\*kwargs)**  
Bases: `kivy.uix.widget.Widget`

Image class, see module documentation for more information.

#### **allow\_stretch**

If True, the normalized image size will be maximized to fit in the image box. Otherwise, if the box is too tall, the image will not be stretched more than 1:1 pixels.

New in version 1.0.7.

`allow_stretch` is a `BooleanProperty` and defaults to False.

#### **anim\_delay**

Delay the animation if the image is sequenced (like an animated gif). If `anim_delay` is set to -1, the animation will be stopped.

New in version 1.0.8.

`anim_delay` is a `NumericProperty` and defaults to 0.25 (4 FPS).

#### **anim\_loop**

Number of loops to play then stop animating. 0 means keep animating.

New in version 1.9.0.

`anim_loop` is a `NumericProperty` and defaults to 0.

#### **color**

Image color, in the format (r, g, b, a). This attribute can be used to 'tint' an image. Be careful: if the source image is not gray/white, the color will not really work as expected.

New in version 1.0.6.

`color` is a `ListProperty` and defaults to [1, 1, 1, 1].

**image\_ratio**

Ratio of the image (width / float(height)).

*image\_ratio* is an *AliasProperty* and is read-only.

**keep\_data**

If True, the underlaying \_coreimage will store the raw image data. This is useful when performing pixel based collision detection.

New in version 1.3.0.

*keep\_data* is a *BooleanProperty* and defaults to False.

**keep\_ratio**

If False along with allow\_stretch being True, the normalized image size will be maximized to fit in the image box and ignores the aspect ratio of the image. Otherwise, if the box is too tall, the image will not be stretched more than 1:1 pixels.

New in version 1.0.8.

*keep\_ratio* is a *BooleanProperty* and defaults to True.

**mipmap**

Indicate if you want OpenGL mipmaping to be applied to the texture. Read *Mipmapping* for more information.

New in version 1.0.7.

*mipmap* is a *BooleanProperty* and defaults to False.

**nocache**

If this property is set True, the image will not be added to the internal cache. The cache will simply ignore any calls trying to append the core image.

New in version 1.6.0.

*nocache* is a *BooleanProperty* and defaults to False.

**norm\_image\_size**

Normalized image size within the widget box.

This size will always fit the widget size and will preserve the image ratio.

*norm\_image\_size* is an *AliasProperty* and is read-only.

**reload()**

Reload image from disk. This facilitates re-loading of images from disk in case the image content changes.

New in version 1.3.0.

Usage:

```
im = Image(source = '1.jpg')
# -- do something --
im.reload()
# image will be re-loaded from disk
```

**source**

Filename / source of your image.

*source* is a *StringProperty* and defaults to None.

**texture**

Texture object of the image. The texture represents the original, loaded image texture. It is stretched and positioned during rendering according to the *allow\_stretch* and *keep\_ratio* properties.

Depending of the texture creation, the value will be a [Texture](#) or a [TextureRegion](#) object.

`texture` is an [ObjectProperty](#) and defaults to None.

#### **texture\_size**

Texture size of the image. This represents the original, loaded image texture size.

**Warning:** The texture size is set after the texture property. So if you listen to the change on `texture`, the property `texture_size` will not be up-to-date. Use `self.texture.size` instead.

```
class kivy.uix.image.AsyncImage(**kwargs)
```

Bases: [kivy.uix.image.Image](#)

Asynchronous Image class. See the module documentation for more information.

---

**Note:** The AsyncImage is a specialized form of the Image class. You may want to refer to the [loader](#) documentation and in particular, the [ProxyImage](#) for more detail on how to handle events around asynchronous image loading.

---

## 35.22 Label



The [Label](#) widget is for rendering text. It supports ascii and unicode strings:

```
# hello world text
l = Label(text='Hello world')

# unicode text; can only display glyphs that are available in the font
l = Label(text=u'Hello world ' + unichr(2764))

# multiline text
l = Label(text='Multi\nLine')

# size
l = Label(text='Hello world', font_size='20sp')
```

### 35.22.1 Sizing and text content

By default, the size of [Label](#) is not affected by `text` content and the text is not affected by the size. In order to control sizing, you must specify `text_size` to constrain the text and/or bind `size` to

`texture_size` to grow with the text.

For example, this label's size will be set to the text content (plus `padding`):

```
Label:  
    size: self.texture_size
```

This label's text will wrap at the specified width and be clipped to the height:

```
Label:  
    text_size: cm(6), cm(4)
```

---

**Note:** The `shorten` and `max_lines` attributes control how overflowing text behaves.

---

Combine these concepts to create a Label that can grow vertically but wraps the text at a certain width:

```
Label:  
    text_size: root.width, None  
    size: self.texture_size
```

### 35.22.2 Text alignment and wrapping

The `Label` has `halign` and `valign` properties to control the alignment of its text. However, by default the text image (`texture`) is only just large enough to contain the characters and is positioned in the center of the Label. The `valign` property will have no effect and `halign` will only have an effect if your text has newlines; a single line of text will appear to be centered even though `halign` is set to left (by default).

In order for the alignment properties to take effect, set the `text_size`, which specifies the size of the bounding box within which text is aligned. For instance, the following code binds this size to the size of the Label, so text will be aligned within the widget bounds. This will also automatically wrap the text of the Label to remain within this area.

```
Label:  
    text_size: self.size  
    halign: 'right'  
    valign: 'middle'
```

### 35.22.3 Markup text

New in version 1.1.0.

You can change the style of the text using `Text Markup`. The syntax is similar to the bbcode syntax but only the inline styling is allowed:

```
# hello world with world in bold  
l = Label(text='Hello [b]World[/b]', markup=True)  
  
# hello in red, world in blue  
l = Label(text='[color=ff3333>Hello[/color][color=3333ff]World[/color]',  
markup = True)
```

If you need to escape the markup from the current text, use `kivy.utils.escape_markup()`:

```
text = 'This is an important message [1]'  
l = Label(text='[b]' + escape_markup(text) + '[/b]', markup=True)
```

The following tags are available:

**[b]**[/b] Activate bold text

**[i]**[/i] Activate italic text

**[u]**[/u] Underlined text

**[s]**[/s] Strikethrough text

**[font=<str>][/font]** Change the font

**[size=<integer>][/size]** Change the font size

**[color=#<color>][/color]** Change the text color

**[ref=<str>][/ref]** Add an interactive zone. The reference + bounding box inside the reference will be available in *Label.refs*

**[anchor=<str>]** Put an anchor in the text. You can get the position of your anchor within the text with *Label.anchors*

**[sub]**[/sub] Display the text at a subscript position relative to the text before it.

**[sup]**[/sup] Display the text at a superscript position relative to the text before it.

If you want to render the markup text with a [ or ] or & character, you need to escape them. We created a simple syntax:

```
[ -> &bl;
] -> &br;
& -> &amp;
```

Then you can write:

```
"[size=24]Hello &bl;World&bt;[/size]"
```

#### 35.22.4 Interactive zone in text

New in version 1.1.0.

You can now have definable “links” using text markup. The idea is to be able to detect when the user clicks on part of the text and to react. The tag **[ref=xxx]** is used for that.

In this example, we are creating a reference on the word “World”. When this word is clicked, the function `print_it` will be called with the name of the reference:

```
def print_it(instance, value):
    print('User clicked on', value)
widget = Label(text='Hello [ref=world]World[/ref]', markup=True)
widget.bind(on_ref_press=print_it)
```

For prettier rendering, you could add a color for the reference. Replace the `text=` in the previous example with:

```
'Hello [ref=world][color=0000ff]World[/color][/ref]'
```

#### 35.22.5 Catering for Unicode languages

The font kivy uses does not contain all the characters required for displaying all languages. When you use the built-in widgets, this results in a block being drawn where you expect a character.

If you want to display such characters, you can chose a font that supports them and deploy it universally via kv:

```
<Label>:  
    font_name: '/<path>/<to>/<font>'
```

Note that this needs to be done before your widgets are loaded as kv rules are only applied at load time.

### 35.22.6 Usage example

The following example marks the anchors and references contained in a label:

```
from kivy.app import App  
from kivy.uix.label import Label  
from kivy.clock import Clock  
from kivy.graphics import Color, Rectangle  
  
class TestApp(App):  
  
    @staticmethod  
    def get_x(label, ref_x):  
        """ Return the x value of the ref/anchor relative to the canvas """  
        return label.center_x - label.texture_size[0] * 0.5 + ref_x  
  
    @staticmethod  
    def get_y(label, ref_y):  
        """ Return the y value of the ref/anchor relative to the canvas """  
        # Note the inversion of direction, as y values start at the top of  
        # the texture and increase downwards  
        return label.center_y + label.texture_size[1] * 0.5 - ref_y  
  
    def show_marks(self, label):  
  
        # Indicate the position of the anchors with a red top marker  
        for name, anc in label.anchors.items():  
            with label.canvas:  
                Color(1, 0, 0)  
                Rectangle(pos=(self.get_x(label, anc[0]),  
                             self.get_y(label, anc[1])),  
                          size=(3, 3))  
  
        # Draw a green surround around the refs. Note the sizes y inversion  
        for name, boxes in label.refs.items():  
            for box in boxes:  
                with label.canvas:  
                    Color(0, 1, 0, 0.25)  
                    Rectangle(pos=(self.get_x(label, box[0]),  
                                 self.get_y(label, box[1])),  
                              size=(box[2] - box[0],  
                                    box[1] - box[3]))  
  
    def build(self):  
        label = Label(  
            text='[anchor=a]a\nChars [anchor=b]b\n[ref=myref]ref[/ref]',  
            markup=True)  
        Clock.schedule_once(lambda dt: self.show_marks(label), 1)  
        return label
```

```
TestApp().run()
```

```
class kivy.uix.label.Label(**kwargs)
Bases: kivy.uix.widget.Widget
```

Label class, see module documentation for more information.

#### Events

*on\_ref\_press* Fired when the user clicks on a word referenced with a [ref] tag in a text markup.

#### anchors

New in version 1.1.0.

Position of all the [anchor=xxx] markup in the text. These co-ordinates are relative to the top left corner of the text, with the y value increasing downwards. Anchors names should be unique and only the first occurrence of any duplicate anchors will be recorded.

You can place anchors in your markup text as follows:

```
text = """
[anchor=title1][size=24]This is my Big title.[/size]
[anchor=content]Hello world
"""
```

Then, all the [anchor=] references will be removed and you'll get all the anchor positions in this property (only after rendering):

```
>>> widget = Label(text=text, markup=True)
>>> widget.texture_update()
>>> widget.anchors
{"content": (20, 32), "title1": (20, 16)}
```

---

**Note:** This works only with markup text. You need *markup* set to True.

---

#### bold

Indicates use of the bold version of your font.

---

**Note:** Depending of your font, the bold attribute may have no impact on your text rendering.

---

*bold* is a *BooleanProperty* and defaults to False.

#### color

Text color, in the format (r, g, b, a).

*color* is a *ListProperty* and defaults to [1, 1, 1, 1].

#### disabled\_color

The color of the text when the widget is disabled, in the (r, g, b, a) format.

New in version 1.8.0.

*disabled\_color* is a *ListProperty* and defaults to [1, 1, 1, .3].

#### disabled\_outline\_color

The color of the text outline when the widget is disabled, in the (r, g, b) format.

---

**Note:** This feature requires the SDL2 text provider.

---

New in version 1.10.0.

*disabled\_outline\_color* is a *ListProperty* and defaults to [0, 0, 0].

### **ellipsis\_options**

Font options for the ellipsis string('...') used to split the text.

Accepts a dict as option name with the value. Only applied when *markup* is true and text is shortened. All font options which work for *Label* will work for *ellipsis\_options*. Defaults for the options not specified are taken from the surrounding text.

```
Label:  
  text: 'Some very long line which will be cut'  
  markup: True  
  shorten: True  
  ellipsis_options: {'color':(1,0.5,0.5,1), 'underline':True}
```

New in version 2.0.0.

*ellipsis\_options* is a *DictProperty* and defaults to {} (the empty dict).

### **font\_blended**

Whether blended or solid font rendering should be used.

---

**Note:** This feature requires the SDL2 text provider.

---

New in version 1.10.0.

*font\_blended* is a *BooleanProperty* and defaults to True.

### **font\_hinting**

What hinting option to use for font rendering. Can be one of 'normal', 'light', 'mono' or None.

---

**Note:** This feature requires the SDL2 text provider.

---

New in version 1.10.0.

*font\_hinting* is an *OptionProperty* and defaults to 'normal'.

### **font\_kerning**

Whether kerning is enabled for font rendering.

---

**Note:** This feature requires the SDL2 text provider.

---

New in version 1.10.0.

*font\_kerning* is a *BooleanProperty* and defaults to True.

### **font\_name**

Filename of the font to use. The path can be absolute or relative. Relative paths are resolved by the *resource\_find()* function.

**Warning:** Depending of your text provider, the font file can be ignored. However, you can mostly use this without problems.

If the font used lacks the glyphs for the particular language/symbols you are using, you will see '[]' blank box characters instead of the actual glyphs. The solution is to use a font that has the glyphs you need to display. For example, to display  , use a font such as freesans.ttf that has the glyph.

`font_name` is a *StringProperty* and defaults to 'Roboto'. This value is taken from *Config*.

#### **font\_size**

Font size of the text, in pixels.

`font_size` is a *NumericProperty* and defaults to 15sp.

#### **halign**

Horizontal alignment of the text.

`halign` is an *OptionProperty* and defaults to 'left'. Available options are : left, center, right and justify.

**Warning:** This doesn't change the position of the text texture of the Label (centered), only the position of the text in this texture. You probably want to bind the size of the Label to the `texture_size` or set a `text_size`.

Changed in version 1.6.0: A new option was added to `halign`, namely *justify*.

#### **is\_shortened**

This property indicates if `text` was rendered with or without shortening when `shorten` is True.

New in version 1.10.0.

`is_shortened` is a *BooleanProperty* and defaults to False.

#### **italic**

Indicates use of the italic version of your font.

**Note:** Depending of your font, the italic attribute may have no impact on your text rendering.

`italic` is a *BooleanProperty* and defaults to False.

#### **line\_height**

Line Height for the text. e.g. `line_height = 2` will cause the spacing between lines to be twice the size.

`line_height` is a *NumericProperty* and defaults to 1.0.

New in version 1.5.0.

#### **markup**

New in version 1.1.0.

If True, the text will be rendered using the *MarkupLabel*: you can change the style of the text using tags. Check the *Text Markup* documentation for more information.

`markup` is a *BooleanProperty* and defaults to False.

**max\_lines**

Maximum number of lines to use, defaults to 0, which means unlimited. Please note that [shorten](#) take over this property. (with shorten, the text is always one line.)

New in version 1.8.0.

*max\_lines* is a [NumericProperty](#) and defaults to 0.

**mipmap**

Indicates whether OpenGL mipmapping is applied to the texture or not. Read [Mipmapping](#) for more information.

New in version 1.0.7.

*mipmap* is a [BooleanProperty](#) and defaults to False.

**outline\_color**

The color of the text outline, in the (r, g, b) format.

---

**Note:** This feature requires the SDL2 text provider.

---

New in version 1.10.0.

*outline\_color* is a [ListProperty](#) and defaults to [0, 0, 0].

**outline\_width**

Width in pixels for the outline around the text. No outline will be rendered if the value is None.

---

**Note:** This feature requires the SDL2 text provider.

---

New in version 1.10.0.

*outline\_width* is a [NumericProperty](#) and defaults to None.

**padding**

Padding of the text in the format (padding\_x, padding\_y)

*padding* is a [ReferenceListProperty](#) of (*padding\_x*, *padding\_y*) properties.

**padding\_x**

Horizontal padding of the text inside the widget box.

*padding\_x* is a [NumericProperty](#) and defaults to 0.

Changed in version 1.9.0: *padding\_x* has been fixed to work as expected. In the past, the text was padded by the negative of its values.

**padding\_y**

Vertical padding of the text inside the widget box.

*padding\_y* is a [NumericProperty](#) and defaults to 0.

Changed in version 1.9.0: *padding\_y* has been fixed to work as expected. In the past, the text was padded by the negative of its values.

**refs**

New in version 1.1.0.

List of [ref=xxx] markup items in the text with the bounding box of all the words contained in a ref, available only after rendering.

For example, if you wrote:

```
Check out my [ref=hello]link[/ref]
```

The refs will be set with:

```
{'hello': ((64, 0, 78, 16), )}
```

The references marked “hello” have a bounding box at (x1, y1, x2, y2). These co-ordinates are relative to the top left corner of the text, with the y value increasing downwards. You can define multiple refs with the same name: each occurrence will be added as another (x1, y1, x2, y2) tuple to this list.

The current Label implementation uses these references if they exist in your markup text, automatically doing the collision with the touch and dispatching an *on\_ref\_press* event.

You can bind a ref event like this:

```
def print_it(instance, value):
    print('User click on', value)
widget = Label(text='Hello [ref=world]World[/ref]', markup=True)
widget.on_ref_press(print_it)
```

---

**Note:** This works only with markup text. You need *markup* set to True.

---

### **shorten**

Indicates whether the label should attempt to shorten its textual contents as much as possible if a *text\_size* is given. Setting this to True without an appropriately set *text\_size* will lead to unexpected results.

*shorten\_from* and *split\_str* control the direction from which the *text* is split, as well as where in the *text* we are allowed to split.

*shorten* is a *BooleanProperty* and defaults to False.

### **shorten\_from**

The side from which we should shorten the text from, can be left, right, or center.

For example, if left, the ellipsis will appear towards the left side and we will display as much text starting from the right as possible. Similar to *shorten*, this option only applies when *text\_size* [0] is not None, In this case, the string is shortened to fit within the specified width.

New in version 1.9.0.

*shorten\_from* is a *OptionProperty* and defaults to *center*.

### **split\_str**

The string used to split the *text* while shortening the string when *shorten* is True.

For example, if it's a space, the string will be broken into words and as many whole words that can fit into a single line will be displayed. If *split\_str* is the empty string, “”, we split on every character fitting as much text as possible into the line.

New in version 1.9.0.

*split\_str* is a *StringProperty* and defaults to “” (the empty string).

### **strikethrough**

Adds a strikethrough line to the text.

---

**Note:** This feature requires the SDL2 text provider.

---

New in version 1.10.0.

*strikethrough* is a *BooleanProperty* and defaults to False.

### strip

Whether leading and trailing spaces and newlines should be stripped from each displayed line. If True, every line will start at the right or left edge, depending on *halign*. If *halign* is *justify* it is implicitly True.

New in version 1.9.0.

*strip* is a *BooleanProperty* and defaults to False.

### text

Text of the label.

Creation of a simple hello world:

```
widget = Label(text='Hello world')
```

If you want to create the widget with an unicode string, use:

```
widget = Label(text=u'My unicode string')
```

*text* is a *StringProperty* and defaults to “”.

### text\_size

By default, the label is not constrained to any bounding box. You can set the size constraint of the label with this property. The text will autoflow into the constraints. So although the font size will not be reduced, the text will be arranged to fit into the box as best as possible, with any text still outside the box clipped.

This sets and clips *texture\_size* to *text\_size* if not None.

New in version 1.0.4.

For example, whatever your current widget size is, if you want the label to be created in a box with width=200 and unlimited height:

```
Label(text='Very big big line', text_size=(200, None))
```

---

**Note:** This *text\_size* property is the same as the *usersize* property in the *Label* class. (It is named *size=* in the constructor.)

---

*text\_size* is a *ListProperty* and defaults to (None, None), meaning no size restriction by default.

### texture

Texture object of the text. The text is rendered automatically when a property changes. The OpenGL texture created in this operation is stored in this property. You can use this *texture* for any graphics elements.

Depending on the texture creation, the value will be a *Texture* or *TextureRegion* object.

**Warning:** The *texture* update is scheduled for the next frame. If you need the texture immediately after changing a property, you have to call the *texture\_update()* method before accessing *texture*:

```
l = Label(text='Hello world')
# l.texture is good
l.font_size = '50sp'
# l.texture is not updated yet
l.texture_update()
# l.texture is good now.
```

`texture` is an *ObjectProperty* and defaults to None.

#### **texture\_size**

Texture size of the text. The size is determined by the font size and text. If `text_size` is [None, None], the texture will be the size required to fit the text, otherwise it's clipped to fit `text_size`.

When `text_size` is [None, None], one can bind to `texture_size` and rescale it proportionally to fit the size of the label in order to make the text fit maximally in the label.

**Warning:** The `texture_size` is set after the `texture` property. If you listen for changes to `texture`, `texture_size` will not be up-to-date in your callback. Bind to `texture_size` instead.

#### **texture\_update(\*args)**

Force texture recreation with the current Label properties.

After this function call, the `texture` and `texture_size` will be updated in this order.

#### **underline**

Adds an underline to the text.

---

**Note:** This feature requires the SDL2 text provider.

---

New in version 1.10.0.

`underline` is a *BooleanProperty* and defaults to False.

#### **unicode\_errors**

How to handle unicode decode errors. Can be 'strict', 'replace' or 'ignore'.

New in version 1.9.0.

`unicode_errors` is an *OptionProperty* and defaults to 'replace'.

#### **valign**

Vertical alignment of the text.

`valign` is an *OptionProperty* and defaults to 'bottom'. Available options are : 'bottom', 'middle' (or 'center') and 'top'.

Changed in version 1.10.0: The 'center' option has been added as an alias of 'middle'.

**Warning:** This doesn't change the position of the text texture of the Label (centered), only the position of the text within this texture. You probably want to bind the size of the Label to the `texture_size` or set a `text_size` to change this behavior.

## 35.23 Layout

Layouts are used to calculate and assign widget positions.

The `Layout` class itself cannot be used directly. You should use one of the following layout classes:

- Anchor layout: `kivy.uix.anchorlayout.AnchorLayout`
- Box layout: `kivy.uix.boxlayout.BoxLayout`
- Float layout: `kivy.uix.floatlayout.FloatLayout`
- Grid layout: `kivy.uix.gridlayout.GridLayout`
- Page Layout: `kivy.uix.pagelayout.PageLayout`
- Relative layout: `kivy.uix.relativelayout.RelativeLayout`
- Scatter layout: `kivy.uix.scatterlayout.ScatterLayout`
- Stack layout: `kivy.uix.stacklayout.StackLayout`

### 35.23.1 Understanding the `size_hint` Property in `Widget`

The `size_hint` is a tuple of values used by layouts to manage the sizes of their children. It indicates the size relative to the layout's size instead of an absolute size (in pixels/points/cm/etc). The format is:

```
widget.size_hint = (width_percent, height_percent)
```

The percent is specified as a floating point number in the range 0-1. For example, 0.5 is 50%, 1 is 100%.

If you want a widget's width to be half of the parent's width and the height to be identical to the parent's height, you would do:

```
widget.size_hint = (0.5, 1.0)
```

If you don't want to use a `size_hint` for either the width or height, set the value to None. For example, to make a widget that is 250px wide and 30% of the parent's height, do:

```
widget.size_hint = (None, 0.3)
widget.width = 250
```

Being `Kivy properties`, these can also be set via constructor arguments:

```
widget = Widget(size_hint=(None, 0.3), width=250)
```

Changed in version 1.4.1: The `reposition_child` internal method (made public by mistake) has been removed.

```
class kivy.uix.layout.Layout(**kwargs)
Bases: kivy.uix.widget.Widget
```

Layout interface class, used to implement every layout. See module documentation for more information.

```
do_layout(*largs)
```

This function is called when a layout is called by a trigger. If you are writing a new Layout subclass, don't call this function directly but use `_trigger_layout()` instead.

The function is by default called *before* the next frame, therefore the layout isn't updated immediately. Anything depending on the positions of e.g. children should be scheduled for the next frame.

New in version 1.0.8.

```
layout_hint_with_bounds(sh_sum, available_space, min_bounded_size, sh_min_vals,  
sh_max_vals, hint)
```

(internal) Computes the appropriate (size) hint for all the widgets given (potential) min or max bounds on the widgets' size. The `hint` list is updated with appropriate sizes.

It walks through the hints and for any widgets whose hint will result in violating min or max constraints, it fixes the hint. Any remaining or missing space after all the widgets are fixed get distributed to the widgets making them smaller or larger according to their size hint.

This algorithm knows nothing about the widgets other than what is passed through the input params, so it's fairly generic for laying things out according to constraints using size hints.

#### Parameters

`sh_sum: float` The sum of the size hints (basically `sum(size_hint)`).

`available_space: float` The amount of pixels available for all the widgets whose size hint is not None. Cannot be zero.

`min_bounded_size: float` The minimum amount of space required according to the `size_hint_min` of the widgets (basically `sum(size_hint_min)`).

`sh_min_vals: list or iterable` Items in the iterable are the `size_hint_min` for each widget. Can be None. The length should be the same as `hint`

`sh_max_vals: list or iterable` Items in the iterable are the `size_hint_max` for each widget. Can be None. The length should be the same as `hint`

`hint: list` A list whose size is the same as the length of `sh_min_vals` and `sh_max_vals` whose each element is the corresponding size hint value of that element. This list is updated in place with correct size hints that ensure the constraints are not violated.

**Returns** Nothing. `hint` is updated in place.

## 35.24 List View

New in version 1.5.

Deprecated since version 1.10.0: `ListView` has been deprecated, use [RecycleView](#) instead.

**Warning:** This code is still experimental, and its API is subject to change in a future version.

The `ListView` implements an `AbstractView` as a vertical, scrollable, pannable list clipped to the scrollview's bounding box and contains list item view instances.

The `AbstractView` has one property: `adapter`. The adapter can be one of the following: a `SimpleListAdapter`, a `ListAdapter` or a `DictAdapter`. The `Adapter` can make use of `args_converters` to prepare your data for passing into the constructor for each item view instantiation.

For an overview of how all these components fit together, please see the `adapters` module documentation.

### 35.24.1 Introduction

Lists are central parts of many software projects. Kivy's approach to lists includes providing solutions for simple lists, along with a substantial framework for building lists of moderate to advanced complexity. For a new user, it can be difficult to ramp up from simple to advanced. For this reason, Kivy provides an extensive set of examples (with the Kivy package) that you may wish to run first, to get a taste of the range of functionality offered. You can tell from the names of the examples that they illustrate the "ramping up" from simple to advanced:

- [kivy/examples/widgets/lists/list\\_simple.py](#)
- [kivy/examples/widgets/lists/list\\_simple\\_in\\_kv.py](#)
- [kivy/examples/widgets/lists/list\\_simple\\_in\\_kv\\_2.py](#)
- [kivy/examples/widgets/lists/list\\_master\\_detail.py](#)
- [kivy/examples/widgets/lists/list\\_two\\_up.py](#)
- [kivy/examples/widgets/lists/list\\_kv.py](#)
- [kivy/examples/widgets/lists/list\\_composite.py](#)
- [kivy/examples/widgets/lists/list\\_reset\\_data.py](#)
- [kivy/examples/widgets/lists/list\\_cascade.py](#)
- [kivy/examples/widgets/lists/list\\_cascade\\_dict.py](#)
- [kivy/examples/widgets/lists/list\\_cascade\\_images.py](#)
- [kivy/examples/widgets/lists/list\\_ops.py](#)

Many of the examples feature selection, some restricting selection to single selection, where only one item at a time can be selected, and others allowing multiple item selection. Many of the examples illustrate how selection in one list can be connected to actions and selections in another view or another list.

Find your own way of reading the documentation here, examining the source code for the example apps and running the examples. Some may prefer to read the documentation through first, others may want to run the examples and view their code. No matter what you do, going back and forth will likely be needed.

### 35.24.2 Basic Example

In its simplest form, we make a listview with 100 items:

```
from kivy.uix.listview import ListView
from kivy.base import runTouchApp

class MainView(ListView):
    def __init__(self, **kwargs):
        super(MainView, self).__init__(
            item_strings=[str(index) for index in range(100)])

if __name__ == '__main__':
    runTouchApp(MainView())
```

Or, we could declare the listview using the kv language:

```

from kivy.uix.boxlayout import BoxLayout
from kivy.lang import Builder
from kivy.base import runTouchApp

Builder.load_string("""
<MyListView>:
    ListView:
        item_strings: [str(index) for index in range(100)]
""")

class MyListView(BoxLayout):
    pass

if __name__ == '__main__':
    runTouchApp(MyListView())

```

### 35.24.3 Using an Adapter

Behind the scenes, the basic example above uses the *SimpleListAdapter*. When the constructor for the *ListView* sees that only a list of strings is provided as an argument (called *item\_strings*), it creates a *SimpleListAdapter* using the list of strings.

“Simple” in *SimpleListAdapter* means *without selection support*. It is a scrollable list of items that does not respond to touch events.

To use a *SimpleListAdapter* explicitly when creating a *ListView* instance, do:

```

simple_list_adapter = SimpleListAdapter(
    data=["Item #{0}".format(i) for i in range(100)],
    cls=Label)

list_view = ListView(adapter=simple_list_adapter)

```

The instance of *SimpleListAdapter* has a required *data* argument which contains data items to use for instantiating *Label* views for the list view (note the *cls=Label* argument). The data items are strings. Each item string is set by the *SimpleListAdapter* as the *text* argument for each *Label* instantiation.

You can declare a *ListView* with an adapter in a kv file with special attention given to the way longer python blocks are indented:

```

from kivy.uix.boxlayout import BoxLayout
from kivy.base import runTouchApp
from kivy.lang import Builder

# Note the special nature of indentation in the adapter declaration, where
# the adapter: is on one line, then the value side must be given at one
# level of indentation.

Builder.load_string("""
#:import label kivy.uix.label
#:import sla kivy.adapters.simplelistadapter

<MyListView>:
    ListView:
        adapter:
            sla.SimpleListAdapter(
                data=["Item #{0}".format(i) for i in range(100)],
                cls=label.Label)

```

```
"""
)

class MyListView(BoxLayout):
    pass

if __name__ == '__main__':
    runTouchApp(MyListView())

```

### 35.24.4ListAdapter and DictAdapter

For most use cases, your data is more complex than a simple list of strings. Selection functionality is also often needed. The *ListAdapter* and *DictAdapter* cover these more elaborate needs.

The *ListAdapter* is the base class for *DictAdapter*, so we can start with it.

Refer to the *ListAdapter* docs for details, but here is a synopsis of its arguments:

- *data*: strings, class instances, dicts, etc. that form the base data for instantiating views.
- *cls*: a Kivy view that is to be instantiated for each list item. There are several built-in types available, including ListItemLabel and ListItemButton, or you can make your own class that mixes in the required *SelectableView*.
- *template*: the name of a Kivy language (kv) template that defines the Kivy view for each list item.

---

**Note:** Pick only one, cls or template, to provide as an argument.


---

- *args\_converters*: a function that takes a data item object as input and uses it to build and return an args dict, ready to be used in a call to instantiate item views using the item view cls or template. In the case of cls, the args dict becomes a kwargs constructor argument. For a template, it is treated as a context (ctx) but is essentially similar in form to the kwargs usage.
- *selection\_mode*: a string with the value ‘single’, ‘multiple’ or other.
- *allow\_empty\_selection*: a boolean, which if False (the default), forces there to always be a selection if there is data available. If True, selection happens only as a result of user action.

In narrative, we can summarize as follows:

A listview’s adapter takes data items and uses an args\_converter function to transform them into arguments for creating list item view instances, using either a cls or a kv template.

In a graphic, a summary of the relationship between a listview and its components can be summarized as follows:



Please refer to the [adapters](#) documentation for more details.

A [DictAdapter](#) has the same arguments and requirements as a [ListAdapter](#) except for two things:

1. There is an additional argument, sorted\_keys, which must meet the requirements of normal python dictionary keys.
2. The data argument is, as you would expect, a dict. Keys in the dict must include the keys in the sorted\_keys argument, but they may form a superset of the keys in sorted\_keys. Values may be strings, class instances, dicts, etc. (The args\_converter uses it accordingly).

### 35.24.5 Using an Args Converter

A [ListView](#) allows use of built-in list item views, such as [ListItemButton](#), your own custom item view class or a custom kv template. Whichever type of list item view is used, an [args\\_converter](#) function is needed to prepare, per list data item, kwargs for the cls or the ctx for the template.

---

**Note:** Only the ListItemLabel, ListItemButton or custom classes like them (and not the simple Label or Button classes) are to be used in the listview system.

---

**Warning:** ListItemButton inherits the `background_normal` and `background_down` properties from the Button widget, so the `selected_color` and `deselected_color` are not represented faithfully by default.

Here is an args\_converter for use with the built-in [ListItemButton](#) specified as a normal Python function:

```
def args_converter(row_index, an_obj):
    return {'text': an_obj.text,
            'size_hint_y': None,
            'height': 25}
```

and as a lambda:

```
args_converter = lambda row_index, an_obj: {'text': an_obj.text,
                                             'size_hint_y': None,
                                             'height': 25}
```

In the args converter example above, the data item is assumed to be an object (class instance), hence the reference `an_obj.text`.

Here is an example of an args converter that works with list data items that are dicts:

```
args_converter = lambda row_index, obj: {'text': obj['text'],
                                         'size_hint_y': None,
                                         'height': 25}
```

So, it is the responsibility of the developer to code the `args_converter` according to the data at hand. The `row_index` argument can be useful in some cases, such as when custom labels are needed.

### 35.24.6 An Example ListView

Now, to some example code:

```
from kivy.adapters.listadapter import ListAdapter
from kivy.uix.listview import ListItemButton, ListView

data = [{'text': str(i), 'is_selected': False} for i in range(100)]

args_converter = lambda row_index, rec: {'text': rec['text'],
                                         'size_hint_y': None,
                                         'height': 25}

list_adapter = ListAdapter(data=data,
                           args_converter=args_converter,
                           cls=ListItemButton,
                           selection_mode='single',
                           allow_empty_selection=False)

list_view = ListView(adapter=list_adapter)
```

This listview will show 100 buttons with text of 0 to 100. The `args_converter` function converts the dict items in the data and instantiates `ListItemButton` views by passing these converted items into its constructor. The listview will only allow single selection and the first item will already be selected as `allow_empty_selection` is False. For a complete discussion on these arguments, please see the [ListAdapter](#) documentation.

The `ListItemLabel` works in much the same way as the `ListItemButton`.

### 35.24.7 Using a Custom Item View Class

The data used in an adapter can be any of the normal Python types or custom classes, as shown below. It is up to the programmer to assure that the `args_converter` performs the appropriate conversions.

Here we make a simple `DataItem` class that has the required `text` and `is_selected` properties:

```
from kivy.uix.listview import ListItemButton
from kivy.adapters.listadapter import ListAdapter

class DataItem(object):
    def __init__(self, text='', is_selected=False):
```

```

        self.text = text
        self.is_selected = is_selected

data_items = [DataItem(text='cat'),
             DataItem(text='dog'),
             DataItem(text='frog')]

list_item_args_converter = lambda row_index, obj: {'text': obj.text,
                                                 'size_hint_y': None,
                                                 'height': 25}

list_adapter = ListAdapter(data=data_items,
                           args_converter=list_item_args_converter,
                           propagate_selection_to_data=True,
                           cls=ListItemButton)

list_view = ListView(adapter=list_adapter)

```

The data is passed to the `ListAdapter` along with an `args_converter` function. The propagation setting means that the `is_selected` property for each data item will be set and kept in sync with the list item views. This setting should be set to True if you wish to initialize the view with item views already selected.

You may also use the provided `SelectableDataItem` mixin to make a custom class. Instead of the “manually-constructed” `DataItem` class above, we could do:

```

from kivy.adapters.models import SelectableDataItem

class DataItem(SelectableDataItem):
    # Add properties here.
    pass

```

`SelectableDataItem` is a simple mixin class that has an `is_selected` property.

### 35.24.8 Using an Item View Template

`SelectableView` is another simple mixin class that has required properties for a list item: `text`, and `is_selected`. To make your own template, mix it in as follows:

```

from kivy.lang import Builder

Builder.load_string("""
[CustomListItem@SelectableView+BoxLayout]:
    size_hint_y: ctx.size_hint_y
    height: ctx.height
    ListItemButton:
        text: ctx.text
        is_selected: ctx.is_selected
""")

```

A class called `CustomListItem` can then be instantiated for each list item. Note that it subclasses a `BoxLayout` and is thus a type of `layout`. It contains a `ListItemButton` instance.

Using the power of the Kivy language (kv), you can easily build composite list items: in addition to `ListItemButton`, you could have a `ListItemLabel` or a custom class you have defined and registered via the `Factory`.

An `args_converter` needs to be constructed that goes along with such a kv template. For example, to use the kv template above:

```

list_item_args_converter = \
    lambda row_index, rec: {'text': rec['text'],
                           'is_selected': rec['is_selected'],
                           'size_hint_y': None,
                           'height': 25}
integers_dict = \
    { str(i): {'text': str(i), 'is_selected': False} for i in range(100)}

dict_adapter = DictAdapter(sorted_keys=[str(i) for i in range(100)],
                           data=integers_dict,
                           args_converter=list_item_args_converter,
                           template='CustomListItem')

list_view = ListView(adapter=dict_adapter)

```

A dict adapter is created with 1..100 integer strings as sorted\_keys, and an integers\_dict as data. integers\_dict has the integer strings as keys and dicts with text and is\_selected properties. The CustomListItem defined above in the Builder.load\_string() call is set as the kv template for the list item views. The list\_item\_args\_converter lambda function will take each dict in integers\_dict and will return an args dict, ready for passing as the context (ctx) for the template.

### 35.24.9 Using CompositeListItem

The class **CompositeListItem** is another option for building advanced composite list items. The kv language approach has its advantages, but here we build a composite list view using a plain Python:

```

args_converter = lambda row_index, rec: \
    {'text': rec['text'],
     'size_hint_y': None,
     'height': 25,
     'cls_dicts': [{ 'cls': ListItemButton,
                     'kwargs': {'text': rec['text']}},
                   { 'cls': ListItemLabel,
                     'kwargs': {'text': "Middle-{0}".format(rec['text'])},
                     'is_representing_cls': True},
                   { 'cls': ListItemButton,
                     'kwargs': {'text': rec['text']}}

item_strings = ["{0}".format(index) for index in range(100)]

integers_dict = \
    {str(i): {'text': str(i), 'is_selected': False} for i in range(100)}

dict_adapter = DictAdapter(sorted_keys=item_strings,
                           data=integers_dict,
                           args_converter=args_converter,
                           selection_mode='single',
                           allow_empty_selection=False,
                           cls=CompositeListItem)

list_view = ListView(adapter=dict_adapter)

```

The args\_converter is somewhat complicated, so we should go through the details. Observe in the **DictAdapter** instantiation that **CompositeListItem** instance is set as the cls to be instantiated for each list item component. The args\_converter will make args dicts for this cls. In the args\_converter, the first three items, text, size\_hint\_y, and height, are arguments for the CompositeListItem itself. After that you see a cls\_dicts list that contains argument sets for each of the member widgets for this composite: 2 **ListItemButtons** and a **ListItemLabel**. This is a similar approach to using a kv template

described above.

For details on how `CompositeListItem` works, examine the code, looking for how parsing of the `cls_dicts` list and `kwargs` processing is done.

### 35.24.10 Uses for Selection

What can we do with selection? Combining selection with the system of bindings in Kivy, we can build a wide range of user interface designs.

We could make data items that contain the names of dog breeds, and connect the selection of dog breed to the display of details in another view, which would update automatically on selection. This is done via a binding to the `on_selection_change` event:

```
list_adapter.bind(on_selection_change=callback_function)
```

where `callback_function()` gets passed the adapter as an argument and does whatever is needed for the update. See the example called `list_master_detail.py`, and imagine that the list on the left could be a list of dog breeds, and the detail view on the right could show details for a selected dog breed.

In another example, we could set the `selection_mode` of a listview to ‘multiple’, and load it with a list of answers to a multiple-choice question. The question could have several correct answers. A color swatch view could be bound to selection change, as above, so that it turns green as soon as the correct choices are made, unless the number of touches exceeds a limit, then answer session could be terminated. See the examples that feature thumbnail the images to get some ideas, e.g. `list_cascade_dict.py`.

In a more involved example, we could chain together three listviews, where selection in the first controls the items shown in the second, and selection in the second controls the items shown in the third. If `allow_empty_selection` were set to `False` for these listviews, a dynamic system of selection “cascading” from one list to the next, would result.

There are so many ways that listviews and Kivy bindings functionality can be used, that we have only scratched the surface here. For on-disk examples, see:

```
kivy/examples/widgets/lists/list_*.py
```

Several examples show the “cascading” behavior described above. Others demonstrate the use of kv templates and composite list views.

```
class kivy.uix.listview.SelectableView(*args, **kwargs)
    Bases: object
```

The `SelectableView` mixin is used with list items and other classes that are to be instantiated in a list view or other classes which use a selection-enabled adapter such as `ListAdapter`. `select()` and `deselect()` can be overridden with display code to mark items as selected or not, if desired.

```
deselect(*args)
```

The list item is responsible for updating the display when being unselected, if desired.

```
select(*args)
```

The list item is responsible for updating the display when being selected, if desired.

```
class kivy.uix.listview.ListItemButton(**kwargs)
    Bases:      kivy.uix.listview.ListItemReprMixin,  kivy.uix.selectableview.
                SelectableView, kivy.uix.button.Button
```

`ListButtonItem` mixes `SelectableView` with `Button` to produce a button suitable for use in `ListView`.

```
deselected_color
```

`deselected_color` is a `ListProperty` and defaults to [0., 1., 0., 1].

**selected\_color**

*selected\_color* is a *ListProperty* and defaults to [1., 0., 0., 1].

**class kivy.uix.listview.ListItemLabel(\*\*kwargs)**

Bases: *kivy.uix.listview.ListItemReprMixin*, *kivy.uix.selectableview.SelectableView*, *kivy.uix.label.Label*

*ListItemLabel* mixes *SelectableView* with *Label* to produce a label suitable for use in *ListView*.

**class kivy.uix.listview.CompositeListItem(\*\*kwargs)**

Bases: *kivy.uix.selectableview.SelectableView*, *kivy.uix.boxlayout.BoxLayout*

*CompositeListItem* mixes *SelectableView* with *BoxLayout* for a generic container-style list item, to be used in *ListView*.

**background\_color**

ListItem subclasses Button, which has *background\_color*, but for a composite list item, we must add this property.

*background\_color* is a *ListProperty* and defaults to [1, 1, 1, 1].

**deselected\_color**

*deselected\_color* is a *ListProperty* and defaults to [.33, .33, .33, 1].

**representing\_cls**

Which component view class, if any, should represent for the composite list item in *\_\_repr\_\_()*?

*representing\_cls* is an *ObjectProperty* and defaults to None.

**selected\_color**

*selected\_color* is a *ListProperty* and defaults to [1., 0., 0., 1].

**class kivy.uix.listview.ListView(\*args, \*\*kwargs)**

Bases: *kivy.uix.abstractview.AbstractView*, *kivy.event.EventDispatcher*

*ListView* is a primary high-level widget, handling the common task of presenting items in a scrolling list. Flexibility is afforded by use of a variety of adapters to interface with data.

The adapter property comes via the mixed in *AbstractView* class.

*ListView* also subclasses *EventDispatcher* for scrolling. The event *on\_scroll\_complete* is used in refreshing the main view.

For a simple list of string items, without selection, use *SimpleListAdapter*. For list items that respond to selection, ranging from simple items to advanced composites, use *ListAdapter*. For an alternate powerful adapter, use *DictAdapter*, rounding out the choice for designing highly interactive lists.

**Events**

*on\_scroll\_complete: (boolean, )* Fired when scrolling completes.

**container**

The container is a *GridLayout* widget held within a *ScrollView* widget. (See the associated kv block in the *Builder.load\_string()* setup). Item view instances managed and provided by the adapter are added to this container. The container is cleared with a call to *clear\_widgets()* when the list is rebuilt by the *populate()* method. A padding *Widget* instance is also added as needed, depending on the row height calculations.

*container* is an *ObjectProperty* and defaults to None.

**divider**

[TODO] Not used.

**divider\_height**

[TODO] Not used.

**item\_strings**

If item\_strings is provided, create an instance of *SimpleListAdapter* with this list of strings, and use it to manage a no-selection list.

*item\_strings* is a *ListProperty* and defaults to [].

**row\_height**

The row\_height property is calculated on the basis of the height of the container and the count of items.

*row\_height* is a *NumericProperty* and defaults to None.

**scrolling**

If the scroll\_to() method is called while scrolling operations are happening, a call recursion error can occur. scroll\_to() checks to see that scrolling is False before calling populate(). scroll\_to() dispatches a scrolling\_complete event, which sets scrolling back to False.

*scrolling* is a *BooleanProperty* and defaults to False.

```
class kivy.uix.listview.ListItemReprMixin(**kwargs)
```

Bases: *kivy.uix.label.Label*

The *ListItemReprMixin* provides a *Label* with a Python 2/3 compatible string representation (*\_\_repr\_\_*). It is intended for internal usage.

## 35.25 ModalView

New in version 1.4.0.

The *ModalView* widget is used to create modal views. By default, the view will cover the whole “parent” window.

Remember that the default size of a Widget is size\_hint=(1, 1). If you don’t want your view to be fullscreen, either use size hints with values lower than 1 (for instance size\_hint=(.8, .8)) or deactivate the size\_hint and use fixed size attributes.

### 35.25.1 Examples

Example of a simple 400x400 Hello world view:

```
view = ModalView(size_hint=(None, None), size=(400, 400))
view.add_widget(Label(text='Hello world'))
```

By default, any click outside the view will dismiss it. If you don’t want that, you can set *ModalView.auto\_dismiss* to False:

```
view = ModalView(auto_dismiss=False)
view.add_widget(Label(text='Hello world'))
view.open()
```

To manually dismiss/close the view, use the *ModalView.dismiss()* method of the ModalView instance:

```
view.dismiss()
```

Both `ModalView.open()` and `ModalView.dismiss()` are bindable. That means you can directly bind the function to an action, e.g. to a button's `on_press`

```
# create content and add it to the view
content = Button(text='Close me!')
view = ModalView(auto_dismiss=False)
view.add_widget(content)

# bind the on_press event of the button to the dismiss function
content.bind(on_press=view.dismiss)

# open the view
view.open()
```

### 35.25.2 ModalView Events

There are two events available: `on_open` which is raised when the view is opening, and `on_dismiss` which is raised when the view is closed. For `on_dismiss`, you can prevent the view from closing by explicitly returning True from your callback.

```
def my_callback(instance):
    print('ModalView', instance, 'is being dismissed, but is prevented!')
    return True
view = ModalView()
view.add_widget(Label(text='Hello world'))
view.bind(on_dismiss=my_callback)
view.open()
```

Changed in version 1.5.0: The `ModalView` can be closed by hitting the escape key on the keyboard if the `ModalView.auto_dismiss` property is True (the default).

`class kivy.uix.modalview.ModalView(**kwargs)`  
Bases: `kivy.uix.anchorlayout.AnchorLayout`

ModalView class. See module documentation for more information.

#### Events

`on_open`: Fired when the `ModalView` is opened.

`on_dismiss`: Fired when the `ModalView` is closed. If the callback returns True, the dismiss will be canceled.

#### attach\_to

If a widget is set on `attach_to`, the view will attach to the nearest parent window of the widget. If none is found, it will attach to the main/global Window.

`attach_to` is an `ObjectProperty` and defaults to None.

#### auto\_dismiss

This property determines if the view is automatically dismissed when the user clicks outside it.

`auto_dismiss` is a `BooleanProperty` and defaults to True.

#### background

Background image of the view used for the view background.

`background` is a `StringProperty` and defaults to 'atlas://data/images/defaulttheme/modalview-background'.

### **background\_color**

Background color in the format (r, g, b, a).

*background\_color* is a *ListProperty* and defaults to [0, 0, 0, .7].

### **border**

Border used for *BorderImage* graphics instruction. Used for the *background\_normal* and the *background\_down* properties. Can be used when using custom backgrounds.

It must be a list of four values: (bottom, right, top, left). Read the *BorderImage* instructions for more information about how to use it.

*border* is a *ListProperty* and defaults to (16, 16, 16, 16).

### **dismiss(\*largs, \*\*kwargs)**

Close the view if it is open. If you really want to close the view, whatever the *on\_dismiss* event returns, you can use the *force* argument:

```
view = ModalView()
view.dismiss(force=True)
```

When the view is dismissed, it will be faded out before being removed from the parent. If you don't want animation, use:

```
view.dismiss(animation=False)
```

### **open(\*largs, \*\*kwargs)**

Show the view window from the *attach\_to* widget. If set, it will attach to the nearest window. If the widget is not attached to any window, the view will attach to the global *Window*.

When the view is opened, it will be faded in with an animation. If you don't want the animation, use:

```
view.open(animation=False)
```

## 35.26 PageLayout

The *PageLayout* class is used to create a simple multi-page layout, in a way that allows easy flipping from one page to another using borders.

*PageLayout* does not currently honor the *size\_hint*, *size\_hint\_min*, *size\_hint\_max*, or *pos\_hint* properties.

New in version 1.8.0.

Example:

```
PageLayout:
    Button:
        text: 'page1'
    Button:
        text: 'page2'
    Button:
        text: 'page3'
```

Transitions from one page to the next are made by swiping in from the border areas on the right or left hand side. If you wish to display multiple widgets in a page, we suggest you use a containing layout.

Ideally, each page should consist of a single `layout` widget that contains the remaining widgets on that page.

```
class kivy.uix.pagelayout.PageLayout(**kwargs)
Bases: kivy.uix.layout.Layout
```

PageLayout class. See module documentation for more information.

#### border

The width of the border around the current page used to display the previous/next page swipe areas when needed.

`border` is a *NumericProperty* and defaults to 50dp.

#### page

The currently displayed page.

`page` is a *NumericProperty* and defaults to 0.

#### swipe\_threshold

The threshold used to trigger swipes as percentage of the widget size.

`swipe_threshold` is a *NumericProperty* and defaults to .5.

## 35.27 Popup

New in version 1.0.7.



The `Popup` widget is used to create modal popups. By default, the popup will cover the whole “parent” window. When you are creating a popup, you must at least set a `Popup.title` and `Popup.content`.

Remember that the default size of a Widget is `size_hint=(1, 1)`. If you don’t want your popup to be fullscreen, either use size hints with values less than 1 (for instance `size_hint=(.8, .8)`) or deactivate the `size_hint` and use fixed size attributes.

Changed in version 1.4.0: The `Popup` class now inherits from `ModalView`. The `Popup` offers a default layout with a title and a separation bar.

### 35.27.1 Examples

Example of a simple 400x400 Hello world popup:

```
popup = Popup(title='Test popup',
    content=Label(text='Hello world'),
    size_hint=(None, None), size=(400, 400))
```

By default, any click outside the popup will dismiss/close it. If you don't want that, you can set `auto_dismiss` to False:

```
popup = Popup(title='Test popup', content=Label(text='Hello world'),
    auto_dismiss=False)
popup.open()
```

To manually dismiss/close the popup, use `dismiss`:

```
popup.dismiss()
```

Both `open()` and `dismiss()` are bindable. That means you can directly bind the function to an action, e.g. to a button's `on_press`:

```
# create content and add to the popup
content = Button(text='Close me!')
popup = Popup(content=content, auto_dismiss=False)

# bind the on_press event of the button to the dismiss function
content.bind(on_press=popup.dismiss)

# open the popup
popup.open()
```

Same thing in KV language only with Factory:

```
#:import Factory kivy.factory.Factory
<MyPopup@Popup>:
    auto_dismiss: False
    Button:
        text: 'Close me!'
        on_release: root.dismiss()

    Button:
        text: 'Open popup'
        on_release: Factory.MyPopup().open()
```

---

**Note:** Popup is a special widget. Don't try to add it as a child to any other widget. If you do, Popup will be handled like an ordinary widget and won't be created hidden in the background.

```
BoxLayout:
    MyPopup: # bad!
```

## 35.27.2 Popup Events

There are two events available: `on_open` which is raised when the popup is opening, and `on_dismiss` which is raised when the popup is closed. For `on_dismiss`, you can prevent the popup from closing by explicitly returning True from your callback:

```
def my_callback(instance):
    print('Popup', instance, 'is being dismissed but is prevented!')
```

```
return True
popup = Popup(content=Label(text='Hello world'))
popup.bind(on_dismiss=my_callback)
popup.open()
```

**class** kivy.uix.popup.Popup(\*\*kwargs)  
Bases: *kivy.uix.modalview.ModalView*

Popup class. See module documentation for more information.

#### Events

*on\_open*: Fired when the Popup is opened.

*on\_dismiss*: Fired when the Popup is closed. If the callback returns True, the dismiss will be canceled.

#### content

Content of the popup that is displayed just under the title.

*content* is an *ObjectProperty* and defaults to None.

#### separator\_color

Color used by the separator between title and content.

New in version 1.1.0.

*separator\_color* is a *ListProperty* and defaults to [47 / 255., 167 / 255., 212 / 255., 1.]

#### separator\_height

Height of the separator.

New in version 1.1.0.

*separator\_height* is a *NumericProperty* and defaults to 2dp.

#### title

String that represents the title of the popup.

*title* is a *StringProperty* and defaults to 'No title'.

#### title\_align

Horizontal alignment of the title.

New in version 1.9.0.

*title\_align* is a *OptionProperty* and defaults to 'left'. Available options are left, center, right and justify.

#### title\_color

Color used by the Title.

New in version 1.8.0.

*title\_color* is a *ListProperty* and defaults to [1, 1, 1, 1].

#### title\_font

Font used to render the title text.

New in version 1.9.0.

*title\_font* is a *StringProperty* and defaults to 'Roboto'. This value is taken from *Config*.

#### title\_size

Represents the font size of the popup title.

New in version 1.6.0.

`title_size` is a *NumericProperty* and defaults to '14sp'.

**class kivy.uix.popup.PopupException**

Bases: `exceptions.Exception`

Popup exception, fired when multiple content widgets are added to the popup.

New in version 1.4.0.

## 35.28 Progress Bar

New in version 1.0.8.



The **ProgressBar** widget is used to visualize the progress of some task. Only the horizontal mode is currently supported: the vertical mode is not yet available.

The progress bar has no interactive elements and is a display-only widget.

To use it, simply assign a value to indicate the current progress:

```
from kivy.uix.progressbar import ProgressBar
pb = ProgressBar(max=1000)

# this will update the graphics automatically (75% done)
pb.value = 750
```

**class kivy.uix.progressbar.ProgressBar(\*\*kwargs)**

Bases: *kivy.uix.widget.Widget*

Class for creating a progress bar widget.

See module documentation for more details.

**max**

Maximum value allowed for `value`.

`max` is a *NumericProperty* and defaults to 100.

**value**

Current value used for the slider.

`value` is an *AliasProperty* that returns the value of the progress bar. If the value is < 0 or > `max`, it will be normalized to those boundaries.

Changed in version 1.6.0: The value is now limited to between 0 and `max`.

**value\_normalized**

Normalized value inside the range 0-1:

```
>>> pb = ProgressBar(value=50, max=100)
>>> pb.value
50
>>> pb.value_normalized
0.5
```

`value_normalized` is an *AliasProperty*.

## 35.29 RecycleBoxLayout

New in version 1.10.0.

**Warning:** This module is highly experimental, its API may change in the future and the documentation is not complete at this time.

The RecycleBoxLayout is designed to provide a *BoxLayout* type layout when used with the *RecycleView* widget. Please refer to the *recycleview* module documentation for more information.

## 35.30 RecycleGridLayout

New in version 1.10.0.

**Warning:** This module is highly experimental, its API may change in the future and the documentation is not complete at this time.

The RecycleGridLayout is designed to provide a *GridLayout* type layout when used with the *RecycleView* widget. Please refer to the *recycleview* module documentation for more information.

## 35.31 RecycleLayout

New in version 1.10.0.

**Warning:** This module is highly experimental, its API may change in the future and the documentation is not complete at this time.

```
class kivy.uix.recyclelayout.RecycleLayout(**kwargs)
    Bases: kivy.uix.recycleview.layout.RecycleLayoutManagerBehavior, kivy.uix.layout.Layout
```

RecycleLayout provides the default layout for RecycleViews.

### **default\_size**

size as in w, h. They each can be None.

## 35.32 Relative Layout

New in version 1.4.0.

This layout allows you to set relative coordinates for children. If you want absolute positioning, use the *FloatLayout*.

The *RelativeLayout* class behaves just like the regular *FloatLayout* except that its child widgets are positioned relative to the layout.

When a widget with position = (0,0) is added to a `RelativeLayout`, the child widget will also move when the position of the `RelativeLayout` is changed. The child widgets coordinates remain (0,0) as they are always relative to the parent layout.

### 35.32.1 Coordinate Systems

#### Window coordinates

By default, there's only one coordinate system that defines the position of widgets and touch events dispatched to them: the window coordinate system, which places (0, 0) at the bottom left corner of the window. Although there are other coordinate systems defined, e.g. local and parent coordinates, these coordinate systems are identical to the window coordinate system as long as a relative layout type widget is not in the widget's parent stack. When `widget.pos` is read or a touch is received, the coordinate values are in parent coordinates, but as mentioned, these are identical to window coordinates, even in complex widget stacks.

For example:

```
BoxLayout:  
    Label:  
        text: 'Left'  
    Button:  
        text: 'Middle'  
        on_touch_down: print('Middle: {}'.format(args[1].pos))  
BoxLayout:  
    on_touch_down: print('Box: {}'.format(args[1].pos))  
    Button:  
        text: 'Right'  
        on_touch_down: print('Right: {}'.format(args[1].pos))
```

When the middle button is clicked and the touch propagates through the different parent coordinate systems, it prints the following:

```
>>> Box: (430.0, 282.0)  
>>> Right: (430.0, 282.0)  
>>> Middle: (430.0, 282.0)
```

As claimed, the touch has identical coordinates to the window coordinates in every coordinate system. `collide_point()` for example, takes the point in window coordinates.

#### Parent coordinates

Other `RelativeLayout` type widgets are `Scatter`, `ScatterLayout`, and `ScrollView`. If such a special widget is in the parent stack, only then does the parent and local coordinate system diverge from the window coordinate system. For each such widget in the stack, a coordinate system with (0, 0) of that coordinate system being at the bottom left corner of that widget is created. **Position and touch coordinates received and read by a widget are in the coordinate system of the most recent special widget in its parent stack (not including itself) or in window coordinates if there are none** (as in the first example). We call these coordinates parent coordinates.

For example:

```
BoxLayout:  
    Label:  
        text: 'Left'  
    Button:  
        text: 'Middle'
```

```

    on_touch_down: print('Middle: {}'.format(args[1].pos))
RelativeLayout:
    on_touch_down: print('Relative: {}'.format(args[1].pos))
    Button:
        text: 'Right'
        on_touch_down: print('Right: {}'.format(args[1].pos))

```

Clicking on the middle button prints:

```

>>> Relative: (396.0, 298.0)
>>> Right: (-137.33, 298.0)
>>> Middle: (396.0, 298.0)

```

As the touch propagates through the widgets, for each widget, the touch is received in parent coordinates. Because both the relative and middle widgets don't have these special widgets in their parent stack, the touch is the same as window coordinates. Only the right widget, which has a RelativeLayout in its parent stack, receives the touch in coordinates relative to that RelativeLayout which is different than window coordinates.

### Local and Widget coordinates

When expressed in parent coordinates, the position is expressed in the coordinates of the most recent special widget in its parent stack, not including itself. When expressed in local or widget coordinates, the widgets themselves are also included.

Changing the above example to transform the parent coordinates into local coordinates:

```

BoxLayout:
    Label:
        text: 'Left'
    Button:
        text: 'Middle'
        on_touch_down: print('Middle: {}'.format(self.to_local(*args[1].pos)))
RelativeLayout:
    on_touch_down: print('Relative: {}'.format(self.to_local(*args[1].pos)))
    Button:
        text: 'Right'
        on_touch_down: print('Right: {}'.format(self.to_local(*args[1].pos)))

```

Now, clicking on the middle button prints:

```

>>> Relative: (-135.33, 301.0)
>>> Right: (-135.33, 301.0)
>>> Middle: (398.0, 301.0)

```

This is because now the relative widget also expresses the coordinates relative to itself.

### Coordinate transformations

**Widget** provides 4 functions to transform coordinates between the various coordinate systems. For now, we assume that the *relative* keyword of these functions is *False*. **to\_widget()** takes the coordinates expressed in window coordinates and returns them in local (widget) coordinates. **to\_window()** takes the coordinates expressed in local coordinates and returns them in window coordinates. **to\_parent()** takes the coordinates expressed in local coordinates and returns them in parent coordinates. **to\_local()** takes the coordinates expressed in parent coordinates and returns them in local coordinates.

Each of the 4 transformation functions take a *relative* parameter. When the relative parameter is True, the coordinates are returned or originate in true relative coordinates - relative to a coordinate system with its (0, 0) at the bottom left corner of the widget in question.

### 35.32.2 Common Pitfalls

As all positions within a *RelativeLayout* are relative to the position of the layout itself, the position of the layout should never be used in determining the position of sub-widgets or the layout's canvas.

Take the following kv code for example:




Fig. 35.1: expected result




Fig. 35.2: actual result

```
FloatLayout:  
    Widget:  
        size_hint: None, None
```

```

size: 200, 200
pos: 200, 200

canvas:
    Color:
        rgba: 1, 1, 1, 1
    Rectangle:
        pos: self.pos
        size: self.size

RelativeLayout:
    size_hint: None, None
    size: 200, 200
    pos: 200, 200

    canvas:
        Color:
            rgba: 1, 0, 0, 0.5
        Rectangle:
            pos: self.pos # incorrect
            size: self.size

```

You might expect this to render a single pink rectangle; however, the content of the `RelativeLayout` is already transformed, so the use of `pos: self.pos` will double that transformation. In this case, using `pos: 0, 0` or omitting `pos` completely will provide the expected result.

This also applies to the position of sub-widgets. Instead of positioning a `Widget` based on the layout's own position:

```

RelativeLayout:
    Widget:
        pos: self.parent.pos
    Widget:
        center: self.parent.center

```

use the `pos_hint` property:

```

RelativeLayout:
    Widget:
        pos_hint: {'x': 0, 'y': 0}
    Widget:
        pos_hint: {'center_x': 0.5, 'center_y': 0.5}

```

Changed in version 1.7.0: Prior to version 1.7.0, the `RelativeLayout` was implemented as a `FloatLayout` inside a `Scatter`. This behaviour/widget has been renamed to `ScatterLayout`. The `RelativeLayout` now only supports relative positions (and can't be rotated, scaled or translated on a multitouch system using two or more fingers). This was done so that the implementation could be optimized and avoid the heavier calculations of `Scatter` (e.g. inverse matrix, recalculating multiple properties etc.)

```

class kivy.uix.relativelayout.RelativeLayout(**kw)
    Bases: kivy.uix.floatlayout.FloatLayout

```

`RelativeLayout` class, see module documentation for more information.

### 35.33 reStructuredText renderer

New in version 1.1.0.

`reStructuredText` is an easy-to-read, what-you-see-is-what-you-get plaintext markup syntax and parser system.

---

**Note:** This widget requires the `docutils` package to run. Install it with `pip` or include it as one of your deployment requirements.

---

**Warning:** This widget is highly experimental. The styling and implementation should not be considered stable until this warning has been removed.

### 35.33.1 Usage with Text

```
text = """
... _top:

Hello world
=====

This is an **emphasized text**, some ``interpreted text``.
And this is a reference to top_::

    $ print("Hello world")

"""
document = RstDocument(text=text)
```

The rendering will output:

## Hello world

---

This is an **emphasized text**, some interpreted text. And this is a reference to [top](#):

```
$ print "Hello world"
```

### 35.33.2 Usage with Source

You can also render a `rst` file using the `source` property:

```
document = RstDocument(source='index.rst')
```

You can reference other documents using the role `:doc:`. For example, in the document `index.rst` you can write:

```
Go to my next document: :doc:`moreinfo.rst`
```

It will generate a link that, when clicked, opens the `moreinfo.rst` document.

```
class kivy.uix.rst.RstDocument(**kwargs)
Bases: kivy.uix.scrollview.ScrollView
```

Base widget used to store an Rst document. See module documentation for more information.

#### **background\_color**

Specifies the background\_color to be used for the RstDocument.

New in version 1.8.0.

*background\_color* is an *AliasProperty* for colors['background'].

#### **base\_font\_size**

Font size for the biggest title, 31 by default. All other font sizes are derived from this.

New in version 1.8.0.

#### **colors**

Dictionary of all the colors used in the RST rendering.

**Warning:** This dictionary is needs special handling. You also need to call *RstDocument.render()* if you change them after loading.

*colors* is a *DictProperty*.

#### **document\_root**

Root path where :doc: will search for rst documents. If no path is given, it will use the directory of the first loaded source file.

*document\_root* is a *StringProperty* and defaults to None.

#### **goto(ref, \*largs)**

Scroll to the reference. If it's not found, nothing will be done.

For this text:

```
.. _myref:  
  
This is something I always wanted.
```

You can do:

```
from kivy.clock import Clock
from functools import partial

doc = RstDocument(...)
Clock.schedule_once(partial(doc.goto, 'myref'), 0.1)
```

---

**Note:** It is preferable to delay the call of the goto if you just loaded the document because the layout might not be finished or the size of the RstDocument has not yet been determined. In either case, the calculation of the scrolling would be wrong.

You can, however, do a direct call if the document is already loaded.

---

New in version 1.3.0.

#### **preload(filename, encoding='utf-8', errors='strict')**

Preload a rst file to get its toctree and its title.

The result will be stored in *toctrees* with the *filename* as key.

**render()**

Force document rendering.

**resolve\_path(*filename*)**

Get the path for this filename. If the filename doesn't exist, it returns the document\_root + filename.

**show\_errors**

Indicate whether RST parsers errors should be shown on the screen or not.

*show\_errors* is a *BooleanProperty* and defaults to False.

**source**

Filename of the RST document.

*source* is a *StringProperty* and defaults to None.

**source\_encoding**

Encoding to be used for the *source* file.

*source\_encoding* is a *StringProperty* and defaults to *utf-8*.

---

**Note:** It is your responsibility to ensure that the value provided is a valid codec supported by python.

---

**source\_error**

Error handling to be used while encoding the *source* file.

*source\_error* is an *OptionProperty* and defaults to *strict*. Can be one of 'strict', 'ignore', 'replace', 'xmlcharrefreplace' or 'backslashreplac'.

**text**

RST markup text of the document.

*text* is a *StringProperty* and defaults to None.

**title**

Title of the current document.

*title* is a *StringProperty* and defaults to ''. It is read-only.

**toctrees**

Toctree of all loaded or preloaded documents. This dictionary is filled when a rst document is explicitly loaded or where *preload()* has been called.

If the document has no filename, e.g. when the document is loaded from a text file, the key will be ''.

*toctrees* is a *DictProperty* and defaults to {}.

**underline\_color**

underline color of the titles, expressed in html color notation

*underline\_color* is a *StringProperty* and defaults to '204a9699'.

## 35.34 Sandbox

New in version 1.8.0.

**Warning:** This is experimental and subject to change as long as this warning notice is present.

This is a widget that runs itself and all of its children in a Sandbox. That means if a child raises an Exception, it will be caught. The Sandbox itself runs its own Clock, Cache, etc.

The SandBox widget is still experimental and required for the Kivy designer. When the user designs their own widget, if they do something wrong (wrong size value, invalid python code), it will be caught correctly without breaking the whole application. Because it has been designed that way, we are still enhancing this widget and the `kivy.context` module. Don't use it unless you know what you are doing.

```
class kivy.uix.sandbox.Sandbox(**kwargs)
    Bases: kivy.uix.floatlayout.FloatLayout
```

Sandbox widget, used to trap all the exceptions raised by child widgets.

**on\_context\_created()**

Override this method in order to load your kv file or do anything else with the newly created context.

**on\_exception(exception, \_traceback=None)**

Override this method in order to catch all the exceptions from children.

If you return True, it will not reraise the exception. If you return False, the exception will be raised to the parent.

**on\_touch\_down(\*args, \*\*kwargs)**

Receive a touch down event.

#### Parameters

*touch: MotionEvent class* Touch received. The touch is in parent coordinates.  
See `relativelayout` for a discussion on coordinate systems.

**Returns** bool If True, the dispatching of the touch event will stop. If False, the event will continue to be dispatched to the rest of the widget tree.

**on\_touch\_move(\*args, \*\*kwargs)**

Receive a touch move event. The touch is in parent coordinates.

See `on_touch_down()` for more information.

**on\_touch\_up(\*args, \*\*kwargs)**

Receive a touch up event. The touch is in parent coordinates.

See `on_touch_down()` for more information.

## 35.35 Scatter

**Scatter** is used to build interactive widgets that can be translated, rotated and scaled with two or more fingers on a multitouch system.

Scatter has its own matrix transformation: the modelview matrix is changed before the children are drawn and the previous matrix is restored when the drawing is finished. That makes it possible to perform rotation, scaling and translation over the entire children tree without changing any widget properties. That specific behavior makes the scatter unique, but there are some advantages / constraints that you should consider:

1. The children are positioned relative to the scatter similarly to a `RelativeLayout`. So when dragging the scatter, the position of the children don't change, only the position of the scatter does.
2. The scatter size has no impact on the size of its children.

3. If you want to resize the scatter, use scale, not size (read #2). Scale transforms both the scatter and its children, but does not change size.
4. The scatter is not a layout. You must manage the size of the children yourself.

For touch events, the scatter converts from the parent matrix to the scatter matrix automatically in `on_touch_down/move/up` events. If you are doing things manually, you will need to use `to_parent()` and `to_local()`.

### 35.35.1 Usage

By default, the Scatter does not have a graphical representation: it is a container only. The idea is to combine the Scatter with another widget, for example an `Image`:

```
scatter = Scatter()
image = Image(source='sun.jpg')
scatter.add_widget(image)
```

### 35.35.2 Control Interactions

By default, all interactions are enabled. You can selectively disable them using the `do_rotation`, `do_translation` and `do_scale` properties.

Disable rotation:

```
scatter = Scatter(do_rotation=False)
```

Allow only translation:

```
scatter = Scatter(do_rotation=False, do_scale=False)
```

Allow only translation on x axis:

```
scatter = Scatter(do_rotation=False, do_scale=False,
                 do_translation_y=False)
```

### 35.35.3 Automatic Bring to Front

If the `Scatter.auto_bring_to_front` property is True, the scatter widget will be removed and re-added to the parent when it is touched (brought to front, above all other widgets in the parent). This is useful when you are manipulating several scatter widgets and don't want the active one to be partially hidden.

### 35.35.4 Scale Limitation

We are using a 32-bit matrix in double representation. That means we have a limit for scaling. You cannot do infinite scaling down/up with our implementation. Generally, you don't hit the minimum scale (because you don't see it on the screen), but the maximum scale is  $9.99506983235e+19$  ( $2^{66}$ ).

You can also limit the minimum and maximum scale allowed:

```
scatter = Scatter(scale_min=.5, scale_max=3.)
```

### 35.35.5 Behavior

Changed in version 1.1.0: If no control interactions are enabled, then the touch handler will never return True.

**class kivy.uix.scatter.Scatter(\*\*kwargs)**  
Bases: [kivy.uix.widget.Widget](#)

Scatter class. See module documentation for more information.

#### Events

**on\_transform\_with\_touch:** Fired when the scatter has been transformed by user touch or multitouch, such as panning or zooming.

**on\_bring\_to\_front:** Fired when the scatter is brought to the front.

Changed in version 1.9.0: Event *on\_bring\_to\_front* added.

Changed in version 1.8.0: Event *on\_transform\_with\_touch* added.

**apply\_transform(trans, post\_multiply=False, anchor=(0, 0))**

Transforms the scatter by applying the “trans” transformation matrix (on top of its current transformation state). The resultant matrix can be found in the [transform](#) property.

#### Parameters

**trans: Matrix.** Transformation matrix to be applied to the scatter widget.

**anchor: tuple, defaults to (0, 0).** The point to use as the origin of the transformation (uses local widget space).

**post\_multiply: bool, defaults to False.** If True, the transform matrix is post multiplied (as if applied before the current transform).

Usage example:

```
from kivy.graphics.transformation import Matrix
mat = Matrix().scale(3, 3, 3)
scatter_instance.apply_transform(mat)
```

#### auto\_bring\_to\_front

If True, the widget will be automatically pushed on the top of parent widget list for drawing.

*auto\_bring\_to\_front* is a [BooleanProperty](#) and defaults to True.

#### bbox

Bounding box of the widget in parent space:

```
((x, y), (w, h))
# x, y = lower left corner
```

*bbox* is an [AliasProperty](#).

#### do\_collide\_after\_children

If True, the collision detection for limiting the touch inside the scatter will be done after dispatching the touch to the children. You can put children outside the bounding box of the scatter and still be able to touch them.

*do\_collide\_after\_children* is a [BooleanProperty](#) and defaults to False.

New in version 1.3.0.

#### do\_rotation

Allow rotation.

*do\_rotation* is a [BooleanProperty](#) and defaults to True.

**do\_scale**

Allow scaling.

*do\_scale* is a *BooleanProperty* and defaults to True.

**do\_translation**

Allow translation on the X or Y axis.

*do\_translation* is an *AliasProperty* of (*do\_translation\_x* + *do\_translation\_y*)

**do\_translation\_x**

Allow translation on the X axis.

*do\_translation\_x* is a *BooleanProperty* and defaults to True.

**do\_translation\_y**

Allow translation on Y axis.

*do\_translation\_y* is a *BooleanProperty* and defaults to True.

**on\_bring\_to\_front(*touch*)**

Called when a touch event causes the scatter to be brought to the front of the parent (only if *auto\_bring\_to\_front* is True)

**Parameters**

*touch*: The touch object which brought the scatter to front.

New in version 1.9.0.

**on\_transform\_with\_touch(*touch*)**

Called when a touch event has transformed the scatter widget. By default this does nothing, but can be overridden by derived classes that need to react to transformations caused by user input.

**Parameters**

*touch*: The touch object which triggered the transformation.

New in version 1.8.0.

**rotation**

Rotation value of the scatter in degrees moving in a counterclockwise direction.

*rotation* is an *AliasProperty* and defaults to 0.0.

**scale**

Scale value of the scatter.

*scale* is an *AliasProperty* and defaults to 1.0.

**scale\_max**

Maximum scaling factor allowed.

*scale\_max* is a *NumericProperty* and defaults to 1e20.

**scale\_min**

Minimum scaling factor allowed.

*scale\_min* is a *NumericProperty* and defaults to 0.01.

**transform**

Transformation matrix.

*transform* is an *ObjectProperty* and defaults to the identity matrix.

---

**Note:** This matrix reflects the current state of the transformation matrix but setting it directly will erase previously applied transformations. To apply a transformation considering context, please use the `apply_transform` method.

---

### **transform\_inv**

Inverse of the transformation matrix.

`transform_inv` is an *ObjectProperty* and defaults to the identity matrix.

### **translation\_touches**

Determine whether translation was triggered by a single or multiple touches. This only has effect when `do_translation` = True.

`translation_touches` is a *NumericProperty* and defaults to 1.

New in version 1.7.0.

```
class kivy.uix.scatter.ScatterPlane(**kwargs)
Bases: kivy.uix.scatter.Scatter
```

This is essentially an unbounded Scatter widget. It's a convenience class to make it easier to handle infinite planes.

## 35.36 Scatter Layout

New in version 1.6.0.

This layout behaves just like a `RelativeLayout`. When a widget is added with position = (0,0) to a `ScatterLayout`, the child widget will also move when you change the position of the `ScatterLayout`. The child widget's coordinates remain (0,0) as they are relative to the parent layout.

However, since `ScatterLayout` is implemented using a `Scatter` widget, you can also translate, rotate and scale the layout using touches or clicks, just like in the case of a normal Scatter widget, and the child widgets will behave as expected.

In contrast to a Scatter, the Layout favours 'hint' properties, such as `size_hint`, `size_hint_x`, `size_hint_y` and `pos_hint`.

---

**Note:** The `ScatterLayout` is implemented as a `FloatLayout` inside a `Scatter`.

---

**Warning:** Since the actual `ScatterLayout` is a `Scatter`, its `add_widget` and `remove_widget` functions are overridden to add children to the embedded `FloatLayout` (accessible as the `content` property of `Scatter`) automatically. So if you want to access the added child elements, you need `self.content.children` instead of `self.children`.

**Warning:** The `ScatterLayout` was introduced in 1.7.0 and was called `RelativeLayout` in prior versions. The `RelativeLayout` is now an optimized implementation that uses only a positional transform to avoid some of the heavier calculation involved for `Scatter`.

```
class kivy.uix.scatterlayout.ScatterLayout(**kw)
Bases: kivy.uix.scatter.Scatter
```

ScatterLayout class, see module documentation for more information.

```
class kivy.uix.scatterlayout.ScatterPlaneLayout(**kwargs)
    Bases: kivy.uix.scatter.ScatterPlane
```

ScatterPlaneLayout class, see module documentation for more information.

Similar to ScatterLayout, but based on ScatterPlane - so the input is not bounded.

New in version 1.9.0.

## 35.37 Screen Manager

New in version 1.4.0.

The screen manager is a widget dedicated to managing multiple screens for your application. The default *ScreenManager* displays only one *Screen* at a time and uses a *TransitionBase* to switch from one Screen to another.

Multiple transitions are supported based on changing the screen coordinates / scale or even performing fancy animation using custom shaders.

### 35.37.1 Basic Usage

Let's construct a Screen Manager with 4 named screens. When you are creating a screen, **you absolutely need to give a name to it**:

```
from kivy.uix.screenmanager import ScreenManager, Screen

# Create the manager
sm = ScreenManager()

# Add few screens
for i in range(4):
    screen = Screen(name='Title %d' % i)
    sm.add_widget(screen)

# By default, the first screen added into the ScreenManager will be
# displayed. You can then change to another screen.

# Let's display the screen named 'Title 2'
# A transition will automatically be used.
sm.current = 'Title 2'
```

The default *ScreenManager.transition* is a *SlideTransition* with options *direction* and *duration*.

Please note that by default, a *Screen* displays nothing: it's just a *RelativeLayout*. You need to use that class as a root widget for your own screen, the best way being to subclass.

**Warning:** As *Screen* is a *RelativeLayout*, it is important to understand the *Common Pitfalls*.

Here is an example with a 'Menu Screen' and a 'Settings Screen':

```

from kivy.app import App
from kivy.lang import Builder
from kivy.uix.screenmanager import ScreenManager, Screen

# Create both screens. Please note the root.manager.current: this is how
# you can control the ScreenManager from kv. Each screen has by default a
# property manager that gives you the instance of the ScreenManager used.
Builder.load_string("""
<MenuScreen>:
    BoxLayout:
        Button:
            text: 'Goto settings'
            on_press: root.manager.current = 'settings'
        Button:
            text: 'Quit'

<SettingsScreen>:
    BoxLayout:
        Button:
            text: 'My settings button'
        Button:
            text: 'Back to menu'
            on_press: root.manager.current = 'menu'
""")

# Declare both screens
class MenuScreen(Screen):
    pass

class SettingsScreen(Screen):
    pass

# Create the screen manager
sm = ScreenManager()
sm.add_widget(MenuScreen(name='menu'))
sm.add_widget(SettingsScreen(name='settings'))

class TestApp(App):

    def build(self):
        return sm

if __name__ == '__main__':
    TestApp().run()

```

### 35.37.2 Changing Direction

A common use case for `ScreenManager` involves using a `SlideTransition` which slides right to the next screen and slides left to the previous screen. Building on the previous example, this can be accomplished like so:

```

Builder.load_string("""
<MenuScreen>:
    BoxLayout:
        Button:
            text: 'Goto settings'
            on_press:
                root.manager.transition.direction = 'left'

```

```

        root.manager.current = 'settings'
    Button:
        text: 'Quit'

<SettingsScreen>:
    BoxLayout:
        Button:
            text: 'My settings button'
        Button:
            text: 'Back to menu'
            on_press:
                root.manager.transition.direction = 'right'
                root.manager.current = 'menu'
    """
)

```

### 35.37.3 Advanced Usage

From 1.8.0, you can now switch dynamically to a new screen, change the transition options and remove the previous one by using `switch_to()`:

```

sm = ScreenManager()
screens = [Screen(name='Title {}'.format(i)) for i in range(4)]

sm.switch_to(screens[0])
# later
sm.switch_to(screens[1], direction='right')

```

Note that this method adds the screen to the `ScreenManager` instance and should not be used if your screens have already been added to this instance. To switch to a screen which is already added, you should use the `current` property.

### 35.37.4 Changing transitions

You have multiple transitions available by default, such as:

- `NoTransition` - switches screens instantly with no animation
- `SlideTransition` - slide the screen in/out, from any direction
- `CardTransition` - new screen slides on the previous or the old one slides off the new one depending on the mode
- `SwapTransition` - implementation of the iOS swap transition
- `FadeTransition` - shader to fade the screen in/out
- `WipeTransition` - shader to wipe the screens from right to left
- `FallOutTransition` - shader where the old screen ‘falls’ and becomes transparent, revealing the new one behind it.
- `RiseInTransition` - shader where the new screen rises from the screen centre while fading from transparent to opaque.

You can easily switch transitions by changing the `ScreenManager.transition` property:

```
sm = ScreenManager(transition=FadeTransition())
```

---

**Note:** Currently, none of Shader based Transitions use anti-aliasing. This is because they use the FBO which doesn't have any logic to handle supersampling. This is a known issue and we are working on a transparent implementation that will give the same results as if it had been rendered on screen.

To be more concrete, if you see sharp edged text during the animation, it's normal.

---

**class** `kivy.uix.screenmanager.Screen(**kw)`  
Bases: `kivy.uix.relativelayout.RelativeLayout`

Screen is an element intended to be used with a `ScreenManager`. Check module documentation for more information.

#### Events

`on_pre_enter: 0` Event fired when the screen is about to be used: the entering animation is started.

`on_enter: 0` Event fired when the screen is displayed: the entering animation is complete.

`on_pre_leave: 0` Event fired when the screen is about to be removed: the leaving animation is started.

`on_leave: 0` Event fired when the screen is removed: the leaving animation is finished.

Changed in version 1.6.0: Events `on_pre_enter`, `on_enter`, `on_pre_leave` and `on_leave` were added.

#### manager

`ScreenManager` object, set when the screen is added to a manager.

`manager` is an `ObjectProperty` and defaults to None, read-only.

#### name

Name of the screen which must be unique within a `ScreenManager`. This is the name used for `ScreenManager.current`.

`name` is a `StringProperty` and defaults to ''.

#### transition\_progress

Value that represents the completion of the current transition, if any is occurring.

If a transition is in progress, whatever the mode, the value will change from 0 to 1. If you want to know if it's an entering or leaving animation, check the `transition_state`.

`transition_progress` is a `NumericProperty` and defaults to 0.

#### transition\_state

Value that represents the state of the transition:

- 'in' if the transition is going to show your screen
- 'out' if the transition is going to hide your screen

After the transition is complete, the state will retain its last value (in or out).

`transition_state` is an `OptionProperty` and defaults to 'out'.

**class** `kivy.uix.screenmanager.ScreenManager(**kwargs)`

Bases: `kivy.uix.floatlayout.FloatLayout`

Screen manager. This is the main class that will control your `Screen` stack and memory.

By default, the manager will show only one screen at a time.

## **current**

Name of the screen currently shown, or the screen to show.

```
from kivy.uix.screenmanager import ScreenManager, Screen

sm = ScreenManager()
sm.add_widget(Screen(name='first'))
sm.add_widget(Screen(name='second'))

# By default, the first added screen will be shown. If you want to
# show another one, just set the 'current' property.
sm.current = 'second'
```

*current* is a *StringProperty* and defaults to None.

## **current\_screen**

Contains the currently displayed screen. You must not change this property manually, use *current* instead.

*current\_screen* is an *ObjectProperty* and defaults to None, read-only.

## **get\_screen(name)**

Return the screen widget associated with the name or raise a *ScreenManagerException* if not found.

## **has\_screen(name)**

Return True if a screen with the *name* has been found.

New in version 1.6.0.

## **next()**

Return the name of the next screen from the screen list.

## **previous()**

Return the name of the previous screen from the screen list.

## **screen\_names**

List of the names of all the *Screen* widgets added. The list is read only.

*screens\_names* is an *AliasProperty* and is read-only. It is updated if the screen list changes or the name of a screen changes.

## **screens**

List of all the *Screen* widgets added. You should not change this list manually. Use the *add\_widget* method instead.

*screens* is a *ListProperty* and defaults to [], read-only.

## **switch\_to(screen, \*\*options)**

Add a new screen to the ScreenManager and switch to it. The previous screen will be removed from the children. *options* are the *transition* options that will be changed before the animation happens.

If no previous screens are available, the screen will be used as the main one:

```
sm = ScreenManager()
sm.switch_to(screen1)
# later
sm.switch_to(screen2, direction='left')
# later
sm.switch_to(screen3, direction='right', duration=1.)
```

If any animation is in progress, it will be stopped and replaced by this one: you should avoid this because the animation will just look weird. Use either `switch_to()` or `current` but not both.

The `screen` name will be changed if there is any conflict with the current screen.

### **transition**

Transition object to use for animating the transition from the current screen to the next one being shown.

For example, if you want to use a `WipeTransition` between slides:

```
from kivy.uix.screenmanager import ScreenManager, Screen,
WipeTransition

sm = ScreenManager(transition=WipeTransition())
sm.add_widget(Screen(name='first'))
sm.add_widget(Screen(name='second'))

# by default, the first added screen will be shown. If you want to
# show another one, just set the 'current' property.
sm.current = 'second'
```

`transition` is an `ObjectProperty` and defaults to a `SlideTransition`.

Changed in version 1.8.0: Default transition has been changed from `SwapTransition` to `SlideTransition`.

### **class kivy.uix.screenmanager.ScreenManagerException**

Bases: `exceptions.Exception`

Exception for the `ScreenManager`.

### **class kivy.uix.screenmanager.TransitionBase**

Bases: `kivy.event.EventDispatcher`

`TransitionBase` is used to animate 2 screens within the `ScreenManager`. This class acts as a base for other implementations like the `SlideTransition` and `SwapTransition`.

#### **Events**

`on_progress`: Transition object, progression float Fired during the animation of the transition.

`on_complete`: Transition object Fired when the transition is finished.

#### **add\_screen(screen)**

(internal) Used to add a screen to the `ScreenManager`.

#### **duration**

Duration in seconds of the transition.

`duration` is a `NumericProperty` and defaults to .4 (= 400ms).

Changed in version 1.8.0: Default duration has been changed from 700ms to 400ms.

#### **is\_active**

Indicate whether the transition is currently active or not.

`is_active` is a `BooleanProperty` and defaults to False, read-only.

#### **manager**

`ScreenManager` object, set when the screen is added to a manager.

`manager` is an `ObjectProperty` and defaults to None, read-only.

**remove\_screen**(*screen*)

(internal) Used to remove a screen from the *ScreenManager*.

**screen\_in**

Property that contains the screen to show. Automatically set by the *ScreenManager*.

*screen\_in* is an *ObjectProperty* and defaults to None.

**screen\_out**

Property that contains the screen to hide. Automatically set by the *ScreenManager*.

*screen\_out* is an *ObjectProperty* and defaults to None.

**start**(*manager*)

(internal) Starts the transition. This is automatically called by the *ScreenManager*.

**stop()**

(internal) Stops the transition. This is automatically called by the *ScreenManager*.

**class kivy.uix.screenmanager.ShaderTransition**

Bases: *kivy.uix.screenmanager.TransitionBase*

Transition class that uses a Shader for animating the transition between 2 screens. By default, this class doesn't assign any fragment/vertex shader. If you want to create your own fragment shader for the transition, you need to declare the header yourself and include the "t", "tex\_in" and "tex\_out" uniform:

```
# Create your own transition. This shader implements a "fading"
# transition.
fs = """$HEADER
uniform float t;
uniform sampler2D tex_in;
uniform sampler2D tex_out;

void main(void) {
    vec4 cin = texture2D(tex_in, tex_coord0);
    vec4 cout = texture2D(tex_out, tex_coord0);
    gl_FragColor = mix(cout, cin, t);
}
"""

# And create your transition
tr = ShaderTransition(fs=fs)
sm = ScreenManager(transition=tr)
```

**clearcolor**

Sets the color of Fbo ClearColor.

New in version 1.9.0.

*clearcolor* is a *ListProperty* and defaults to [0, 0, 0, 1].

**fs**

Fragment shader to use.

*fs* is a *StringProperty* and defaults to None.

**vs**

Vertex shader to use.

*vs* is a *StringProperty* and defaults to None.

**class kivy.uix.screenmanager.SlideTransition**

Bases: *kivy.uix.screenmanager.TransitionBase*

Slide Transition, can be used to show a new screen from any direction: left, right, up or down.

#### **direction**

Direction of the transition.

*direction* is an *OptionProperty* and defaults to 'left'. Can be one of 'left', 'right', 'up' or 'down'.

**class kivy.uix.screenmanager.SwapTransition(\*\*kwargs)**  
Bases: *kivy.uix.screenmanager.TransitionBase*

Swap transition that looks like iOS transition when a new window appears on the screen.

**class kivy.uix.screenmanager.FadeTransition**  
Bases: *kivy.uix.screenmanager.ShaderTransition*

Fade transition, based on a fragment Shader.

**class kivy.uix.screenmanager.WipeTransition**  
Bases: *kivy.uix.screenmanager.ShaderTransition*

Wipe transition, based on a fragment Shader.

**class kivy.uix.screenmanager.FallOutTransition**  
Bases: *kivy.uix.screenmanager.ShaderTransition*

Transition where the new screen 'falls' from the screen centre, becoming smaller and more transparent until it disappears, and revealing the new screen behind it. Mimics the popular/standard Android transition.

New in version 1.8.0.

#### **duration**

Duration in seconds of the transition, replacing the default of *TransitionBase*.

*duration* is a *NumericProperty* and defaults to .15 (= 150ms).

**class kivy.uix.screenmanager.RiseInTransition**  
Bases: *kivy.uix.screenmanager.ShaderTransition*

Transition where the new screen rises from the screen centre, becoming larger and changing from transparent to opaque until it fills the screen. Mimics the popular/standard Android transition.

New in version 1.8.0.

#### **duration**

Duration in seconds of the transition, replacing the default of *TransitionBase*.

*duration* is a *NumericProperty* and defaults to .2 (= 200ms).

**class kivy.uix.screenmanager.NoTransition**  
Bases: *kivy.uix.screenmanager.TransitionBase*

No transition, instantly switches to the next screen with no delay or animation.

New in version 1.8.0.

**class kivy.uix.screenmanager.CardTransition**  
Bases: *kivy.uix.screenmanager.SlideTransition*

Card transition that looks similar to Android 4.x application drawer interface animation.

It supports 4 directions like SlideTransition: left, right, up and down, and two modes, pop and push. If push mode is activated, the previous screen does not move, and the new one slides in from the given direction. If the pop mode is activated, the previous screen slides out, when the new screen is already on the position of the ScreenManager.

New in version 1.10.

### **mode**

Indicates if the transition should push or pop the screen on/off the ScreenManager.

- ‘push’ means the screen slides in in the given direction
- ‘pop’ means the screen slides out in the given direction

*mode* is an *OptionProperty* and defaults to ‘push’.

### **start(manager)**

(internal) Starts the transition. This is automatically called by the *ScreenManager*.

## 35.38 ScrollView

New in version 1.0.4.

The *ScrollView* widget provides a scrollable/pannable viewport that is clipped at the scrollview’s bounding box.

### 35.38.1 Scrolling Behavior

The ScrollView accepts only one child and applies a viewport/window to it according to the *scroll\_x* and *scroll\_y* properties. Touches are analyzed to determine if the user wants to scroll or control the child in some other manner: you cannot do both at the same time. To determine if interaction is a scrolling gesture, these properties are used:

- *scroll\_distance*: the minimum distance to travel, defaults to 20 pixels.
- *scroll\_timeout*: the maximum time period, defaults to 55 milliseconds.

If a touch travels *scroll\_distance* pixels within the *scroll\_timeout* period, it is recognized as a scrolling gesture and translation (scroll/pan) will begin. If the timeout occurs, the touch down event is dispatched to the child instead (no translation).

The default value for those settings can be changed in the configuration file:

```
[widgets]
scroll_timeout = 250
scroll_distance = 20
```

New in version 1.1.1: ScrollView now animates scrolling in Y when a mousewheel is used.

### 35.38.2 Limiting to the X or Y Axis

By default, the ScrollView allows scrolling along both the X and Y axes. You can explicitly disable scrolling on an axis by setting the *do\_scroll\_x* or *do\_scroll\_y* properties to False.

### 35.38.3 Managing the Content Size and Position

The ScrollView manages the position of its children similarly to a *RelativeLayout* but does not use the *size\_hint*. You must carefully specify the *size* of your content to get the desired scroll/pan effect.

By default, the *size\_hint* is (1, 1), so the content size will fit your ScrollView exactly (you will have nothing to scroll). You must deactivate at least one of the *size\_hint* instructions (x or y) of the child to enable scrolling. Setting *size\_hint\_min* to not be None will also enable scrolling for that dimension when the *ScrollView* is smaller than the minimum size.

To scroll a `GridLayout` on its Y-axis/vertically, set the child's width to that of the `ScrollView` (`size_hint_x=1`), and set the `size_hint_y` property to `None`:

```
from kivy.uix.gridlayout import GridLayout
from kivy.uix.button import Button
from kivy.uix.scrollview import ScrollView
from kivy.core.window import Window
from kivy.app import runTouchApp

layout = GridLayout(cols=1, spacing=10, size_hint_y=None)
# Make sure the height is such that there is something to scroll.
layout.bind(minimum_height=layout.setter('height'))
for i in range(100):
    btn = Button(text=str(i), size_hint_y=None, height=40)
    layout.add_widget(btn)
root = ScrollView(size_hint=(1, None), size=(Window.width, Window.height))
root.add_widget(layout)

runTouchApp(root)
```

### 35.38.4 Overscroll Effects

New in version 1.7.0.

When scrolling would exceed the bounds of the `ScrollView`, it uses a `ScrollEffect` to handle the overscroll. These effects can perform actions like bouncing back, changing opacity, or simply preventing scrolling beyond the normal boundaries. Note that complex effects may perform many computations, which can be slow on weaker hardware.

You can change what effect is being used by setting `effect_cls` to any effect class. Current options include:

- `ScrollEffect`: Does not allow scrolling beyond the `ScrollView` boundaries.
- `DampedScrollEffect`: The current default. Allows the user to scroll beyond the normal boundaries, but has the content spring back once the touch/click is released.
- `OpacityScrollEffect`: Similar to the `DampedScrollEffect`, but also reduces opacity during overscroll.

You can also create your own scroll effect by subclassing one of these, then pass it as the `effect_cls` in the same way.

Alternatively, you can set `effect_x` and/or `effect_y` to an *instance* of the effect you want to use. This will override the default effect set in `effect_cls`.

All the effects are located in the `kivy.effects`.

```
class kivy.uix.scrollview.ScrollView(**kwargs)
Bases: kivy.uix.stencilview.StencilView
```

ScrollView class. See module documentation for more information.

#### Events

`on_scroll_start` Generic event fired when scrolling starts from touch.

`on_scroll_move` Generic event fired when scrolling move from touch.

`on_scroll_stop` Generic event fired when scrolling stops from touch.

Changed in version 1.9.0: `on_scroll_start`, `on_scroll_move` and `on_scroll_stop` events are now dispatched when scrolling to handle nested `ScrollViews`.

Changed in version 1.7.0: `auto_scroll`, `scroll_friction`, `scroll_moves`, `scroll_stoptime`' has been deprecated, use `:attr:'effect_cls` instead.

#### **bar\_color**

Color of horizontal / vertical scroll bar, in RGBA format.

New in version 1.2.0.

`bar_color` is a *ListProperty* and defaults to [.7, .7, .7, .9].

#### **bar\_inactive\_color**

Color of horizontal / vertical scroll bar (in RGBA format), when no scroll is happening.

New in version 1.9.0.

`bar_inactive_color` is a *ListProperty* and defaults to [.7, .7, .7, .2].

#### **bar\_margin**

Margin between the bottom / right side of the scrollview when drawing the horizontal / vertical scroll bar.

New in version 1.2.0.

`bar_margin` is a *NumericProperty*, default to 0

#### **bar\_pos**

Which side of the scroll view to place each of the bars on.

`bar_pos` is a *ReferenceListProperty* of (`bar_pos_x`, `bar_pos_y`)

#### **bar\_pos\_x**

Which side of the ScrollView the horizontal scroll bar should go on. Possible values are 'top' and 'bottom'.

New in version 1.8.0.

`bar_pos_x` is an *OptionProperty*, defaults to 'bottom'.

#### **bar\_pos\_y**

Which side of the ScrollView the vertical scroll bar should go on. Possible values are 'left' and 'right'.

New in version 1.8.0.

`bar_pos_y` is an *OptionProperty* and defaults to 'right'.

#### **bar\_width**

Width of the horizontal / vertical scroll bar. The width is interpreted as a height for the horizontal bar.

New in version 1.2.0.

`bar_width` is a *NumericProperty* and defaults to 2.

#### **convert\_distance\_to\_scroll(dx, dy)**

Convert a distance in pixels to a scroll distance, depending on the content size and the scrollview size.

The result will be a tuple of scroll distance that can be added to `scroll_x` and `scroll_y`

#### **do\_scroll**

Allow scroll on X or Y axis.

`do_scroll` is a *AliasProperty* of (`do_scroll_x + do_scroll_y`)

#### **do\_scroll\_x**

Allow scroll on X axis.

`do_scroll_x` is a *BooleanProperty* and defaults to True.

## **do\_scroll\_y**

Allow scroll on Y axis.

*do\_scroll\_y* is a *BooleanProperty* and defaults to True.

## **effect\_cls**

Class effect to instantiate for X and Y axis.

New in version 1.7.0.

*effect\_cls* is an *ObjectProperty* and defaults to DampedScrollEffect.

Changed in version 1.8.0: If you set a string, the *Factory* will be used to resolve the class.

## **effect\_x**

Effect to apply for the X axis. If None is set, an instance of *effect\_cls* will be created.

New in version 1.7.0.

*effect\_x* is an *ObjectProperty* and defaults to None.

## **effect\_y**

Effect to apply for the Y axis. If None is set, an instance of *effect\_cls* will be created.

New in version 1.7.0.

*effect\_y* is an *ObjectProperty* and defaults to None, read-only.

## **hbar**

Return a tuple of (position, size) of the horizontal scrolling bar.

New in version 1.2.0.

The position and size are normalized between 0-1, and represent a percentage of the current scrollview height. This property is used internally for drawing the little horizontal bar when you're scrolling.

*vbar* is a *AliasProperty*, readonly.

## **scroll\_distance**

Distance to move before scrolling the *ScrollView*, in pixels. As soon as the distance has been traveled, the *ScrollView* will start to scroll, and no touch event will go to children. It is advisable that you base this value on the dpi of your target device's screen.

*scroll\_distance* is a *NumericProperty* and defaults to 20 (pixels), according to the default value in user configuration.

## **scroll\_timeout**

Timeout allowed to trigger the *scroll\_distance*, in milliseconds. If the user has not moved *scroll\_distance* within the timeout, the scrolling will be disabled, and the touch event will go to the children.

*scroll\_timeout* is a *NumericProperty* and defaults to 55 (milliseconds) according to the default value in user configuration.

Changed in version 1.5.0: Default value changed from 250 to 55.

## **scroll\_to(widget, padding=10, animate=True)**

Scrolls the viewport to ensure that the given widget is visible, optionally with padding and animation. If animate is True (the default), then the default animation parameters will be used. Otherwise, it should be a dict containing arguments to pass to *Animation* constructor.

New in version 1.9.1.

## **scroll\_type**

Sets the type of scrolling to use for the content of the scrollview. Available options are: ['content'], ['bars'], ['bars', 'content'].

['content']	Content is scrolled by dragging or swiping the content directly.
['bars']	Content is scrolled by dragging or swiping the scroll bars.
['bars', 'content']	Content is scrolled by either of the above methods.

New in version 1.8.0.

`scroll_type` is an *OptionProperty* and defaults to ['content'].

#### **scroll\_wheel\_distance**

Distance to move when scrolling with a mouse wheel. It is advisable that you base this value on the dpi of your target device's screen.

New in version 1.8.0.

`scroll_wheel_distance` is a *NumericProperty*, defaults to 20 pixels.

#### **scroll\_x**

X scrolling value, between 0 and 1. If 0, the content's left side will touch the left side of the ScrollView. If 1, the content's right side will touch the right side.

This property is controlled by `ScrollView` only if `do_scroll_x` is True.

`scroll_x` is a *NumericProperty* and defaults to 0.

#### **scroll\_y**

Y scrolling value, between 0 and 1. If 0, the content's bottom side will touch the bottom side of the ScrollView. If 1, the content's top side will touch the top side.

This property is controlled by `ScrollView` only if `do_scroll_y` is True.

`scroll_y` is a *NumericProperty* and defaults to 1.

#### **update\_from\_scroll(\*args)**

Force the reposition of the content, according to current value of `scroll_x` and `scroll_y`.

This method is automatically called when one of the `scroll_x`, `scroll_y`, `pos` or `size` properties change, or if the size of the content changes.

#### **vbar**

Return a tuple of (position, size) of the vertical scrolling bar.

New in version 1.2.0.

The position and size are normalized between 0-1, and represent a percentage of the current scrollview height. This property is used internally for drawing the little vertical bar when you're scrolling.

`vbar` is a *AliasProperty*, readonly.

#### **viewport\_size**

(internal) Size of the internal viewport. This is the size of your only child in the scrollview.

## 35.39 SelectableView

Deprecated since version 1.10.0: The feature has been deprecated.

This module houses the `SelectableView` mixin class. This is used by the `ListView` and it's associated `Adapters` to provide selection behaviour when presenting large lists.

```
class kivy.uix.selectableview.SelectableView(*args, **kwargs)
Bases: object
```

The `SelectableView` mixin is used with list items and other classes that are to be instantiated in a list view or other classes which use a selection-enabled adapter such as `ListAdapter`. `select()` and `deselect()` can be overridden with display code to mark items as selected or not, if desired.

**deselect(\*args)**

The list item is responsible for updating the display when being unselected, if desired.

**index**

The index into the underlying data list or the data item this view represents.

**is\_selected**

A `SelectableView` instance carries this property which should be kept in sync with the equivalent property the data item represents.


**select(\*args)**

The list item is responsible for updating the display when being selected, if desired.

## 35.40 Settings

New in version 1.0.7.

This module provides a complete and extensible framework for adding a Settings interface to your application. By default, the interface uses a `SettingsWithSpinner`, which consists of a `Spinner` (top) to switch between individual settings panels (bottom). See [Different panel layouts](#) for some alternatives.



A `SettingsPanel` represents a group of configurable options. The `SettingsPanel.title` property is used by `Settings` when a panel is added: it determines the name of the sidebar button. `SettingsPanel` controls a `ConfigParser` instance.

The panel can be automatically constructed from a JSON definition file: you describe the settings you want and corresponding sections/keys in the ConfigParser instance... and you're done!

Settings are also integrated into the `App` class. Use `Settings.add_kivy_panel()` to configure the Kivy core settings in a panel.

### 35.40.1 Create a panel from JSON

To create a panel from a JSON-file, you need two things:

- a `ConfigParser` instance with default values
- a JSON file

**Warning:** The `kivy.config.ConfigParser` is required. You cannot use the default ConfigParser from Python libraries.

You must create and handle the `ConfigParser` object. SettingsPanel will read the values from the associated ConfigParser instance. Make sure you have set default values (using `setdefaults`) for all the sections/keys in your JSON file!

The JSON file contains structured information to describe the available settings. Here is an example:

```
[  
  {  
    "type": "title",  
    "title": "Windows"  
  },  
  {  
    "type": "bool",  
    "title": "Fullscreen",  
    "desc": "Set the window in windowed or fullscreen",  
    "section": "graphics",  
    "key": "fullscreen"  
  }  
]
```

Each element in the root list represents a setting that the user can configure. Only the “type” key is mandatory: an instance of the associated class will be created and used for the setting - other keys are assigned to corresponding properties of that class.

Type	Associated class
title	<code>SettingTitle</code>
bool	<code>SettingBoolean</code>
numeric	<code>SettingNumeric</code>
options	<code>SettingOptions</code>
string	<code>SettingString</code>
path	<code>SettingPath</code>

New in version 1.1.0: Added `SettingPath` type

In the JSON example above, the first element is of type “title”. It will create a new instance of `SettingTitle` and apply the rest of the key-value pairs to the properties of that class, i.e. “title”: “Windows” sets the `title` property of the panel to “Windows”.

To load the JSON example to a `Settings` instance, use the `Settings.add_json_panel()` method. It will automatically instantiate a `SettingsPanel` and add it to `Settings`:

```

from kivy.config import ConfigParser

config = ConfigParser()
config.read('myconfig.ini')

s = Settings()
s.add_json_panel('My custom panel', config, 'settings_custom.json')
s.add_json_panel('Another panel', config, 'settings_test2.json')

# then use the s as a widget...

```

### 35.40.2 Different panel layouts

A kivy *App* can automatically create and display a *Settings* instance. See the *settings\_cls* documentation for details on how to choose which settings class to display.

Several pre-built settings widgets are available. All except *SettingsWithNoMenu* include close buttons triggering the *on\_close* event.

- *Settings*: Displays settings with a sidebar at the left to switch between json panels.
- *SettingsWithSidebar*: A trivial subclass of *Settings*.
- *SettingsWithSpinner*: Displays settings with a spinner at the top, which can be used to switch between json panels. Uses *InterfaceWithSpinner* as the *interface\_cls*. This is the default behavior from Kivy 1.8.0.
- *SettingsWithTabbedPanel*: Displays json panels as individual tabs in a *TabbedPanel*. Uses *InterfaceWithTabbedPanel* as the *interface\_cls*.
- *SettingsWithNoMenu*: Displays a single json panel, with no way to switch to other panels and no close button. This makes it impossible for the user to exit unless *close\_settings()* is overridden with a different close trigger! Uses *InterfaceWithNoMenu* as the *interface\_cls*.

You can construct your own settings panels with any layout you choose by setting *Settings.interface\_cls*. This should be a widget that displays a json settings panel with some way to switch between panels. An instance will be automatically created by *Settings*.

Interface widgets may be anything you like, but *must* have a method *add\_panel* that receives newly created json settings panels for the interface to display. See the documentation for *InterfaceWithSidebar* for more information. They may optionally dispatch an *on\_close* event, for instance if a close button is clicked. This event is used by *Settings* to trigger its own *on\_close* event.

For a complete, working example, please see `kivy/examples/settings/main.py`.

**class** `kivy.uix.settings.Settings(*args, **kargs)`  
 Bases: `kivy.uix.boxlayout.BoxLayout`

Settings UI. Check module documentation for more information on how to use this class.

#### Events

*on\_config\_change*: `ConfigParser instance, section, key, value` Fired when the section's key-value pair of a `ConfigParser` changes.

*on\_close* Fired by the default panel when the Close button is pressed.

#### `add_interface()`

(Internal) creates an instance of *Settings.interface\_cls*, and sets it to *interface*. When json panels are created, they will be added to this interface which will display them to the user.

## **add\_json\_panel**(*title, config, filename=None, data=None*)

Create and add a new *SettingsPanel* using the configuration *config* with the JSON definition *filename*.

Check the [Create a panel from JSON](#) section in the documentation for more information about JSON format and the usage of this function.

## **add\_kivy\_panel()**

Add a panel for configuring Kivy. This panel acts directly on the kivy configuration. Feel free to include or exclude it in your configuration.

See [use\\_kivy\\_settings\(\)](#) for information on enabling/disabling the automatic kivy panel.

## **create\_json\_panel**(*title, config, filename=None, data=None*)

Create new *SettingsPanel*.

New in version 1.5.0.

Check the documentation of [add\\_json\\_panel\(\)](#) for more information.

## **interface**

(internal) Reference to the widget that will contain, organise and display the panel configuration panel widgets.

*interface* is an *ObjectProperty* and defaults to None.

## **interface\_cls**

The widget class that will be used to display the graphical interface for the settings panel. By default, it displays one Settings panel at a time with a sidebar to switch between them.

*interface\_cls* is an *ObjectProperty* and defaults to *InterfaceWithSidebar*.

Changed in version 1.8.0: If you set a string, the *Factory* will be used to resolve the class.

## **register\_type**(*tp, cls*)

Register a new type that can be used in the JSON definition.

## **class kivy.uix.settings.SettingsPanel(\*\*kwargs)**

Bases: *kivy.uix.gridlayout.GridLayout*

This class is used to construct panel settings, for use with a *Settings* instance or subclass.

### **config**

A *kivy.config.ConfigParser* instance. See module documentation for more information.

### **get\_value**(*section, key*)

Return the value of the section/key from the *config* ConfigParser instance. This function is used by *SettingItem* to get the value for a given section/key.

If you don't want to use a ConfigParser instance, you might want to override this function.

### **settings**

A *Settings* instance that will be used to fire the *on\_config\_change* event.

### **title**

Title of the panel. The title will be reused by the *Settings* in the sidebar.

## **class kivy.uix.settings.SettingItem(\*\*kwargs)**

Bases: *kivy.uix.floatlayout.FloatLayout*

Base class for individual settings (within a panel). This class cannot be used directly; it is used for implementing the other setting classes. It builds a row with a title/description (left) and a setting control (right).

Look at *SettingBoolean*, *SettingNumeric* and *SettingOptions* for usage examples.

## Events

*on\_release* Fired when the item is touched and then released.

### content

(internal) Reference to the widget that contains the real setting. As soon as the content object is set, any further call to add\_widget will call the content.add\_widget. This is automatically set.

*content* is an *ObjectProperty* and defaults to None.

### desc

Description of the setting, rendered on the line below the title.

*desc* is a *StringProperty* and defaults to None.

### disabled

Indicate if this setting is disabled. If True, all touches on the setting item will be discarded.

*disabled* is a *BooleanProperty* and defaults to False.

### key

Key of the token inside the *section* in the *ConfigParser* instance.

*key* is a *StringProperty* and defaults to None.

### panel

(internal) Reference to the SettingsPanel for this setting. You don't need to use it.

*panel* is an *ObjectProperty* and defaults to None.

### section

Section of the token inside the *ConfigParser* instance.

*section* is a *StringProperty* and defaults to None.

### selected\_alpha

(internal) Float value from 0 to 1, used to animate the background when the user touches the item.

*selected\_alpha* is a *NumericProperty* and defaults to 0.

### title

Title of the setting, defaults to '<No title set>'.

*title* is a *StringProperty* and defaults to '<No title set>'.

### value

Value of the token according to the *ConfigParser* instance. Any change to this value will trigger a `Settings.on_config_change()` event.

*value* is an *ObjectProperty* and defaults to None.

## class kivy.uix.settings.**SettingString**(\*\*kwargs)

Bases: *kivy.uix.settings.SettingItem*

Implementation of a string setting on top of a *SettingItem*. It is visualized with a *Label* widget that, when clicked, will open a *Popup* with a *TextInput* so the user can enter a custom value.

### popup

(internal) Used to store the current popup when it's shown.

*popup* is an *ObjectProperty* and defaults to None.

### textinput

(internal) Used to store the current textinput from the popup and to listen for changes.

*textinput* is an *ObjectProperty* and defaults to None.

```
class kivy.uix.settings.SettingPath(**kwargs)
Bases: kivy.uix.settings.SelectedItem
```

Implementation of a Path setting on top of a *SettingItem*. It is visualized with a *Label* widget that, when clicked, will open a *Popup* with a *FileChooserListView* so the user can enter a custom value.

New in version 1.1.0.

#### dirselect

Whether to allow selection of directories.

*dirselect* is a *BooleanProperty* and defaults to True.

New in version 1.10.0.

#### popup

(internal) Used to store the current popup when it is shown.

*popup* is an *ObjectProperty* and defaults to None.

#### show\_hidden

Whether to show ‘hidden’ filenames. What that means is operating-system-dependent.

*show\_hidden* is an *BooleanProperty* and defaults to False.

New in version 1.10.0.

#### textinput

(internal) Used to store the current textinput from the popup and to listen for changes.

*textinput* is an *ObjectProperty* and defaults to None.

```
class kivy.uix.settings.SettingBoolean(**kwargs)
Bases: kivy.uix.settings.SelectedItem
```

Implementation of a boolean setting on top of a *SettingItem*. It is visualized with a *Switch* widget. By default, 0 and 1 are used for values: you can change them by setting *values*.

#### values

Values used to represent the state of the setting. If you want to use “yes” and “no” in your ConfigParser instance:

```
SettingBoolean(..., values=['no', 'yes'])
```

**Warning:** You need a minimum of two values, the index 0 will be used as False, and index 1 as True

*values* is a *ListProperty* and defaults to [‘0’, ‘1’]

```
class kivy.uix.settings.SettingNumeric(**kwargs)
Bases: kivy.uix.settings.SelectedItem
```

Implementation of a numeric setting on top of a *SettingString*. It is visualized with a *Label* widget that, when clicked, will open a *Popup* with a Textinput so the user can enter a custom value.

```
class kivy.uix.settings.SettingOptions(**kwargs)
Bases: kivy.uix.settings.SelectedItem
```

Implementation of an option list on top of a *SettingItem*. It is visualized with a *Label* widget that, when clicked, will open a *Popup* with a list of options from which the user can select.

### **options**

List of all available options. This must be a list of “string” items. Otherwise, it will crash. :)

*options* is a *ListProperty* and defaults to [].

### **popup**

(internal) Used to store the current popup when it is shown.

*popup* is an *ObjectProperty* and defaults to None.

**class kivy.uix.settings.SettingsTitle(\*\*kwargs)**

Bases: *kivy.uix.label.Label*

A simple title label, used to organize the settings in sections.

**class kivy.uix.settings.SettingsWithSidebar(\*args, \*\*kwargs)**

Bases: *kivy.uix.settings.Settings*

A settings widget that displays settings panels with a sidebar to switch between them. This is the default behaviour of *Settings*, and this widget is a trivial wrapper subclass.

**class kivy.uix.settings.SettingsWithSpinner(\*args, \*\*kwargs)**

Bases: *kivy.uix.settings.Settings*

A settings widget that displays one settings panel at a time with a spinner at the top to switch between them.

**class kivy.uix.settings.SettingsWithTabbedPanel(\*args, \*\*kwargs)**

Bases: *kivy.uix.settings.Settings*

A settings widget that displays settings panels as pages in a *TabbedPanel*.

**class kivy.uix.settings.SettingsWithNoMenu(\*args, \*\*kwargs)**

Bases: *kivy.uix.settings.Settings*

A settings widget that displays a single settings panel with *no* Close button. It will not accept more than one Settings panel. It is intended for use in programs with few enough settings that a full panel switcher is not useful.

**Warning:** This Settings panel does *not* provide a Close button, and so it is impossible to leave the settings screen unless you also add other behaviour or override *display\_settings()* and *close\_settings()*.

**class kivy.uix.settings.InterfaceWithSidebar(\*args, \*\*kwargs)**

Bases: *kivy.uix.boxlayout.BoxLayout*

The default Settings interface class. It displays a sidebar menu with names of available settings panels, which may be used to switch which one is currently displayed.

See *add\_panel()* for information on the method you must implement if creating your own interface.

This class also dispatches an event ‘on\_close’, which is triggered when the sidebar menu’s close button is released. If creating your own interface widget, it should also dispatch such an event which will automatically be caught by *Settings* and used to trigger its own ‘on\_close’ event.

**add\_panel(panel, name, uid)**

This method is used by Settings to add new panels for possible display. Any replacement for ContentPanel *must* implement this method.

#### **Parameters**

*panel: SettingsPanel* It should be stored and the interface should provide a way to switch between panels.

*name*: The name of the panel as a string. It may be used to represent the panel but isn't necessarily unique.

*uid*: A unique int identifying the panel. It should be used to identify and switch between panels.

### content

(internal) A reference to the panel display widget (a *ContentPanel*).

*content* is an *ObjectProperty* and defaults to None.

### menu

(internal) A reference to the sidebar menu widget.

*menu* is an *ObjectProperty* and defaults to None.

**class** kivy.uix.settings.**ContentPanel**(\*\*kwargs)

Bases: *kivy.uix.scrollview.ScrollView*

A class for displaying settings panels. It displays a single settings panel at a time, taking up the full size and shape of the ContentPanel. It is used by *InterfaceWithSidebar* and *InterfaceWithSpinner* to display settings.

**add\_panel**(panel, name, uid)

This method is used by Settings to add new panels for possible display. Any replacement for ContentPanel must implement this method.

#### Parameters

*panel*: **SettingsPanel** It should be stored and displayed when requested.

*name*: The name of the panel as a string. It may be used to represent the panel.

*uid*: A unique int identifying the panel. It should be stored and used to identify panels when switching.

### container

(internal) A reference to the GridLayout that contains the settings panel.

*container* is an *ObjectProperty* and defaults to None.

### current\_panel

(internal) A reference to the current settings panel.

*current\_panel* is an *ObjectProperty* and defaults to None.

### current\_uid

(internal) A reference to the uid of the current settings panel.

*current\_uid* is a *NumericProperty* and defaults to 0.

### on\_current\_uid(\*args)

The uid of the currently displayed panel. Changing this will automatically change the displayed panel.

#### Parameters

*uid*: A panel uid. It should be used to retrieve and display a settings panel that has previously been added with *add\_panel()*.

### panels

(internal) Stores a dictionary mapping settings panels to their uids.

*panels* is a *DictProperty* and defaults to {}.

**class** kivy.uix.settings.**MenuSidebar**(\*\*kwargs)

Bases: *kivy.uix.floatlayout.FloatLayout*

The menu used by *InterfaceWithSidebar*. It provides a sidebar with an entry for each settings panel, which the user may click to select.

### **add\_item(name, uid)**

This method is used to add new panels to the menu.

#### **Parameters**

*name*: The name (a string) of the panel. It should be used to represent the panel in the menu.

*uid*: The name (an int) of the panel. It should be used internally to represent the panel and used to set self.selected\_uid when the panel is changed.

### **buttons\_layout**

(internal) Reference to the GridLayout that contains individual settings panel menu buttons.

*buttons\_layout* is an *ObjectProperty* and defaults to None.

### **close\_button**

(internal) Reference to the widget's Close button.

*buttons\_layout* is an *ObjectProperty* and defaults to None.

### **on\_selected\_uid(\*args)**


(internal) unselects any currently selected menu buttons, unless they represent the current panel.

### **selected\_uid**

The uid of the currently selected panel. This may be used to switch between displayed panels, e.g. by binding it to the *current\_uid* of a *ContentPanel*.

*selected\_uid* is a *NumericProperty* and defaults to 0.

## 35.41 Slider



The *Slider* widget looks like a scrollbar. It supports horizontal and vertical orientations, min/max values and a default value.

To create a slider from -100 to 100 starting from 25:

```
from kivy.uix.slider import Slider
s = Slider(min=-100, max=100, value=25)
```

To create a vertical slider:

```
from kivy.uix.slider import Slider
s = Slider(orientation='vertical')
```

To create a slider with a red line tracking the value:

```
from kivy.uix.slider import Slider
s = Slider(value_track=True, value_track_color=[1, 0, 0, 1])
```

**class kivy.uix.slider.Slider(\*\*kwargs)**  
Bases: *kivy.uix.widget.Widget*

Class for creating a Slider widget.

Check module documentation for more details.

#### **background\_disabled\_horizontal**

Background of the disabled slider used in the horizontal orientation.

New in version 1.10.0.

*background\_disabled\_horizontal* is a *StringProperty* and defaults to *atlas://data/images/defaulttheme/sliderh\_background\_disabled*.

#### **background\_disabled\_vertical**

Background of the disabled slider used in the vertical orientation.

New in version 1.10.0.

*background\_disabled\_vertical* is a *StringProperty* and defaults to *atlas://data/images/defaulttheme/sliderv\_background\_disabled*.

#### **background\_horizontal**

Background of the slider used in the horizontal orientation.

New in version 1.10.0.

*background\_horizontal* is a *StringProperty* and defaults to *atlas://data/images/defaulttheme/sliderh\_background*.

#### **background\_vertical**

Background of the slider used in the vertical orientation.

New in version 1.10.0.

*background\_vertical* is a *StringProperty* and defaults to *atlas://data/images/defaulttheme/sliderv\_background*.

#### **background\_width**

Slider's background's width (thickness), used in both horizontal and vertical orientations.

*background\_width* is a *NumericProperty* and defaults to 36sp.

#### **border\_horizontal**

Border used to draw the slider background in horizontal orientation.

*border\_horizontal* is a *ListProperty* and defaults to [0, 18, 0, 18].

#### **border\_vertical**

Border used to draw the slider background in vertical orientation.

*border\_vertical* is a *ListProperty* and defaults to [18, 0, 18, 0].

#### **cursor\_disabled\_image**

Path of the image used to draw the disabled slider cursor.

*cursor\_image* is a *StringProperty* and defaults to *atlas://data/images/defaulttheme/slider\_cursor\_disabled*.

#### **cursor\_height**

Height of the cursor image.

*cursor\_height* is a *NumericProperty* and defaults to 32sp.

**cursor\_image**

Path of the image used to draw the slider cursor.

*cursor\_image* is a *StringProperty* and defaults to *atlas://data/images/defaulttheme/slider\_cursor*.

**cursor\_size**

Size of the cursor image.

*cursor\_size* is a *ReferenceListProperty* of (*cursor\_width*, *cursor\_height*) properties.

**cursor\_width**

Width of the cursor image.

*cursor\_width* is a *NumericProperty* and defaults to 32sp.

**max**

Maximum value allowed for *value*.

*max* is a *NumericProperty* and defaults to 100.

**min**

Minimum value allowed for *value*.

*min* is a *NumericProperty* and defaults to 0.

**orientation**

Orientation of the slider.

*orientation* is an *OptionProperty* and defaults to 'horizontal'. Can take a value of 'vertical' or 'horizontal'.

**padding**

Padding of the slider. The padding is used for graphical representation and interaction. It prevents the cursor from going out of the bounds of the slider bounding box.

By default, padding is 16sp. The range of the slider is reduced from padding \*2 on the screen. It allows drawing the default cursor of 32sp width without having the cursor go out of the widget.

*padding* is a *NumericProperty* and defaults to 16sp.

**range**

Range of the slider in the format (minimum value, maximum value):

```
>>> slider = Slider(min=10, max=80)
>>> slider.range
[10, 80]
>>> slider.range = (20, 100)
>>> slider.min
20
>>> slider.max
100
```

*range* is a *ReferenceListProperty* of (*min*, *max*) properties.

**sensitivity**

Whether the touch collides with the whole body of the widget or with the slider handle part only.

New in version 1.10.1.

*sensitivity* is a *OptionProperty* and defaults to 'all'. Can take a value of 'all' or 'handle'.

## **step**

Step size of the slider.

New in version 1.4.0.

Determines the size of each interval or step the slider takes between min and max. If the value range can't be evenly divisible by step the last step will be capped by slider.max

*step* is a *NumericProperty* and defaults to 1.

## **value**

Current value used for the slider.

*value* is a *NumericProperty* and defaults to 0.

## **value\_normalized**

Normalized value inside the *range* (min/max) to 0-1 range:

```
>>> slider = Slider(value=50, min=0, max=100)
>>> slider.value
50
>>> slider.value_normalized
0.5
>>> slider.value = 0
>>> slider.value_normalized
0
>>> slider.value = 100
>>> slider.value_normalized
1
```

You can also use it for setting the real value without knowing the minimum and maximum:

```
>>> slider = Slider(min=0, max=200)
>>> slider.value_normalized = .5
>>> slider.value
100
>>> slider.value_normalized = 1.
>>> slider.value
200
```

*value\_normalized* is an *AliasProperty*.

## **value\_pos**

Position of the internal cursor, based on the normalized value.

*value\_pos* is an *AliasProperty*.

## **value\_track**

Decides if slider should draw the line indicating the space between *min* and *value* properties values.

*value\_track* is a *BooleanProperty* and defaults to False.

## **value\_track\_color**

Color of the *value\_line* in rgba format.

*value\_track\_color* is a *ListProperty* and defaults to [1, 1, 1, 1].

## **value\_track\_width**

Width of the track line.

*value\_track\_width* is a *NumericProperty* and defaults to 3dp.

## 35.42 Spinner

New in version 1.4.0.



Spinner is a widget that provides a quick way to select one value from a set. In the default state, a spinner shows its currently selected value. Touching the spinner displays a dropdown menu with all the other available values from which the user can select a new one.

Example:

```
from kivy.base import runTouchApp
from kivy.uix.spinner import Spinner

spinner = Spinner(
    # default value shown
    text='Home',
    # available values
    values=('Home', 'Work', 'Other', 'Custom'),
    # just for positioning in our example
    size_hint=(None, None),
    size=(100, 44),
    pos_hint={'center_x': .5, 'center_y': .5})

def show_selected_value(spinner, text):
    print('The spinner', spinner, 'have text', text)

spinner.bind(text=show_selected_value)

runTouchApp(spinner)
```

**class kivy.uix.spinner.Spinner(\*\*kwargs)**  
Bases: [kivy.uix.button.Button](#)

Spinner class, see module documentation for more information.

### **dropdown\_cls**

Class used to display the dropdown list when the Spinner is pressed.

*dropdown\_cls* is an [ObjectProperty](#) and defaults to [DropDown](#).

Changed in version 1.8.0: If you set a string, the [Factory](#) will be used to resolve the class.

### **is\_open**

By default, the spinner is not open. Set to True to open it.

*is\_open* is a *BooleanProperty* and defaults to False.

New in version 1.4.0.

### **option\_cls**

Class used to display the options within the dropdown list displayed under the Spinner. The *text* property of the class will be used to represent the value.

The option class requires:

- a *text* property, used to display the value.
- an *on\_release* event, used to trigger the option when pressed/touched.
- a *size\_hint\_y* of None.
- the *height* to be set.

*option\_cls* is an *ObjectProperty* and defaults to *SpinnerOption*.

Changed in version 1.8.0: If you set a string, the *Factory* will be used to resolve the class.

### **sync\_height**

Each element in a dropdown list uses a default/user-supplied height. Set to True to propagate the Spinner's height value to each dropdown list element.

New in version 1.10.0.

*sync\_height* is a *BooleanProperty* and defaults to False.

### **text\_autoupdate**

Indicates if the spinner's *text* should be automatically updated with the first value of the *values* property. Setting it to True will cause the spinner to update its *text* property every time attr:*values* are changed.

New in version 1.10.0.

*text\_autoupdate* is a *BooleanProperty* and defaults to False.

### **values**

Values that can be selected by the user. It must be a list of strings.

*values* is a *ListProperty* and defaults to [].


**class kivy.uix.spinner.SpinnerOption(\*\*kwargs)**

Bases: *kivy.uix.button.Button*

Special button used in the *Spinner* dropdown list. By default, this is just a *Button* with a *size\_hint\_y* of None and a height of *48dp*.

## 35.43 Splitter

New in version 1.5.0.



The **Splitter** is a widget that helps you re-size it's child widget/layout by letting you re-size it via dragging the boundary or double tapping the boundary. This widget is similar to the **ScrollView** in that it allows only one child widget.

Usage:

```
splitter = Splitter(sizable_from = 'right')
splitter.add_widget(layout_or_widget_instance)
splitter.min_size = 100
splitter.max_size = 250
```

To change the size of the strip/border used for resizing:

```
splitter.strip_size = '10pt'
```

To change its appearance:

```
splitter.strip_cls = your_custom_class
```

You can also change the appearance of the *strip\_cls*, which defaults to **SplitterStrip**, by overriding the *kv* rule in your app:

```
<SplitterStrip>:
    horizontal: True if self.parent and self.parent.sizable_from[0] in ('t', 'b')_
    ↪else False
    background_normal: 'path to normal horizontal image' if self.horizontal else
    ↪'path to vertical normal image'
    background_down: 'path to pressed horizontal image' if self.horizontal else
    ↪'path to vertical pressed image'
```

```
class kivy.uix.splitter.Splitter(**kwargs)
Bases: kivy.uix.boxlayout.BoxLayout
```

See module documentation.

#### Events

**on\_press:** Fired when the splitter is pressed.

**on\_release:** Fired when the splitter is released.

Changed in version 1.6.0: Added *on\_press* and *on\_release* events.

#### border

Border used for the **BorderImage** graphics instruction.

This must be a list of four values: (bottom, right, top, left). Read the BorderImage instructions for more information about how to use it.

`border` is a *ListProperty* and defaults to (4, 4, 4, 4).

#### **keep\_within\_parent**

If True, will limit the splitter to stay within its parent widget.

`keep_within_parent` is a *BooleanProperty* and defaults to False.

New in version 1.9.0.

#### **max\_size**

Specifies the maximum size beyond which the widget is not resizable.

`max_size` is a *NumericProperty* and defaults to *500pt*.

#### **min\_size**

Specifies the minimum size beyond which the widget is not resizable.

`min_size` is a *NumericProperty* and defaults to *100pt*.

#### **rescale\_with\_parent**

If True, will automatically change size to take up the same proportion of the parent widget when it is resized, while staying within `min_size` and `max_size`. As long as these attributes can be satisfied, this stops the *Splitter* from exceeding the parent size during rescaling.

`rescale_with_parent` is a *BooleanProperty* and defaults to False.

New in version 1.9.0.

#### **sizable\_from**

Specifies whether the widget is resizable. Options are: *left*, *right*, *top* or *bottom*

`sizable_from` is an *OptionProperty* and defaults to *left*.

#### **strip\_cls**

Specifies the class of the resize Strip.

`strip_cls` is an *kivy.properties.ObjectProperty* and defaults to `SplitterStrip`, which is of type *Button*.


Changed in version 1.8.0: If you set a string, the *Factory* will be used to resolve the class.

#### **strip\_size**

Specifies the size of resize strip

`strip_size` is a *NumericProperty* defaults to *10pt*

## 35.44 Stack Layout



New in version 1.0.5.

The **StackLayout** arranges children vertically or horizontally, as many as the layout can fit. The size of the individual children widgets do not have to be uniform.

For example, to display widgets that get progressively larger in width:

```
root = StackLayout()
for i in range(25):
    btn = Button(text=str(i), width=40 + i * 5, size_hint=(None, 0.15))
    root.add_widget(btn)
```



```
class kivy.uix.stacklayout.StackLayout(**kwargs)
```

Bases: *kivy.uix.layout.Layout*

Stack layout class. See module documentation for more information.

### **minimum\_height**

Minimum height needed to contain all children. It is automatically set by the layout.

New in version 1.0.8.

*minimum\_height* is a [kivy.properties.NumericProperty](#) and defaults to 0.

### **minimum\_size**

Minimum size needed to contain all children. It is automatically set by the layout.

New in version 1.0.8.

*minimum\_size* is a [ReferenceListProperty](#) of (*minimum\_width*, *minimum\_height*) properties.

### **minimum\_width**

Minimum width needed to contain all children. It is automatically set by the layout.

New in version 1.0.8.

*minimum\_width* is a [kivy.properties.NumericProperty](#) and defaults to 0.

### **orientation**

Orientation of the layout.

*orientation* is an [OptionProperty](#) and defaults to 'lr-tb'.

Valid orientations are 'lr-tb', 'tb-lr', 'rl-tb', 'tb-rl', 'lr-bt', 'bt-lr', 'rl-bt' and 'bt-rl'.

Changed in version 1.5.0: *orientation* now correctly handles all valid combinations of 'lr', 'rl', 'tb', 'bt'. Before this version only 'lr-tb' and 'tb-lr' were supported, and 'tb-lr' was misnamed and placed widgets from bottom to top and from right to left (reversed compared to what was expected).

---

**Note:** 'lr' means Left to Right. 'rl' means Right to Left. 'tb' means Top to Bottom. 'bt' means Bottom to Top.

---

### **padding**

Padding between the layout box and its children: [padding\_left, padding\_top, padding\_right, padding\_bottom].

*padding* also accepts a two argument form [padding\_horizontal, padding\_vertical] and a single argument form [padding].

Changed in version 1.7.0: Replaced the NumericProperty with a VariableListProperty.

*padding* is a [VariableListProperty](#) and defaults to [0, 0, 0, 0].

### **spacing**

Spacing between children: [spacing\_horizontal, spacing\_vertical].

*spacing* also accepts a single argument form [spacing].

*spacing* is a [VariableListProperty](#) and defaults to [0, 0].

## 35.45 Stencil View

New in version 1.0.4.

[StencilView](#) limits the drawing of child widgets to the StencilView's bounding box. Any drawing outside the bounding box will be clipped (trashed).

The StencilView uses the stencil graphics instructions under the hood. It provides an efficient way to clip the drawing area of children.

---

**Note:** As with the stencil graphics instructions, you cannot stack more than 128 stencil-aware widgets.

---

**Note:** StencilView is not a layout. Consequently, you have to manage the size and position of its children directly. You can combine (subclass both) a StencilView and a Layout in order to achieve a layout's behavior. For example:

```
class BoxStencil(BoxLayout, StencilView):  
    pass
```

---

```
class kivy.uix.stencilview.StencilView(**kwargs)
```

Bases: *kivy.uix.widget.Widget*

StencilView class. See module documentation for more information.

## 35.46 Switch

New in version 1.0.7.



The **Switch** widget is active or inactive, like a mechanical light switch. The user can swipe to the left/right to activate/deactivate it:

```
switch = Switch(active=True)
```

To attach a callback that listens to the activation state:

```
def callback(instance, value):  
    print('the switch', instance, 'is', value)  
  
switch = Switch()  
switch.bind(active=callback)
```

By default, the representation of the widget is static. The minimum size required is 83x32 pixels (defined by the background image). The image is centered within the widget.

The entire widget is active, not just the part with graphics. As long as you swipe over the widget's bounding box, it will work.

---

**Note:** If you want to control the state with a single touch instead of a swipe, use the `ToggleButton` instead.

---

```
class kivy.uix.switch.Switch(**kwargs)
    Bases: kivy.uix.widget.Widget
```

Switch class. See module documentation for more information.

**active**

Indicate whether the switch is active or inactive.

`active` is a *BooleanProperty* and defaults to False.

**active\_norm\_pos**

(internal) Contains the normalized position of the movable element inside the switch, in the 0-1 range.

`active_norm_pos` is a *NumericProperty* and defaults to 0.

**touch\_control**

(internal) Contains the touch that currently interacts with the switch.


`touch_control` is an *ObjectProperty* and defaults to None.

**touch\_distance**

(internal) Contains the distance between the initial position of the touch and the current position to determine if the swipe is from the left or right.

`touch_distance` is a *NumericProperty* and defaults to 0.

## 35.47 TabbedPanel



New in version 1.3.0.

The `TabbedPanel` widget manages different widgets in tabs, with a header area for the actual tab buttons and a content area for showing the current tab content.

The `TabbedPanel` provides one default tab.

### 35.47.1 Simple example

```
...
TabbedPanel
=====

Test of the widget TabbedPanel.
...

from kivy.app import App
from kivy.uix.tabbedpanel import TabbedPanel
from kivy.lang import Builder

Builder.load_string("""


<Test>:
    size_hint: .5, .5
    pos_hint: {'center_x': .5, 'center_y': .5}
    do_default_tab: False

    TabbedPanelItem:
        text: 'first tab'
        Label:
            text: 'First tab content area'
    TabbedPanelItem:
        text: 'tab2'
        BoxLayout:
            Label:
                text: 'Second tab content area'
            Button:
                text: 'Button that does nothing'
    TabbedPanelItem:
        text: 'tab3'
        RstDocument:
            text:
                '\n'.join(("Hello world", "-----",
                           "You are in the third tab."))
    """)

class Test(TabbedPanel):
    pass


class TabbedPanelApp(App):
    def build(self):
        return Test()

if __name__ == '__main__':
    TabbedPanelApp().run()
```

---

**Note:** A new class **TabbedPanelItem** has been introduced in 1.5.0 for convenience. So now one can simply add a **TabbedPanelItem** to a **TabbedPanel** and *content* to the **TabbedPanelItem** as in the example provided above.

---

### 35.47.2 Customize the Tabbed Panel

You can choose the position in which the tabs are displayed:

```
tab_pos = 'top_mid'
```

An individual tab is called a `TabbedPanelHeader`. It is a special button containing a `content` property. You add the `TabbedPanelHeader` first, and set its `content` property separately:

```
tp = TabbedPanel()  
th = TabbedPanelHeader(text='Tab2')  
tp.add_widget(th)
```

An individual tab, represented by a `TabbedPanelHeader`, needs its content set. This content can be any widget. It could be a layout with a deep hierarchy of widgets, or it could be an individual widget, such as a label or a button:

```
th.content = your_content_instance
```

There is one “shared” main content area active at any given time, for all the tabs. Your app is responsible for adding the content of individual tabs and for managing them, but it’s not responsible for content switching. The tabbed panel handles switching of the main content object as per user action.

There is a default tab added when the tabbed panel is instantiated. Tabs that you add individually as above, are added in addition to the default tab. Thus, depending on your needs and design, you will want to customize the default tab:

```
tp.default_tab_text = 'Something Specific To Your Use'
```

The default tab machinery requires special consideration and management. Accordingly, an `on_default_tab` event is provided for associating a callback:

```
tp.bind(default_tab = my_default_tab_callback)
```

It's important to note that by default, `default_tab_cls` is of type `TabbedPanelHeader` and thus has the same properties as other tabs.

Since 1.5.0, it is now possible to disable the creation of the `default_tab` by setting `do_default_tab` to False.

Tabs and content can be removed in several ways:

```
tp.remove_widget(widget/tabbed_panel_header)  
or  
tp.clear_widgets() # to clear all the widgets in the content area  
or  
tp.clear_tabs() # to remove the TabbedPanelHeaders
```

To access the children of the tabbed panel, use `content.children`:

```
tp.content.children
```

To access the list of tabs:

```
tp.tab_list
```

To change the appearance of the main tabbed panel content:

```
background_color = (1, 0, 0, .5) #50% translucent red  
border = [0, 0, 0, 0]  
background_image = 'path/to/background/image'
```

To change the background of a individual tab, use these two properties:

```
tab_header_instance.background_normal = 'path/to/tab_head/img'  
tab_header_instance.background_down = 'path/to/tab_head/img_pressed'
```

A TabbedPanelStrip contains the individual tab headers. To change the appearance of this tab strip, override the canvas of TabbedPanelStrip. For example, in the kv language:

```
<TabbedPanelStrip>  
    canvas:  
        Color:  
            rgba: (0, 1, 0, 1) # green  
        Rectangle:  
            size: self.size  
            pos: self.pos
```

By default the tabbed panel strip takes its background image and color from the tabbed panel's background\_image and background\_color.

**class kivy.uix.tabbedpanel.StripLayout(\*\*kwargs)**  
Bases: *kivy.uix.gridlayout.GridLayout*

The main layout that is used to house the entire tabbedpanel strip including the blank areas in case the tabs don't cover the entire width/height.

New in version 1.8.0.

#### **background\_image**

Background image to be used for the Strip layout of the TabbedPanel.

*background\_image* is a *StringProperty* and defaults to a transparent image.

#### **border**

Border property for the *background\_image*.

*border* is a *ListProperty* and defaults to [4, 4, 4]

**class kivy.uix.tabbedpanel.TabbedPanel(\*\*kwargs)**  
Bases: *kivy.uix.gridlayout.GridLayout*

The TabbedPanel class. See module documentation for more information.

#### **background\_color**

Background color, in the format (r, g, b, a).

*background\_color* is a *ListProperty* and defaults to [1, 1, 1, 1].

#### **background\_disabled\_image**

Background image of the main shared content object when disabled.

New in version 1.8.0.

*background\_disabled\_image* is a *StringProperty* and defaults to 'atlas://data/images/defaulttheme/tab'.

#### **background\_image**

Background image of the main shared content object.

*background\_image* is a *StringProperty* and defaults to 'atlas://data/images/defaulttheme/tab'.

#### **border**

Border used for *BorderImage* graphics instruction, used itself for *background\_image*. Can be changed for a custom background.

It must be a list of four values: (bottom, right, top, left). Read the BorderImage instructions for more information.

*border* is a *ListProperty* and defaults to (16, 16, 16, 16)

#### **content**

This is the object holding (current\_tab's content is added to this) the content of the current tab. To Listen to the changes in the content of the current tab, you should bind to current\_tabs *content* property.

*content* is an *ObjectProperty* and defaults to 'None'.

#### **current\_tab**

Links to the currently selected or active tab.

New in version 1.4.0.

*current\_tab* is an *AliasProperty*, read-only.

#### **default\_tab**

Holds the default tab.

---

**Note:** For convenience, the automatically provided default tab is deleted when you change default\_tab to something else. As of 1.5.0, this behaviour has been extended to every *default\_tab* for consistency and not just the automatically provided one.

---

*default\_tab* is an *AliasProperty*.

#### **default\_tab\_cls**

Specifies the class to use for the styling of the default tab.

New in version 1.4.0.

**Warning:** *default\_tab\_cls* should be subclassed from *TabbedPanelHeader*

*default\_tab\_cls* is an *ObjectProperty* and defaults to *TabbedPanelHeader*. If you set a string, the *Factory* will be used to resolve the class.

Changed in version 1.8.0: The *Factory* will resolve the class if a string is set.

#### **default\_tab\_content**

Holds the default tab content.

*default\_tab\_content* is an *AliasProperty*.

#### **default\_tab\_text**

Specifies the text displayed on the default tab header.

*default\_tab\_text* is a *StringProperty* and defaults to 'default tab'.

#### **do\_default\_tab**

Specifies whether a default\_tab head is provided.

New in version 1.5.0.

*do\_default\_tab* is a *BooleanProperty* and defaults to 'True'.

#### **strip\_border**

Border to be used on *strip\_image*.

New in version 1.8.0.

*strip\_border* is a *ListProperty* and defaults to [4, 4, 4, 4].

**strip\_image**

Background image of the tabbed strip.

New in version 1.8.0.

*strip\_image* is a *StringProperty* and defaults to a empty image.

**switch\_to(header, do\_scroll=False)**

Switch to a specific panel header.

Changed in version 1.10.0.

If used with *do\_scroll=True*, it scrolls to the header's tab too.

**tab\_height**

Specifies the height of the tab header.

*tab\_height* is a *NumericProperty* and defaults to 40.

**tab\_list**

List of all the tab headers.

*tab\_list* is an *AliasProperty* and is read-only.

**tab\_pos**

Specifies the position of the tabs relative to the content. Can be one of: *left\_top*, *left\_mid*, *left\_bottom*, *top\_left*, *top\_mid*, *top\_right*, *right\_top*, *right\_mid*, *right\_bottom*, *bottom\_left*, *bottom\_mid*, *bottom\_right*.

*tab\_pos* is an *OptionProperty* and defaults to 'top\_left'.

**tab\_width**

Specifies the width of the tab header.

*tab\_width* is a *NumericProperty* and defaults to 100.

**class kivy.uix.tabbedpanel.TabbedPanelContent(\*\*kwargs)**

Bases: *kivy.uix.floatlayout.FloatLayout*

The TabbedPanelContent class.

**class kivy.uix.tabbedpanel.TabbedPanelHeader(\*\*kwargs)**

Bases: *kivy.uix.togglebutton.ToggleButton*

A Base for implementing a Tabbed Panel Head. A button intended to be used as a Heading/Tab for a TabbedPanel widget.

You can use this TabbedPanelHeader widget to add a new tab to a TabbedPanel.

**content**

Content to be loaded when this tab header is selected.

*content* is an *ObjectProperty* and defaults to None.

**class kivy.uix.tabbedpanel.TabbedPanelItem(\*\*kwargs)**

Bases: *kivy.uix.tabbedpanel.TabbedPanelHeader*

This is a convenience class that provides a header of type TabbedPanelHeader and links it with the content automatically. Thus facilitating you to simply do the following in kv language:

```
<TabbedPanel>:  
    # ...other settings  
    TabbedPanelItem:  
        BoxLayout:  
            Label:  
                text: 'Second tab content area'  
            Button:  
                text: 'Button that does nothing'
```

New in version 1.5.0.

```
class kivy.uix.tabbedpanel.TabbedPanelStrip(**kwargs)
Bases: kivy.uix.gridlayout.GridLayout
```

A strip intended to be used as background for Heading/Tab. This does not cover the blank areas in case the tabs don't cover the entire width/height of the TabbedPanel(use *StripLayout* for that).

#### **tabbed\_panel**

Link to the panel that the tab strip is a part of.

*tabbed\_panel* is an *ObjectProperty* and defaults to None .


```
class kivy.uix.tabbedpanel.TabbedPanelException
```

Bases: exceptions.Exception

The TabbedPanelException class.

## 35.48 Text Input

New in version 1.0.4.



The *TextInput* widget provides a box for editable plain text.

Unicode, multiline, cursor navigation, selection and clipboard features are supported.

The *TextInput* uses two different coordinate systems:

- (x, y) - coordinates in pixels, mostly used for rendering on screen.
- (row, col) - cursor index in characters / lines, used for selection and cursor movement.

### 35.48.1 Usage example

To create a multiline *TextInput* (the 'enter' key adds a new line):

```
from kivy.uix.textinput import TextInput
textinput = TextInput(text='Hello world')
```

To create a singleline *TextInput*, set the *TextInput.multiline* property to False (the 'enter' key will defocus the TextInput and emit an *TextInput.on\_text\_validate()* event):

```

def on_enter(instance, value):
    print('User pressed enter in', instance)

textinput = TextInput(text='Hello world', multiline=False)
textinput.bind(on_text_validate=on_enter)

```

The textinput's text is stored in its `TextInput.text` property. To run a callback when the text changes:

```

def on_text(instance, value):
    print('The widget', instance, 'have:', value)

textinput = TextInput()
textinput.bind(text=on_text)

```

You can set the `focus` to a Textinput, meaning that the input box will be highlighted and keyboard focus will be requested:

```
textinput = TextInput(focus=True)
```

The textinput is defocused if the 'escape' key is pressed, or if another widget requests the keyboard. You can bind a callback to the focus property to get notified of focus changes:

```

def on_focus(instance, value):
    if value:
        print('User focused', instance)
    else:
        print('User defocused', instance)

textinput = TextInput()
textinput.bind(focus=on_focus)

```

See [FocusBehavior](#), from which the `TextInput` inherits, for more details.

### 35.48.2 Selection

The selection is automatically updated when the cursor position changes. You can get the currently selected text from the `TextInput.selection_text` property.

### 35.48.3 Filtering

You can control which text can be added to the `TextInput` by overwriting `TextInput.insert_text()`. Every string that is typed, pasted or inserted by any other means into the `TextInput` is passed through this function. By overwriting it you can reject or change unwanted characters.

For example, to write only in capitalized characters:

```

class CapitalInput(TextInput):

    def insert_text(self, substring, from_undo=False):
        s = substring.upper()
        return super(CapitalInput, self).insert_text(s, from_undo=from_undo)

```

Or to only allow floats (0 - 9 and a single period):

```
class FloatInput(TextInput):
```

```

pat = re.compile('^[0-9]')
def insert_text(self, substring, from_undo=False):
    pat = self.pat
    if '.' in self.text:
        s = re.sub(pat, '', substring)
    else:
        s = '.'.join([re.sub(pat, '', s) for s in substring.split('.', 1)])
    return super(FloatInput, self).insert_text(s, from_undo=from_undo)

```

### 35.48.4 Default shortcuts

Shortcuts	Description
Left	Move cursor to left
Right	Move cursor to right
Up	Move cursor to up
Down	Move cursor to down
Home	Move cursor at the beginning of the line
End	Move cursor at the end of the line
PageUp	Move cursor to 3 lines before
PageDown	Move cursor to 3 lines after
Backspace	Delete the selection or character before the cursor
Del	Delete the selection of character after the cursor
Shift + <dir>	Start a text selection. Dir can be Up, Down, Left or Right
Control + c	Copy selection
Control + x	Cut selection
Control + v	Paste clipboard content
Control + a	Select all the content
Control + z	undo
Control + r	redo

---

**Note:** To enable Emacs-style keyboard shortcuts, you can use [EmacsBehavior](#).

---

**class** kivy.uix.textinput.TextInput(\*\*kwargs)  
Bases: [kivy.uix.behaviors.focus.FocusBehavior](#), [kivy.uix.widget.Widget](#)

TextInput class. See module documentation for more information.

#### Events

**on\_text\_validate** Fired only in multiline=False mode when the user hits ‘enter’.  
This will also unfocus the textinput.

**on\_double\_tap** Fired when a double tap happens in the text input. The default behavior selects the text around the cursor position. More info at [on\\_double\\_tap\(\)](#).

**on\_triple\_tap** Fired when a triple tap happens in the text input. The default behavior selects the line around the cursor position. More info at [on\\_triple\\_tap\(\)](#).

**on\_quad\_touch** Fired when four fingers are touching the text input. The default behavior selects the whole text. More info at [on\\_quad\\_touch\(\)](#).

**Warning:** When changing a `TextInput` property that requires re-drawing, e.g. modifying the `text`, the updates occur on the next clock cycle and not instantly. This might cause any changes to the `TextInput` that occur between the modification and the next cycle to be ignored, or to use previous values. For example, after a update to the `text`, changing the cursor in the same clock frame will move it using the previous text and will likely end up in an incorrect position. The solution is to schedule any updates to occur on the next clock cycle using `schedule_once()`.

---

**Note:** Selection is cancelled when `TextInput` is focused. If you need to show selection when `TextInput` is focused, you should delay (use `Clock.schedule`) the call to the functions for selecting text (`select_all`, `select_text`).

---

Changed in version 1.10.0: `background_disabled_active` has been removed.

Changed in version 1.9.0: `TextInput` now inherits from `FocusBehavior`. `keyboard_mode`, `show_keyboard()`, `hide_keyboard()`, `focus()`, and `input_type` have been removed since they are now inherited from `FocusBehavior`.

Changed in version 1.7.0: `on_double_tap`, `on_triple_tap` and `on_quad_touch` events added.

#### **allow\_copy**

Decides whether to allow copying the text.

New in version 1.8.0.

`allow_copy` is a `BooleanProperty` and defaults to True.

#### **auto\_indent**

Automatically indent multiline text.

New in version 1.7.0.

`auto_indent` is a `BooleanProperty` and defaults to False.

#### **background\_active**

Background image of the `TextInput` when it's in focus.

New in version 1.4.1.

`background_active` is a `StringProperty` and defaults to 'atlas://data/images/defaulttheme/textinput\_active'.

#### **background\_color**

Current color of the background, in (r, g, b, a) format.

New in version 1.2.0.

`background_color` is a `ListProperty` and defaults to [1, 1, 1, 1] (white).

#### **background\_disabled\_normal**

Background image of the `TextInput` when disabled.

New in version 1.8.0.

`background_disabled_normal` is a `StringProperty` and defaults to 'atlas://data/images/defaulttheme/textinput\_disabled'.

#### **background\_normal**

Background image of the `TextInput` when it's not in focus.

New in version 1.4.1.

`background_normal` is a *StringProperty* and defaults to 'atlas://data/images/defaulttheme/textinput'.

### **border**

Border used for *BorderImage* graphics instruction. Used with `background_normal` and `background_active`. Can be used for a custom background.

New in version 1.4.1.

It must be a list of four values: (bottom, right, top, left). Read the *BorderImage* instruction for more information about how to use it.

`border` is a *ListProperty* and defaults to (4, 4, 4, 4).

### **cancel\_selection()**

Cancel current selection (if any).

### **copy(*data*=”)**

Copy the value provided in argument *data* into current clipboard. If data is not of type string it will be converted to string. If no data is provided then current selection if present is copied.

New in version 1.8.0.

### **cursor**

Tuple of (row, col) values indicating the current cursor position. You can set a new (row, col) if you want to move the cursor. The scrolling area will be automatically updated to ensure that the cursor is visible inside the viewport.

`cursor` is an *AliasProperty*.

### **cursor\_blink**

This property is used to set whether the graphic cursor should blink or not.

Changed in version 1.10.1: `cursor_blink` has been refactored to enable switching the blinking on/off and the previous behavior has been moved to a private `_cursor_blink` property. The previous default value `False` has been changed to `True`.

`cursor_blink` is a *BooleanProperty* and defaults to True.

### **cursor\_col**

Current column of the cursor.

`cursor_col` is an *AliasProperty* to `cursor[0]`, read-only.

### **cursor\_color**

Current color of the cursor, in (r, g, b, a) format.

New in version 1.9.0.

`cursor_color` is a *ListProperty* and defaults to [1, 0, 0, 1].

### **cursor\_index(*cursor=None*)**

Return the cursor index in the text/value.

### **cursor\_offset()**

Get the cursor x offset on the current line.

### **cursor\_pos**

Current position of the cursor, in (x, y).

`cursor_pos` is an *AliasProperty*, read-only.

### **cursor\_row**

Current row of the cursor.

`cursor_row` is an *AliasProperty* to `cursor[1]`, read-only.

**cursor\_width**

Current width of the cursor.

New in version 1.10.0.

*cursor\_width* is a *NumericProperty* and defaults to ‘1sp’.

**cut()**

Copy current selection to clipboard then delete it from TextInput.

New in version 1.8.0.

**delete\_selection(*from\_undo=False*)**

Delete the current text selection (if any).

**disabled\_foreground\_color**

Current color of the foreground when disabled, in (r, g, b, a) format.

New in version 1.8.0.

*disabled\_foreground\_color* is a *ListProperty* and defaults to [0, 0, 0, 5] (50% transparent black).

**do\_backspace(*from\_undo=False, mode='bkspc'*)**

Do backspace operation from the current cursor position. This action might do several things:

- removing the current selection if available.
- removing the previous char and move the cursor back.
- do nothing, if we are at the start.

**do\_cursor\_movement(*action, control=False, alt=False*)**

Move the cursor relative to its current position. Action can be one of :

- cursor\_left: move the cursor to the left
- cursor\_right: move the cursor to the right
- cursor\_up: move the cursor on the previous line
- cursor\_down: move the cursor on the next line
- cursor\_home: move the cursor at the start of the current line
- cursor\_end: move the cursor at the end of current line
- cursor\_pgup: move one “page” before
- cursor\_pgdown: move one “page” after

In addition, the behavior of certain actions can be modified:

- control + cursor\_left: move the cursor one word to the left
- control + cursor\_right: move the cursor one word to the right
- control + cursor\_up: scroll up one line
- control + cursor\_down: scroll down one line
- control + cursor\_home: go to beginning of text
- control + cursor\_end: go to end of text
- alt + cursor\_up: shift line(s) up
- alt + cursor\_down: shift line(s) down

Changed in version 1.9.1.

**do\_redo()**

Do redo operation.

New in version 1.3.0.

This action re-does any command that has been un-done by do\_undo/ctrl+z. This function is automatically called when *ctrl+r* keys are pressed.

**do\_undo()**

Do undo operation.

New in version 1.3.0.

This action un-does any edits that have been made since the last call to reset\_undo(). This function is automatically called when *ctrl+z* keys are pressed.

**font\_name**

Filename of the font to use. The path can be absolute or relative. Relative paths are resolved by the *resource\_find()* function.

**Warning:** Depending on your text provider, the font file may be ignored. However, you can mostly use this without problems.

If the font used lacks the glyphs for the particular language/symbols you are using, you will see '[]' blank box characters instead of the actual glyphs. The solution is to use a font that has the glyphs you need to display. For example, to display , use a font like freesans.ttf that has the glyph.

*font\_name* is a *StringProperty* and defaults to 'Roboto'. This value is taken from *Config*.

**font\_size**

Font size of the text in pixels.

*font\_size* is a *NumericProperty* and defaults to 15*sp*.

**foreground\_color**

Current color of the foreground, in (r, g, b, a) format.

New in version 1.2.0.

*foreground\_color* is a *ListProperty* and defaults to [0, 0, 0, 1] (black).

**get\_cursor\_from\_index(index)**

Return the (row, col) of the cursor from text index.

**get\_cursor\_from\_xy(x, y)**

Return the (row, col) of the cursor from an (x, y) position.

**handle\_image\_left**

Image used to display the Left handle on the TextInput for selection.

New in version 1.8.0.

*handle\_image\_left* is a *StringProperty* and defaults to 'atlas://data/images/defaulttheme/selector\_left'.

**handle\_image\_middle**

Image used to display the middle handle on the TextInput for cursor positioning.

New in version 1.8.0.

*handle\_image\_middle* is a *StringProperty* and defaults to 'atlas://data/images/defaulttheme/selector\_middle'.

### **handle\_image\_right**

Image used to display the Right handle on the TextInput for selection.

New in version 1.8.0.

*handle\_image\_right* is a *StringProperty* and defaults to ‘atlas://data/images/defaulttheme/selector\_right’.

### **hint\_text**

Hint text of the widget, shown if text is “”.

New in version 1.6.0.

Changed in version 1.10.0: The property is now an AliasProperty and byte values are decoded to strings. The hint text will stay visible when the widget is focused.

*hint\_text* a *AliasProperty* and defaults to “”.

### **hint\_text\_color**

Current color of the hint\_text text, in (r, g, b, a) format.

New in version 1.6.0.

*hint\_text\_color* is a *ListProperty* and defaults to [0.5, 0.5, 0.5, 1.0] (grey).

### **input\_filter**

Filters the input according to the specified mode, if not None. If None, no filtering is applied.

New in version 1.9.0.

*input\_filter* is an *ObjectProperty* and defaults to *None*. Can be one of *None*, ‘*int*’ (string), or ‘*float*’ (string), or a callable. If it is ‘*int*’, it will only accept numbers. If it is ‘*float*’ it will also accept a single period. Finally, if it is a callable it will be called with two parameters; the string to be added and a bool indicating whether the string is a result of undo (True). The callable should return a new substring that will be used instead.

### **insert\_text(substring, from\_undo=False)**

Insert new text at the current cursor position. Override this function in order to pre-process text for input validation.

### **keyboard\_suggestions**

If True provides auto suggestions on top of keyboard. This will only work if *input\_type* is set to *text*.

New in version 1.8.0.

*keyboard\_suggestions* is a *BooleanProperty* and defaults to True.

### **line\_height**

Height of a line. This property is automatically computed from the *font\_name*, *font\_size*. Changing the line\_height will have no impact.

---

**Note:** *line\_height* is the height of a single line of text. Use *minimum\_height*, which also includes padding, to get the height required to display the text properly.

---

*line\_height* is a *NumericProperty*, read-only.

### **line\_spacing**

Space taken up between the lines.

New in version 1.8.0.

*line\_spacing* is a *NumericProperty* and defaults to 0.

## **minimum\_height**

Minimum height of the content inside the TextInput.

New in version 1.8.0.

*minimum\_height* is a readonly *AliasProperty*.

**Warning:** `minimum_width` is calculated based on `width` therefore code like this will lead to an infinite loop:

```
<FancyTextInput>:  
    height: self.minimum_height  
    width: self.height
```

## **multiline**

If True, the widget will be able show multiple lines of text. If False, the “enter” keypress will defocus the textinput instead of adding a new line.

*multiline* is a *BooleanProperty* and defaults to True.

## **on\_double\_tap()**

This event is dispatched when a double tap happens inside TextInput. The default behavior is to select the word around the current cursor position. Override this to provide different behavior. Alternatively, you can bind to this event to provide additional functionality.

## **on\_quad\_touch()**

This event is dispatched when four fingers are touching inside TextInput. The default behavior is to select all text. Override this to provide different behavior. Alternatively, you can bind to this event to provide additional functionality.

## **on\_triple\_tap()**

This event is dispatched when a triple tap happens inside TextInput. The default behavior is to select the line around current cursor position. Override this to provide different behavior. Alternatively, you can bind to this event to provide additional functionality.

## **padding**

Padding of the text: [padding\_left, padding\_top, padding\_right, padding\_bottom].

padding also accepts a two argument form [padding\_horizontal, padding\_vertical] and a one argument form [padding].

Changed in version 1.7.0: Replaced AliasProperty with VariableListProperty.

*padding* is a *VariableListProperty* and defaults to [6, 6, 6, 6].

## **padding\_x**

Horizontal padding of the text: [padding\_left, padding\_right].

padding\_x also accepts a one argument form [padding\_horizontal].

*padding\_x* is a *VariableListProperty* and defaults to [0, 0]. This might be changed by the current theme.

Deprecated since version 1.7.0: Use *padding* instead.

## **padding\_y**

Vertical padding of the text: [padding\_top, padding\_bottom].

padding\_y also accepts a one argument form [padding\_vertical].

*padding\_y* is a *VariableListProperty* and defaults to [0, 0]. This might be changed by the current theme.

Deprecated since version 1.7.0: Use *padding* instead.

**password**

If True, the widget will display its characters as the character set in *password\_mask*.

New in version 1.2.0.

*password* is a *BooleanProperty* and defaults to False.

**password\_mask**

Sets the character used to mask the text when *password* is True.

New in version 1.10.0.

*password\_mask* is a *StringProperty* and defaults to '\*'.

**paste()**

Insert text from system Clipboard into the *TextInput* at current cursor position.

New in version 1.8.0.

**readonly**

If True, the user will not be able to change the content of a textinput.

New in version 1.3.0.

*readonly* is a *BooleanProperty* and defaults to False.

**replace\_crlf**

Automatically replace CRLF with LF.

New in version 1.9.1.

*replace\_crlf* is a *BooleanProperty* and defaults to True.

**reset\_undo()**

Reset undo and redo lists from memory.

New in version 1.3.0.

**scroll\_x**

X scrolling value of the viewport. The scrolling is automatically updated when the cursor is moved or text changed. If there is no user input, the scroll\_x and scroll\_y properties may be changed.

*scroll\_x* is a *NumericProperty* and defaults to 0.

**scroll\_y**

Y scrolling value of the viewport. See *scroll\_x* for more information.

*scroll\_y* is a *NumericProperty* and defaults to 0.

**select\_all()**

Select all of the text displayed in this TextInput.

New in version 1.4.0.

**select\_text(start, end)**

Select a portion of text displayed in this TextInput.

New in version 1.4.0.

**Parameters**

*start* Index of textinput.text from where to start selection

*end* Index of textinput.text till which the selection should be displayed

**selection\_color**

Current color of the selection, in (r, g, b, a) format.

**Warning:** The color should always have an “alpha” component less than 1 since the selection is drawn after the text.

`selection_color` is a *ListProperty* and defaults to [0.1843, 0.6549, 0.8313, .5].

#### **selection\_from**

If a selection is in progress or complete, this property will represent the cursor index where the selection started.

Changed in version 1.4.0: `selection_from` is an *AliasProperty* and defaults to None, readonly.

#### **selection\_text**

Current content selection.

`selection_text` is a *StringProperty* and defaults to "", readonly.

#### **selection\_to**

If a selection is in progress or complete, this property will represent the cursor index where the selection started.

Changed in version 1.4.0: `selection_to` is an *AliasProperty* and defaults to None, readonly.

#### **suggestion\_text**

Shows a suggestion text at the end of the current line. The feature is useful for text autocomplete, and it does not implement validation (accepting the suggested text on enter etc.). This can also be used by the IME to setup the current word being edited.

New in version 1.9.0.

`suggestion_text` is a *StringProperty* and defaults to "".

#### **tab\_width**

By default, each tab will be replaced by four spaces on the text input widget. You can set a lower or higher value.

`tab_width` is a *NumericProperty* and defaults to 4.

#### **text**

Text of the widget.

Creation of a simple hello world:

```
widget = TextInput(text='Hello world')
```

If you want to create the widget with an unicode string, use:

```
widget = TextInput(text=u'My unicode string')
```

`text` is an *AliasProperty*.

#### **text\_validate\_unfocus**

If True, the `TextInput.on_text_validate()` event will unfocus the widget, therefore make it stop listening to the keyboard. When disabled, the `TextInput.on_text_validate()` event can be fired multiple times as the result of TextInput keeping the focus enabled.

New in version 1.10.1.

`text_validate_unfocus` is a *BooleanProperty* and defaults to True.

**use\_bubble**

Indicates whether the cut/copy/paste bubble is used.

New in version 1.7.0.

`use_bubble` is a *BooleanProperty* and defaults to True on mobile OS's, False on desktop OS's.

**use\_handles**

Indicates whether the selection handles are displayed.

New in version 1.8.0.

`use_handles` is a *BooleanProperty* and defaults to True on mobile OS's, False on desktop OS's.

**write\_tab**

Whether the tab key should move focus to the next widget or if it should enter a tab in the `TextInput`. If *True* a tab will be written, otherwise, focus will move to the next widget.

New in version 1.9.0.

`write_tab` is a *BooleanProperty* and defaults to *True*.

## 35.49 Toggle button



The `ToggleButton` widget acts like a checkbox. When you touch or click it, the state toggles between 'normal' and 'down' (as opposed to a `Button` that is only 'down' as long as it is pressed).

Toggle buttons can also be grouped to make radio buttons - only one button in a group can be in a 'down' state. The group name can be a string or any other hashable Python object:

```
btn1 = ToggleButton(text='Male', group='sex',)
btn2 = ToggleButton(text='Female', group='sex', state='down')
btn3 = ToggleButton(text='Mixed', group='sex')
```


Only one of the buttons can be 'down'/checked at the same time.

To configure the `ToggleButton`, you can use the same properties that you can use for a `Button` class.

```
class kivy.uix.togglebutton.ToggleButton(**kwargs)
    Bases: kivy.uix.behaviors.togglebutton.ToggleButtonBehavior, kivy.uix.button.Button
```

Toggle button class, see module documentation for more information.

## 35.50 Tree View



New in version 1.0.4.

*TreeView* is a widget used to represent a tree structure. It is currently very basic, supporting a minimal feature set.

### 35.50.1 Introduction

A *TreeView* is populated with *TreeNode* instances, but you cannot use a *TreeNode* directly. You must combine it with another widget, such as *Label*, *Button* or even your own widget. The TreeView always creates a default root node, based on *TreeViewChildLabel*.

*TreeNode* is a class object containing needed properties for serving as a tree node. Extend *TreeNode* to create custom node types for use with a *TreeView*.

For constructing your own subclass, follow the pattern of *TreeViewChildLabel* which combines a *Label* and a *TreeNode*, producing a *TreeViewChildLabel* for direct use in a *TreeView* instance.

To use the *TreeViewChildLabel* class, you could create two nodes directly attached to root:

```
tv = TreeView()
tv.add_node(TreeViewChildLabel(text='My first item'))
tv.add_node(TreeViewChildLabel(text='My second item'))
```

Or, create two nodes attached to a first:

```
tv = TreeView()
n1 = tv.add_node(TreeViewChildLabel(text='Item 1'))
tv.add_node(TreeViewChildLabel(text='SubItem 1'), n1)
tv.add_node(TreeViewChildLabel(text='SubItem 2'), n1)
```

If you have a large tree structure, perhaps you would need a utility function to populate the tree view:

```
def populate_tree_view(tree_view, parent, node):
    if parent is None:
        tree_node = tree_view.add_node(TreeViewChildLabel(text=node['node_id'],
                                                          is_open=True))
    else:
        tree_node = tree_view.add_node(TreeViewChildLabel(text=node['node_id'],
                                                          is_open=True), parent)

    for child_node in node['children']:
        populate_tree_view(tree_view, tree_node, child_node)
```

```

tree = {'node_id': '1',
        'children': [{('node_id': '1.1',
                      'children': [{('node_id': '1.1.1',
                                      'children': [{('node_id': '1.1.1.1',
                                                      'children': []),
                                                    ('node_id': '1.1.1.2',
                                                      'children': []),
                                                    ('node_id': '1.1.1.3',
                                                      'children': [])}],
                      ('node_id': '1.1.2',
                        'children': []),
                      ('node_id': '1.1.3',
                        'children': [])}],
                     ('node_id': '1.2',
                       'children': [])}]

class TreeWidget(FloatLayout):
    def __init__(self, **kwargs):
        super(TreeWidget, self).__init__(**kwargs)

        tv = TreeView(root_options=dict(text='Tree One'),
                      hide_root=False,
                      indent_level=4)

        populate_tree_view(tv, None, tree)

        self.add_widget(tv)

```

The root widget in the tree view is opened by default and has text set as ‘Root’. If you want to change that, you can use the `TreeView.root_options` property. This will pass options to the root widget:

```
tv = TreeView(root_options=dict(text='My root label'))
```

### 35.50.2 Creating Your Own Node Widget

For a button node type, combine a `Button` and a `TreeViewNode` as follows:

```

class TreeViewButton(Button, TreeViewNode):
    pass

```

You must know that, for a given node, only the `size_hint_x` will be honored. The allocated width for the node will depend of the current width of the TreeView and the level of the node. For example, if a node is at level 4, the width allocated will be:

```
treeview.width - treeview.indent_start - treeview.indent_level * node.level
```

You might have some trouble with that. It is the developer’s responsibility to correctly handle adapting the graphical representation nodes, if needed.

```

class kivy.uix.treeview.TreeView(**kwargs)
Bases: kivy.uix.widget.Widget

```

TreeView class. See module documentation for more information.

#### Events

`on_node_expand: (node, )` Fired when a node is being expanded

`on_nodeCollapse: (node, )` Fired when a node is being collapsed

`add_node(node, parent=None)`

Add a new node to the tree.

## Parameters

**node:** instance of a **TreeviewNode** Node to add into the tree

**parent:** instance of a **TreeviewNode**, defaults to **None** Parent node to attach the new node. If **None**, it is added to the **root** node.

**Returns** the node *node*.

### **deselect\_node(\*args)**

Deselect any selected node.

New in version 1.10.0.

### **get\_node\_at\_pos(pos)**

Get the node at the position (x, y).

### **hide\_root**

Use this property to show/hide the initial root node. If True, the root node will appear as a closed node.

*hide\_root* is a **BooleanProperty** and defaults to False.

### **indent\_level**

Width used for the indentation of each level except the first level.

Computation of indent for each level of the tree is:

```
indent = indent_start + level * indent_level
```

*indent\_level* is a **NumericProperty** and defaults to 16.

### **indent\_start**

Indentation width of the level 0 / root node. This is mostly the initial size to accommodate a tree icon (collapsed / expanded). See *indent\_level* for more information about the computation of level indentation.

*indent\_start* is a **NumericProperty** and defaults to 24.

### **iterate\_all\_nodes(node=None)**

Generator to iterate over all nodes from *node* and down whether expanded or not. If *node* is **None**, the generator starts with **root**.

### **iterate\_open\_nodes(node=None)**

Generator to iterate over all the expended nodes starting from *node* and down. If *node* is **None**, the generator starts with **root**.

To get all the open nodes:

```
treeview = TreeView()  
# ... add nodes ...  
for node in treeview.iterate_open_nodes():  
    print(node)
```

### **load\_func**

Callback to use for asynchronous loading. If set, asynchronous loading will be automatically done. The callback must act as a Python generator function, using **yield** to send data back to the treeview.

The callback should be in the format:

```
def callback(treeview, node):  
    for name in ('Item 1', 'Item 2'):  
        yield TreeViewLabel(text=name)
```

*load\_func* is a *ObjectProperty* and defaults to None.

### **minimum\_height**

Minimum height needed to contain all children.

New in version 1.0.9.

*minimum\_height* is a *NumericProperty* and defaults to 0.

### **minimum\_size**

Minimum size needed to contain all children.

New in version 1.0.9.

*minimum\_size* is a *ReferenceListProperty* of (*minimum\_width*, *minimum\_height*) properties.

### **minimum\_width**

Minimum width needed to contain all children.

New in version 1.0.9.

*minimum\_width* is a *NumericProperty* and defaults to 0.

### **remove\_node(node)**

Removes a node from the tree.

New in version 1.0.7.

#### **Parameters**

*node*: instance of a *TreeViewNode* Node to remove from the tree. If *node* is *root*, it is not removed.

### **root**

Root node.

By default, the root node widget is a *TreeViewChild* with text 'Root'. If you want to change the default options passed to the widget creation, use the *root\_options* property:

```
treeview = TreeView(root_options={  
    'text': 'Root directory',  
    'font_size': 15})
```

*root\_options* will change the properties of the *TreeViewChild* instance. However, you cannot change the class used for root node yet.

*root* is an *AliasProperty* and defaults to None. It is read-only. However, the content of the widget can be changed.

### **root\_options**

Default root options to pass for root widget. See *root* property for more information about the usage of *root\_options*.

*root\_options* is an *ObjectProperty* and defaults to {}.

### **select\_node(node)**

Select a node in the tree.

### **selected\_node**

Node selected by *TreeView.select\_node()* or by touch.

*selected\_node* is a *AliasProperty* and defaults to None. It is read-only.

### **toggle\_node(node)**

Toggle the state of the node (open/collapsed).

```
class kivy.uix.treeview.TreeViewException
    Bases: exceptions.Exception

    Exception for errors in the TreeView.

class kivy.uix.treeview.TreeViewLabel(**kwargs)
    Bases: kivy.uix.label.Label, kivy.uix.treeview.TreeNode

    Combines a Label and a TreeNode to create a TreeViewLabel that can be used as a text node in the tree.

    See module documentation for more information.

class kivy.uix.treeview.TreeNode(**kwargs)
    Bases: object

    TreeNode class, used to build a node class for a TreeView object.

color_selected
    Background color of the node when the node is selected.

    color_selected is a ListProperty and defaults to [.1, .1, .1, 1].

even_color
    Background color of even nodes when the node is not selected.

    bg_color is a ListProperty and defaults to [.5, .5, .5, .1].
```

**is\_leaf**  
Boolean to indicate whether this node is a leaf or not. Used to adjust the graphical representation.  
*is\_leaf* is a *BooleanProperty* and defaults to True. It is automatically set to False when child is added.

**is\_loaded**  
Boolean to indicate whether this node is already loaded or not. This property is used only if the *TreeView* uses asynchronous loading.  
*is\_loaded* is a *BooleanProperty* and defaults to False.

**is\_open**  
Boolean to indicate whether this node is opened or not, in case there are child nodes. This is used to adjust the graphical representation.

**Warning:** This property is automatically set by the *TreeView*. You can read but not write it.

*is\_open* is a *BooleanProperty* and defaults to False.

**is\_selected**  
Boolean to indicate whether this node is selected or not. This is used to adjust the graphical representation.

**Warning:** This property is automatically set by the *TreeView*. You can read but not write it.

*is\_selected* is a *BooleanProperty* and defaults to False.

**level**  
Level of the node.

`level` is a *NumericProperty* and defaults to -1.

#### **no\_selection**

Boolean used to indicate whether selection of the node is allowed or not.

`no_selection` is a *BooleanProperty* and defaults to False.

#### **nodes**

List of nodes. The nodes list is different than the children list. A node in the nodes list represents a node on the tree. An item in the children list represents the widget associated with the node.

**Warning:** This property is automatically set by the *TreeView*. You can read but not write it.

`nodes` is a *ListProperty* and defaults to [].

#### **odd**

This property is set by the TreeView widget automatically and is read-only.

`odd` is a *BooleanProperty* and defaults to False.

#### **odd\_color**

Background color of odd nodes when the node is not selected.

`odd_color` is a *ListProperty* and defaults to [1., 1., 1., 0.].

#### **parent\_node**

Parent node. This attribute is needed because the `parent` can be None when the node is not displayed.

New in version 1.0.7.

`parent_node` is an *ObjectProperty* and defaults to None.

## 35.51 Video

The `Video` widget is used to display video files and streams. Depending on your Video core provider, platform, and plugins, you will be able to play different formats. For example, the pygame video provider only supports MPEG1 on Linux and OSX. GStreamer is more versatile, and can read many video containers and codecs such as MKV, OGV, AVI, MOV, FLV (if the correct gstreamer plugins are installed). Our `VideoBase` implementation is used under the hood.

Video loading is asynchronous - many properties are not available until the video is loaded (when the texture is created):

```
def on_position_change(instance, value):
    print('The position in the video is', value)
def on_duration_change(instance, value):
    print('The duration of the video is', value)
video = Video(source='PandaSneezes.avi')
video.bind(position=on_position_change,
           duration=on_duration_change)
```

**class kivy.uix.video.Video(\*\*kwargs)**

Bases: `kivy.uix.image.Image`

Video class. See module documentation for more information.

## **duration**

Duration of the video. The duration defaults to -1, and is set to a real duration when the video is loaded.

*duration* is a *NumericProperty* and defaults to -1.

## **eos**

Boolean, indicates whether the video has finished playing or not (reached the end of the stream).

*eos* is a *BooleanProperty* and defaults to False.

## **loaded**

Boolean, indicates whether the video is loaded and ready for playback or not.

New in version 1.6.0.

*loaded* is a *BooleanProperty* and defaults to False.

## **options**

Options to pass at Video core object creation.

New in version 1.0.4.

*options* is an *kivy.properties.ObjectProperty* and defaults to {}.

## **play**

Deprecated since version 1.4.0: Use *state* instead.

Boolean, indicates whether the video is playing or not. You can start/stop the video by setting this property:

```
# start playing the video at creation
video = Video(source='movie.mkv', play=True)

# create the video, and start later
video = Video(source='movie.mkv')
# and later
video.play = True
```

*play* is a *BooleanProperty* and defaults to False.

Deprecated since version 1.4.0: Use *state* instead.

## **position**

Position of the video between 0 and *duration*. The position defaults to -1 and is set to a real position when the video is loaded.

*position* is a *NumericProperty* and defaults to -1.

## **seek(*percent*, *precise*=True)**

Change the position to a percentage of duration.

### **Parameters**

***percent*: float or int** Position to seek, must be between 0-1.

***precise*: bool, defaults to True** Precise seeking is slower, but seeks to exact requested percent.

**Warning:** Calling seek() before the video is loaded has no effect.

New in version 1.2.0.

Changed in version 1.10.1: The *precise* keyword argument has been added.

## state

String, indicates whether to play, pause, or stop the video:

```
# start playing the video at creation
video = Video(source='movie.mkv', state='play')

# create the video, and start later
video = Video(source='movie.mkv')
# and later
video.state = 'play'
```

**state** is an *OptionProperty* and defaults to 'stop'.

## unload()

Unload the video. The playback will be stopped.

New in version 1.8.0.

## volume


Volume of the video, in the range 0-1. 1 means full volume, 0 means mute.

**volume** is a *NumericProperty* and defaults to 1.

## 35.52 Video player

New in version 1.2.0.

The video player widget can be used to play video and let the user control the play/pausing, volume and position. The widget cannot be customized much because of the complex assembly of numerous base widgets.




### 35.52.1 Annotations

If you want to display text at a specific time and for a certain duration, consider annotations. An annotation file has a “.jsa” extension. The player will automatically load the associated annotation file if it exists.

An annotation file is JSON-based, providing a list of label dictionary items. The key and value must match one of the `VideoPlayerAnnotation` items. For example, here is a short version of a jsa file that you can find in `examples/widgets/cityCC0.jsa`:

```
[  
    {"start": 0, "duration": 2,  
     "text": "This is an example of annotation"},  
    {"start": 2, "duration": 2,  
     "bgcolor": [0.5, 0.2, 0.4, 0.5],  
     "text": "You can change the background color"}  
]
```

For our cityCC0.mpg example, the result will be:



If you want to experiment with annotation files, test with:

```
python -m kivy.uix.videoplayer examples/widgets/cityCC0.mpg
```

### 35.52.2 Fullscreen

The video player can play the video in fullscreen, if `VideoPlayer.allowFullscreen` is activated by a double-tap on the video. By default, if the video is smaller than the Window, it will not be stretched.

You can allow stretching by passing custom options to a `VideoPlayer` instance:

```
player = VideoPlayer(source='myvideo.avi', state='play',  
                     options={'allow_stretch': True})
```

### 35.52.3 End-of-stream behavior

You can specify what happens when the video has finished playing by passing an *eos* (end of stream) directive to the underlying *VideoBase* class. *eos* can be one of ‘stop’, ‘pause’ or ‘loop’ and defaults to ‘stop’. For example, in order to loop the video:

```
player = VideoPlayer(source='myvideo.avi', state='play',
    options={'eos': 'loop'})
```

---

**Note:** The *eos* property of the *VideoBase* class is a string specifying the end-of-stream behavior. This property differs from the *eos* properties of the *VideoPlayer* and *Video* classes, whose *eos* property is simply a boolean indicating that the end of the file has been reached.

---

**class** `kivy.uix.videoplayer.VideoPlayer(**kwargs)`  
Bases: `kivy.uix.gridlayout.GridLayout`

VideoPlayer class. See module documentation for more information.

**allowFullscreen**

By default, you can double-tap on the video to make it fullscreen. Set this property to False to prevent this behavior.

*allowFullscreen* is a *BooleanProperty* defaults to True.

**annotations**

If set, it will be used for reading annotations box.

*annotations* is a *StringProperty* and defaults to “”.

**duration**

Duration of the video. The duration defaults to -1 and is set to the real duration when the video is loaded.

*duration* is a *NumericProperty* and defaults to -1.

**fullscreen**

Switch to fullscreen view. This should be used with care. When activated, the widget will remove itself from its parent, remove all children from the window and will add itself to it. When fullscreen is unset, all the previous children are restored and the widget is restored to its previous parent.

**Warning:** The re-add operation doesn’t care about the index position of it’s children within the parent.

*fullscreen* is a *BooleanProperty* and defaults to False.

**image\_loading**

Image filename used when the video is loading.

*image\_loading* is a *StringProperty* and defaults to ‘data/images/image-loading.gif’.

**imageOverlayPlay**

Image filename used to show a “play” overlay when the video has not yet started.

*imageOverlayPlay* is a *StringProperty* and defaults to ‘atlas://data/images/defaulttheme/player-play-overlay’.

**imagePause**

Image filename used for the “Pause” button.

*image\_pause* is a *StringProperty* and defaults to ‘atlas://data/images/defaulttheme/media-playback-pause’.

### **image\_play**

Image filename used for the “Play” button.

*image\_play* is a *StringProperty* and defaults to ‘atlas://data/images/defaulttheme/media-playback-start’.

### **image\_stop**

Image filename used for the “Stop” button.

*image\_stop* is a *StringProperty* and defaults to ‘atlas://data/images/defaulttheme/media-playback-stop’.

### **image\_volumehigh**

Image filename used for the volume icon when the volume is high.

*image\_volumehigh* is a *StringProperty* and defaults to ‘atlas://data/images/defaulttheme/audio-volume-high’.

### **image\_volumelow**

Image filename used for the volume icon when the volume is low.

*image\_volumelow* is a *StringProperty* and defaults to ‘atlas://data/images/defaulttheme/audio-volume-low’.

### **image\_volumemedium**

Image filename used for the volume icon when the volume is medium.

*image\_volumemedium* is a *StringProperty* and defaults to ‘atlas://data/images/defaulttheme/audio-volume-medium’.

### **image\_volumemuted**

Image filename used for the volume icon when the volume is muted.

*image\_volumemuted* is a *StringProperty* and defaults to ‘atlas://data/images/defaulttheme/audio-volume-muted’.

### **options**

Optional parameters can be passed to a *Video* instance with this property.

*options* a *DictProperty* and defaults to {}.

### **play**

Deprecated since version 1.4.0: Use *state* instead.

Boolean, indicates whether the video is playing or not. You can start/stop the video by setting this property:

```
# start playing the video at creation
video = VideoPlayer(source='movie.mkv', play=True)

# create the video, and start later
video = VideoPlayer(source='movie.mkv')
# and later
video.play = True
```

*play* is a *BooleanProperty* and defaults to False.

### **position**

Position of the video between 0 and *duration*. The position defaults to -1 and is set to the real position when the video is loaded.

*position* is a *NumericProperty* and defaults to -1.

## **seek**(percent, precise=True)

Change the position to a percentage of duration.

### Parameters

*percent*: float or int Position to seek, must be between 0-1.

*precise*: bool, defaults to True Precise seeking is slower, but seeks to exact requested percent.

**Warning:** Calling seek() before the video is loaded has no effect.

New in version 1.2.0.

Changed in version 1.10.1: The *precise* keyword argument has been added.

## **source**

Source of the video to read.

*source* is a *StringProperty* and defaults to ''.

Changed in version 1.4.0.

## **state**

String, indicates whether to play, pause, or stop the video:

```
# start playing the video at creation
video = VideoPlayer(source='movie.mkv', state='play')

# create the video, and start later
video = VideoPlayer(source='movie.mkv')
# and later
video.state = 'play'
```

*state* is an *OptionProperty* and defaults to 'stop'.

## **thumbnail**

Thumbnail of the video to show. If None, VideoPlayer will try to find the thumbnail from the *source* + '.png'.

*thumbnail* a *StringProperty* and defaults to ''.

Changed in version 1.4.0.

## **volume**

Volume of the video in the range 0-1. 1 means full volume and 0 means mute.

*volume* is a *NumericProperty* and defaults to 1.

## **class kivy.uix.videoplayer.VideoPlayerAnnotation(\*\*kwargs)**

Bases: *kivy.uix.label.Label*

Annotation class used for creating annotation labels.

Additional keys are available:

- bgcolor: [r, g, b, a] - background color of the text box
- bgsource: 'filename' - background image used for the background text box
- border: (n, e, s, w) - border used for the background image

## **duration**

Duration of the annotation.

*duration* is a *NumericProperty* and defaults to 1.

## **start**

Start time of the annotation.

*start* is a *NumericProperty* and defaults to 0.

## 35.53 VKeyboard



New in version 1.0.8.

VKeyboard is an onscreen keyboard for Kivy. Its operation is intended to be transparent to the user. Using the widget directly is NOT recommended. Read the section [Request keyboard](#) first.

### 35.53.1 Modes

This virtual keyboard has a docked and free mode:

- docked mode (*VKeyboard.docked* = True) Generally used when only one person is using the computer, like a tablet or personal computer etc.
- free mode: (*VKeyboard.docked* = False) Mostly for multitouch surfaces. This mode allows multiple virtual keyboards to be used on the screen.

If the docked mode changes, you need to manually call *VKeyboard.setup\_mode()* otherwise the change will have no impact. During that call, the VKeyboard, implemented on top of a *Scatter*, will change the behavior of the scatter and position the keyboard near the target (if target and docked mode is set).

### 35.53.2 Layouts

The virtual keyboard is able to load a custom layout. If you create a new layout and put the JSON in <kivy\_data\_dir>/keyboards/<layoutid>.json, you can load it by setting *VKeyboard.layout* to your layoutid.

The JSON must be structured like this:

```
{  
    "title": "Title of your layout",  
    "description": "Description of your layout",  
    "cols": 15,  
    "rows": 5,
```

```
    ...
}
```

Then, you need to describe the keys in each row, for either a “normal”, “shift” or a “special” (added in version 1.9.0) mode. Keys for this row data must be named `normal_<row>`, `shift_<row>` and `special_<row>`. Replace `row` with the row number. Inside each row, you will describe the key. A key is a 4 element list in the format:

```
[ <text displayed on the keyboard>, <text to put when the key is pressed>,
  <text that represents the keycode>, <size of cols> ]
```

Here are example keys:

```
# f key
["f", "f", "f", 1]
# capslock
["\u21B9", " ", "tab", 1.5]
```

Finally, complete the JSON:

```
{
    ...
    "normal_1": [
        ["`", "`", "`", 1],      ["1", "1", "1", 1],      ["2", "2", "2", 1],
        ["3", "3", "3", 1],      ["4", "4", "4", 1],      ["5", "5", "5", 1],
        ["6", "6", "6", 1],      ["7", "7", "7", 1],      ["8", "8", "8", 1],
        ["9", "9", "9", 1],      ["0", "0", "0", 1],      ["+", "+", "+", 1],
        [=, "=", "=", 1],       ["\u232b", null, "backspace", 2]
    ],
    "shift_1": [ ... ],
    "normal_2": [ ... ],
    "special_2": [ ... ],
    ...
}
```

### 35.53.3 Request Keyboard

The instantiation of the virtual keyboard is controlled by the configuration. Check `keyboard_mode` and `keyboard_layout` in the [Configuration object](#).

If you intend to create a widget that requires a keyboard, do not use the virtual keyboard directly, but prefer to use the best method available on the platform. Check the `request_keyboard()` method in the [Window](#).

If you want a specific layout when you request the keyboard, you should write something like this (from 1.8.0, numeric.json can be in the same directory as your main.py):

```
keyboard = Window.request_keyboard(
    self._keyboard_close, self)
if keyboard.widget:
    vkeyboard = self._keyboard.widget
    vkeyboard.layout = 'numeric.json'
```

```
class kivy.uix.vkeyboard.VKeyboard(**kwargs)
    Bases: kivy.uix.scatter.Scatter
```

VKeyboard is an onscreen keyboard with multitouch support. Its layout is entirely customizable and you can switch between available layouts using a button in the bottom right of the widget.

## Events

***on\_key\_down: keycode, internal, modifiers*** Fired when the keyboard received a key down event (key press).

***on\_key\_up: keycode, internal, modifiers*** Fired when the keyboard received a key up event (key release).

## **available\_layouts**

Dictionary of all available layouts. Keys are the layout ID, and the value is the JSON (translated into a Python object).

*available\_layouts* is a *DictProperty* and defaults to {}.

## **background**

Filename of the background image.

*background* is a *StringProperty* and defaults to `atlas://data/images/defaulttheme/vkeyboard_background`.

## **background\_border**

Background image border. Used for controlling the *border* property of the background.

*background\_border* is a *ListProperty* and defaults to [16, 16, 16, 16]

## **background\_color**

Background color, in the format (r, g, b, a). If a background is set, the color will be combined with the background texture.

*background\_color* is a *ListProperty* and defaults to [1, 1, 1, 1].

## **background\_disabled**

Filename of the background image when the vkeyboard is disabled.

New in version 1.8.0.

*background\_disabled* is a *StringProperty* and defaults to `atlas://data/images/defaulttheme/vkeyboard_disabled_background`.

## **callback**

Callback can be set to a function that will be called if the VKeyboard is closed by the user.

*target* is an *ObjectProperty* instance and defaults to None.

## **collide\_margin(x, y)**

Do a collision test, and return True if the (x, y) is inside the vkeyboard margin.

## **docked**

Indicate whether the VKeyboard is docked on the screen or not. If you change it, you must manually call *setup\_mode()* otherwise it will have no impact. If the VKeyboard is created by the Window, the docked mode will be automatically set by the configuration, using the *keyboard\_mode* token in [kivy] section.

*docked* is a *BooleanProperty* and defaults to False.

## **font\_size**

*font\_size*, specifies the size of the text on the virtual keyboard keys. It should be kept within limits to ensure the text does not extend beyond the bounds of the key or become too small to read.

New in version 1.10.0.

*font\_size* is a *NumericProperty* and defaults to 20.

## **key\_background\_color**

Key background color, in the format (r, g, b, a). If a key background is set, the color will be combined with the key background texture.

`key_background_color` is a *ListProperty* and defaults to [1, 1, 1, 1].

### **key\_background\_down**

Filename of the key background image for use when a touch is active on the widget.

`key_background_down` is a *StringProperty* and defaults to `atlas://data/images/defaulttheme/vkeyboard_key_down`.

### **key\_background\_normal**

Filename of the key background image for use when no touches are active on the widget.

`key_background_normal` is a *StringProperty* and defaults to `atlas://data/images/defaulttheme/vkeyboard_key_normal`.

### **key\_border**

Key image border. Used for controlling the `border` property of the key.

`key_border` is a *ListProperty* and defaults to [16, 16, 16, 16]

### **key\_disabled\_background\_normal**

Filename of the key background image for use when no touches are active on the widget and vkeyboard is disabled.

New in version 1.8.0.

`key_disabled_background_normal` is a *StringProperty* and defaults to `atlas://data/images/defaulttheme/vkeyboard_disabled_key_normal`.

### **key\_margin**

Key margin, used to create space between keys. The margin is composed of four values, in pixels:

```
key_margin = [top, right, bottom, left]
```

`key_margin` is a *ListProperty* and defaults to [2, 2, 2, 2]

### **layout**

Layout to use for the VKeyboard. By default, it will be the layout set in the configuration, according to the `keyboard_layout` in `[kivy]` section.

Changed in version 1.8.0: If layout is a .json filename, it will loaded and added to the available\_layouts.

`layout` is a *StringProperty* and defaults to None.

### **layout\_path**

Path from which layouts are read.

`layout` is a *StringProperty* and defaults to `<kivy_data_dir>/keyboards/`

### **margin\_hint**

Margin hint, used as spacing between keyboard background and keys content. The margin is composed of four values, between 0 and 1:

```
margin_hint = [top, right, bottom, left]
```

The margin hints will be multiplied by width and height, according to their position.

`margin_hint` is a *ListProperty* and defaults to [.05, .06, .05, .06]

### **refresh(`force=False`)**

(internal) Recreate the entire widget and graphics according to the selected layout.

### **setup\_mode(\*args)**

Call this method when you want to readjust the keyboard according to options: `docked` or not, with attached `target` or not:

- If `docked` is True, it will call `setup_mode_dock()`
- If `docked` is False, it will call `setup_mode_free()`

Feel free to overload these methods to create new positioning behavior.

#### `setup_mode_dock(*args)`

Setup the keyboard in docked mode.

Dock mode will reset the rotation, disable translation, rotation and scale. Scale and position will be automatically adjusted to attach the keyboard to the bottom of the screen.

**Note:** Don't call this method directly, use `setup_mode()` instead.

#### `setup_mode_free()`

Setup the keyboard in free mode.

Free mode is designed to let the user control the position and orientation of the keyboard. The only real usage is for a multiuser environment, but you might find other ways to use it. If a `target` is set, it will place the vkeyboard under the target.

**Note:** Don't call this method directly, use `setup_mode()` instead.

#### `target`

Target widget associated with the VKeyboard. If set, it will be used to send keyboard events. If the VKeyboard mode is “free”, it will also be used to set the initial position.

`target` is an `ObjectProperty` instance and defaults to None.

## 35.54 Widget class

The `Widget` class is the base class required for creating Widgets. This widget class was designed with a couple of principles in mind:

- *Event Driven*

Widget interaction is built on top of events that occur. If a property changes, the widget can respond to the change in the ‘on\_<propname>’ callback. If nothing changes, nothing will be done. That’s the main goal of the `Property` class.

- *Separation Of Concerns (the widget and its graphical representation)*

Widgets don’t have a `draw()` method. This is done on purpose: The idea is to allow you to create your own graphical representation outside the widget class. Obviously you can still use all the available properties to do that, so that your representation properly reflects the widget’s current state. Every widget has its own `Canvas` that you can use to draw. This separation allows Kivy to run your application in a very efficient manner.

- *Bounding Box / Collision*

Often you want to know if a certain point is within the bounds of your widget. An example would be a button widget where you only want to trigger an action when the button itself is actually touched. For this, you can use the `collide_point()` method, which will return True if the point you pass to it is inside the axis-aligned bounding box defined by the widget’s position and size. If a simple AABB is not sufficient, you can override the method to perform the collision checks with more complex shapes, e.g. a polygon. You can also check if a widget collides with another widget with `collide_widget()`.

We also have some default values and behaviors that you should be aware of:

- A **Widget** is not a **Layout**: it will not change the position or the size of its children. If you want control over positioning or sizing, use a **Layout**.
- The default size of a widget is (100, 100). This is only changed if the parent is a **Layout**. For example, if you add a **Label** inside a **Button**, the label will not inherit the button's size or position because the button is not a **Layout**: it's just another **Widget**.
- The default size\_hint is (1, 1). If the parent is a **Layout**, then the widget size will be the parent layout's size.
- **on\_touch\_down()**, **on\_touch\_move()**, **on\_touch\_up()** don't do any sort of collisions. If you want to know if the touch is inside your widget, use **collide\_point()**.

### 35.54.1 Using Properties

When you read the documentation, all properties are described in the format:

```
<name> is a <property class> and defaults to <default value>.
```

e.g.

**text** is a **StringProperty** and defaults to ''.

If you want to be notified when the pos attribute changes, i.e. when the widget moves, you can bind your own callback function like this:

```
def callback_pos(instance, value):
    print('The widget', instance, 'moved to', value)

wid = Widget()
wid.bind(pos=callback_pos)
```

Read more about **Properties**.

### 35.54.2 Basic drawing

Widgets support a range of drawing instructions that you can use to customize the look of your widgets and layouts. For example, to draw a background image for your widget, you can do the following:

```
def redraw(self, args):
    self.bg_rect.size = self.size
    self.bg_rect.pos = self.pos

widget = Widget()
with widget.canvas:
    widget.bg_rect = Rectangle(source="cover.jpg", pos=self.pos, size=self.size)
widget.bind(pos=redraw, size=redraw)
```

To draw a background in kv:

```
Widget:
    canvas:
        Rectangle:
            source: "cover.jpg"
            size: self.size
            pos: self.pos
```

These examples only scratch the surface. Please see the **kivy.graphics** documentation for more information.

### 35.54.3 Widget touch event bubbling

When you catch touch events between multiple widgets, you often need to be aware of the order in which these events are propagated. In Kivy, events bubble up from the first child upwards through the other children. If a widget has children, the event is passed through its children before being passed on to the widget after it.

As the `on_touch_up()` method inserts widgets at index 0 by default, this means the event goes from the most recently added widget back to the first one added. Consider the following:

```
box = BoxLayout()
box.add_widget(Label(text="a"))
box.add_widget(Label(text="b"))
box.add_widget(Label(text="c"))
```

The label with text “c” gets the event first, “b” second and “a” last. You can reverse this order by manually specifying the index:

```
box = BoxLayout()
box.add_widget(Label(text="a"), index=0)
box.add_widget(Label(text="b"), index=1)
box.add_widget(Label(text="c"), index=2)
```

Now the order would be “a”, “b” then “c”. One thing to keep in mind when using kv is that declaring a widget uses the `add_widget()` method for insertion. Hence, using

```
BoxLayout:
    MyLabel:
        text: "a"
    MyLabel:
        text: "b"
    MyLabel:
        text: "c"
```

would result in the event order “c”, “b” then “a” as “c” was actually the last added widget. It thus has index 0, “b” index 1 and “a” index 2. Effectively, the child order is the reverse of its listed order.

This ordering is the same for the `on_touch_move()` and `on_touch_up()` events.

In order to stop this event bubbling, a method can return `True`. This tells Kivy the event has been handled and the event propagation stops. For example:

```
class MyWidget(Widget):
    def on_touch_down(self, touch):
        if <some_condition>:
            # Do stuff here and kill the event
            return True
        else:
            return super(MyWidget, self).on_touch_down(touch)
```

This approach gives you good control over exactly how events are dispatched and managed. Sometimes, however, you may wish to let the event be completely propagated before taking action. You can use the `Clock` to help you here:

```
class MyWidget(Label):
    def on_touch_down(self, touch, after=False):
        if after:
            print "Fired after the event has been dispatched!"
        else:
```

```
Clock.schedule_once(lambda dt: self.on_touch_down(touch, True))
return super(MyWidget, self).on_touch_down(touch)
```

### 35.54.4 Usage of `Widget.center`, `Widget.right`, and `Widget.top`

A common mistake when using one of the computed properties such as `Widget.right` is to use it to make a widget follow its parent with a KV rule such as `right: self.parent.right`. Consider, for example:

```
FloatLayout:
    id: layout
    width: 100
    Widget:
        id: wid
        right: layout.right
```

The (mistaken) expectation is that this rule ensures that `wid.right` will always be whatever layout's `right` is - that is `wid.right` and `layout.right` will always be identical. In actual fact, this rule only says that "whenever layout's `right` changes, `wid.right` will be set to that value". The difference being that as long as `layout.right` doesn't change, `wid.right` could be anything, even a value that will make them different.

Specifically, for the KV code above, consider the following example:

```
>>> print(layout.right, wid.right)
(100, 100)
>>> wid.x = 200
>>> print(layout.right, wid.right)
(100, 300)
```

As can be seen, initially they are in sync, however, when we change `wid.x` they go out of sync because `layout.right` is not changed and the rule is not triggered.

The proper way to make the widget follow its parent's `right` is to use `Widget.pos_hint`. If instead of `right: layout.right` we did `pos_hint: {'right': 1}`, then the widget's `right` will always be set to be at the parent's `right` at each layout update.

```
class kivy.uix.widget.Widget(**kwargs)
Bases: kivy.uix.widget.WidgetBase
```

Widget class. See module documentation for more information.

#### Events

`on_touch_down`: Fired when a new touch event occurs

`on_touch_move`: Fired when an existing touch moves

`on_touch_up`: Fired when an existing touch disappears

**Warning:** Adding a `__del__` method to a class derived from `Widget` with Python prior to 3.4 will disable automatic garbage collection for instances of that class. This is because the `Widget` class creates reference cycles, thereby preventing garbage collection.

Changed in version 1.0.9: Everything related to event properties has been moved to the `EventDispatcher`. Event properties can now be used when constructing a simple class without subclassing `Widget`.

Changed in version 1.5.0: The constructor now accepts `on_*` arguments to automatically bind callbacks to properties or events, as in the Kv language.

## `add_widget(widget, index=0, canvas=None)`

Add a new widget as a child of this widget.

### Parameters

`widget: Widget` Widget to add to our list of children.

`index: int, defaults to 0` Index to insert the widget in the list. Notice that the default of 0 means the widget is inserted at the beginning of the list and will thus be drawn on top of other sibling widgets. For a full discussion of the index and widget hierarchy, please see the [Widgets Programming Guide](#).

New in version 1.0.5.

`canvas: str, defaults to None` Canvas to add widget's canvas to. Can be 'before', 'after' or None for the default canvas.

New in version 1.9.0.

```
>>> from kivy.uix.button import Button
>>> from kivy.uix.slider import Slider
>>> root = Widget()
>>> root.add_widget(Button())
>>> slider = Slider()
>>> root.add_widget(slider)
```

## `canvas = None`

Canvas of the widget.

The canvas is a graphics object that contains all the drawing instructions for the graphical representation of the widget.

There are no general properties for the Widget class, such as background color, to keep the design simple and lean. Some derived classes, such as Button, do add such convenience properties but generally the developer is responsible for implementing the graphics representation for a custom widget from the ground up. See the derived widget classes for patterns to follow and extend.

See [Canvas](#) for more information about the usage.

## `center`

Center position of the widget.

`center` is a [ReferenceListProperty](#) of (`center_x`, `center_y`) properties.

## `center_x`

X center position of the widget.

`center_x` is an [AliasProperty](#) of (`x + width / 2.`).

## `center_y`

Y center position of the widget.

`center_y` is an [AliasProperty](#) of (`y + height / 2.`).

## `children`

List of children of this widget.

`children` is a [ListProperty](#) and defaults to an empty list.

Use `add_widget()` and `remove_widget()` for manipulating the children list. Don't manipulate the children list directly unless you know what you are doing.

### **clear\_widgets**(*children=None*)

Remove all (or the specified) *children* of this widget. If the ‘children’ argument is specified, it should be a list (or filtered list) of children of the current widget.

Changed in version 1.8.0: The *children* argument can be used to specify the children you want to remove.

### **cls**

Class of the widget, used for styling.

### **collide\_point**(*x, y*)

Check if a point (*x, y*) is inside the widget’s axis aligned bounding box.

#### Parameters

*x*: numeric x position of the point (in parent coordinates)

*y*: numeric y position of the point (in parent coordinates)

**Returns** A bool. True if the point is inside the bounding box, False otherwise.

```
>>> Widget(pos=(10, 10), size=(50, 50)).collide_point(40, 40)
True
```

### **collide\_widget**(*wid*)

Check if another widget collides with this widget. This function performs an axis-aligned bounding box intersection test by default.

#### Parameters

*wid*: **Widget** class Widget to test collision with.

**Returns** bool. True if the other widget collides with this widget, False otherwise.

```
>>> wid = Widget(size=(50, 50))
>>> wid2 = Widget(size=(50, 50), pos=(25, 25))
>>> wid.collide_widget(wid2)
True
>>> wid2.pos = (55, 55)
>>> wid.collide_widget(wid2)
False
```

### **disabled**

Indicates whether this widget can interact with input or not.

---

#### Note:

1. Child Widgets, when added to a disabled widget, will be disabled automatically.
  2. Disabling/enabling a parent disables/enables all of its children.
- 

New in version 1.8.0.

*disabled* is a **BooleanProperty** and defaults to False.

Changed in version 1.10.1.

*disabled* is now an **AliasProperty** which allows to remember the previous disabled state when a parent’s disabled state is changed.

### **export\_to\_png**(*filename, \*args*)

Saves an image of the widget and its children in png format at the specified filename. Works by removing the widget canvas from its parent, rendering to an **Fbo**, and calling **save()**.

---

**Note:** The image includes only this widget and its children. If you want to include widgets elsewhere in the tree, you must call `export_to_png()` from their common parent, or use `screenshot()` to capture the whole window.

---

**Note:** The image will be saved in png format, you should include the extension in your filename.

---

New in version 1.9.0.

### **get\_parent\_window()**

Return the parent window.

**Returns** Instance of the parent window. Can be a `WindowBase` or `Widget`.

### **get\_root\_window()**

Return the root window.

**Returns** Instance of the root window. Can be a `WindowBase` or `Widget`.

### **get\_window\_matrix(*x=0, y=0*)**

Calculate the transformation matrix to convert between window and widget coordinates.

#### **Parameters**

***x: float, defaults to 0*** Translates the matrix on the x axis.

***y: float, defaults to 0*** Translates the matrix on the y axis.

### **height**

Height of the widget.

***height*** is a `NumericProperty` and defaults to 100.

**Warning:** Keep in mind that the `height` property is subject to layout logic and that this has not yet happened at the time of the widget's `__init__` method.

### **id**

Unique identifier of the widget in the tree.

***id*** is a `StringProperty` and defaults to None.

**Warning:** If the `id` is already used in the tree, an exception will be raised.

### **ids**

This is a dictionary of ids defined in your kv language. This will only be populated if you use ids in your kv language code.

New in version 1.7.0.

***ids*** is a `DictProperty` and defaults to an empty dict {}.

The `ids` are populated for each root level widget definition. For example:

```
# in kv
<MyWidget@Widget>:
    id: my_widget
    Label:
```

```

        id: label_widget
    Widget:
        id: inner_widget
    Label:
        id: inner_label
    TextInput:
        id: text_input
    OtherWidget:
        id: other_widget

<OtherWidget@Widget>
    id: other_widget
    Label:
        id: other_label
    TextInput:
        id: other_textinput

```

Then, in python:

```

>>> widget = MyWidget()
>>> print(widget.ids)
{'other_widget': <weakproxy at 041CFED0 to OtherWidget at 041BEC38>,
 'inner_widget': <weakproxy at 04137EA0 to Widget at 04138228>,
 'inner_label': <weakproxy at 04143540 to Label at 04138260>,
 'label_widget': <weakproxy at 04137B70 to Label at 040F97A0>,
 'text_input': <weakproxy at 041BB5D0 to TextInput at 041BEC00>}
>>> print(widget.ids['other_widget'].ids)
{'other_textinput': <weakproxy at 041DBB40 to TextInput at 041BEF48>,
 'other_label': <weakproxy at 041DB570 to Label at 041BEEA0>}
>>> print(widget.ids['label_widget'].ids)
{}
```

### **on\_touch\_down(*touch*)**

Receive a touch down event.

#### **Parameters**

*touch*: **MotionEvent class** Touch received. The touch is in parent coordinates.  
See [relative layout](#) for a discussion on coordinate systems.

**Returns** bool If True, the dispatching of the touch event will stop. If False, the event will continue to be dispatched to the rest of the widget tree.

### **on\_touch\_move(*touch*)**

Receive a touch move event. The touch is in parent coordinates.

See [on\\_touch\\_down\(\)](#) for more information.

### **on\_touch\_up(*touch*)**

Receive a touch up event. The touch is in parent coordinates.

See [on\\_touch\\_down\(\)](#) for more information.

### **opacity**

Opacity of the widget and all its children.

New in version 1.4.1.

The opacity attribute controls the opacity of the widget and its children. Be careful, it's a cumulative attribute: the value is multiplied by the current global opacity and the result is applied to the current context color.

For example, if the parent has an opacity of 0.5 and a child has an opacity of 0.2, the real opacity of the child will be  $0.5 * 0.2 = 0.1$ .

Then, the opacity is applied by the shader as:

```
frag_color = color * vec4(1.0, 1.0, 1.0, opacity);
```

*opacity* is a *NumericProperty* and defaults to 1.0.

#### **parent**

Parent of this widget. The parent of a widget is set when the widget is added to another widget and unset when the widget is removed from its parent.

*parent* is an *ObjectProperty* and defaults to None.

#### **pos**

Position of the widget.

*pos* is a *ReferenceListProperty* of (*x*, *y*) properties.

#### **pos\_hint**

Position hint. This property allows you to set the position of the widget inside its parent layout, in percent (similar to size\_hint).

For example, if you want to set the top of the widget to be at 90% height of its parent layout, you can write:

```
widget = Widget(pos_hint={'top': 0.9})
```

The keys 'x', 'right' and 'center\_x' will use the parent width. The keys 'y', 'top' and 'center\_y' will use the parent height.

See *Float Layout* for further reference.

---

**Note:** *pos\_hint* is not used by all layouts. Check the documentation of the layout in question to see if it supports pos\_hint.

---

*pos\_hint* is an *ObjectProperty* containing a dict.

#### **proxy\_ref**

Return a proxy reference to the widget, i.e. without creating a reference to the widget. See *weakref.proxy* for more information.

New in version 1.7.2.

#### **remove\_widget(widget)**

Remove a widget from the children of this widget.

##### **Parameters**

*widget: Widget* Widget to remove from our children list.

```
>>> from kivy.uix.button import Button
>>> root = Widget()
>>> button = Button()
>>> root.add_widget(button)
>>> root.remove_widget(button)
```

#### **right**

Right position of the widget.

*right* is an *AliasProperty* of (*x* + *width*).

## **size**

Size of the widget.

`size` is a *ReferenceListProperty* of (`width`, `height`) properties.

## **size\_hint**

Size hint.

`size_hint` is a *ReferenceListProperty* of (`size_hint_x`, `size_hint_y`) properties.

See `size_hint_x` for more information.

## **size\_hint\_max**

Maximum size when using `size_hint`.

`size_hint_max` is a *ReferenceListProperty* of (`size_hint_max_x`, `size_hint_max_y`) properties.

New in version 1.10.0.

## **size\_hint\_max\_x**

When not None, the x-direction maximum size (in pixels, like `width`) when `size_hint_x` is also not None.

Similar to `size_hint_min_x`, except that it sets the maximum width.

`size_hint_max_x` is a *NumericProperty* and defaults to None.

New in version 1.10.0.

## **size\_hint\_max\_y**

When not None, the y-direction maximum size (in pixels, like `height`) when `size_hint_y` is also not None.

Similar to `size_hint_min_y`, except that it sets the maximum height.

`size_hint_max_y` is a *NumericProperty* and defaults to None.

New in version 1.10.0.

## **size\_hint\_min**

Minimum size when using `size_hint`.

`size_hint_min` is a *ReferenceListProperty* of (`size_hint_min_x`, `size_hint_min_y`) properties.

New in version 1.10.0.

## **size\_hint\_min\_x**

When not None, the x-direction minimum size (in pixels, like `width`) when `size_hint_x` is also not None.

When `size_hint_x` is not None, it is the minimum width that the widget will be set due to the `size_hint_x`. I.e. when a smaller size would be set, `size_hint_min_x` is the value used instead for the widget width. When None, or when `size_hint_x` is None, `size_hint_min_x` doesn't do anything.

Only the `Layout` and `Window` classes make use of the hint.

`size_hint_min_x` is a *NumericProperty* and defaults to None.

New in version 1.10.0.

## **size\_hint\_min\_y**

When not None, the y-direction minimum size (in pixels, like `height`) when `size_hint_y` is also not None.

When `size_hint_y` is not None, it is the minimum height that the widget will be set due to the `size_hint_y`. I.e. when a smaller size would be set, `size_hint_min_y` is the value used instead for the widget height. When None, or when `size_hint_y` is None, `size_hint_min_y` doesn't do anything.

Only the `Layout` and `Window` classes make use of the hint.

`size_hint_min_y` is a `NumericProperty` and defaults to None.

New in version 1.10.0.

### `size_hint_x`

x size hint. Represents how much space the widget should use in the direction of the x axis relative to its parent's width. Only the `Layout` and `Window` classes make use of the hint.

The size\_hint is used by layouts for two purposes:

- When the layout considers widgets on their own rather than in relation to its other children, the `size_hint_x` is a direct proportion of the parent width, normally between 0.0 and 1.0. For instance, a widget with `size_hint_x=0.5` in a vertical `BoxLayout` will take up half the `BoxLayout`'s width, or a widget in a `FloatLayout` with `size_hint_x=0.2` will take up 20% of the `FloatLayout` width. If the `size_hint` is greater than 1, the widget will be wider than the parent.
- When multiple widgets can share a row of a layout, such as in a horizontal `BoxLayout`, their widths will be their `size_hint_x` as a fraction of the sum of widget `size_hints`. For instance, if the `size_hint_xs` are (0.5, 1.0, 0.5), the first widget will have a width of 25% of the parent width.

`size_hint_x` is a `NumericProperty` and defaults to 1.

### `size_hint_y`

y size hint.

`size_hint_y` is a `NumericProperty` and defaults to 1.

See `size_hint_x` for more information, but with widths and heights swapped.

### `to_local(x, y, relative=False)`

Transform parent coordinates to local coordinates. See `relativelayout` for details on the coordinate systems.

#### Parameters

`relative: bool, defaults to False` Change to True if you want to translate coordinates to relative widget coordinates.

### `to_parent(x, y, relative=False)`

Transform local coordinates to parent coordinates. See `relativelayout` for details on the coordinate systems.

#### Parameters

`relative: bool, defaults to False` Change to True if you want to translate relative positions from a widget to its parent coordinates.

### `to_widget(x, y, relative=False)`

Convert the given coordinate from window to local widget coordinates. See `relativelayout` for details on the coordinate systems.

### `to_window(x, y, initial=True, relative=False)`

Transform local coordinates to window coordinates. See `relativelayout` for details on the coordinate systems.

### `top`

Top position of the widget.

`top` is an *AliasProperty* of (`y + height`).

### `walk(restrict=False, loopback=False)`

Iterator that walks the widget tree starting with this widget and goes forward returning widgets in the order in which layouts display them.

#### Parameters

**`restrict: bool, defaults to False`** If True, it will only iterate through the widget and its children (or children of its children etc.). Defaults to False.

**`loopback: bool, defaults to False`** If True, when the last widget in the tree is reached, it'll loop back to the uppermost root and start walking until we hit this widget again. Naturally, it can only loop back when `restrict` is False. Defaults to False.

**Returns** A generator that walks the tree, returning widgets in the forward layout order.

For example, given a tree with the following structure:

```
GridLayout:  
    Button  
    BoxLayout:  
        id: box  
        Widget  
        Button  
    Widget
```

walking this tree:

```
>>> # Call walk on box with loopback True, and restrict False  
>>> [type(widget) for widget in box.walk(loopback=True)]  
[<class 'BoxLayout'>, <class 'Widget'>, <class 'Button'>,  
 <class 'Widget'>, <class 'GridLayout'>, <class 'Button'>]  
>>> # Now with loopback False, and restrict False  
>>> [type(widget) for widget in box.walk()]  
[<class 'BoxLayout'>, <class 'Widget'>, <class 'Button'>,  
 <class 'Widget'>]  
>>> # Now with restrict True  
>>> [type(widget) for widget in box.walk(restrict=True)]  
[<class 'BoxLayout'>, <class 'Widget'>, <class 'Button'>]
```

New in version 1.9.0.

### `walk_reverse(loopback=False)`

Iterator that walks the widget tree backwards starting with the widget before this, and going backwards returning widgets in the reverse order in which layouts display them.

This walks in the opposite direction of `walk()`, so a list of the tree generated with `walk()` will be in reverse order compared to the list generated with this, provided `loopback` is True.

#### Parameters

**`loopback: bool, defaults to False`** If True, when the uppermost root in the tree is reached, it'll loop back to the last widget and start walking back until after we hit widget again. Defaults to False.

**Returns** A generator that walks the tree, returning widgets in the reverse layout order.

For example, given a tree with the following structure:

```
GridLayout:  
    Button  
BoxLayout:  
    id: box  
    Widget  
    Button  
Widget
```

walking this tree:

```
>>> # Call walk on box with loopback True  
>>> [type(widget) for widget in box.walk_reverse(loopback=True)]  
[<class 'Button'>, <class 'GridLayout'>, <class 'Widget'>,  
 <class 'Button'>, <class 'Widget'>, <class 'BoxLayout'>]  
>>> # Now with loopback False  
>>> [type(widget) for widget in box.walk_reverse()]  
[<class 'Button'>, <class 'GridLayout'>]  
>>> forward = [w for w in box.walk(loopback=True)]  
>>> backward = [w for w in box.walk_reverse(loopback=True)]  
>>> forward == backward[::-1]  
True
```

New in version 1.9.0.

### width

Width of the widget.

*width* is a *NumericProperty* and defaults to 100.

**Warning:** Keep in mind that the *width* property is subject to layout logic and that this has not yet happened at the time of the widget's *\_\_init\_\_* method.

### x

X position of the widget.

*x* is a *NumericProperty* and defaults to 0.

### y

Y position of the widget.

*y* is a *NumericProperty* and defaults to 0.

### class kivy.uix.widget.WidgetException

Bases: exceptions.Exception

Fired when the widget gets an exception.

## Part V

# APPENDIX

The appendix contains licensing information and an enumeration of all the different modules, classes, functions and variables available in Kivy.



## License

---

Kivy is released and distributed under the terms of the MIT license starting version 1.7.2. Older versions are still under the LGPLv3.

You should have received a copy of the MIT license alongside your Kivy distribution. See the LICENSE file in the Kivy root folder. An online version of the license can be found at:

<https://github.com/kivy/kivy/blob/master/LICENSE>

In a nutshell, the license allows you to use Kivy in your own projects regardless of whether they are open source, closed source, commercial or free. Even if the license doesn't require it, we would really appreciate when you make changes to the Kivy sourcecode **itself**, share those changes with us!

For a list of authors, please see the file AUTHORS that accompanies the Kivy source code distribution (next to LICENSE).

Kivy – Copyright 2010-2017, The Kivy Authors.



---

# Python Module Index

---

k  
kivy, 179  
kivy.adapters, 273  
kivy.adapters.adapter, 275  
kivy.adapters.args\_converters, 277  
kivy.adapters.dictadapter, 276  
kivy.adapters.listadapter, 277  
kivy.adapters.models, 280  
kivy.adapters.simplelistadapter, 281  
kivy.animation, 180  
kivy.app, 191  
kivy.atlas, 204  
kivy.base, 237  
kivy.cache, 207  
kivy.clock, 209  
kivy.compat, 218  
kivy.config, 218  
kivy.context, 224  
kivy.core, 283  
kivy.core.audio, 283  
kivy.core.camera, 285  
kivy.core.clipboard, 286  
kivy.core.gl, 286  
kivy.core.image, 286  
kivy.core.spelling, 290  
kivy.core.text, 291  
kivy.core.text.markup, 297  
kivy.core.text.text\_layout, 294  
kivy.core.video, 298  
kivy.core.window, 299  
kivy.deps, 315  
kivy.effects, 317  
kivy.effects.dampedscroll, 317  
kivy.effects.kinetic, 318  
kivy.effects.opacityscroll, 319  
kivy.effects.scroll, 320  
kivy.event, 224  
kivy.factory, 232  
kivy.garden, 321  
kivy.geometry, 232  
kivy.gesture, 233  
kivy.graphics, 323  
kivy.graphics.cgl, 349  
kivy.graphics.compiler, 358  
kivy.graphics.context, 354  
kivy.graphics.context\_instructions, 350  
kivy.graphics.fbo, 354  
kivy.graphics.gl\_instructions, 357  
kivy.graphics.instructions, 345  
kivy.graphics.opengl, 359  
kivy.graphics.opengl\_utils, 367  
kivy.graphics.scissor\_instructions, 369  
kivy.graphics.shader, 370  
kivy.graphics.stencil\_instructions, 371  
kivy.graphics.svg, 373  
Kivy.graphics.tesselator, 374  
kivy.graphics.texture, 377  
kivy.graphics.transformation, 383  
kivy.graphics.vertex\_instructions, 386  
kivy.input, 397  
kivy.input.factory, 414  
Kivy.input.motionevent, 409  
kivy.input.postproc, 399  
Kivy.input.postproc.calibration, 399  
kivy.input.postproc.dejitter, 400  
kivy.input.postproc.doubletap, 400  
kivy.input.postproc.ignorelist, 401  
kivy.input.postproc.retaintouch, 401  
Kivy.input.postproc.tripletap, 401  
kivy.input.provider, 414  
kivy.input.providers, 402  
Kivy.input.providers.androidjoystick, 402  
kivy.input.providers.hidinput, 403  
kivy.input.providers.leapfinger, 402  
kivy.input.providers.linuxwacom, 405

kivy.input.providers.mactouch, 405  
kivy.input.providers.mouse, 402  
kivy.input.providers.mtdev, 404  
kivy.input.providers.probesysfs, 402  
kivy.input.providers.tuio, 406  
kivy.input.providers.wm\_common, 402  
kivy.input.providers.wm\_pen, 405  
kivy.input.providers.wm\_touch, 405  
kivy.input.recorder, 407  
kivy.input.shape, 414  
kivy.interactive, 234  
kivy.lang, 417  
kivy.lang.builder, 432  
kivy.lang.parser, 434  
kivy.lib, 437  
kivy.lib.ddsfile, 439  
kivy.lib.gstplayer, 437  
kivy.lib.mtdev, 440  
kivy.lib.osc, 437  
kivy.lib.osc.OSC, 438  
kivy.lib.osc.oscAPI, 438  
kivy.loader, 202  
kivy.logger, 239  
kivy.metrics, 240  
kivy.modules, 441  
kivy.modules.console, 442  
kivy.modules.inspector, 446  
kivy.modules.joycursor, 447  
kivy.modules.keybinding, 448  
kivy.modules.monitor, 449  
kivy.modules.recorder, 449  
kivy.modules.screen, 450  
kivy.modules.touchring, 450  
kivy.modules.webdebugger, 451  
kivy.multistroke, 242  
kivy.network, 453  
kivy.network.urlrequest, 453  
kivy.parser, 251  
kivy.properties, 252  
kivy.resources, 264  
kivy.storage, 457  
kivy.storage.dictstore, 461  
kivy.storage.jsonstore, 461  
kivy.storage.redisstore, 461  
kivy.support, 265  
kivy.tools, 463  
kivy.tools.packaging, 464  
kivy.tools.packaging.pyinstaller\_hooks, 464  
kivy.uix, 467  
kivy.uix.abstractview, 505  
kivy.uix.accordion, 505  
kivy.uix.actionbar, 509  
kivy.uix.anchorlayout, 514  
kivy.uix.behaviors, 467  
kivy.uix.behaviors.button, 474  
kivy.uix.behaviors.codenavigation, 475  
kivy.uix.behaviors.compoundselection, 475  
kivy.uix.behaviors.cover, 481  
kivy.uix.behaviors.drag, 482  
kivy.uix.behaviors.emacs, 483  
kivy.uix.behaviors.focus, 484  
kivy.uix.behaviors.knspase, 488  
kivy.uix.behaviors.togglebutton, 493  
kivy.uix.behaviors.touchripple, 495  
kivy.uix.boxlayout, 515  
kivy.uix.bubble, 517  
kivy.uix.button, 520  
kivy.uix.camera, 522  
kivy.uix.carousel, 523  
kivy.uix.checkbox, 525  
kivy.uix.codeinput, 527  
kivy.uix.colorpicker, 528  
kivy.uix.dropdown, 530  
kivy.uix.effectwidget, 533  
kivy.uix.filechooser, 537  
kivy.uix.floatlayout, 545  
kivy.uix.gesturesurface, 547  
kivy.uix.gridlayout, 550  
kivy.uix.image, 553  
kivy.uix.label, 556  
kivy.uix.layout, 567  
kivy.uix.listview, 568  
kivy.uix.modalview, 578  
kivy.uix.pagelayout, 580  
kivy.uix.popup, 581  
kivy.uix.progressbar, 584  
kivy.uix.recycleboxlayout, 585  
kivy.uix.recyclegridlayout, 585  
kivy.uix.recyclelayout, 585  
kivy.uix.recycleview, 496  
kivy.uix.recycleview.datamodel, 500  
kivy.uix.recycleview.layout, 501  
kivy.uix.recycleview.views, 502  
kivy.uix.relativelayout, 585  
kivy.uix.rst, 589  
kivy.uix.sandbox, 592  
kivy.uix.scatter, 593  
kivy.uix.scatterlayout, 597  
kivy.uix.screenmanager, 598  
kivy.uix.scrollview, 606  
kivy.uix.selectableview, 610  
kivy.uix.settings, 611  
kivy.uix.slider, 619  
kivy.uix.spinner, 623  
kivy.uix.splitter, 624  
kivy.uix.stacklayout, 627  
kivy.uix.stencilview, 628  
kivy.uix.switch, 629

`kivy.uix.tabbedpanel`, 630  
`kivy.uix.textinput`, 636  
`kivy.uix.togglebutton`, 647  
`kivy.uixtreeview`, 648  
`kivy.uix.video`, 653  
`kivy.uix.videoplayer`, 655  
`kivy.uix.vkeyboard`, 660  
`kivy.uix.widget`, 664  
`kivy.utils`, 266  
`kivy.vector`, 268  
`kivy.weakmethod`, 271  
`kivy.weakproxy`, 272



---

# Index

---

## A

a (kivy.graphics.ClearColor attribute), 343  
a (kivy.graphics.Color attribute), 329  
a (kivy.graphics.context\_instructions.Color attribute), 351  
a (kivy.graphics.gl\_instructions.ClearColor attribute), 357  
a (kivy.uix.colorpicker.ColorWheel attribute), 530  
AbstractStore (class in kivy.storage), 459  
AbstractView (class in kivy.uix.abstractview), 505  
accept\_stroke() (kivy.uix.gesturesurface.GestureContainer method), 549  
Accordion (class in kivy.uix.accordion), 507  
accordion (kivy.uix.accordion.AccordionItem attribute), 507  
AccordionException (class in kivy.uix.accordion), 509  
AccordionItem (class in kivy.uix.accordion), 507  
action\_previous (kivy.uix.actionbar.ActionView attribute), 512  
action\_view (kivy.uix.actionbar.ActionBar attribute), 513  
ActionBar (class in kivy.uix.actionbar), 513  
ActionBarException (class in kivy.uix.actionbar), 510  
ActionButton (class in kivy.uix.actionbar), 510  
ActionCheck (class in kivy.uix.actionbar), 511  
ActionDropDown (class in kivy.uix.actionbar), 511  
ActionGroup (class in kivy.uix.actionbar), 511  
ActionItem (class in kivy.uix.actionbar), 510  
ActionOverflow (class in kivy.uix.actionbar), 512  
ActionPrevious (class in kivy.uix.actionbar), 512  
ActionSeparator (class in kivy.uix.actionbar), 511  
ActionToggleButton (class in kivy.uix.actionbar), 511  
ActionView (class in kivy.uix.actionbar), 512  
activate() (kivy.modules.console.ConsoleAddon method), 445  
activated (kivy.modules.console.Console at-

tribute), 445  
active (kivy.uix.checkbox.CheckBox attribute), 526  
active (kivy.uix.switch.Switch attribute), 630  
active\_norm\_pos (kivy.uix.switch.Switch attribute), 630  
Adapter (class in kivy.adapters.adapter), 275  
adapter (kivy.uix.abstractview.AbstractView attribute), 505  
add() (kivy.graphics.InstructionGroup method), 332  
add() (kivy.graphics.instructions.InstructionGroup method), 345  
add() (kivy.lib.osc.OSC.CallbackManager method), 438  
add\_callback() (kivy.config.ConfigParser method), 222  
add\_contour() (kivy.graphics.tesselator.Tesselator method), 376  
add\_dep\_paths() (in module kivy.tools.packaging.pyinstaller\_hooks), 465  
add\_event\_listener() (kivy.base.EventLoopBase method), 237  
add\_gesture() (kivy.gesture.GestureDatabase method), 234  
add\_gesture() (kivy.multistroke.Recognizer method), 244  
add\_handler() (kivy.base.ExceptionManagerBase method), 239  
add\_input\_provider() (kivy.base.EventLoopBase method), 237  
add\_interface() (kivy.uix.settings.Settings method), 613  
add\_item() (kivy.uix.settings.MenuSidebar method), 619  
add\_json\_panel() (kivy.uix.settings.Settings method), 613  
add\_kivy\_panel() (kivy.uix.settings.Settings method), 614  
add\_mipmap() (kivy.core.image.ImageData

method), 290  
add\_node() (kivy.uix.treeview.TreeView method), 649  
add\_panel() (kivy.modules.console.Console method), 445  
add\_panel() (kivy.uix.settings.ContentPanel method), 618  
add\_panel() (kivy.uix.settings.InterfaceWithSidebar method), 617  
add\_point() (kivy.gesture.GestureStroke method), 234  
add\_point() (kivy.graphics.Point method), 338  
add\_point() (kivy.graphics.vertex\_instructions.Point method), 394  
add\_point() (kivy.multistroke.UnistrokeTemplate method), 250  
add\_postproc\_module() (kivy.base.EventLoopBase method), 237  
add\_reload\_observer() (kivy.graphics.context.Context method), 354  
add\_reload\_observer() (kivy.graphics.Fbo method), 330  
add\_reload\_observer() (kivy.graphics.fbo.Fbo method), 356  
add\_reload\_observer() (kivy.graphics.texture.Texture method), 380  
add\_screen() (kivy.uix.screenmanager.TransitionBase method), 603  
add\_stroke() (kivy.gesture.Gesture method), 233  
add\_stroke() (kivy.multistroke.Candidate method), 251  
add\_stroke() (kivy.multistroke.MultistrokeGesture method), 249  
add\_stroke() (kivy.uix.gesturesurface.GestureContainer method), 549  
add\_toolbar\_widget() (kivy.modules.console.Console method), 445  
add\_widget() (kivy.core.window.WindowBase method), 302  
add\_widget() (kivy.uix.widget.Widget method), 667  
adddefaultsection() (kivy.config.ConfigParser method), 223  
addons (kivy.modules.console.Console attribute), 445  
AdvancedEffectBase (class in kivy.effectwidget), 535  
after (kivy.graphics.Canvas attribute), 327  
after (kivy.graphics.instructions.Canvas attribute), 347  
AliasProperty (class in kivy.properties), 261  
allow\_copy (kivy.uix.textinput.TextInput attribute), 639  
allow\_empty\_selection (kivy.adapters.listadapter.ListAdapter attribute), 278  
allow\_fullscreen (kivy.uix.videoplayer.VideoPlayer attribute), 657  
allow\_no\_selection (kivy.uix.behaviors.togglebutton.ToggleButton attribute), 494  
allow\_screensaver (kivy.core.window.WindowBase attribute), 302  
allow\_stretch (kivy.uix.image.Image attribute), 554  
always\_release (kivy.uix.behaviors.button.ButtonBehavior attribute), 474  
always\_release (kivy.uix.behaviors.touchripple.TouchRippleButton attribute), 496  
anchor\_x (kivy.graphics.svg.Svg attribute), 374  
anchor\_x (kivy.uix.anchorlayout.AnchorLayout attribute), 515  
anchor\_y (kivy.graphics.svg.Svg attribute), 374  
anchor\_y (kivy.uix.anchorlayout.AnchorLayout attribute), 515  
AnchorLayout (class in kivy.uix.anchorlayout), 514  
anchors (kivy.core.text.markup.MarkupLabel attribute), 298  
anchors (kivy.uix.label.Label attribute), 560  
angle (kivy.graphics.context\_instructions.Rotate attribute), 352  
angle (kivy.graphics.Rotate attribute), 340  
angle() (kivy.vector.Vector method), 269  
angle\_end (kivy.graphics.Ellipse attribute), 330  
angle\_end (kivy.graphics.vertex\_instructions.Ellipse attribute), 389  
angle\_start (kivy.graphics.Ellipse attribute), 330  
angle\_start (kivy.graphics.vertex\_instructions.Ellipse attribute), 389  
anim\_available (kivy.core.image.Image attribute), 287  
anim\_cancel\_duration (kivy.uix.carousel.Carousel attribute), 523  
anim\_delay (kivy.core.image.Image attribute), 287  
anim\_delay (kivy.uix.image.Image attribute), 554  
anim\_duration (kivy.uix.accordion.Accordion attribute), 507  
anim\_func (kivy.uix.accordion.Accordion attribute), 507  
anim\_index (kivy.core.image.Image attribute), 288  
anim\_loop (kivy.uix.image.Image attribute), 554  
anim\_move\_duration (kivy.uix.carousel.Carousel attribute), 523  
anim\_reset() (kivy.core.image.Image method), 288  
anim\_type (kivy.uix.carousel.Carousel attribute), 523

animated\_properties (kivy.animation.Animation attribute), 182  
Animation (class in kivy.animation), 181  
AnimationTransition (class in kivy.animation), 183  
annotations (kivy.uix.videoplayer.VideoPlayer attribute), 657  
App (class in kivy.app), 196  
app\_icon (kivy.uix.actionbar.ActionPrevious attribute), 512  
app\_icon\_height (kivy.uix.actionbar.ActionPrevious attribute), 513  
app\_icon\_width (kivy.uix.actionbar.ActionPrevious attribute), 513  
append() (kivy.cache.Cache static method), 208  
append() (kivy.lib.osc.OSC.OSCMessage method), 438  
appendToBundle() (in module kivy.lib.osc.oscAPI), 439  
apply() (kivy.lang.builder.BuilderBase method), 432  
apply() (kivy.lang.BuilderBase method), 429  
apply\_property() (kivy.event.EventDispatcher method), 224  
apply\_rules() (kivy.lang.builder.BuilderBase method), 432  
apply\_rules() (kivy.lang.BuilderBase method), 429  
apply\_selection() (kivy.uix.recycleview.layout.Layout method), 501  
apply\_transform() (kivy.uix.scatter.Scatter method), 595  
apply\_transform\_2d() (kivy.input.MotionEvent method), 397  
apply\_transform\_2d() (kivy.input.motionevent.MotionEvent method), 411  
ApplyContextMatrix (class in kivy.graphics), 344  
args\_converter (kivy.adapters.adapter.Adapter attribute), 275  
arrow\_image (kivy.uix.bubble.Bubble attribute), 519  
arrow\_pos (kivy.uix.bubble.Bubble attribute), 519  
ask\_update() (kivy.graphics.Callback method), 327  
ask\_update() (kivy.graphics.Canvas method), 327  
ask\_update() (kivy.graphics.instructions.Callback method), 349  
ask\_update() (kivy.graphics.instructions.Canvas method), 347  
ask\_update() (kivy.graphics.texture.Texture method), 380  
async\_clear() (kivy.storage.AbstractStore method), 459  
async\_count() (kivy.storage.AbstractStore method), 459  
async\_delete() (kivy.storage.AbstractStore method), 459  
async\_exists() (kivy.storage.AbstractStore method), 459  
async\_find() (kivy.storage.AbstractStore method), 459  
async\_get() (kivy.storage.AbstractStore method), 459  
async\_keys() (kivy.storage.AbstractStore method), 460  
async\_put() (kivy.storage.AbstractStore method), 460  
AsyncImage (class in kivy.uix.image), 556  
Atlas (class in kivy.atlas), 206  
attach\_recycleview() (kivy.uix.recycleview.datamodel.RecycleData method), 500  
attach\_recycleview() (kivy.uix.recycleview.views.RecycleDataAdapter method), 503  
attach\_to (kivy.uix.dropdown.DropDown attribute), 532  
attach\_to (kivy.uix.modalview.ModalView attribute), 579  
auto\_bring\_to\_front (kivy.uix.scatter.Scatter attribute), 595  
auto\_dismiss (kivy.uix.dropdown.DropDown attribute), 532  
auto\_dismiss (kivy.uix.modalview.ModalView attribute), 579  
auto\_indent (kivy.uix.textinput.TextInput attribute), 639  
auto\_scale (kivy.graphics.BorderImage attribute), 326  
auto\_scale (kivy.graphics.vertex\_instructions.BorderImage attribute), 389  
auto\_width (kivy.uix.dropdown.DropDown attribute), 532  
available\_layouts (kivy.uix.vkeyboard.VKeyboard attribute), 662  
axis (kivy.graphics.context\_instructions.Rotate attribute), 352  
axis (kivy.graphics.Rotate attribute), 340

## B

b (kivy.graphics.ClearColor attribute), 343  
b (kivy.graphics.Color attribute), 329  
b (kivy.graphics.context\_instructions.Color attribute), 351  
b (kivy.graphics.gl\_instructions.ClearColor attribute), 357  
b (kivy.uix.colorpicker.ColorWheel attribute), 530  
background (kivy.uix.modalview.ModalView attribute), 579  
background (kivy.uix.vkeyboard.VKeyboard attribute), 662  
background\_active (kivy.uix.textinput.TextInput attribute), 639

background\_border (kivy.uix.vkeyboard.VKeyboard attribute), 662  
background\_checkbox\_disabled\_down (kivy.uix.checkbox.CheckBox attribute), 526  
background\_checkbox\_disabled\_normal (kivy.uix.checkbox.CheckBox attribute), 526  
background\_checkbox\_down (kivy.uix.checkbox.CheckBox attribute), 526  
background\_checkbox\_normal (kivy.uix.checkbox.CheckBox attribute), 526  
background\_color (kivy.uix.actionbar.ActionBar attribute), 514  
background\_color (kivy.uix.actionbar.ActionView attribute), 512  
background\_color (kivy.uix.bubble.Bubble attribute), 519  
background\_color (kivy.uix.button.Button attribute), 521  
background\_color (kivy.uix.effectwidget.EffectWidget attribute), 535  
background\_color (kivy.uix.listview.CompositeListIt attribute), 577  
background\_color (kivy.uix.modalview.ModalView attribute), 579  
background\_color (kivy.uix.rst.RstDocument attribute), 591  
background\_color (kivy.uix.tabbedpanel.TabbedPanel attribute), 633  
background\_color (kivy.uix.textinput.TextInput attribute), 639  
background\_color (kivy.uix.vkeyboard.VKeyboard attribute), 662  
background\_disabled (kivy.uix.vkeyboard.VKeyboard attribute), 662  
background\_disabled\_down (kivy.uix.button.Button attribute), 521  
background\_disabled\_horizontal (kivy.uix.slider.Slider attribute), 620  
background\_disabled\_image (kivy.uix.tabbedpanel.TabbedPanel attribute), 633  
background\_disabled\_normal (kivy.uix.accordion.AccordionItem attribute), 507  
background\_disabled\_normal (kivy.uix.button.Button attribute), 521  
background\_disabled\_normal (kivy.uix.textinput.TextInput attribute), 639  
background\_disabled\_selected  
(kivy.uix.accordion.AccordionItem attribute), 507  
background\_disabled\_vertical (kivy.uix.slider.Slider attribute), 620  
background\_down (kivy.uix.actionbar.ActionItem attribute), 510  
background\_down (kivy.uix.button.Button attribute), 521  
background\_horizontal (kivy.uix.slider.Slider attribute), 620  
background\_image (kivy.uix.actionbar.ActionBar attribute), 514  
background\_image (kivy.uix.actionbar.ActionSeparator attribute), 511  
background\_image (kivy.uix.actionbar.ActionView attribute), 512  
background\_image (kivy.uix.bubble.Bubble attribute), 519  
background\_image (kivy.uix.tabbedpanel.StripLayout attribute), 633  
background\_image (kivy.uix.tabbedpanel.TabbedPanel attribute), 633  
background\_normal (kivy.uix.accordion.AccordionItem attribute), 508  
background\_normal (kivy.uix.actionbar.ActionItem attribute), 510  
background\_normal (kivy.uix.button.Button attribute), 521  
background\_normal (kivy.uix.textinput.TextInput attribute), 639  
background\_radio\_disabled\_down (kivy.uix.checkbox.CheckBox attribute), 526  
background\_radio\_disabled\_normal (kivy.uix.checkbox.CheckBox attribute), 527  
background\_radio\_down (kivy.uix.checkbox.CheckBox attribute), 527  
background\_radio\_normal (kivy.uix.checkbox.CheckBox attribute), 527  
background\_selected (kivy.uix.accordion.AccordionItem attribute), 508  
background\_vertical (kivy.uix.slider.Slider attribute), 620  
background\_width (kivy.uix.slider.Slider attribute), 620  
bar\_color (kivy.uix.scrollview.ScrollView attribute), 608  
bar\_inactive\_color (kivy.uix.scrollview.ScrollView attribute), 608  
bar\_margin (kivy.uix.scrollview.ScrollView attribute), 608

bar\_pos (kivy.uix.scrollview.ScrollView attribute), 608  
bar\_pos\_x (kivy.uix.scrollview.ScrollView attribute), 608  
bar\_pos\_y (kivy.uix.scrollview.ScrollView attribute), 608  
bar\_width (kivy.uix.scrollview.ScrollView attribute), 608  
base\_font\_size (kivy.uix.rst.RstDocument attribute), 591  
bbox (kivy.uix.scatter.Scatter attribute), 595  
before (kivy.graphics.Canvas attribute), 327  
before (kivy.graphics.instructions.Canvas attribute), 347  
best (kivy.multistroke.ProgressTracker attribute), 248  
Bezier (class in kivy.graphics), 324  
Bezier (class in kivy.graphics.vertex\_instructions), 395  
bezier (kivy.graphics.Line attribute), 334  
bezier (kivy.graphics.vertex\_instructions.Line attribute), 391  
bezier\_precision (kivy.graphics.Line attribute), 334  
bezier\_precision (kivy.graphics.vertex\_instructions.Line attribute), 391  
bind() (in module kivy.lib.osc.oscAPI), 439  
bind() (kivy.event.EventDispatcher method), 224  
bind() (kivy.graphics.Fbo method), 330  
bind() (kivy.graphics.fbo.Fbo method), 356  
bind() (kivy.graphics.texture.Texture method), 380  
bind() (kivy.properties.Property method), 257  
BindTexture (class in kivy.graphics), 325  
BindTexture (class in kivy.graphics.context\_instructions), 351  
blit\_buffer() (kivy.graphics.texture.Texture method), 380  
blit\_data() (kivy.graphics.texture.Texture method), 381  
bold (kivy.uix.label.Label attribute), 560  
BooleanProperty (class in kivy.properties), 259  
border (kivy.graphics.BorderImage attribute), 326  
border (kivy.graphics.vertex\_instructions.BorderImage attribute), 389  
border (kivy.uix.actionbar.ActionBar attribute), 514  
border (kivy.uix.bubble.Bubble attribute), 519  
border (kivy.uix.button.Button attribute), 521  
border (kivy.uix.modalview.ModalView attribute), 580  
border (kivy.uix.pagelayout.PageLayout attribute), 581  
border (kivy.uix.splitter.Splitter attribute), 625  
border (kivy.uix.tabbedpanel.StripLayout attribute), 633  
border (kivy.uix.tabbedpanel.TabbedPanel attribute), 633  
border (kivy.uix.textinput.TextInput attribute), 640  
border\_horizontal (kivy.uix.slider.Slider attribute), 620  
border\_vertical (kivy.uix.slider.Slider attribute), 620  
BorderImage (class in kivy.graphics), 325  
BorderImage (class in kivy.graphics.vertex\_instructions), 388  
borderless (kivy.core.window.WindowBase attribute), 303  
boundary() (in module kivy.utils), 266  
BoundedNumericProperty (class in kivy.properties), 259  
bounds (kivy.properties.BoundedNumericProperty attribute), 259  
BoxLayout (class in kivy.uix.boxlayout), 516  
Bubble (class in kivy.uix.bubble), 519  
BubbleButton (class in kivy.uix.bubble), 520  
bufferfmt (kivy.graphics.texture.Texture attribute), 381  
build() (kivy.app.App method), 197  
build\_config() (kivy.app.App method), 197  
build\_settings() (kivy.app.App method), 197  
Builder (in module kivy.lang.builder), 432  
BuilderBase (class in kivy.lang), 429  
BuilderBase (class in kivy.lang.builder), 432  
BuilderException (class in kivy.lang), 431  
BuilderException (class in kivy.lang.builder), 434  
Button (class in kivy.uix.button), 520  
ButtonBehavior (class in kivy.uix.behaviors), 468  
ButtonBehavior (class in kivy.uix.behaviors.button), 474  
buttons\_layout (kivy.uix.settings.MenuSidebar attribute), 619

C

Cache (class in kivy.cache), 207  
cached\_views (kivy.adapters.listadapter.ListAdapter attribute), 278  
Callback (class in kivy.graphics), 326  
Callback (class in kivy.graphics.instructions), 348  
callback (kivy.core.window.Keyboard attribute), 300  
callback (kivy.uix.vkeyboard.VKeyboard attribute), 662  
CallbackManager (class in kivy.lib.osc.OSC), 438  
Camera (class in kivy.uix.camera), 522  
CameraBase (class in kivy.core.camera), 285  
cancel() (kivy.animation.Animation method), 182  
cancel() (kivy.clock.ClockEvent method), 214  
cancel() (kivy.effects.kinetic.KineticEffect method), 318  
cancel() (kivy.uix.filechooser.FileChooserController method), 542

cancel() (kivy.uix.filechooser.FileChooserProgressBase method), 545  
cancel\_all() (kivy.animation.Animation static method), 182  
cancel\_property() (kivy.animation.Animation method), 182  
cancel\_selection() (kivy.uix.textinput.TextInput method), 640  
Candidate (class in kivy.multistroke), 250  
Canvas (class in kivy.graphics), 327  
Canvas (class in kivy.graphics.instructions), 347  
canvas (kivy.uix.widget.Widget attribute), 668  
CanvasBase (class in kivy.graphics), 328  
CanvasBase (class in kivy.graphics.instructions), 348  
cap (kivy.graphics.Line attribute), 334  
cap (kivy.graphics.vertex\_instructions.Line attribute), 391  
cap\_precision (kivy.graphics.Line attribute), 334  
cap\_precision (kivy.graphics.vertex\_instructions.Line attribute), 391  
CardTransition (class in kivy.uix.screenmanager), 605  
Carousel (class in kivy.uix.carousel), 523  
center (kivy.core.window.WindowBase attribute), 303  
center (kivy.uix.widget.Widget attribute), 668  
center\_stroke() (kivy.gesture.GestureStroke method), 234  
center\_x (kivy.uix.widget.Widget attribute), 668  
center\_y (kivy.uix.widget.Widget attribute), 668  
ChangeState (class in kivy.graphics), 344  
ChannelMixEffect (class in kivy.uix.effectwidget), 536  
check() (kivy.core.spelling.SpellingBase method), 291  
CheckBox (class in kivy.uix.checkbox), 526  
children (kivy.core.window.WindowBase attribute), 303  
children (kivy.uix.widget.Widget attribute), 668  
chunk\_size (kivy.network.urlrequest.UrlRequest attribute), 455  
circle (kivy.graphics.Line attribute), 334  
circle (kivy.graphics.vertex\_instructions.Line attribute), 391  
circumcircle() (in module kivy.geometry), 232  
clear() (kivy.core.window.WindowBase method), 303  
clear() (kivy.graphics.Canvas method), 327  
clear() (kivy.graphics.InstructionGroup method), 332  
clear() (kivy.graphics.instructions.Canvas method), 347  
clear() (kivy.graphics.instructions.InstructionGroup method), 345  
clear() (kivy.storage.AbstractStore method), 460  
clear\_buffer() (kivy.graphics.Fbo method), 331  
clear\_buffer() (kivy.graphics.fbo.Fbo method), 356  
clear\_color (kivy.graphics.ClearBuffers attribute), 344  
clear\_color (kivy.graphics.Fbo attribute), 331  
clear\_color (kivy.graphics.fbo.Fbo attribute), 356  
clear\_color (kivy.graphics.gl\_instructions.ClearBuffers attribute), 357  
clear\_depth (kivy.graphics.ClearBuffers attribute), 344  
clear\_depth (kivy.graphics.gl\_instructions.ClearBuffers attribute), 358  
clear\_selection() (kivy.uix.behaviors.compoundselection.CompoundSelectionBehavior method), 477  
clear\_selection() (kivy.uix.behaviors.CompoundSelectionBehavior method), 470  
clear\_stencil (kivy.graphics.ClearBuffers attribute), 344  
clear\_stencil (kivy.graphics.gl\_instructions.ClearBuffers attribute), 358  
clear\_widgets() (kivy.uix.widget.Widget method), 668  
ClearBuffers (class in kivy.graphics), 343  
ClearBuffers (class in kivy.graphics.gl\_instructions), 357  
ClearColor (class in kivy.graphics), 343  
ClearColor (class in kivy.graphics.gl\_instructions), 357  
clearcolor (kivy.core.window.WindowBase attribute), 303  
clearcolor (kivy.uix.screenmanager.ShaderTransition attribute), 604  
Clock (in module kivy.clock), 214  
clock (kivy.clock.ClockEvent attribute), 214  
clock() (in module kivy.compat), 218  
clock\_resolution (kivy.clock.CyClockBase attribute), 215  
ClockBase (class in kivy.clock), 217  
ClockBaseBehavior (class in kivy.clock), 216  
ClockBaseFreeInterruptAll (class in kivy.clock), 217  
ClockBaseFreeInterruptOnly (class in kivy.clock), 217  
ClockBaseInterrupt (class in kivy.clock), 217  
ClockBaseInterruptBehavior (class in kivy.clock), 217  
ClockBaseInterruptFreeBehavior (class in kivy.clock), 217  
ClockEvent (class in kivy.clock), 214  
close (kivy.graphics.Line attribute), 335  
close (kivy.graphics.vertex\_instructions.Line attribute), 392  
close() (kivy.base.EventLoopBase method), 238  
close() (kivy.core.window.WindowBase method),

303  
close\_button (kivy.uix.settings.MenuSidebar attribute), 619  
close\_settings() (kivy.app.App method), 197  
cls (kivy.adapters.adapter.Adapter attribute), 275  
cls (kivy.uix.widget.Widget attribute), 669  
cm() (in module kivy.metrics), 242  
CodeInput (class in kivy.uix.codeinput), 528  
CodeNavigationBehavior (class in kivy.uix.behaviors), 472  
CodeNavigationBehavior (class in kivy.uix.behaviors.codenavigation), 475  
col\_default\_width (kivy.uix.gridlayout.GridLayout attribute), 552  
col\_force\_default (kivy.uix.gridlayout.GridLayout attribute), 552  
collapse (kivy.uix.accordion.AccordionItem attribute), 508  
collapse\_alpha (kivy.uix.accordion.AccordionItem attribute), 508  
collide\_margin() (kivy.uix.vkeyboard.VKeyboard method), 662  
collide\_point() (kivy.uix.widget.Widget method), 669  
collide\_widget() (kivy.uix.widget.Widget method), 669  
Color (class in kivy.graphics), 328  
Color (class in kivy.graphics.context\_instructions), 350  
color (kivy.uix.actionbar.ActionPrevious attribute), 513  
color (kivy.uix.checkbox.CheckBox attribute), 527  
color (kivy.uix.colorpicker.ColorPicker attribute), 529  
color (kivy.uix.colorpicker.ColorWheel attribute), 530  
color (kivy.uix.image.Image attribute), 554  
color (kivy.uix.label.Label attribute), 560  
color\_selected (kivy.uix.treeview.TreeViewNode attribute), 652  
colorfmt (kivy.graphics.texture.Texture attribute), 381  
ColorPicker (class in kivy.uix.colorpicker), 529  
colors (kivy.uix.rst.RstDocument attribute), 591  
ColorWheel (class in kivy.uix.colorpicker), 529  
cols (kivy.uix.gridlayout.GridLayout attribute), 552  
cols\_minimum (kivy.uix.gridlayout.GridLayout attribute), 552  
complete\_stroke() (kivy.uix.gesturesurface.Gesture method), 549  
CompositeListItem (class in kivy.uix.listview), 577  
CompoundSelectionBehavior (class in kivy.uix.behaviors), 470  
CompoundSelectionBehavior (class in kivy.uix.behaviors.compoundselection), 477  
compute\_visible\_views() (kivy.uix.recycleview.layout.RecycleLayoutManagerBehavior method), 502  
Config (in module kivy.config), 222  
config (kivy.app.App attribute), 197  
config (kivy.uix.settings.SettingsPanel attribute), 614  
ConfigParser (class in kivy.config), 222  
ConfigParserProperty (class in kivy.properties), 262  
Console (class in kivy.modules.console), 445  
console (kivy.modules.console.ConsoleAddon attribute), 445  
ConsoleAddon (class in kivy.modules.console), 445  
ConsoleButton (class in kivy.modules.console), 446  
ConsoleLabel (class in kivy.modules.console), 446  
ConsoleToggleButton (class in kivy.modules.console), 446  
container (kivy.uix.accordion.AccordionItem attribute), 508  
container (kivy.uix.dropdown.DropDown attribute), 532  
container (kivy.uix.listview.ListView attribute), 577  
container (kivy.uix.settings.ContentPanel attribute), 618  
container\_title (kivy.uix.accordion.AccordionItem attribute), 508  
content (kivy.uix.bubble.Bubble attribute), 519  
content (kivy.uix.popup.Popup attribute), 583  
content (kivy.uix.settings.InterfaceWithSidebar attribute), 618  
content (kivy.uix.settings.SettingItem attribute), 615  
content (kivy.uix.tabbedpanel.TabbedPanel attribute), 634  
content (kivy.uix.tabbedpanel.TabbedPanelHeader attribute), 635  
content\_height (kivy.core.text.LabelBase attribute), 293  
content\_size (kivy.core.text.LabelBase attribute), 293  
content\_size (kivy.uix.accordion.AccordionItem attribute), 508  
content\_width (kivy.core.text.LabelBase attribute), 293  
ContentPanel (class in kivy.uix.settings), 618  
Context (class in kivy.graphics.context), 354  
ContextInstruction (class in kivy.graphics), 329  
ContextInstruction (class in kivy.uix.settings), 618

kivy.graphics.instructions), 346  
 ContextualActionView (class in kivy.uix.actionbar), 512  
 convert\_distance\_to\_scroll() (kivy.uix.scrollview.ScrollView method), 608  
 copy() (kivy.uix.textinput.TextInput method), 640  
 copy\_to() (kivy.input MotionEvent method), 397  
 copy\_to() (kivy.input.motionevent.MotionEvent method), 411  
 count() (kivy.storage.AbstractStore method), 460  
 counter (kivy.input.recorder.Recorder attribute), 409  
 cover\_pos (kivy.uix.behaviors.cover.CoverBehavior attribute), 481  
 cover\_size (kivy.uix.behaviors.cover.CoverBehavior attribute), 481  
 CoverBehavior (class in kivy.uix.behaviors), 473  
 CoverBehavior (class in kivy.uix.behaviors.cover), 481  
 create() (kivy.atlas.Atlas static method), 206  
 create() (kivy.graphics.texture.Texture static method), 381  
 create() (kivy.input.providers.tuio.TuioMotionEvent static method), 407  
 create\_from\_data() (kivy.graphics.texture.Texture static method), 381  
 create\_inspector() (in module kivy.modules.inspector), 447  
 create\_joycursor() (in module kivy.modules.joycursor), 448  
 create\_json\_panel() (kivy.uix.settings.Settings method), 614  
 create\_property() (kivy.event.EventDispatcher method), 226  
 create\_settings() (kivy.app.App method), 197  
 create\_trigger() (kivy.clock.CyClockBase method), 215  
 create\_trigger\_free() (kivy.clock.CyClockBaseFree method), 216  
 create\_view() (kivy.adapters.listadapter.ListAdapter method), 278  
 create\_view() (kivy.uix.recycleview.views.RecycleData method), 503  
 create\_window() (kivy.core.window.WindowBase method), 303  
 createBinaryMsg() (in module kivy.lib.osc.oscAPI), 439  
 createBundle() (in module kivy.lib.osc.oscAPI), 439  
 current (kivy.uix.screenmanager.ScreenManager attribute), 601  
 current\_panel (kivy.uix.settings.ContentPanel attribute), 618  
 current\_screen (kivy.uix.screenmanager.ScreenManager attribute), 602  
 current\_slide (kivy.uix.carousel.Carousel attribute), 523  
 current\_tab (kivy.uix.tabbedpanel.TabbedPanel attribute), 634  
 current\_uid (kivy.uix.settings.ContentPanel attribute), 618  
 cursor (kivy.uix.textinput.TextInput attribute), 640  
 cursor\_blink (kivy.uix.textinput.TextInput attribute), 640  
 cursor\_col (kivy.uix.textinput.TextInput attribute), 640  
 cursor\_color (kivy.uix.textinput.TextInput attribute), 640  
 cursor\_disabled\_image (kivy.uix.slider.Slider attribute), 620  
 cursor\_height (kivy.uix.slider.Slider attribute), 620  
 cursor\_image (kivy.uix.slider.Slider attribute), 620  
 cursor\_index() (kivy.uix.textinput.TextInput method), 640  
 cursor\_offset() (kivy.uix.textinput.TextInput method), 640  
 cursor\_pos (kivy.uix.textinput.TextInput attribute), 640  
 cursor\_provider (kivy.uix.textinput.TextInput attribute), 640  
 cursor\_row (kivy.uix.textinput.TextInput attribute), 640  
 cursor\_size (kivy.uix.slider.Slider attribute), 621  
 cursor\_width (kivy.uix.slider.Slider attribute), 621  
 cursor\_width (kivy.uix.textinput.TextInput attribute), 640  
 cut() (kivy.uix.textinput.TextInput method), 641  
 cut\_to\_sel() (kivy.adapters.dictadapter.DictAdapter method), 276  
 cut\_to\_sel() (kivy.adapters.listadapterListAdapter method), 278  
 CyClockBase (class in kivy.clock), 214  
 CyClockBaseFree (class in kivy.clock), 216

## D

DampedScrollEffect (class in kivy.effects.dampedscroll), 317  
 dash\_length (kivy.graphics.Bezier attribute), 324  
 dash\_length (kivy.graphics.Line attribute), 335  
 dash\_length (kivy.graphics.vertex\_instructions.Bezier attribute), 395  
 dash\_length (kivy.graphics.vertex\_instructions.Line attribute), 392  
 dash\_offset (kivy.graphics.Bezier attribute), 324  
 dash\_offset (kivy.graphics.Line attribute), 335  
 dash\_offset (kivy.graphics.vertex\_instructions.Bezier attribute), 395  
 dash\_offset (kivy.graphics.vertex\_instructions.Line attribute), 392  
 data (kivy.adapters.adapter.Adapter attribute), 275

data (kivy.adapters.dictadapter.DictAdapter attribute), 276  
data (kivy.adapters.listadapter.ListAdapter attribute), 278  
data (kivy.adapters.simplelistadapter.SimpleListAdapter attribute), 281  
data (kivy.core.image.ImageData attribute), 290  
data (kivy.uix.recycleview.datamodel.RecycleDataManager attribute), 501  
data (kivy.uix.recycleview.RecycleView attribute), 500  
data\_model (kivy.uix.recycleview.RecycleViewBehavior attribute), 499  
deactivate() (kivy.modules.console.ConsoleAddon method), 446  
decode\_result() (kivy.network.urlrequest.UrlRequest method), 455  
default\_size (kivy.uix.recyclelayout.RecycleLayout attribute), 585  
default\_tab (kivy.uix.tabbedpanel.TabbedPanel attribute), 634  
default\_tab\_cls (kivy.uix.tabbedpanel.TabbedPanel attribute), 634  
default\_tab\_content (kivy.uix.tabbedpanel.TabbedPanel attribute), 634  
default\_tab\_text (kivy.uix.tabbedpanel.TabbedPanel attribute), 634  
delete() (kivy.storage.AbstractStore method), 460  
delete\_selection() (kivy.uix.textinput.TextInput method), 641  
delete\_word\_left() (kivy.uix.behaviors.emacs.Emacs method), 484  
delete\_word\_left() (kivy.uix.behaviors.EmacsBehavior method), 472  
delete\_word\_right() (kivy.uix.behaviors.emacs.Emacs method), 484  
delete\_word\_right() (kivy.uix.behaviors.EmacsBehavior method), 472  
density() (kivy.metrics.MetricsBase method), 242  
depack() (kivy.input MotionEvent method), 398  
depack() (kivy.input.motionevent MotionEvent method), 411  
deprecated() (in module kivy.utils), 266  
desc (kivy.uix.settings.SettingItem attribute), 615  
deselect() (kivy.uix.listview.SelectableView method), 576  
deselect() (kivy.uix.selectableview.SelectableView method), 611  
deselect\_node() (kivy.uix.behaviors.compoundselection.CompoundSelection method), 477  
deselect\_node() (kivy.uix.behaviors.CompoundSelection method), 470  
deselect\_node() (kivy.uix.treeview.TreeView method), 650  
deselected\_color (kivy.uix.listview.CompositeListItem attribute), 577  
deselected\_color (kivy.uix.listview.ListItemButton attribute), 576  
destroy\_settings() (kivy.app.App method), 197  
detach\_recycleview() (kivy.uix.recycleview.datamodel.RecycleDataManagerBehavior method), 500  
detach\_recycleview() (kivy.uix.recycleview.views.RecycleDataAdapter method), 503  
device (kivy.input.motionevent.MotionEvent attribute), 411  
DictAdapter (class in kivy.adapters.dictadapter), 276  
DictProperty (class in kivy.properties), 261  
DictStore (class in kivy.storage.dictstore), 461  
difference() (in module kivy.utils), 266  
direction (kivy.uix.carousel.Carousel attribute), 524  
direction (kivy.uix.screenmanager.SlideTransition attribute), 605  
directory (kivy.app.App attribute), 198  
dirselect (kivy.uix.filechooser.FileChooserController attribute), 542  
dirselect (kivy.uix.settings.SettingPath attribute), 616  
disabled (kivy.uix.settings.SettingItem attribute), 615  
disabled (kivy.uix.widget.Widget attribute), 669  
disabled\_color (kivy.uix.label.Label attribute), 560  
disabled\_foreground\_color (kivy.uix.textinput.TextInput attribute), 641  
disabled\_outline\_color (kivy.uix.label.Label attribute), 560  
dismiss() (kivy.uix.dropdown.DropDown method), 532  
dismiss() (kivy.uix.modalview.ModalView method), 580  
dismiss\_on\_select (kivy.uix.dropdown.DropDown attribute), 532  
dispatch() (kivy.event.EventDispatcher method), 227  
dispatch() (kivy.lib.osc.OSC.CallbackManager method), 438  
dispatch() (kivy.properties.Property method), 257  
dispatch\_input() (kivy.base.EventLoopBase method), 238  
display\_border (kivy.graphics.vertex\_instructions.BorderImage attribute), 389  
display\_settings() (kivy.app.App method), 198

distance() (kivy.input MotionEvent method), 398  
distance() (kivy.input.motionevent MotionEvent method), 411  
distance() (kivy.vector.Vector method), 269  
distance2() (kivy.vector.Vector method), 269  
divider (kivy.uix.listview.ListView attribute), 577  
divider\_height (kivy.uix.listview.ListView attribute), 577  
do\_backspace() (kivy.uix.textinput.TextInput method), 641  
do\_collide\_after\_children (kivy.uix.scatter.Scatter attribute), 595  
do\_cursor\_movement()  
    (kivy.uix.textinput.TextInput method), 641  
do\_default\_tab (kivy.uix.tabbedpanel.TabbedPanel attribute), 634  
do\_layout() (kivy.uix.layout.Layout method), 567  
do\_redo() (kivy.uix.textinput.TextInput method), 641  
do\_rotation (kivy.uix.scatter.Scatter attribute), 595  
do\_scale (kivy.uix.scatter.Scatter attribute), 596  
do\_scroll (kivy.uix.scrollview.ScrollView attribute), 608  
do\_scroll\_x (kivy.uix.scrollview.ScrollView attribute), 608  
do\_scroll\_y (kivy.uix.scrollview.ScrollView attribute), 608  
do\_translation (kivy.uix.scatter.Scatter attribute), 596  
do\_translation\_x (kivy.uix.scatter.Scatter attribute), 596  
do\_translation\_y (kivy.uix.scatter.Scatter attribute), 596  
do\_undo() (kivy.uix.textinput.TextInput method), 642  
docked (kivy.uix.vkeyboard.VKeyboard attribute), 662  
document\_root (kivy.uix.rst.RstDocument attribute), 591  
dontListen() (in module kivy.lib.osc.oscAPI), 439  
dot() (kivy.vector.Vector method), 269  
dot\_product() (kivy.gesture.Gesture method), 234  
double\_tap\_time (kivy.input.motionevent MotionEvent attribute), 411  
dp() (in module kivy.metrics), 242  
dpi() (kivy.core.window.WindowBase method), 303  
dpi() (kivy.metrics.MetricsBase method), 242  
dpi\_rounded() (kivy.metrics.MetricsBase method), 242  
dpos (kivy.input MotionEvent attribute), 398  
dpos (kivy.input.motionevent MotionEvent attribute), 411  
drag\_distance (kivy.uix.behaviors.drag.DragBehavior attribute), 482  
drag\_rect\_height (kivy.uix.behaviors.drag.DragBehavior attribute), 483  
drag\_rect\_width (kivy.uix.behaviors.drag.DragBehavior attribute), 483  
drag\_rect\_x (kivy.uix.behaviors.drag.DragBehavior attribute), 483  
drag\_rect\_y (kivy.uix.behaviors.drag.DragBehavior attribute), 483  
drag\_rectangle (kivy.uix.behaviors.drag.DragBehavior attribute), 483  
drag\_threshold (kivy.effects.scroll.ScrollEffect attribute), 320  
drag\_timeout (kivy.uix.behaviors.drag.DragBehavior attribute), 483  
DragBehavior (class in kivy.uix.behaviors), 469  
DragBehavior (class in kivy.uix.behaviors.drag), 482  
draw() (kivy.graphics.Canvas method), 327  
draw()  
    (kivy.graphics.instructions.Canvas method), 347  
DropDown (class in kivy.uix.dropdown), 531  
dropdown\_cls (kivy.uix.spinner.Spinner attribute), 623  
dropdown\_width (kivy.uix.actionbar.ActionGroup attribute), 511  
dsx (kivy.input.motionevent MotionEvent attribute), 411  
dsy (kivy.input.motionevent MotionEvent attribute), 411  
dsz (kivy.input.motionevent MotionEvent attribute), 411  
duration (kivy.animation.Animation attribute), 182  
duration (kivy.core.video.VideoBase attribute), 299  
duration (kivy.uix.screenmanager.FallOutTransition attribute), 605  
duration (kivy.uix.screenmanager.RiseInTransition attribute), 605  
duration (kivy.uix.screenmanager.TransitionBase attribute), 603  
duration (kivy.uix.video.Video attribute), 653  
duration (kivy.uix.videoplayer.VideoPlayer attribute), 657  
duration (kivy.uix.videoplayer.VideoPlayerAnnotation attribute), 659  
dx (kivy.input.motionevent MotionEvent attribute), 411  
dy (kivy.input.motionevent MotionEvent attribute), 411  
dz (kivy.input.motionevent MotionEvent attribute), 411

E

edge\_damping (kivy.effects.dampedscroll.DampedScrollEffect

attribute), 317  
 effect\_cls (kivy.uix.scrollview.ScrollView attribute), 609  
 effect\_x (kivy.uix.scrollview.ScrollView attribute), 609  
 effect\_y (kivy.uix.scrollview.ScrollView attribute), 609  
 EffectBase (class in kivy.uix.effectwidget), 535  
 effects (kivy.uix.effectwidget.EffectWidget attribute), 535  
 EffectWidget (class in kivy.uix.effectwidget), 534  
 element\_count (kivy.graphics.tesselator.Tesselator attribute), 376  
 Ellipse (class in kivy.graphics), 329  
 Ellipse (class in kivy.graphics.vertex\_instructions), 389  
 ellipse (kivy.graphics.Line attribute), 335  
 ellipse (kivy.graphics.vertex\_instructions.Line attribute), 392  
 ellipsis\_options (kivy.uix.label.Label attribute), 561  
 EmacsBehavior (class in kivy.uix.behaviors), 472  
 EmacsBehavior (class in kivy.uix.behaviors.emacs), 484  
 ensure\_window() (kivy.base.EventLoopBase method), 238  
 entry\_released() (kivy.uix.filechooser.FileChooserController method), 542  
 entry\_touched() (kivy.uix.filechooser.FileChooserController method), 542  
 eos (kivy.uix.video.Video attribute), 654  
 error (kivy.network.urlrequest.UrlRequest attribute), 455  
 error\_image (kivy.loader.LoaderBase attribute), 203  
 escape\_markup() (in module kivy.utils), 267  
 even\_color (kivy.uix.treeview.TreeViewNode attribute), 652  
 EventDispatcher (class in kivy.event), 224  
 EventLoop (in module kivy.base), 237  
 EventLoopBase (class in kivy.base), 237  
 events() (kivy.event.EventDispatcher method), 227  
 ExceptionHandler (class in kivy.base), 239  
 ExceptionManager (in module kivy.base), 239  
 ExceptionManagerBase (class in kivy.base), 239  
 exists() (kivy.storage.AbstractStore method), 460  
 exit() (kivy.base.EventLoopBase method), 238  
 export\_gesture() (kivy.multistroke.Recognizer method), 244  
 export\_to\_png() (kivy.uix.widget.Widget method), 669

F

Factory (in module kivy.factory), 232  
 FadeTransition (class in kivy.uix.screenmanager), 605

FallOutTransition (class in kivy.uix.screenmanager), 605  
 fbind() (kivy.event.EventDispatcher method), 227  
 fbind() (kivy.event.Observable method), 231  
 fbind() (kivy.lang.builder.Observable method), 432  
 fbind() (kivy.lang.Observable method), 429  
 fbind() (kivy.properties.Property method), 257  
 Fbo (class in kivy.graphics), 330  
 Fbo (class in kivy.graphics.fbo), 355  
 fbo (kivy.uix.effectwidget.EffectBase attribute), 535  
 fbo\_list (kivy.uix.effectwidget.EffectWidget attribute), 535  
 file\_encodings (kivy.uix.filechooser.FileChooserController attribute), 542  
 file\_system (kivy.uix.filechooser.FileChooserController attribute), 543  
 FileChooser (class in kivy.uix.filechooser), 541  
 FileChooserController (class in kivy.uix.filechooser), 542  
 FileChooserIconLayout (class in kivy.uix.filechooser), 541  
 FileChooserIconView (class in kivy.uix.filechooser), 541  
 FileChooserListLayout (class in kivy.uix.filechooser), 541  
 FileChooserListView (class in kivy.uix.filechooser), 541  
 FileChooserProgressBase (class in kivy.uix.filechooser), 544  
 filename (kivy.atlas.Atlas attribute), 207  
 filename (kivy.core.audio.Sound attribute), 284  
 filename (kivy.core.image.Image attribute), 288  
 filename (kivy.core.video.VideoBase attribute), 299  
 filename (kivy.graphics.svg.Svg attribute), 374  
 filename (kivy.input.recorder.Recorder attribute), 409  
 files (kivy.uix.filechooser.FileChooserController attribute), 543  
 FileSystemAbstract (class in kivy.uix.filechooser), 545  
 FileSystemLocal (class in kivy.uix.filechooser), 545  
 filter() (kivy.multistroke.Recognizer method), 245  
 filter\_dirs (kivy.uix.filechooser.FileChooserController attribute), 543  
 filters (kivy.uix.filechooser.FileChooserController attribute), 543  
 find() (kivy.gesture.GestureDatabase method), 234  
 find() (kivy.storage.AbstractStore method), 460  
 find\_colliding\_gesture() (kivy.uix.gesturesurface.GestureSurface method), 548  
 find\_double\_tap() (kivy.input.postproc.doubletap.InputPostprocD

method), 400  
find\_triple\_tap() (kivy.input.postproc.tripletap.InputPostproc method), 401  
flip() (kivy.core.window.WindowBase method), 304  
flip\_horizontal() (kivy.graphics.texture.Texture method), 381  
flip\_vertical (kivy.core.image.ImageData attribute), 290  
flip\_vertical() (kivy.graphics.texture.Texture method), 381  
FloatLayout (class in kivy.uix.floatlayout), 546  
fmt (kivy.core.image.ImageData attribute), 290  
focus (kivy.core.window.WindowBase attribute), 304  
focus (kivy.uix.behaviors.focus.FocusBehavior attribute), 485  
focus\_next (kivy.uix.behaviors.focus.FocusBehavior attribute), 486  
focus\_previous (kivy.uix.behaviors.focus.FocusBehavior attribute), 486  
FocusBehavior (class in kivy.uix.behaviors), 469  
FocusBehavior (class in kivy.uix.behaviors.focus), 485  
focused (kivy.uix.behaviors.focus.FocusBehavior attribute), 486  
font\_blended (kivy.uix.label.Label attribute), 561  
font\_hinting (kivy.uix.label.Label attribute), 561  
font\_kerning (kivy.uix.label.Label attribute), 561  
font\_name (kivy.uix.colorpicker.ColorPicker attribute), 529  
font\_name (kivy.uix.label.Label attribute), 561  
font\_name (kivy.uix.textinput.TextInput attribute), 642  
font\_size (kivy.uix.label.Label attribute), 562  
font\_size (kivy.uix.textinput.TextInput attribute), 642  
font\_size (kivy.uix.vkeyboard.VKeyboard attribute), 662  
fontid (kivy.core.text.LabelBase attribute), 293  
fontscale() (kivy.metrics.MetricsBase method), 242  
foreground\_color (kivy.uix.textinput.TextInput attribute), 642  
fork() (kivy.uix.behaviors.knspase.KNSpace method), 492  
frames (kivy.clock.ClockBaseBehavior attribute), 216  
frames\_displayed (kivy.clock.ClockBaseBehavior attribute), 216  
frametime (kivy.clock.ClockBaseBehavior attribute), 216  
free (kivy.clock.FreeClockEvent attribute), 214  
FreeClockEvent (class in kivy.clock), 214  
friction (kivy.effects.kinetic.KineticEffect attribute), 318  
fs (kivy.graphics.shader.Shader attribute), 371  
PostprocTripleTap (kivy.input.postproc.tripletap.Postproc method), 401  
ShaderTransition (kivy.core.window.WindowBase attribute), 604  
fullscreen (kivy.core.window.WindowBase attribute), 304  
fullscreen (kivy.uix.videoplayer.VideoPlayer attribute), 657  
funbind() (kivy.event.EventDispatcher method), 229  
funbind() (kivy.event.Observable method), 231  
funbind() (kivy.lang.builder.Observable method), 432  
funbind() (kivy.lang.Observable method), 429  
funbind() (kivy.properties.Property method), 257  
func\_op (kivy.graphics.stencil\_instructions.StencilUse attribute), 373  
func\_op (kivy.graphics.StencilUse attribute), 341  
FXAAEffect (class in kivy.uix.effectwidget), 536

**G**

g (kivy.graphics.ClearColor attribute), 343  
g (kivy.graphics.Color attribute), 329  
g (kivy.graphics.context\_instructions.Color attribute), 351  
g (kivy.graphics.gl\_instructions.ClearColor attribute), 357  
g (kivy.uix.colorpicker.ColorWheel attribute), 530  
garden\_system\_dir (in module kivy.garden), 322  
Gesture (class in kivy.gesture), 233  
gesture\_to\_str() (kivy.gesture.GestureDatabase method), 234  
GestureContainer (class in kivy.uix.gesturesurface), 548  
GestureDatabase (class in kivy.gesture), 234  
GestureStroke (class in kivy.gesture), 234  
GestureSurface (class in kivy.uix.gesturesurface), 547  
get() (kivy.cache.Cache static method), 208  
get() (kivy.graphics.transformation.Matrix method), 383  
get() (kivy.input.factory.MotionEventFactory static method), 414  
get() (kivy.input.MotionEventFactory static method), 399  
get() (kivy.properties.Property method), 257  
get() (kivy.storage.AbstractStore method), 460  
get\_angle\_similarity() (kivy.multistroke.Candidate method), 251  
get\_application\_config() (kivy.app.App method), 198  
get\_application\_icon() (kivy.app.App method), 198  
get\_application\_name() (kivy.app.App method), 198

get\_boottime() (kivy.clock.ClockBaseBehavior method), 216  
get\_cached\_extents() (kivy.core.text.LabelBase method), 293  
get\_callback() (kivy.clock.ClockEvent method), 214  
get\_cls() (kivy.adapters.adapter.Adapter method), 275  
get\_color\_from\_hex() (in module kivy.utils), 266  
get\_configparser() (kivy.config.ConfigParser static method), 223  
get\_connection\_for\_scheme()  
    (kivy.network.urlrequest.UrlRequest method), 455  
get\_current\_context() (in module kivy.context), 224  
get\_cursor\_from\_index()  
    (kivy.uix.textinput.TextInput method), 642  
get\_cursor\_from\_xy()  
    (kivy.uix.textinput.TextInput method), 642  
get\_deps\_all() (in module kivy.tools.packaging.pyinstaller\_hooks), 465  
get\_deps\_minimal() (in module kivy.tools.packaging.pyinstaller\_hooks), 465  
get\_distance() (kivy.multistroke.MultistrokeGesture method), 249  
get\_events() (kivy.clock.CyClockBase method), 215  
get\_extents() (kivy.core.text.LabelBase method), 294  
get\_factory\_modules() (in module kivy.tools.packaging.pyinstaller\_hooks), 466  
get\_focus\_next() (kivy.uix.behaviors.focus.FocusBehavior method), 486  
get\_focus\_next() (kivy.uix.behaviors.FocusBehavior method), 469  
get\_focus\_previous()  
    (kivy.uix.behaviors.FocusBehavior method), 486  
get\_focus\_previous()  
    (kivy.uix.behaviors.FocusBehavior method), 469  
get\_format() (kivy.properties.NumericProperty method), 258  
get\_fps() (kivy.clock.ClockBaseBehavior method), 216  
get\_gesture() (kivy.uix.gesturesurface.GestureSurface method), 548  
get\_group() (kivy.graphics.InstructionGroup method), 332  
get\_group() (kivy.graphics.instructions.InstructionGroup method), 345  
get\_hex\_from\_color() (in module kivy.utils), 266  
get\_hooks() (in module kivy.tools.packaging.pyinstaller\_hooks), 466  
get\_index\_of\_node() (kivy.uix.behaviors.compoundselection.CompoundSelectionBehavior method), 477  
get\_index\_of\_node() (kivy.uix.behaviors.CompoundSelectionBehavior method), 470  
get\_lastaccess() (kivy.cache.Cache static method), 208  
get\_max() (kivy.properties.BoundedNumericProperty method), 260  
get\_min() (kivy.properties.BoundedNumericProperty method), 260  
get\_min\_free\_timeout()  
    (kivy.clock.CyClockBaseFree method), 216  
get\_min\_timeout() (kivy.clock.CyClockBase method), 215  
get\_mipmap() (kivy.core.image.ImageData method), 290  
get\_nice\_size() (kivy.uix.filechooser.FileChooserController method), 543  
get\_node\_at\_pos() (kivy.uixtreeview.TreeView method), 650  
get\_parent\_window() (kivy.uix.widget.Widget method), 670  
get\_pixel\_color() (kivy.graphics.Fbo method), 331  
get\_pixel\_color() (kivy.graphics.fbo.Fbo method), 356  
get\_pos() (kivy.core.audio.Sound method), 284  
get\_property\_observers()  
    (kivy.event.EventDispatcher method), 229  
get\_protractor\_vector()  
    (kivy.multistroke.Candidate method), 251  
get\_random\_color() (in module kivy.utils), 266  
get\_region() (kivy.graphics.texture.Texture method), 381  
get\_resolution() (kivy.clock.CyClockBase method), 215  
get\_rfps() (kivy.clock.ClockBaseBehavior method), 216  
get\_rigid\_rotation() (kivy.gesture.Gesture method), 234  
get\_root\_window() (kivy.uix.widget.Widget method), 670  
get\_running\_app() (kivy.app.App static method), 198  
get\_score() (kivy.gesture.Gesture method), 234  
get\_screen() (kivy.uix.screenmanager.ScreenManager method), 602

get_selectable_nodes()	kivy.uix.behaviors.compoundselection.CompoundSelectionBehavior (in module kivy.uix.behaviors.compoundselection), 478	kivy.graphics.opengl_utils), 368
get_selectable_nodes()	(kivy.uix.behaviors.CompoundSelectionBehavior method), 471	kivy.graphics.opengl_utils), 368
get_start_unit_vector()	(kivy.multistroke.Candidate method), 251	gl_has_texture_native_format() (in module kivy.graphics.opengl_utils), 368
get_system_fonts_dir()	(kivy.core.text.LabelBase static method), 294	gl_register_get_size() (in module kivy.graphics.opengl_utils), 368
get_time()	(kivy.clock.ClockBaseBehavior method), 217	glActiveTexture() (in module kivy.graphics.opengl), 359
get_timestamp()	(kivy.cache.Cache static method), 208	glAttachShader() (in module kivy.graphics.opengl), 359
get_value()	(kivy.uix.settings.SettingsPanel method), 614	glBindAttribLocation() (in module kivy.graphics.opengl), 359
get_vectors()	(kivy.uix.gesturesurface.GestureContainer method), 549	glBindBuffer() (in module kivy.graphics.opengl), 359
get_view()	(kivy.uix.recycleview.views.RecycleDataAggregation method), 503	glBindFramebuffer() (in module kivy.graphics.opengl), 359
get_view_index_at()	(kivy.uix.recycleview.layout.RecycleGridLayout method), 502	glBindRenderbuffer() (in module kivy.graphics.opengl), 359
get_visible_view()	(kivy.uix.recycleview.views.RecycleGrid method), 503	glBindTexture() (in module kivy.graphics.opengl), 359
get_widgets()	(kivy.uix.behaviors.togglebutton.ToggleButtonBehavior static method), 494	glBlendEquation() (in module kivy.graphics.opengl), 359
get_widgets()	(kivy.uix.behaviors.ToggleButtonBehavior static method), 469	glBlendEquationSeparate() (in module kivy.graphics.opengl), 359
get_window_matrix()	(kivy.uix.widget.Widget method), 670	glBlendFunc() (in module kivy.graphics.opengl), 359
getBinary()	(kivy.lib.osc.OSC.OSCMessage method), 438	glBlendFuncSeparate() (in module kivy.graphics.opengl), 359
getdefault()	(kivy.config.ConfigParser method), 223	glBufferData() (in module kivy.graphics.opengl), 359
getdefaultint()	(kivy.config.ConfigParser method), 223	glBufferSubData() (in module kivy.graphics.opengl), 359
getsize()	(kivy.uix.filechooser.FileSystemAbstract method), 545	glCheckFramebufferStatus() (in module kivy.graphics.opengl), 359
getter()	(kivy.event.EventDispatcher method), 229	glClear() (in module kivy.graphics.opengl), 359
gl_get_extensions()	(in module kivy.graphics.opengl_utils), 367	glClearColor() (in module kivy.graphics.opengl), 359
gl_get_texture_formats()	(in module kivy.graphics.opengl_utils), 368	glClearStencil() (in module kivy.graphics.opengl), 360
gl_get_version()	(in module kivy.graphics.opengl_utils), 368	glColorMask() (in module kivy.graphics.opengl), 360
gl_get_version_major()	(in module kivy.graphics.opengl_utils), 368	glCompileShader() (in module kivy.graphics.opengl), 360
gl_get_version_minor()	(in module kivy.graphics.opengl_utils), 368	glCompressedTexImage2D() (in module kivy.graphics.opengl), 360
gl_has_capability()	(in module kivy.graphics.opengl_utils), 367	glCompressedTexSubImage2D() (in module kivy.graphics.opengl), 360
gl_has_extension()	(in module kivy.graphics.opengl_utils), 367	glCopyTexImage2D() (in module kivy.graphics.opengl), 360
gl_has_texture_conversion()	(in module kivy.graphics.opengl_utils), 367	glCopyTexSubImage2D() (in module kivy.graphics.opengl), 360
		glCreateProgram() (in module kivy.graphics.opengl), 360

glCreateShader()	(in module kivy.graphics.opengl),	360	module	glGetAttribLocation()	(in module kivy.graphics.opengl),	361	module
glCullFace()	(in module kivy.graphics.opengl),	360	module	glGetBooleanv()	(in module kivy.graphics.opengl),	362	module
glDeleteBuffers()	(in module kivy.graphics.opengl),	360	module	glGetBufferParameteriv()	(in module kivy.graphics.opengl),	362	module
glDeleteFramebuffers()	(in module kivy.graphics.opengl),	360	module	glGetError()	(in module kivy.graphics.opengl),	362	module
glDeleteProgram()	(in module kivy.graphics.opengl),	360	module	glGetFloatv()	(in module kivy.graphics.opengl),	362	module
glDeleteRenderbuffers()	(in module kivy.graphics.opengl),	360	module	glGetFramebufferAttachmentParameteriv()	(in module kivy.graphics.opengl),	362	module
glDeleteShader()	(in module kivy.graphics.opengl),	360	module	glGetIntegerv()	(in module kivy.graphics.opengl),	362	module
glDeleteTextures()	(in module kivy.graphics.opengl),	360	module	glGetProgramInfoLog()	(in module kivy.graphics.opengl),	362	module
glDepthFunc()	(in module kivy.graphics.opengl),	360	module	glGetProgramiv()	(in module kivy.graphics.opengl),	362	module
glDepthMask()	(in module kivy.graphics.opengl),	360	module	glGetRenderbufferParameteriv()	(in module kivy.graphics.opengl),	362	module
glDetachShader()	(in module kivy.graphics.opengl),	360	module	glGetShaderInfoLog()	(in module kivy.graphics.opengl),	362	module
glDisable()	(in module kivy.graphics.opengl),	360	module	glGetShaderiv()	(in module kivy.graphics.opengl),	362	module
glDisableVertexAttribArray()	(in module kivy.graphics.opengl),	360	module	glGetShaderPrecisionFormat()	(in module kivy.graphics.opengl),	362	module
glDrawArrays()	(in module kivy.graphics.opengl),	360	module	glGetShaderSource()	(in module kivy.graphics.opengl),	362	module
glDrawElements()	(in module kivy.graphics.opengl),	361	module	glGetString()	(in module kivy.graphics.opengl),	362	module
glEnable()	(in module kivy.graphics.opengl),	361	module	glGetTexParameterfv()	(in module kivy.graphics.opengl),	363	module
glEnableVertexAttribArray()	(in module kivy.graphics.opengl),	361	module	glGetTexParameteriv()	(in module kivy.graphics.opengl),	363	module
glFinish()	(in module kivy.graphics.opengl),	361	module	glGetUniformfv()	(in module kivy.graphics.opengl),	363	module
glFlush()	(in module kivy.graphics.opengl),	361	module	glGetUniformiv()	(in module kivy.graphics.opengl),	363	module
glFramebufferRenderbuffer()	(in module kivy.graphics.opengl),	361	module	glGetUniformLocation()	(in module kivy.graphics.opengl),	363	module
glFramebufferTexture2D()	(in module kivy.graphics.opengl),	361	module	glGetVertexAttribfv()	(in module kivy.graphics.opengl),	363	module
glFrontFace()	(in module kivy.graphics.opengl),	361	module	glGetVertexAttribiv()	(in module kivy.graphics.opengl),	363	module
glGenBuffers()	(in module kivy.graphics.opengl),	361	module	glGetVertexAttribPointerv()	(in module kivy.graphics.opengl),	363	module
glGenerateMipmap()	(in module kivy.graphics.opengl),	361	module	glHint()	(in module kivy.graphics.opengl),	363	module
glGenFramebuffers()	(in module kivy.graphics.opengl),	361	module	glIsBuffer()	(in module kivy.graphics.opengl),	363	module
glGenRenderbuffers()	(in module kivy.graphics.opengl),	361	module	glIsEnabled()	(in module kivy.graphics.opengl),	363	module
glGenTextures()	(in module kivy.graphics.opengl),	361	module	glIsFramebuffer()	(in module kivy.graphics.opengl),	363	module
glGetActiveAttrib()	(in module kivy.graphics.opengl),	361	module	glIsProgram()	(in module kivy.graphics.opengl),	363	module
glGetActiveUniform()	(in module kivy.graphics.opengl),	361	module	glIsRenderbuffer()	(in module kivy.graphics.opengl),	363	module
glGetAttachedShaders()	(in module kivy.graphics.opengl),	361	module				

kivy.graphics.opengl), 363  
glIsShader() (in module kivy.graphics.opengl), 363  
glIsTexture() (in module kivy.graphics.opengl), 363  
glLineWidth() (in module kivy.graphics.opengl), 363  
glLinkProgram() (in module kivy.graphics.opengl), 363  
glPixelStorei() (in module kivy.graphics.opengl), 363  
glPolygonOffset() (in module kivy.graphics.opengl), 363  
glReadPixels() (in module kivy.graphics.opengl), 364  
glReleaseShaderCompiler() (in module kivy.graphics.opengl), 364  
glRenderbufferStorage() (in module kivy.graphics.opengl), 364  
glSampleCoverage() (in module kivy.graphics.opengl), 364  
glScissor() (in module kivy.graphics.opengl), 364  
glShaderBinary() (in module kivy.graphics.opengl), 364  
glShaderSource() (in module kivy.graphics.opengl), 364  
glsl (kivy.uix.effectwidget.EffectBase attribute), 535  
glStencilFunc() (in module kivy.graphics.opengl), 364  
glStencilFuncSeparate() (in module kivy.graphics.opengl), 364  
glStencilMask() (in module kivy.graphics.opengl), 364  
glStencilMaskSeparate() (in module kivy.graphics.opengl), 364  
glStencilOp() (in module kivy.graphics.opengl), 364  
glStencilOpSeparate() (in module kivy.graphics.opengl), 364  
glTexImage2D() (in module kivy.graphics.opengl), 364  
glTexParameterf() (in module kivy.graphics.opengl), 364  
glTexParameterfv() (in module kivy.graphics.opengl), 364  
glTexParameteri() (in module kivy.graphics.opengl), 364  
glTexParameteriv() (in module kivy.graphics.opengl), 365  
glTexSubImage2D() (in module kivy.graphics.opengl), 365  
glUniform1f() (in module kivy.graphics.opengl), 365  
glUniform1fv() (in module kivy.graphics.opengl), 365  
glUniform1i() (in module kivy.graphics.opengl), 365  
glUniform1iv() (in module kivy.graphics.opengl), 365  
glUniform2f() (in module kivy.graphics.opengl), 365  
glUniform2fv() (in module kivy.graphics.opengl), 365  
glUniform2i() (in module kivy.graphics.opengl), 365  
glUniform2iv() (in module kivy.graphics.opengl), 365  
glUniform3f() (in module kivy.graphics.opengl), 365  
glUniform3fv() (in module kivy.graphics.opengl), 365  
glUniform3i() (in module kivy.graphics.opengl), 365  
glUniform3iv() (in module kivy.graphics.opengl), 366  
glUniform4f() (in module kivy.graphics.opengl), 366  
glUniform4fv() (in module kivy.graphics.opengl), 366  
glUniform4i() (in module kivy.graphics.opengl), 366  
glUniform4iv() (in module kivy.graphics.opengl), 366  
glUniformMatrix2fv() (in module kivy.graphics.opengl), 366  
glUniformMatrix3fv() (in module kivy.graphics.opengl), 366  
glUniformMatrix4fv() (in module kivy.graphics.opengl), 366  
glUseProgram() (in module kivy.graphics.opengl), 366  
glValidateProgram() (in module kivy.graphics.opengl), 366  
glVertexAttrib1f() (in module kivy.graphics.opengl), 366  
glVertexAttrib1fv() (in module kivy.graphics.opengl), 366  
glVertexAttrib2f() (in module kivy.graphics.opengl), 367  
glVertexAttrib2fv() (in module kivy.graphics.opengl), 367  
glVertexAttrib3f() (in module kivy.graphics.opengl), 367  
glVertexAttrib3fv() (in module kivy.graphics.opengl), 367  
glVertexAttrib4f() (in module kivy.graphics.opengl), 367  
glVertexAttrib4fv() (in module kivy.graphics.opengl), 367  
glVertexAttribPointer() (in module kivy.graphics.opengl), 367

kivy.graphics.opengl), 367  
 glViewport() (in module kivy.graphics.opengl), 367  
 goto() (kivy.uix.rst.RstDocument method), 591  
 goto\_node() (kivy.uix.behaviors.compoundselection.CompoundSelectionBehavior method), 478  
 goto\_node() (kivy.uix.behaviors.CompoundSelectionBehavior method), 471  
 goto\_view() (kivy.uix.recycleview.layout.RecycleLayoutManager method), 502  
 grab() (kivy.input MotionEvent method), 398  
 grab() (kivy.input.motionevent MotionEvent method), 411  
 grab\_current (kivy.input.motionevent MotionEvent attribute), 411  
 grab\_mouse() (kivy.core.window.WindowBase method), 304  
 GraphicException (class in kivy.graphics), 331  
 GraphicException (class in kivy.graphics.vertex\_instructions), 395  
 GridLayout (class in kivy.uix.gridlayout), 552  
 GridLayoutException (class in kivy.uix.gridlayout), 553  
 group (kivy.uix.behaviors.togglebutton.ToggleButtonBehavior attribute), 494

**H**

h (kivy.graphics.Color attribute), 329  
 h (kivy.graphics.context\_instructions.Color attribute), 351  
 halign (kivy.uix.label.Label attribute), 562  
 handle() (kivy.lib.osc.OSC.CallbackManager method), 438  
 handle\_exception() (kivy.base.ExceptionHandler method), 239  
 handle\_exception() (kivy.base.ExceptionManagerBase method), 239  
 handle\_image\_left (kivy.uix.textinput.TextInput attribute), 642  
 handle\_image\_middle (kivy.uix.textinput.TextInput attribute), 642  
 handle\_image\_right (kivy.uix.textinput.TextInput attribute), 642  
 handles() (kivy.uix.gesturesurface.GestureContainer method), 549  
 has\_after (kivy.graphics.Canvas attribute), 327  
 has\_after (kivy.graphics.instructions.Canvas attribute), 347  
 has\_before (kivy.graphics.Canvas attribute), 327  
 has\_before (kivy.graphics.instructions.Canvas attribute), 347  
 has\_screen() (kivy.uix.screenmanager.ScreenManager method), 602  
 have\_properties\_to\_animate()

(kivy.animation.Animation method), 182  
 hbar (kivy.uix.scrollview.ScrollView attribute), 609  
 height (kivy.core.image.Image attribute), 288  
 height (kivy.uix.selectionbehavior.SelectionBehaviorData attribute), 290  
 height (kivy.core.window.WindowBase attribute), 304  
 height (kivy.graphics.texture.Texture attribute), 381  
 height (kivy.input.shape.ShapeRect attribute), 414  
 height (kivy.uix.widget.Widget attribute), 670  
 hex\_color (kivy.uix.colorpicker.ColorPicker attribute), 529  
 hexDump() (in module kivy.lib.osc.OSC), 438  
 hide() (kivy.core.window.WindowBase method), 304  
 hide\_keyboard() (kivy.uix.behaviors.focus.FocusBehavior method), 486  
 hide\_keyboard() (kivy.uix.behaviors.FocusBehavior method), 470  
 hide\_root (kivy.uix.treeview.TreeView attribute), 650  
 highlight\_at() (kivy.modules.console.ConsoleBehavior method), 445  
 hint\_text (kivy.uix.textinput.TextInput attribute), 643  
 hint\_text\_color (kivy.uix.textinput.TextInput attribute), 643  
 hookspath() (in module kivy.tools.packaging.pyinstaller\_hooks), 466  
 HorizontalBlurEffect (class in kivy.uix.effectwidget), 536  
 hsv (kivy.graphics.Color attribute), 329  
 hsv (kivy.graphics.context\_instructions.Color attribute), 351  
 hsv (kivy.uix.colorpicker.ColorPicker attribute), 529

**I**

icon (kivy.app.App attribute), 199  
 icon (kivy.core.window.WindowBase attribute), 304  
 icon (kivy.uix.actionbar.ActionButton attribute), 511  
 icon (kivy.uix.actionbar.ActionToggleButton attribute), 511  
 id (kivy.graphics.texture.Texture attribute), 381  
 id (kivy.input.motionevent MotionEvent attribute), 412  
 id (kivy.uix.widget.Widget attribute), 670  
 identity() (kivy.graphics.transformation.Matrix method), 384  
 idle() (kivy.base.EventLoopBase method), 238  
 idle() (kivy.clock.ClockBaseBehavior method), 217

ids (kivy.uix.widget.Widget attribute), 670  
ignore\_perpendicular\_swipes  
    (kivy.uix.carousel.Carousel attribute), 524  
ignored\_touch (kivy.uix.behaviors.focus.FocusBehavior attribute), 486  
Image (class in kivy.core.image), 287  
Image (class in kivy.uix.image), 554  
image (kivy.core.image.Image attribute), 288  
image() (kivy.loader.LoaderBase method), 203  
image\_loading (kivy.uix.videoplayer.VideoPlayer attribute), 657  
image\_overlay\_play (kivy.uix.videoplayer.VideoPlayer attribute), 657  
image\_pause (kivy.uix.videoplayer.VideoPlayer attribute), 657  
image\_play (kivy.uix.videoplayer.VideoPlayer attribute), 658  
image\_ratio (kivy.uix.image.Image attribute), 554  
image\_stop (kivy.uix.videoplayer.VideoPlayer attribute), 658  
image\_volumehigh (kivy.uix.videoplayer.VideoPlayer attribute), 658  
image\_volumelow (kivy.uix.videoplayer.VideoPlayer attribute), 658  
image\_volumemedium  
    (kivy.uix.videoplayer.VideoPlayer attribute), 658  
image\_volumemuted  
    (kivy.uix.videoplayer.VideoPlayer attribute), 658  
ImageData (class in kivy.core.image), 290  
import\_gesture() (kivy.multistroke.Recognizer method), 246  
important (kivy.uix.actionbar.ActionItem attribute), 510  
in\_back() (kivy.animation.AnimationTransition static method), 183  
in\_bbox() (kivy.vector.Vector static method), 270  
in\_bounce() (kivy.animation.AnimationTransition static method), 183  
in\_circ() (kivy.animation.AnimationTransition static method), 183  
in\_cubic() (kivy.animation.AnimationTransition static method), 184  
in\_elastic() (kivy.animation.AnimationTransition static method), 184  
in\_expo() (kivy.animation.AnimationTransition static method), 184  
in\_out\_back() (kivy.animation.AnimationTransition static method), 184  
in\_out\_bounce() (kivy.animation.AnimationTransition static method), 185  
in\_out\_circ() (kivy.animation.AnimationTransition static method), 185  
in\_out\_cubic() (kivy.animation.AnimationTransition static method), 185  
in\_out\_elastic() (kivy.animation.AnimationTransition static method), 185  
in\_out\_expo() (kivy.animation.AnimationTransition static method), 186  
in\_out\_quad() (kivy.animation.AnimationTransition static method), 186  
in\_out\_quart() (kivy.animation.AnimationTransition static method), 186  
in\_out\_quint() (kivy.animation.AnimationTransition static method), 186  
in\_out\_sine() (kivy.animation.AnimationTransition static method), 187  
in\_quad() (kivy.animation.AnimationTransition static method), 187  
in\_quart() (kivy.animation.AnimationTransition static method), 187  
in\_quint() (kivy.animation.AnimationTransition static method), 187  
in\_sine() (kivy.animation.AnimationTransition static method), 188  
inch() (in module kivy.metrics), 242  
indent\_level (kivy.uixtreeview.TreeView attribute), 650  
indent\_start (kivy.uixtreeview.TreeView attribute), 650  
index (kivy.core.camera.CameraBase attribute), 286  
index (kivy.uix.camera.Camera attribute), 522  
index (kivy.uix.carousel.Carousel attribute), 524  
index (kivy.uix.filechooser.FileChooserProgressBase attribute), 545  
index (kivy.uix.selectableview.SelectableView attribute), 611  
indices (kivy.graphics.Mesh attribute), 338  
indices (kivy.graphics.vertex\_instructions.Mesh attribute), 395  
init() (in module kivy.lib.osc.oscAPI), 439  
init() (kivy.modules.console.ConsoleAddon method), 446  
init\_camera() (kivy.core.camera.CameraBase method), 286  
init\_gesture() (kivy.uix.gesturesurface.GestureSurface method), 548  
input\_filter (kivy.uix.textinput.TextInput attribute), 643  
input\_type (kivy.uix.behaviors.focus.FocusBehavior attribute), 487  
InputPostprocCalibration (class in kivy.input.postproc.calibration), 399  
InputPostprocDejitter (class in kivy.input.postproc.dejitter), 400  
InputPostprocDoubleTap (class in kivy.input.postproc.doubletap), 400

InputPostprocIgnoreList (class in kivy.input.postproc.ignorelist), 401  
 InputPostprocRetainTouch (class in kivy.input.postproc.retaintouch), 401  
 InputPostprocTripleTap (class in kivy.input.postproc.tripletap), 401  
 insert() (kivy.graphics.InstructionGroup method), 332  
 insert() (kivy.graphics.instructions.InstructionGroup method), 345  
 insert\_text() (kivy.uix.textinput.TextInput method), 643  
 inside\_group (kivy.uix.actionbar.ActionItem attribute), 510  
 inspect\_enabled (kivy.modules.console.Console attribute), 445  
 install\_android() (in module kivy.support), 265  
 install\_gobject\_iteration() (in module kivy.support), 265  
 install\_twisted\_reactor() (in module kivy.support), 265  
 Instruction (class in kivy.graphics), 331  
 Instruction (class in kivy.graphics.instructions), 345  
 InstructionGroup (class in kivy.graphics), 331  
 InstructionGroup (class in kivy.graphics.instructions), 345  
 InteractiveLauncher (class in kivy.interactive), 237  
 interface (kivy.uix.settings.Settings attribute), 614  
 interface\_cls (kivy.uix.settings.Settings attribute), 614  
 InterfaceWithSidebar (class in kivy.uix.settings), 617  
 interpolate() (in module kivy.utils), 266  
 intersection() (in module kivy.utils), 266  
 invalidate() (kivy.uix.recycleview.views.RecycleData method), 503  
 inverse() (kivy.graphics.transformation.Matrix method), 384  
 InvertEffect (class in kivy.uix.effectwidget), 536  
 is\_active (kivy.uix.screenmanager.TransitionBase attribute), 603  
 is\_color\_transparent() (in module kivy.utils), 266  
 is\_dead() (kivy.weakmethod.WeakMethod method), 271  
 is\_dir() (kivy.uix.filechooser.FileSystemAbstract method), 545  
 is\_double\_tap (kivy.input.motionevent.MotionEvent attribute), 412  
 is\_event\_type() (kivy.event.EventDispatcher method), 229  
 is\_finished (kivy.network.urlrequest.UrlRequest attribute), 455  
 is\_focusable (kivy.uix.behaviors.focus.FocusBehavior attribute), 487  
 in is\_hidden() (kivy.uix.filechooser.FileSystemAbstract method), 545  
 in is\_leaf (kivy.uix.treeview.TreeNode attribute), 652  
 in is\_loaded (kivy.uix.treeview.TreeNode attribute), 652  
 is\_manual (kivy.effects.kinetic.KineticEffect attribute), 318  
 is\_mouse\_scrolling (kivy.input.MotionEvent attribute), 398  
 is\_mouse\_scrolling (kivy.input.motionevent.MotionEvent attribute), 412  
 is\_open (kivy.uix.actionbar.ActionGroup attribute), 511  
 is\_open (kivy.uix.spinner.Spinner attribute), 623  
 is\_open (kivy.uix.treeview.TreeNode attribute), 652  
 is\_selected (kivy.adapters.models.SelectableDataItem attribute), 281  
 is\_selected (kivy.uix.selectableview.SelectableView attribute), 611  
 is\_selected (kivy.uix.treeview.TreeNode attribute), 652  
 is\_shortened (kivy.uix.label.Label attribute), 562  
 is\_touch (kivy.input.motionevent.MotionEvent attribute), 412  
 is\_triggered (kivy.clock.ClockEvent attribute), 214  
 is\_triple\_tap (kivy.input.motionevent.MotionEvent attribute), 412  
 isclose() (in module kivy.compat), 218  
 italic (kivy.uix.label.Label attribute), 562  
 item\_strings (kivy.uix.listview.ListView attribute), 578  
 iterate\_all\_nodes() (kivy.uix.treeview.TreeView method), 650  
 Adapter.mipmaps() (kivy.core.image.ImageData method), 290  
 iterate\_open\_nodes() (kivy.uix.treeview.TreeView method), 650

J

joint (kivy.graphics.Line attribute), 335  
 joint (kivy.graphics.vertex\_instructions.Line attribute), 392  
 joint\_precision (kivy.graphics.Line attribute), 335  
 joint\_precision (kivy.graphics.vertex\_instructions.Line attribute), 392

K

keep\_data (kivy.uix.image.Image attribute), 555  
 keep\_ratio (kivy.uix.image.Image attribute), 555  
 keep\_ref (kivy.uix.behaviors.knspase.KNSpace attribute), 492  
 keep\_within\_parent (kivy.uix.splitter.Splitter attribute), 626

key (kivy.uix.settings.SettingItem attribute), 615  
 key\_background\_color  
     (kivy.uix.vkeyboard.VKeyboard  
         tribute), 662  
 key\_background\_down  
     (kivy.uix.vkeyboard.VKeyboard  
         tribute), 663  
 key\_background\_normal  
     (kivy.uix.vkeyboard.VKeyboard  
         tribute), 663  
 key\_bindings (kivy.uix.behaviors.emacs.EmacsBehavior  
     attribute), 484  
 key\_border (kivy.uix.vkeyboard.VKeyboard  
     tribute), 663  
 key\_disabled\_background\_normal  
     (kivy.uix.vkeyboard.VKeyboard  
         tribute), 663  
 key\_margin (kivy.uix.vkeyboard.VKeyboard  
     tribute), 663  
 key\_selection (kivy.uix.recycleview.layout.LayoutSelectionBehavior  
     attribute), 502  
 key\_viewclass (kivy.uix.recycleview.layout.RecycleLayout  
     attribute), 502  
 key\_viewclass (kivy.uix.recycleview.RecycleView  
     attribute), 500  
 Keyboard (class in kivy.core.window), 299  
 keyboard (kivy.uix.behaviors.focus.FocusBehavior  
     attribute), 487  
 keyboard\_anim\_args  
     (kivy.core.window.WindowBase  
         tribute), 304  
 keyboard\_height (kivy.core.window.WindowBase  
     attribute), 305  
 keyboard\_mode (kivy.uix.behaviors.focus.FocusBehavior  
     attribute), 487  
 keyboard\_on\_key\_down()  
     (kivy.uix.behaviors.focus.FocusBehavior  
         method), 488  
 keyboard\_on\_key\_down()  
     (kivy.uix.behaviors.FocusBehavior  
         method), 470  
 keyboard\_on\_key\_up()  
     (kivy.uix.behaviors.focus.FocusBehavior  
         method), 488  
 keyboard\_on\_key\_up()  
     (kivy.uix.behaviors.FocusBehavior  
         method), 470  
 keyboard\_padding (kivy.core.window.WindowBase  
     attribute), 305  
 keyboard\_select (kivy.uix.behaviors.compoundselection.CompoundSelectionBehavior  
     attribute), 478  
 keyboard\_suggestions  
     (kivy.uix.textinput.TextInput  
         attribute), 643  
 keycode\_to\_string() (kivy.core.window.Keyboard  
     method), 300  
 keys() (kivy.storage.AbstractStore method), 460  
 KineticEffect (class in kivy.effects.kinetic), 318  
 kivy (module), 179  
 kivy.adapters (module), 273  
 kivy.adapters.adapter (module), 275  
 kivy.adapters.args\_converters (module), 277  
 kivy.adapters.dictadapter (module), 276  
 kivy.adapters.listadapter (module), 277  
 kivy.adapters.models (module), 280  
 kivy.adapters.simplelistadapter (module), 281  
 kivy.animation (module), 180  
 kivy.app (module), 191  
 kivy.atlas (module), 204  
 kivy.base (module), 237  
 kivy.cache (module), 207  
 kivy.clock (module), 209  
 kivy.compat (module), 218  
 kivy.config (module), 218  
 kivy.core (module), 283  
 kivy.core.camera (module), 285  
 kivy.core.clipboard (module), 286  
 kivy.core.gl (module), 286  
 kivy.core.image (module), 286  
 kivy.core.spelling (module), 290  
 kivy.core.text (module), 291  
 kivy.core.text.markup (module), 297  
 kivy.core.text.text\_layout (module), 294  
 kivy.core.video (module), 298  
 kivy.core.window (module), 299  
 kivy.deps (module), 315  
 kivy.effects (module), 317  
 kivy.effects.dampedscroll (module), 317  
 kivy.effects.kinetic (module), 318  
 kivy.effects.opacityscroll (module), 319  
 kivy.effects.scroll (module), 320  
 kivy.event (module), 224  
 kivy.factory (module), 232  
 kivy.garden (module), 321  
 kivy.geometry (module), 232  
 kivy.gesture (module), 233  
 kivy.graphics (module), 323  
 kivy.graphics.cgl (module), 349  
 kivy.graphics.compiler (module), 358  
 kivy.graphics.context (module), 354  
 kivy.graphics.context\_instructions (module), 350  
 kivy.graphics.fbo (module), 354  
 kivy.graphics.selection\_behavior (module), 357  
 kivy.graphics.instructions (module), 345  
 kivy.graphics.opengl (module), 359  
 kivy.graphics.opengl\_utils (module), 367  
 kivy.graphics.scissor\_instructions (module), 369  
 kivy.graphics.shader (module), 370

kivy.graphics.stencil\_instructions (module), 371  
kivy.graphics.svg (module), 373  
kivy.graphics.tesselator (module), 374  
kivy.graphics.texture (module), 377  
kivy.graphics.transformation (module), 383  
kivy.graphics.vertex\_instructions (module), 386  
kivy.input (module), 397  
kivy.input.factory (module), 414  
kivy.input.motionevent (module), 409  
kivy.input.postproc (module), 399  
kivy.input.postproc.calibration (module), 399  
kivy.input.postproc.dejitter (module), 400  
kivy.input.postproc.doubletap (module), 400  
kivy.input.postproc.ignorelist (module), 401  
kivy.input.postproc.retaintouch (module), 401  
kivy.input.postproc.tripletap (module), 401  
kivy.input.provider (module), 414  
kivy.input.providers (module), 402  
kivy.input.providers.androidjoystick (module), 402  
kivy.input.providers.hidinput (module), 403  
kivy.input.providers.leapfinger (module), 402  
kivy.input.providers.linuxwacom (module), 405  
kivy.input.providers.mactouch (module), 405  
kivy.input.providers.mouse (module), 402  
kivy.input.providers.mtdev (module), 404  
kivy.input.providers.probesysfs (module), 402  
kivy.input.providers.tuio (module), 406  
kivy.input.providers.wm\_common (module), 402  
kivy.input.providers.wm\_pen (module), 405  
kivy.input.providers.wm\_touch (module), 405  
kivy.input.recorder (module), 407  
kivy.input.shape (module), 414  
kivy.interactive (module), 234  
kivy.lang (module), 417  
kivy.lang.builder (module), 432  
kivy.lang.parser (module), 434  
kivy.lib (module), 437  
kivy.lib.ddsfile (module), 439  
kivy.lib.gstplayer (module), 437  
kivy.lib.mtdev (module), 440  
kivy.lib.osc (module), 437  
kivy.lib.osc.OSC (module), 438  
kivy.lib.osc.oscAPI (module), 438  
kivy.loader (module), 202  
kivy.logger (module), 239  
kivy.metrics (module), 240  
kivy.modules (module), 441  
kivy.modules.console (module), 442  
kivy.modules.inspector (module), 446  
kivy.modules.joycursor (module), 447  
kivy.modules.keybinding (module), 448  
kivy.modules.monitor (module), 449  
kivy.modules.recorder (module), 449  
kivy.modules.screen (module), 450  
kivy.modules.touchring (module), 450  
kivy.modules.webdebugger (module), 451  
kivy.multistroke (module), 242  
kivy.network (module), 453  
kivy.network.urlrequest (module), 453  
kivy.parser (module), 251  
kivy.properties (module), 252  
kivy.resources (module), 264  
kivy.storage (module), 457  
kivy.storage.dictstore (module), 461  
kivy.storage.jsonstore (module), 461  
kivy.storage.redisstore (module), 461  
kivy.support (module), 265  
kivy.tools (module), 463  
kivy.tools.packaging (module), 464  
kivy.tools.packaging.pyinstaller\_hooks (module), 464  
kivy.uix (module), 467  
kivy.uix.abstractview (module), 505  
kivy.uix.accordion (module), 505  
kivy.uix.actionbar (module), 509  
kivy.uix.anchorlayout (module), 514  
kivy.uix.behaviors (module), 467  
kivy.uix.behaviors.button (module), 474  
kivy.uix.behaviors.codenavigation (module), 475  
kivy.uix.behaviors.compoundselection (module), 475  
kivy.uix.behaviors.cover (module), 481  
kivy.uix.behaviors.drag (module), 482  
kivy.uix.behaviors.emacs (module), 483  
kivy.uix.behaviors.focus (module), 484  
kivy.uix.behaviors.knspase (module), 488  
kivy.uix.behaviors.togglebutton (module), 493  
kivy.uix.behaviors.touchripple (module), 495  
kivy.uix.boxlayout (module), 515  
kivy.uix.bubble (module), 517  
kivy.uix.button (module), 520  
kivy.uix.camera (module), 522  
kivy.uix.carousel (module), 523  
kivy.uix.checkbox (module), 525  
kivy.uix.codeinput (module), 527  
kivy.uix.colorpicker (module), 528  
kivy.uix.dropdown (module), 530  
kivy.uix.effectwidget (module), 533  
kivy.uix.filechooser (module), 537  
kivy.uix.floatlayout (module), 545  
kivy.uix.gesturesurface (module), 547  
kivy.uix.gridlayout (module), 550  
kivy.uix.image (module), 553  
kivy.uix.label (module), 556  
kivy.uix.layout (module), 567  
kivy.uix.listview (module), 568  
kivy.uix.modalview (module), 578  
kivy.uix.pagelayout (module), 580  
kivy.uix.popup (module), 581

kivy.uix.progressbar (module), 584  
kivy.uix.recycleboxlayout (module), 585  
kivy.uix.recyclegridlayout (module), 585  
kivy.uix.recyclelayout (module), 585  
kivy.uix.recycleview (module), 496  
kivy.uix.recycleview.datamodel (module), 500  
kivy.uix.recycleview.layout (module), 501  
kivy.uix.recycleview.views (module), 502  
kivy.uix.relativelayout (module), 585  
kivy.uix.rst (module), 589  
kivy.uix.sandbox (module), 592  
kivy.uix.scatter (module), 593  
kivy.uix.scatterlayout (module), 597  
kivy.uix.screenmanager (module), 598  
kivy.uix.scrollview (module), 606  
kivy.uix.selectableview (module), 610  
kivy.uix.settings (module), 611  
kivy.uix.slider (module), 619  
kivy.uix.spinner (module), 623  
kivy.uix.splitter (module), 624  
kivy.uix.stacklayout (module), 627  
kivy.uix.stencilview (module), 628  
kivy.uix.switch (module), 629  
kivy.uix.tabbedpanel (module), 630  
kivy.uix.textinput (module), 636  
kivy.uix.togglebutton (module), 647  
kivy.uixtreeview (module), 648  
kivy.uix.video (module), 653  
kivy.uix.videoplayer (module), 655  
kivy.uix.vkeyboard (module), 660  
kivy.uix.widget (module), 664  
kivy.utils (module), 266  
kivy.vector (module), 268  
kivy.weakmethod (module), 271  
kivy.weakproxy (module), 272  
kivy\_base\_dir (in module kivy), 180  
kivy\_config\_fn (in module kivy), 180  
kivy\_configure() (in module kivy), 180  
kivy\_data\_dir (in module kivy), 180  
kivy\_home\_dir (in module kivy), 180  
kivy\_icons\_dir (in module kivy), 180  
kivy\_modules\_dir (in module kivy), 180  
kivy\_options (in module kivy), 180  
kivy\_register\_post\_configuration() (in module kivy), 180  
kivy\_shader\_dir (in module kivy), 180  
kivy\_usermodules\_dir (in module kivy), 180  
knspname (kivy.uix.behaviors.knspce.KNSpaceBehavior attribute), 493  
KNSpace (class in kivy.uix.behaviors.knspce), 492  
knspce (in module kivy.uix.behaviors.knspce), 493  
knspce (kivy.uix.behaviors.knspce.KNSpaceBehavior attribute), 493  
knspce\_key (kivy.uix.behaviors.knspce.KNSpaceBehavior attribute), 493  
KNSpaceBehavior (class in kivy.uix.behaviors.knspce), 492  
kv\_directory (kivy.app.App attribute), 199  
kv\_file (kivy.app.App attribute), 199

**L**

Label (class in kivy.uix.label), 560  
label (kivy.core.text.LabelBase attribute), 294  
LabelBase (class in kivy.core.text), 292  
last\_touch (kivy.uix.behaviors.button.ButtonBehavior attribute), 474  
last\_touch (kivy.uix.behaviors.touchripple.TouchRippleButtonBehavior attribute), 496  
Layout (class in kivy.uix.layout), 567  
layout (kivy.uix.filechooser.FileChooserController attribute), 543  
layout (kivy.uix.vkeyboard.VKeyboard attribute), 663  
layout\_hint\_with\_bounds() (kivy.uix.layout.Layout method), 568  
layout\_manager (kivy.uix.recycleview.RecycleViewBehavior attribute), 499  
layout\_path (kivy.uix.vkeyboard.VKeyboard attribute), 663  
layout\_text() (in kivy.core.text.text\_layout), 294  
LayoutLine (class in kivy.core.text.text\_layout), 296  
LayoutSelectionBehavior (class in kivy.uix.recycleview.layout), 501  
LayoutWord (class in kivy.core.text.text\_layout), 296  
left (kivy.core.window.WindowBase attribute), 305  
length (kivy.core.audio.Sound attribute), 284  
length() (kivy.vector.Vector method), 270  
length2() (kivy.vector.Vector method), 270  
level (kivy.uixtreeview.TreeViewNode attribute), 652  
lexer (kivy.uix.codeinput.CodeInput attribute), 528  
limit\_to (kivy.uix.bubble.Bubble attribute), 519  
Line (class in kivy.graphics), 332  
Line (class in kivy.graphics.vertex\_instructions), 389  
line\_height (kivy.uix.label.Label attribute), 562  
line\_height (kivy.uix.textinput.TextInput attribute), 643  
line\_intersection() (kivy.vector.Vector static method), 270  
line\_spacing (kivy.uix.textinput.TextInput attribute), 643  
linear() (kivy.animation.AnimationTransition static method), 188

link() (kivy.properties.Property method), 257  
list() (kivy.input.factory.MotionEventFactory static method), 414  
list() (kivy.input.MotionEventFactory static method), 399  
list\_languages() (kivy.core.spelling.SpellingBase method), 291  
ListAdapter (class in kivy.adapters.listadapter), 278  
listdir() (kivy.uix.filechooser.FileSystemAbstract method), 545  
listen() (in module kivy.lib.osc.oscAPI), 439  
ListItemButton (class in kivy.uix.listview), 576  
ListItemIcon (class in kivy.uix.listview), 577  
ListItemReprMixin (class in kivy.uix.listview), 578  
ListProperty (class in kivy.properties), 258  
ListView (class in kivy.uix.listview), 577  
load() (kivy.core.audio.Sound method), 284  
load() (kivy.core.audio.SoundLoader static method), 285  
load() (kivy.core.image.Image static method), 288  
load() (kivy.core.video.VideoBase method), 299  
load\_config() (kivy.app.App method), 199  
load\_file() (kivy.lang.builder.BuilderBase method), 433  
load\_file() (kivy.lang.BuilderBase method), 430  
load\_func (kivy.uixtreeview.TreeView attribute), 650  
load\_kv() (kivy.app.App method), 199  
load\_memory() (kivy.core.image.Image method), 288  
load\_next() (kivy.uix.carousel.Carousel method), 524  
load\_previous() (kivy.uix.carousel.Carousel method), 524  
load\_slide() (kivy.uix.carousel.Carousel method), 524  
load\_string() (kivy.lang.builder.BuilderBase method), 433  
load\_string() (kivy.lang.BuilderBase method), 430  
loaded (kivy.uix.video.Video attribute), 654  
LoaderBase (class in kivy.loader), 202  
LoadIdentity (class in kivy.graphics), 344  
loading\_image (kivy.loader.LoaderBase attribute), 203  
Logger (in module kivy.logger), 240  
LoggerHistory (class in kivy.logger), 240  
look\_at() (kivy.graphics.transformation.Matrix method), 384  
loop (kivy.clock.ClockEvent attribute), 214  
loop (kivy.core.audio.Sound attribute), 284  
loop (kivy.uix.carousel.Carousel attribute), 524

tribute), 382  
mainthread() (in module kivy.clock), 217  
make\_view\_dirty() (kivy.uix.recycleview.views.RecycleDataAdapter method), 503  
make\_views\_dirty() (kivy.uix.recycleview.views.RecycleDataAdapter method), 504  
manager (kivy.uix.filechooser.FileChooser attribute), 542  
manager (kivy.uix.screenmanager.Screen attribute), 601  
manager (kivy.uix.screenmanager.TransitionBase attribute), 603  
margin\_hint (kivy.uix.vkeyboard.VKeyboard attribute), 663  
markup (kivy.core.text.markup.MarkupLabel attribute), 298  
markup (kivy.uix.actionbar.ActionBarPrevious attribute), 513  
markup (kivy.uix.label.Label attribute), 562  
MarkupLabel (class in kivy.core.text.markup), 298  
match() (kivy.lang.builder.BuilderBase method), 433  
match() (kivy.lang.BuilderBase method), 430  
match\_candidate() (kivy.multistroke.MultistrokeGesture method), 249  
match\_rule\_name() (kivy.lang.builder.BuilderBase method), 433  
match\_rule\_name() (kivy.lang.BuilderBase method), 430  
Matrix (class in kivy.graphics.transformation), 383  
matrix (kivy.graphics.context\_instructions.MatrixInstruction attribute), 353  
matrix (kivy.graphics.MatrixInstruction attribute), 337  
MatrixInstruction (class in kivy.graphics), 337  
MatrixInstruction (class in kivy.graphics.context\_instructions), 353  
max (kivy.effects.scroll.ScrollEffect attribute), 320  
max (kivy.uix.progressbar.ProgressBar attribute), 584  
max (kivy.uix.slider.Slider attribute), 621  
max\_height (kivy.uix.dropdown.DropDown attribute), 532  
max\_history (kivy.effects.kinetic.KineticEffect attribute), 319  
max\_iteration (kivy.clock.CyClockBase attribute), 215  
max\_lines (kivy.uix.label.Label attribute), 562  
max\_size (kivy.uix.splitter.Splitter attribute), 626  
max\_upload\_per\_frame (kivy.loader.LoaderBase attribute), 203  
maximize() (kivy.core.window.WindowBase method), 305  
menu (kivy.uix.settings.InterfaceWithSidebar attribute), 601

## M

mag\_filter (kivy.graphics.texture.Texture attribute), 562

tribute), 618  
MenuSidebar (class in kivy.uix.settings), 618  
merge\_gestures() (kivy.uix.gesturesurface.GestureSurface method), 548  
Mesh (class in kivy.graphics), 337  
Mesh (class in kivy.graphics.vertex\_instructions), 394  
meshes (kivy.graphics.tesselator.Tesselator attribute), 376  
Metrics (in module kivy.metrics), 242  
MetricsBase (class in kivy.metrics), 242  
min (kivy.effects.scroll.ScrollEffect attribute), 320  
min (kivy.uix.slider.Slider attribute), 621  
min\_distance (kivy.effects.kinetic.KineticEffect attribute), 319  
min\_filter (kivy.graphics.texture.Texture attribute), 382  
min\_move (kivy.uix.carousel.Carousel attribute), 524  
min\_overscroll (kivy.effects.dampedscroll.DampedScrollEffect attribute), 317  
min\_size (kivy.uix.splitter.Splitter attribute), 626  
MIN\_SLEEP (kivy.clock.ClockBaseBehavior attribute), 216  
min\_space (kivy.uix.accordion.Accordion attribute), 507  
min\_space (kivy.uix.accordion.AccordionItem attribute), 508  
min\_state\_time (kivy.uix.behaviors.button.ButtonBehavior attribute), 475  
min\_state\_time (kivy.uix.dropdown.DropDown attribute), 532  
min\_velocity (kivy.effects.kinetic.KineticEffect attribute), 319  
minimize() (kivy.core.window.WindowBase method), 305  
minimum\_bounding\_circle() (in module kivy.geometry), 233  
minimum\_height (kivy.core.window.WindowBase attribute), 305  
minimum\_height (kivy.uix.boxlayout.BoxLayout attribute), 516  
minimum\_height (kivy.uix.gridlayout.GridLayout attribute), 552  
minimum\_height (kivy.uix.stacklayout.StackLayout attribute), 627  
minimum\_height (kivy.uix.textinput.TextInput attribute), 643  
minimum\_height (kivy.uix.treeview.TreeView attribute), 651  
minimum\_size (kivy.uix.boxlayout.BoxLayout attribute), 516  
minimum\_size (kivy.uix.gridlayout.GridLayout attribute), 552  
minimum\_size (kivy.uix.stacklayout.StackLayout attribute), 628  
minimum\_size (kivy.uix.treeview.TreeView attribute), 651  
minimum\_width (kivy.core.window.WindowBase attribute), 305  
minimum\_width (kivy.uix.actionbar.ActionItem attribute), 510  
minimum\_width (kivy.uix.boxlayout.BoxLayout attribute), 516  
minimum\_width (kivy.uix.gridlayout.GridLayout attribute), 552  
minimum\_width (kivy.uix.stacklayout.StackLayout attribute), 628  
minimum\_width (kivy.uix.treeview.TreeView attribute), 651  
mipmap (kivy.graphics.texture.Texture attribute), 382  
mipmap (kivy.uix.actionbar.ActionItem attribute), 510  
SmoothEffect (kivy.uix.image.Image attribute), 555  
mipmap (kivy.uix.label.Label attribute), 563  
mipmaps (kivy.core.image.ImageData attribute), 290  
mm() (in module kivy.metrics), 242  
ModalView (class in kivy.uix.modalview), 579  
mode (kivy.graphics.Mesh attribute), 338  
mode (kivy.graphics.vertex\_instructions.Mesh attribute), 395  
mode (kivy.modules.console.Console attribute), 445  
mode (kivy.uix.actionbar.ActionGroup attribute), 511  
mode (kivy.uix.screenmanager.CardTransition attribute), 605  
modifiers (kivy.core.window.WindowBase attribute), 306  
MonochromeEffect (class in kivy.uix.effectwidget), 536  
MotionEvent (class in kivy.input), 397  
MotionEvent (class in kivy.input.motionevent), 410  
MotionEventFactory (class in kivy.input), 399  
MotionEventFactory (class in kivy.input.factory), 414  
MotionEventProvider (class in kivy.input), 398  
MotionEventProvider (class in kivy.input.provider), 414  
mouse\_pos (kivy.core.window.WindowBase attribute), 306  
move() (kivy.input.MotionEvent method), 398  
move() (kivy.input.motionevent.MotionEvent method), 412  
multiline (kivy.uix.textinput.TextInput attribute), 644  
multiply() (kivy.graphics.transformation.Matrix

method), 384  
**multiselect** (kivy.uix.behaviors.compoundselection.CompoundSelectionBehavior attribute), 478  
**multiselect** (kivy.uix.filechooser.FileChooserController attribute), 544  
**MultistrokeGesture** (class in kivy.multistroke), 248

**N**

**name** (kivy.app.App attribute), 200  
**name** (kivy.config.ConfigParser attribute), 223  
**name** (kivy.uix.screenmanager.Screen attribute), 601  
**next** (kivy.clock.ClockEvent attribute), 214  
**next()** (kivy.uix.screenmanager.ScreenManager method), 602  
**next\_slide** (kivy.uix.carousel.Carousel attribute), 524  
**no\_selection** (kivy.uix.treeview.TreeNode attribute), 653  
**nocache** (kivy.core.image.Image attribute), 288  
**nocache** (kivy.uix.image.Image attribute), 555  
**nodes** (kivy.uix.treeview.TreeNode attribute), 653  
**nodes\_order\_reversed** (kivy.uix.behaviors.compoundselection.CompoundSelectionBehavior attribute), 479  
**NoLanguageSelectedError** (class in kivy.core.spelling), 291  
**norm\_image\_size** (kivy.uix.image.Image attribute), 555  
**normal\_matrix()** (kivy.graphics.transformation.Matrix method), 384  
**normalize()** (kivy.gesture.Gesture method), 234  
**normalize()** (kivy.vector.Vector method), 270  
**normalize\_stroke()** (kivy.gesture.GestureStroke method), 234  
**NoSuchLangError** (class in kivy.core.spelling), 291  
**NoTransition** (class in kivy.uix.screenmanager), 605  
**num\_workers** (kivy.loader.LoaderBase attribute), 203  
**NumericProperty** (class in kivy.properties), 257

**O**

**ObjectProperty** (class in kivy.properties), 258  
**ObjectWithUid** (class in kivy.event), 231  
**Observable** (class in kivy.event), 231  
**Observable** (class in kivy.lang), 429  
**Observable** (class in kivy.lang.builder), 432  
**observable\_dict** (kivy.uix.recycleview.datamodel.RecycleDataModel attribute), 501  
**odd** (kivy.uix.treeview.TreeNode attribute), 653  
**odd\_color** (kivy.uix.treeview.TreeNode attribute), 653

**on\_bring\_to\_front()** (kivy.uix.scatter.Scatter method), 306  
**on\_close()** (kivy.core.window.WindowBase method), 306  
**on\_config\_change()** (kivy.app.App method), 200  
**on\_context\_created()** (kivy.uix.sandbox.Sandbox method), 593  
**on\_current\_uid()** (kivy.uix.settings.ContentPanel method), 618  
**on\_cursor\_enter()** (kivy.core.window.WindowBase method), 306  
**on\_cursor\_leave()** (kivy.core.window.WindowBase method), 306  
**on\_double\_tap()** (kivy.uix.textinput.TextInput method), 644  
**on\_dropfile()** (kivy.core.window.WindowBase method), 306  
**on\_exception()** (kivy.uix.sandbox.Sandbox method), 593  
**on\_flip()** (kivy.core.window.WindowBase method), 306  
**on\_hide()** (kivy.core.window.WindowBase method), 306  
**on\_joy\_axis()** (kivy.core.window.WindowBase method), 306  
**on\_joy\_ball()** (kivy.core.window.WindowBase method), 306  
**on\_joy\_button\_down()** (kivy.core.window.WindowBase method), 307  
**on\_joy\_button\_up()** (kivy.core.window.WindowBase method), 307  
**on\_joy\_hat()** (kivy.core.window.WindowBase method), 307  
**on\_key\_down()** (kivy.core.window.WindowBase method), 307  
**on\_key\_up()** (kivy.core.window.WindowBase method), 307  
**on\_keyboard()** (kivy.core.window.WindowBase method), 307  
**on\_maximize()** (kivy.core.window.WindowBase method), 307  
**on\_memorywarning()** (kivy.core.window.WindowBase method), 307  
**on\_minimize()** (kivy.core.window.WindowBase method), 307  
**on\_motion()** (kivy.core.window.WindowBase method), 307  
**on\_mouse\_down()** (kivy.core.window.WindowBase method), 307  
**on\_mouse\_move()** (kivy.core.window.WindowBase method), 308  
**on\_mouse\_up()** (kivy.core.window.WindowBase method), 308

on\_pause() (kivy.app.App method), 200  
on\_pause() (kivy.base.EventLoopBase method), 238  
on\_quad\_touch() (kivy.uix.textinput.TextInput method), 644  
on\_request\_close() (kivy.core.window.WindowBase method), 308  
on\_resize() (kivy.core.window.WindowBase method), 308  
on\_restore() (kivy.core.window.WindowBase method), 308  
on\_resume() (kivy.app.App method), 200  
on\_rotate() (kivy.core.window.WindowBase method), 308  
on\_schedule() (kivy.clock.CyClockBase method), 215  
on\_selected\_uid() (kivy.uix.settings.MenuSidebar method), 619  
on\_selection\_change()  
    (kivy.adapters.listadapter.ListAdapter method), 278  
on\_show() (kivy.core.window.WindowBase method), 308  
on\_start() (kivy.app.App method), 200  
on\_start() (kivy.base.EventLoopBase method), 238  
on\_stop() (kivy.app.App method), 200  
on\_stop() (kivy.base.EventLoopBase method), 238  
on\_textinput() (kivy.core.window.WindowBase method), 308  
on\_texture() (kivy.core.image.Image method), 288  
on\_touch\_down() (kivy.core.window.WindowBase method), 308  
on\_touch\_down() (kivy.uix.gesturesurface.GestureSurface method), 548  
on\_touch\_down() (kivy.uix.sandbox.Sandbox method), 593  
on\_touch\_down() (kivy.uix.widget.Widget method), 671  
on\_touch\_move() (kivy.core.window.WindowBase method), 308  
on\_touch\_move() (kivy.uix.gesturesurface.GestureSurface method), 548  
on\_touch\_move() (kivy.uix.sandbox.Sandbox method), 593  
on\_touch\_move() (kivy.uix.widget.Widget method), 671  
on\_touch\_up() (kivy.core.window.WindowBase method), 308  
on\_touch\_up() (kivy.uix.sandbox.Sandbox method), 593  
on\_touch\_up() (kivy.uix.widget.Widget method), 671  
on\_transform\_with\_touch()  
    (kivy.uix.scatter.Scatter method), 596  
on\_triple\_tap() (kivy.uix.textinput.TextInput method), 644  
opacity (kivy.graphics.Canvas attribute), 327  
opacity (kivy.graphics.instructions.Canvas attribute), 347  
opacity (kivy.uix.widget.Widget attribute), 671  
OpacityScrollEffect (class in kivy.effects.opacityscroll), 319  
open() (kivy.uix.dropdown.DropDown method), 532  
open() (kivy.uix.modalview.ModalView method), 580  
open\_settings() (kivy.app.App method), 201  
opos (kivy.input.MotionEvent attribute), 398  
opos (kivy.input.motionevent.MotionEvent attribute), 412  
option\_cls (kivy.uix.spinner.Spinner attribute), 624  
OptionProperty (class in kivy.properties), 260  
options (kivy.app.App attribute), 201  
options (kivy.properties.OptionProperty attribute), 261  
options (kivy.uix.settings.SettingOptions attribute), 616  
options (kivy.uix.video.Video attribute), 654  
options (kivy.uix.videoplayer.VideoPlayer attribute), 658  
order (kivy.uix.effectwidget.ChannelMixEffect attribute), 536  
orientation (kivy.uix.accordion.Accordion attribute), 507  
orientation (kivy.uix.accordion.AccordionItem attribute), 508  
orientation (kivy.uix.boxlayout.BoxLayout attributeSurface), 516  
orientation (kivy.uix.bubble.Bubble attribute), 519  
orientation (kivy.uix.slider.Slider attribute), 621  
orientation (kivy.uix.stacklayout.StackLayout attribute), 628  
origin (kivy.graphics.context\_instructions.Rotate attribute), 352  
origin (kivy.graphics.context\_instructions.Scale attributeSurface), 353  
origin (kivy.graphics.Rotate attribute), 340  
origin (kivy.graphics.Scale attribute), 341  
original\_textures (kivy.atlas.Atlas attribute), 207  
OSCArgument() (in module kivy.lib.osc.OSC), 438  
OSCBlob() (in module kivy.lib.osc.OSC), 438  
OSCMessages (class in kivy.lib.osc.OSC), 438  
osx (kivy.input.motionevent.MotionEvent attribute), 412  
osy (kivy.input.motionevent.MotionEvent attribute), 412  
osz (kivy.input.motionevent.MotionEvent attribute), 412  
out\_back() (kivy.animation.AnimationTransition static method), 188

out\_bounce() (kivy.animation.AnimationTransition static method), 188  
out\_circ() (kivy.animation.AnimationTransition static method), 189  
out\_cubic() (kivy.animation.AnimationTransition static method), 189  
out\_elastic() (kivy.animation.AnimationTransition static method), 189  
out\_expo() (kivy.animation.AnimationTransition static method), 189  
out\_quad() (kivy.animation.AnimationTransition static method), 190  
out\_quart() (kivy.animation.AnimationTransition static method), 190  
out\_quint() (kivy.animation.AnimationTransition static method), 190  
out\_sine() (kivy.animation.AnimationTransition static method), 190  
outline\_color (kivy.uix.label.Label attribute), 563  
outline\_width (kivy.uix.label.Label attribute), 563  
overdraw\_width (kivy.graphics.SmoothLine attribute), 337  
overdraw\_width (kivy.graphics.vertex\_instructions.attribute), 396  
overflow\_group (kivy.uix.actionbar.ActionView attribute), 512  
overflow\_image (kivy.uix.actionbar.ActionOverflow attribute), 512  
overscroll (kivy.effects.scroll.ScrollEffect attribute), 320  
ox (kivy.input.motionevent.MotionEvent attribute), 412  
oy (kivy.input.motionevent.MotionEvent attribute), 412  
oz (kivy.input.motionevent.MotionEvent attribute), 412

P

pack\_width (kivy.uix.actionbar.ActionItem attribute), 510  
padding (kivy.uix.anchorlayout.AnchorLayout attribute), 515  
padding (kivy.uix.boxlayout.BoxLayout attribute), 517  
padding (kivy.uix.gridlayout.GridLayout attribute), 552  
padding (kivy.uix.label.Label attribute), 563  
padding (kivy.uix.slider.Slider attribute), 621  
padding (kivy.uix.stacklayout.StackLayout attribute), 628  
padding (kivy.uix.textinput.TextInput attribute), 644  
padding\_x (kivy.uix.label.Label attribute), 563  
padding\_x (kivy.uix.textinput.TextInput attribute), 644  
padding\_y (kivy.uix.label.Label attribute), 563  
padding\_y (kivy.uix.textinput.TextInput attribute), 644  
page (kivy.uix.pagelayout.PageLayout attribute), 581  
page\_count (kivy.uix.behaviors.compoundselection.CompoundSelection attribute), 479  
PageLayout (class in kivy.uix.pagelayout), 581  
panel (kivy.uix.settings.SettingItem attribute), 615  
panels (kivy.uix.settings.ContentPanel attribute), 618  
parent (kivy.core.window.WindowBase attribute), 309  
parent (kivy.uix.behaviors.knspaced.KNSpace attribute), 492  
parent (kivy.uix.widget.Widget attribute), 672  
parent\_node (kivy.uix.treeview.TreeNode attribute), 653  
parse() (kivy.lang.Parser method), 431  
parse() (kivy.lang.parser.Parser method), 435  
parse\_bool() (in module kivy.parser), 251  
parse\_color() (in module kivy.parser), 251  
SmoothLine (in module kivy.parser), 252  
parse\_float (in module kivy.parser), 251  
parse\_float4() (in module kivy.parser), 252  
parse\_gesture() (kivy.multistroke.Recognizer method), 246  
parse\_int (in module kivy.parser), 251  
parse\_int2() (in module kivy.parser), 252  
parse\_level() (kivy.lang.Parser method), 431  
parse\_level() (kivy.lang.parser.Parser method), 435  
parse\_string() (in module kivy.parser), 251  
parseArgs() (in module kivy.lib.osc.OSC), 438  
Parser (class in kivy.lang), 431  
Parser (class in kivy.lang.parser), 434  
ParserException (class in kivy.lang), 432  
ParserException (class in kivy.lang.parser), 435  
password (kivy.uix.textinput.TextInput attribute), 644  
password\_mask (kivy.uix.textinput.TextInput attribute), 645  
paste() (kivy.uix.textinput.TextInput method), 645  
path (kivy.uix.filechooser.FileChooserController attribute), 544  
path (kivy.uix.filechooser.FileChooserProgressBase attribute), 545  
pause() (kivy.core.video.VideoBase method), 299  
pause() (kivy.loader.LoaderBase method), 204  
permute() (kivy.multistroke.MultistrokeGesture method), 249  
perspective() (kivy.graphics.transformation.Matrix method), 384  
pick() (kivy.modules.console.Console method), 445  
pitch (kivy.core.audio.Sound attribute), 284

pixel\_size (kivy.uix.effectwidget.PixelateEffect attribute), 536  
PixelateEffect (class in kivy.uix.effectwidget), 536  
pixels (kivy.graphics.Fbo attribute), 331  
pixels (kivy.graphics.fbo.Fbo attribute), 356  
pixels (kivy.graphics.texture.Texture attribute), 382  
platform (in module kivy.utils), 267  
play (kivy.input.recorder.Recorder attribute), 409  
play (kivy.uix.camera.Camera attribute), 522  
play (kivy.uix.video.Video attribute), 654  
play (kivy.uix.videoplayer.VideoPlayer attribute), 658  
play() (kivy.core.audio.Sound method), 284  
play() (kivy.core.video.VideoBase method), 299  
Point (class in kivy.graphics), 338  
Point (class in kivy.graphics.vertex\_instructions), 393  
points (kivy.graphics.Bezier attribute), 324  
points (kivy.graphics.Line attribute), 336  
points (kivy.graphics.Point attribute), 338  
points (kivy.graphics.Quad attribute), 339  
points (kivy.graphics.Triangle attribute), 342  
points (kivy.graphics.vertex\_instructions.Bezier attribute), 396  
points (kivy.graphics.vertex\_instructions.Line attribute), 393  
points (kivy.graphics.vertex\_instructions.Point attribute), 394  
points (kivy.graphics.vertex\_instructions.Quad attribute), 387  
points (kivy.graphics.vertex\_instructions.Triangle attribute), 387  
points\_distance() (kivy.gesture.GestureStroke method), 234  
pointsize (kivy.graphics.Point attribute), 339  
pointsize (kivy.graphics.vertex\_instructions.Point attribute), 394  
pop() (kivy.input MotionEvent method), 398  
pop() (kivy.input.motionevent MotionEvent method), 412  
PopMatrix (class in kivy.graphics), 339  
PopMatrix (class in kivy.graphics.context\_instructions), 352  
PopState (class in kivy.graphics), 344  
Popup (class in kivy.uix.popup), 583  
popup (kivy.uix.settings.SettingsOptions attribute), 617  
popup (kivy.uix.settings.SettingPath attribute), 616  
popup (kivy.uix.settings.SettingsString attribute), 615  
PopupException (class in kivy.uix.popup), 584  
pos (kivy.graphics.Rectangle attribute), 339  
pos (kivy.graphics.vertex\_instructions.Rectangle attribute), 387  
pos (kivy.input.motionevent MotionEvent attribute), 412  
pos (kivy.uix.widget.Widget attribute), 672  
pos\_hint (kivy.uix.widget.Widget attribute), 672  
position (kivy.core.video.VideoBase attribute), 299  
position (kivy.uix.video.Video attribute), 654  
position (kivy.uix.videoplayer.VideoPlayer attribute), 658  
post\_dispatch\_input() (kivy.base.EventLoopBase method), 238  
ppos (kivy.input MotionEvent attribute), 398  
ppos (kivy.input.motionevent MotionEvent attribute), 412  
preload() (kivy.uix.rst.RstDocument method), 591  
prepare() (kivy.multistroke.Candidate method), 251  
prepare() (kivy.multistroke.UnistrokeTemplate method), 250  
prepare\_templates() (kivy.multistroke.Recognizer method), 246  
prev (kivy.clock.ClockEvent attribute), 214  
previous() (kivy.uix.screenmanager.ScreenManager method), 602  
previous\_image (kivy.uix.actionbar.ActionPrevious attribute), 513  
previous\_image\_height (kivy.uix.actionbar.ActionPrevious attribute), 513  
previous\_image\_width (kivy.uix.actionbar.ActionPrevious attribute), 513  
previous\_slide (kivy.uix.carousel.Carousel attribute), 524  
print\_usage() (kivy.cache.Cache static method), 208  
profile (kivy.input.motionevent MotionEvent attribute), 412  
progress (kivy.multistroke.ProgressTracker attribute), 248  
progress\_cls (kivy.uix.filechooser.FileChooserController attribute), 544  
ProgressBar (class in kivy.uix.progressbar), 584  
ProgressTracker (class in kivy.multistroke), 247  
project() (kivy.graphics.transformation.Matrix method), 384  
propagate\_selection\_to\_data (kivy.adapters.listadapter.ListAdapter attribute), 279  
properties() (kivy.event.EventDispatcher method), 229  
Property (class in kivy.properties), 256  
property() (kivy.event.EventDispatcher method), 229

proxy\_ref (kivy.event.EventDispatcher attribute), [230](#)  
 proxy\_ref (kivy.graphics.Instruction attribute), [331](#)  
 proxy\_ref (kivy.graphics.instructions.Instruction attribute), [345](#)  
 proxy\_ref (kivy.uix.widget.Widget attribute), [672](#)  
 ProxyImage (class in kivy.loader), [204](#)  
 psx (kivy.input.motionevent.MotionEvent attribute), [412](#)  
 psy (kivy.input.motionevent.MotionEvent attribute), [412](#)  
 psz (kivy.input.motionevent.MotionEvent attribute), [412](#)  
 pt() (in module kivy.metrics), [242](#)  
 push() (kivy.input.MotionEvent method), [398](#)  
 push() (kivy.input.motionevent.MotionEvent method), [413](#)  
 push\_attrs\_stack (kivy.input.motionevent.MotionEvent attribute), [413](#)  
 PushMatrix (class in kivy.graphics), [339](#)  
 PushMatrix (class in kivy.graphics.context\_instructions), [352](#)  
 PushState (class in kivy.graphics), [344](#)  
 put() (kivy.storage.AbstractStore method), [460](#)  
 px (kivy.input.motionevent.MotionEvent attribute), [413](#)  
 py (kivy.input.motionevent.MotionEvent attribute), [413](#)  
 PY2 (in module kivy.compat), [218](#)  
 pz (kivy.input.motionevent.MotionEvent attribute), [413](#)

**Q**

Quad (class in kivy.graphics), [339](#)  
 Quad (class in kivy.graphics.vertex\_instructions), [387](#)  
 QueryDict (class in kivy.utils), [267](#)

**R**

r (kivy.graphics.ClearColor attribute), [343](#)  
 r (kivy.graphics.Color attribute), [329](#)  
 r (kivy.graphics.context\_instructions.Color attribute), [351](#)  
 r (kivy.graphics.gl\_instructions.ClearColor attribute), [357](#)  
 r (kivy.uix.colorpicker.ColorWheel attribute), [530](#)  
 radius (kivy.graphics.vertex\_instructions.RoundedRectangle attribute), [388](#)  
 raise\_window() (kivy.core.window.WindowBase method), [309](#)  
 range (kivy.uix.slider.Slider attribute), [621](#)  
 rawAppend() (kivy.lib.osc.OSC.OSCMessage method), [438](#)  
 read() (kivy.config.ConfigParser method), [223](#)  
 read\_pixel() (kivy.core.image.Image method), [288](#)  
 readDouble() (in module kivy.lib.osc.OSC), [438](#)  
 readLong() (in module kivy.lib.osc.OSC), [438](#)  
 readonly (kivy.uix.textinput.TextInput attribute), [645](#)  
 readQueue() (in module kivy.lib.osc.oscAPI), [439](#)  
 recognize() (kivy.multistroke.Recognizer method), [246](#)  
 Recognizer (class in kivy.multistroke), [244](#)  
 record (kivy.input.recorder.Recorder attribute), [409](#)  
 recordAttrs (kivy.input.recorder.Recorder attribute), [409](#)  
 record\_profile\_mask (kivy.input.recorder.Recorder attribute), [409](#)  
 Recorder (class in kivy.input.recorder), [408](#)  
 Rect (class in kivy.graphics.scissor\_instructions), [369](#)  
 Rectangle (class in kivy.graphics), [339](#)  
 Rectangle (class in kivy.graphics.vertex\_instructions), [387](#)  
 rectangle (kivy.graphics.Line attribute), [336](#)  
 rectangle (kivy.graphics.vertex\_instructions.Line attribute), [393](#)  
 RecycleDataAdapter (class in kivy.uix.recycleview.views), [503](#)  
 RecycleDataModel (class in kivy.uix.recycleview.datamodel), [500](#)  
 RecycleDataModelBehavior (class in kivy.uix.recycleview.datamodel), [500](#)  
 RecycleDataViewBehavior (class in kivy.uix.recycleview.views), [504](#)  
 RecycleLayout (class in kivy.uix.recyclelayout), [585](#)  
 RecycleLayoutManagerBehavior (class in kivy.uix.recycleview.layout), [502](#)  
 RecycleView (class in kivy.uix.recycleview), [500](#)  
 recycleview (kivy.uix.recycleview.datamodel.RecycleDataModelBehavior attribute), [500](#)  
 recycleview (kivy.uix.recycleview.views.RecycleDataAdapter attribute), [504](#)  
 RecycleViewBehavior (class in kivy.uix.recycleview), [499](#)  
 RedisStore (class in kivy.storage.redisstore), [461](#)  
 reference\_size (kivy.uix.behaviors.cover.CoverBehavior attribute), [482](#)  
 ReferenceListProperty (class in kivy.properties), [261](#)  
 refresh() (kivy.core.text.LabelBase method), [294](#)  
 refresh() (kivy.uix.vkeyboard.VKeyboard method), [663](#)  
 refresh\_fbo\_setup() (kivy.uix.effectwidget.EffectWidget method), [535](#)  
 refresh\_from\_data() (kivy.uix.recycleview.RecycleViewBehavior method), [499](#)

refresh\_from\_layout()  
    (kivy.uix.recycleview.RecycleViewBehavior  
        method), 499

refresh\_from\_viewport()  
    (kivy.uix.recycleview.RecycleViewBehavior  
        method), 499

refresh\_view\_attrs()  
    (kivy.uix.recycleview.views.RecycleData  
        method), 504

refresh\_view\_attrs()  
    (kivy.uix.recycleview.views.RecycleData  
        method), 504

refresh\_view\_layout()  
    (kivy.uix.recycleview.layout.RecycleLayoutManager  
        method), 502

refresh\_view\_layout()  
    (kivy.uix.recycleview.views.RecycleDataAdapter  
        method), 504

refresh\_view\_layout()  
    (kivy.uix.recycleview.views.RecycleData  
        method), 505

refs (kivy.core.text.markup.MarkupLabel  
    attribute), 298

refs (kivy.uix.label.Label attribute), 563

register() (kivy.cache.Cache static method), 208

register() (kivy.core.audio.SoundLoader  
    static  
        method), 285

register() (kivy.core.text.LabelBase static method),  
    294

register() (kivy.input.factory.MotionEventFactory  
    static method), 414

register() (kivy.input.MotionEventFactory  
    static  
        method), 399

register() (kivy.input.providers.tuio.TuioMotionEvent  
    static method), 407

register\_context() (in module kivy.context), 224

register\_event\_type() (kivy.event.EventDispatcher  
    method), 230

register\_type() (kivy.uix.settings.Settings method),  
    614

reify (class in kivy.utils), 267

RelativeLayout (class in kivy.uix.relativelayout),  
    589

release() (kivy.clock.ClockEvent method), 214

release() (kivy.core.window.Keyboard  
    method), 301

release() (kivy.graphics.Fbo method), 331

release() (kivy.graphics.fbo.Fbo method), 356

release\_all\_keyboards()  
    (kivy.core.window.WindowBase  
        method), 309

release\_keyboard() (kivy.core.window.WindowBase  
    method), 309

reload() (kivy.uix.image.Image method), 555

remove() (kivy.cache.Cache static method), 208

remove() (kivy.graphics.InstructionGroup  
    method), 332

remove() (kivy.graphics.instructions.InstructionGroup  
    method), 345

remove\_android\_splash()  
    (kivy.base.EventLoopBase  
        method), 238

remove\_callback() (kivy.config.ConfigParser  
    Adapter), 223

remove\_event\_listener()  
    (kivy.uix.listview.CompositeListItem  
        attribute), 577

remove\_from\_cache()  
    (kivy.core.image.Image  
        Backend), 289

remove\_group() (kivy.graphics.InstructionGroup  
    method), 332

remove\_group() (kivy.graphics.instructions.InstructionGroup  
    method), 345

remove\_handler() (kivy.base.ExceptionManagerBase  
    method), 239

remove\_input\_provider()  
    (kivy.base.EventLoopBase  
        method), 238

remove\_node()  
    (kivy.uixtreeview.TreeView  
        method), 651

remove\_postproc\_module()  
    (kivy.base.EventLoopBase  
        method), 238

remove\_reload\_observer()  
    (kivy.graphics.context.Context  
        method), 354

remove\_reload\_observer() (kivy.graphics.Fbo  
    method), 331

remove\_reload\_observer() (kivy.graphics.fbo.Fbo  
    method), 356

remove\_reload\_observer()  
    (kivy.graphics.texture.Texture  
        method), 382

remove\_screen() (kivy.uix.screenmanager.TransitionBase  
    method), 603

remove\_toolbar\_widget()  
    (kivy.modules.console.Console  
        method), 445

remove\_widget() (kivy.core.window.WindowBase  
    method), 309

remove\_widget() (kivy.uix.widget.Widget  
    method), 672

render() (kivy.core.text.LabelBase method), 294

render() (kivy.uix.rst.RstDocument method), 591

RenderContext (class in kivy.graphics), 339

RenderContext (class  
    in  
        kivy.graphics.instructions), 348

replace\_crlf (kivy.uix.textinput.TextInput  
    attribute), 645

representing\_cls (kivy.uix.listview.CompositeListItem  
    attribute), 577

req\_body (kivy.network.urlrequest.UrlRequest  
    attribute), 714

tribute), 455  
req\_headers (kivy.network.urlrequest.UrlRequest attribute), 455  
request\_keyboard() (kivy.core.window.WindowBase method), 309  
require() (in module kivy), 179  
rescale\_with\_parent (kivy.uix.splitter.Splitter attribute), 626  
reset() (kivy.effects.scroll.ScrollEffect method), 320  
reset\_context (kivy.graphics.Callback attribute), 327  
reset\_context (kivy.graphics.instructions.Callback attribute), 349  
reset\_undo() (kivy.uix.textinput.TextInput method), 645  
resolution (kivy.core.camera.CameraBase attribute), 286  
resolution (kivy.uix.camera.Camera attribute), 522  
resolve\_path() (kivy.uix.rst.RstDocument method), 592  
resource\_add\_path() (in module kivy.resources), 265  
resource\_find() (in module kivy.resources), 265  
resource\_remove\_path() (in module kivy.resources), 265  
resp\_headers (kivy.network.urlrequest.UrlRequest attribute), 455  
resp\_status (kivy.network.urlrequest.UrlRequest attribute), 455  
restore() (kivy.core.window.WindowBase method), 310  
result (kivy.network.urlrequest.UrlRequest attribute), 455  
resume() (kivy.loader.LoaderBase method), 204  
rgb (kivy.graphics.ClearColor attribute), 343  
rgb (kivy.graphics.Color attribute), 329  
rgb (kivy.graphics.context\_instructions.Color attribute), 351  
rgb (kivy.graphics.gl\_instructions.ClearColor attribute), 357  
rgba (kivy.graphics.ClearColor attribute), 343  
rgba (kivy.graphics.Color attribute), 329  
rgba (kivy.graphics.context\_instructions.Color attribute), 351  
rgba (kivy.graphics.gl\_instructions.ClearColor attribute), 357  
rgba() (in module kivy.utils), 268  
right (kivy.uix.widget.Widget attribute), 672  
right\_count (kivy.uix.behaviors.compoundselection.CompoundSelection attribute), 479  
ripple\_duration\_in (kivy.uix.behaviors.touchripple.TouchRippleBehavior attribute), 495  
ripple\_duration\_out (kivy.uix.behaviors.touchripple.TouchRippleBehavior attribute), 495  
ripple\_fade() (kivy.uix.behaviors.touchripple.TouchRippleBehavior method), 495  
ripple\_fade() (kivy.uix.behaviors.TouchRippleBehavior method), 473  
ripple\_fade\_from\_alpha (kivy.uix.behaviors.touchripple.TouchRippleBehavior attribute), 495  
ripple\_fade\_to\_alpha (kivy.uix.behaviors.touchripple.TouchRippleBehavior attribute), 496  
ripple\_func\_in (kivy.uix.behaviors.touchripple.TouchRippleBehavior attribute), 496  
ripple\_func\_out (kivy.uix.behaviors.touchripple.TouchRippleBehavior attribute), 496  
ripple\_rad\_default (kivy.uix.behaviors.touchripple.TouchRippleBehavior attribute), 496  
ripple\_scale (kivy.uix.behaviors.touchripple.TouchRippleBehavior attribute), 496  
ripple\_show() (kivy.uix.behaviors.touchripple.TouchRippleBehavior method), 496  
ripple\_show() (kivy.uix.behaviors.TouchRippleBehavior method), 473  
RiseInTransition (class in kivy.uix.screenmanager), 605  
root (kivy.app.App attribute), 201  
root (kivy.uix.treeview.TreeView attribute), 651  
root\_options (kivy.uix.treeview.TreeView attribute), 651  
root\_window (kivy.app.App attribute), 201  
rootpath (kivy.uix.filechooser.FileChooserController attribute), 544  
Rotate (class in kivy.graphics), 340  
Rotate (class in kivy.graphics.context\_instructions), 352  
rotate() (kivy.graphics.transformation.Matrix method), 385  
rotate() (kivy.vector.Vector method), 270  
rotation (kivy.core.window.WindowBase attribute), 310  
rotation (kivy.uix.scatter.Scatter attribute), 596  
round\_value (kivy.effects.dampedscroll.DampedScrollEffect attribute), 318  
rounded\_rectangle (kivy.graphics.Line attribute), 336  
rounded\_rectangle (kivy.graphics.vertex\_instructions.Line attribute), 393  
RoundedRectangle (class in kivy.graphics.vertex\_instructions), 387  
row\_default\_height (kivy.uix.gridlayout.GridLayout attribute), 573  
row\_force\_default (kivy.uix.gridlayout.GridLayout attribute), 553  
row\_height (kivy.uix.listview.ListView attribute), 573  
rowlength (kivy.core.image.ImageData attribute), 291

rows (kivy.uix.gridlayout.GridLayout attribute), 553  
rows\_minimum (kivy.uix.gridlayout.GridLayout attribute), 553  
RstDocument (class in kivy.uix.rst), 590  
run() (kivy.app.App method), 201  
run() (kivy.base.EventLoopBase method), 238  
run() (kivy.loader.LoaderBase method), 204  
runtime\_hooks() (in module kivy.tools.packaging.pyinstaller\_hooks), 466  
runTouchApp() (in module kivy.base), 239

**S**

s (kivy.graphics.Color attribute), 329  
s (kivy.graphics.context\_instructions.Color attribute), 351  
safeIn() (kivy.interactive.SafeMembrane method), 237  
SafeList (class in kivy.utils), 266  
SafeMembrane (class in kivy.interactive), 237  
safeOut() (kivy.interactive.SafeMembrane method), 237  
Sandbox (class in kivy.uix.sandbox), 593  
save() (kivy.core.image.Image method), 289  
save() (kivy.graphics.texture.Texture method), 382  
Scale (class in kivy.graphics), 341  
Scale (class in kivy.graphics.context\_instructions), 352  
scale (kivy.graphics.context\_instructions.Scale attribute), 353  
scale (kivy.graphics.Scale attribute), 341  
scale (kivy.uix.scatter.Scatter attribute), 596  
scale() (kivy.graphics.transformation.Matrix method), 385  
scale\_for\_screen() (kivy.input.MotionEvent method), 398  
scale\_for\_screen() (kivy.input.motionevent.MotionEvent method), 413  
scale\_max (kivy.uix.scatter.Scatter attribute), 596  
scale\_min (kivy.uix.scatter.Scatter attribute), 596  
scale\_stroke() (kivy.gesture.GestureStroke method), 234  
ScanlinesEffect (class in kivy.uix.effectwidget), 536  
Scatter (class in kivy.uix.scatter), 595  
ScatterLayout (class in kivy.uix.scatterlayout), 597  
ScatterPlane (class in kivy.uix.scatter), 597  
ScatterPlaneLayout (class in kivy.uix.scatterlayout), 598  
schedule\_interval() (kivy.clock.CyClockBase method), 215  
schedule\_interval\_free() (kivy.clock.CyClockBaseFree method), 216  
schedule\_once() (kivy.clock.CyClockBase method), 215  
schedule\_once\_free() (kivy.clock.CyClockBaseFree method), 216  
ScissorPop (class in kivy.graphics.scissor\_instructions), 369  
ScissorPush (class in kivy.graphics.scissor\_instructions), 369  
ScissorStack (class in kivy.graphics.scissor\_instructions), 369  
Screen (class in kivy.uix.screenmanager), 601  
screen\_in (kivy.uix.screenmanager.TransitionBase attribute), 604  
screen\_names (kivy.uix.screenmanager.ScreenManager attribute), 602  
screen\_out (kivy.uix.screenmanager.TransitionBase attribute), 604  
ScreenManager (class in kivy.uix.screenmanager), 601  
ScreenManagerException (class in kivy.uix.screenmanager), 603  
screens (kivy.uix.screenmanager.ScreenManager attribute), 602  
screenshot() (kivy.core.window.WindowBase method), 310  
scroll (kivy.effects.scroll.ScrollEffect attribute), 320  
scroll\_count (kivy.uix.behaviors.compoundselection.CompoundSelection attribute), 479  
scroll\_distance (kivy.uix.carousel.Carousel attribute), 525  
scroll\_distance (kivy.uix.scrollview.ScrollView attribute), 609  
scroll\_timeout (kivy.uix.carousel.Carousel attribute), 525  
scroll\_timeout (kivy.uix.scrollview.ScrollView attribute), 609  
scroll\_to() (kivy.uix.scrollview.ScrollView method), 609  
scroll\_type (kivy.uix.scrollview.ScrollView attribute), 609  
scroll\_wheel\_distance (kivy.uix.scrollview.ScrollView attribute), 610  
scroll\_x (kivy.uix.scrollview.ScrollView attribute), 610  
scroll\_x (kivy.uix.textinput.TextInput attribute), 645  
scroll\_y (kivy.uix.scrollview.ScrollView attribute), 610  
scroll\_y (kivy.uix.textinput.TextInput attribute), 645

ScrollEffect (class in kivy.effects.scroll), 320  
scrolling (kivy.uix.listview.ListView attribute), 578  
ScrollView (class in kivy.uix.scrollview), 607  
section (kivy.uix.settings.SelectedItem attribute), 615  
seek() (kivy.core.audio.Sound method), 284  
seek() (kivy.core.video.VideoBase method), 299  
seek() (kivy.uix.video.Video method), 654  
seek() (kivy.uix.videoplayer.VideoPlayer method), 658  
segment\_intersection() (kivy.vector.Vector static method), 271  
segments (kivy.graphics.Bezier attribute), 325  
segments (kivy.graphics.Ellipse attribute), 330  
segments (kivy.graphics.vertex\_instructions.Bezier attribute), 396  
segments (kivy.graphics.vertex\_instructions.Ellipse attribute), 389  
segments (kivy.graphics.vertex\_instructions.Rounded attribute), 388  
select() (kivy.uix.dropdown.DropDown method), 533  
select() (kivy.uix.listview.SelectableView method), 576  
select() (kivy.uix.selectableview.SelectableView method), 611  
select\_all() (kivy.uix.textinput.TextInput method), 645  
select\_language() (kivy.core.spelling.SpellingBase method), 291  
select\_list() (kivy.adapters.listadapter.ListAdapter method), 279  
select\_node() (kivy.uix.behaviors.compoundselections.CompoundSelectionBehavior method), 479  
select\_node() (kivy.uix.behaviors.CompoundSelectionBehavior method), 471  
select\_node() (kivy.uix.treeview.TreeView method), 651  
select\_text() (kivy.uix.textinput.TextInput method), 645  
select\_with\_key\_down() (kivy.uix.behaviors.compoundselections.CompoundSelectionBehavior method), 479  
select\_with\_key\_down() (kivy.uix.behaviors.CompoundSelectionBehavior method), 472  
select\_with\_key\_up() (kivy.uix.behaviors.compoundselections.CompoundSelectionBehavior method), 479  
select\_with\_key\_up() (kivy.uix.behaviors.CompoundSelectionBehavior method), 472  
select\_with\_touch() (kivy.uix.behaviors.compoundselections.CompoundSelectionBehavior method), 480  
select\_with\_touch() (kivy.uix.behaviors.CompoundSelectionBehavior method), 479  
method), 472  
SelectableDataItem (class in kivy.adapters.models), 281  
SelectableView (class in kivy.uix.listview), 576  
SelectableView (class in kivy.uix.selectableview), 610  
selected\_alpha (kivy.uix.settings.SelectedItem attribute), 615  
selected\_color (kivy.uix.listview.CompositeListItem attribute), 577  
selected\_color (kivy.uix.listview.ListItemButton attribute), 576  
selected\_node (kivy.uix.treeview.TreeView attribute), 651  
selected\_nodes (kivy.uix.behaviors.compoundselection.CompoundSelectionBehavior method), 480  
selected\_uid (kivy.uix.settings.MenuSidebar attribute), 619  
Rectangle (kivy.adapters.listadapterListAdapter attribute), 279  
selection (kivy.uix.filechooser.FileChooserController attribute), 544  
selection\_color (kivy.uix.textinput.TextInput attribute), 645  
selection\_from (kivy.uix.textinput.TextInput attribute), 646  
selection\_limit (kivy.adapters.listadapterListAdapter attribute), 279  
selection\_mode (kivy.adapters.listadapterListAdapter attribute), 279  
selection\_text (kivy.uix.textinput.TextInput attribute), 646  
SelectableListBehavior (kivy.uix.textinput.TextInput attribute), 646  
sendBundle() (in module kivy.lib.osc.oscAPI), 439  
sendMsg() (in module kivy.lib.osc.oscAPI), 439  
sensitivity (kivy.uix.slider.Slider attribute), 621  
separator\_color (kivy.uix.popup.Popup attribute), 583  
separator\_height (kivy.uix.popup.Popup attribute), 583  
separateIntelligenceBehavior (kivy.actionbar.ActionGroup attribute), 511  
separator\_width (kivy.uix.actionbar.ActionGroup attribute), 512  
set() (kivy.config.ConfigParser method), 223  
set() (kivy.graphics.context\_instructions.RotateSelectionBehavior), 152  
set() (kivy.graphics.Rotate method), 340  
set() (kivy.graphics.transformation.Matrix method), 385  
set() (kivy.properties.Property method), 257  
setConfig (kivy.properties.SelectionBehaviorConfigParserProperty method), 264  
setSectionBehavior (kivy.modules.console.Console

method), 445  
set\_fbo\_shader() (kivy.uix.effectwidget.EffectBase method), 535  
set\_icon() (kivy.core.window.WindowBase method), 310  
set\_max() (kivy.properties.BoundedNumericProperty method), 260  
set\_min() (kivy.properties.BoundedNumericProperty method), 260  
set\_system\_cursor() (kivy.core.window.WindowBase method), 310  
set\_title() (kivy.core.window.WindowBase method), 311  
set\_visible\_views() (kivy.uix.recycleview.layout.RecycleView method), 502  
set\_visible\_views() (kivy.uix.recycleview.views.RecycleData view method), 504  
set\_vkeyboard\_class() (kivy.core.window.WindowBase method), 311  
set\_window() (kivy.base.EventLoopBase method), 238  
setall() (kivy.config.ConfigParser method), 223  
setdefault() (kivy.config.ConfigParser method), 223  
setdefaults() (kivy.config.ConfigParser method), 223  
setter() (kivy.event.EventDispatcher method), 230  
SettingBoolean (class in kivy.uix.settings), 616  
SettingItem (class in kivy.uix.settings), 614  
SettingNumeric (class in kivy.uix.settings), 616  
SettingOptions (class in kivy.uix.settings), 616  
SettingPath (class in kivy.uix.settings), 615  
Settings (class in kivy.uix.settings), 613  
settings (kivy.uix.settings.SettingsPanel attribute), 614  
settings\_cls (kivy.app.App attribute), 201  
SettingsPanel (class in kivy.uix.settings), 614  
SettingString (class in kivy.uix.settings), 615  
SettingsWithNoMenu (class in kivy.uix.settings), 617  
SettingsWithSidebar (class in kivy.uix.settings), 617  
SettingsWithSpinner (class in kivy.uix.settings), 617  
SettingsWithTabbedPanel (class in kivy.uix.settings), 617  
SettingTitle (class in kivy.uix.settings), 617  
setup\_mode() (kivy.uix.vkeyboard.VKeyboard method), 663  
setup\_mode\_dock() (kivy.uix.vkeyboard.VKeyboard method), 664  
setup\_mode\_free() (kivy.uix.vkeyboard.VKeyboard method), 664  
Shader (class in kivy.graphics.shader), 371  
shader (kivy.graphics.instructions.RenderContext attribute), 348  
shader (kivy.graphics.RenderContext attribute), 340  
ShaderTransition (class in kivy.uix.screenmanager), 604  
Shape (class in kivy.input.shape), 414  
shape (kivy.input.motionevent.MotionEvent attribute), 413  
shape\_color\_key (kivy.core.window.WindowBase attribute), 311  
shape\_cutoff (kivy.core.window.WindowBase attribute), 311  
shape\_immediate (kivy.core.window.WindowBase attribute), 311  
shape\_immediate\_behavior (kivy.core.window.WindowBase attribute), 311  
shape\_immediate\_behavior\_immediate (kivy.core.window.WindowBase attribute), 311  
shaped (kivy.core.window.WindowBase attribute), 312  
ShapeRect (class in kivy.input.shape), 414  
shorten (kivy.uix.label.Label attribute), 564  
shorten() (kivy.core.text.LabelBase method), 294  
shorten\_from (kivy.uix.label.Label attribute), 564  
shorten\_post() (kivy.core.text.markup.MarkupLabel method), 298  
show() (kivy.core.window.WindowBase method), 312  
show\_arrow (kivy.uix.bubble.Bubble attribute), 520  
show\_cursor (kivy.core.window.WindowBase attribute), 312  
show\_errors (kivy.uix.rst.RstDocument attribute), 592  
show\_hidden (kivy.uix.filechooser.FileChooserController attribute), 544  
show\_hidden (kivy.uix.settings.SettingPath attribute), 616  
show\_keyboard() (kivy.uix.behaviors.focus.FocusBehavior method), 488  
show\_keyboard() (kivy.uix.behaviors.FocusBehavior method), 470  
SimpleListAdapter (class in kivy.adapters.simplelistadapter), 281  
single\_points\_test() (kivy.uix.gesturesurface.GestureContainer method), 549  
sizable\_from (kivy.uix.splitter.Splitter attribute), 626  
size (kivy.core.image.Image attribute), 289  
size (kivy.core.image.ImageData attribute), 290  
size (kivy.core.window.WindowBase attribute), 312  
size (kivy.graphics.Fbo attribute), 331  
size (kivy.graphics.fbo.Fbo attribute), 357  
size (kivy.graphics.Rectangle attribute), 339  
size (kivy.graphics.texture.Texture attribute), 382

size (kivy.graphics.vertex\_instructions.Rectangle attribute), 387  
size (kivy.uix.effectwidget.HorizontalBlurEffect attribute), 536  
size (kivy.uix.effectwidget.VerticalBlurEffect attribute), 536  
size (kivy.uix.widget.Widget attribute), 672  
size\_hint (kivy.uix.widget.Widget attribute), 673  
size\_hint\_max (kivy.uix.widget.Widget attribute), 673  
size\_hint\_max\_x (kivy.uix.widget.Widget attribute), 673  
size\_hint\_max\_y (kivy.uix.widget.Widget attribute), 673  
size\_hint\_min (kivy.uix.widget.Widget attribute), 673  
size\_hint\_min\_x (kivy.uix.widget.Widget attribute), 673  
size\_hint\_min\_y (kivy.uix.widget.Widget attribute), 673  
size\_hint\_x (kivy.uix.widget.Widget attribute), 674  
size\_hint\_y (kivy.uix.widget.Widget attribute), 674  
Slider (class in kivy.uix.slider), 620  
slides (kivy.uix.carousel.Carousel attribute), 525  
SlideTransition (class in kivy.uix.screenmanager), 604  
SmoothLine (class in kivy.graphics), 336  
SmoothLine (class in kivy.graphics.vertex\_instructions), 396  
softinput\_mode (kivy.core.window.WindowBase attribute), 312  
sort\_func (kivy.uix.filechooser.FileChooserController attribute), 544  
sorted\_keys (kivy.adapters.dictadapter.DictAdapter attribute), 276  
Sound (class in kivy.core.audio), 284  
SoundLoader (class in kivy.core.audio), 285  
source (kivy.core.audio.Sound attribute), 285  
source (kivy.core.image.ImageData attribute), 290  
source (kivy.graphics.BindTexture attribute), 325  
source (kivy.graphics.context\_instructions.BindText attribute), 351  
source (kivy.graphics.instructions.VertexInstruction attribute), 346  
source (kivy.graphics.shader.Shader attribute), 371  
source (kivy.graphics.VertexInstruction attribute), 342  
source (kivy.uix.effectwidget.EffectBase attribute), 535  
source (kivy.uix.image.Image attribute), 555  
source (kivy.uix.rst.RstDocument attribute), 592  
source (kivy.uix.videoplayer.VideoPlayer attribute), 659  
source\_encoding (kivy.uix.rst.RstDocument attribute), 592  
source\_error (kivy.uix.rst.RstDocument attribute), 592  
source\_stack (kivy.graphics.ApplyContextMatrix attribute), 344  
sp() (in module kivy.metrics), 242  
spacing (kivy.uix.boxlayout.BoxLayout attribute), 517  
spacing (kivy.uix.gridlayout.GridLayout attribute), 553  
spacing (kivy.uix.stacklayout.StackLayout attribute), 628  
SpellingBase (class in kivy.core.spelling), 291  
Spinner (class in kivy.uix.spinner), 623  
SpinnerOption (class in kivy.uix.spinner), 624  
split\_str (kivy.uix.label.Label attribute), 564  
Splitter (class in kivy.uix.splitter), 625  
spos (kivy.input MotionEvent attribute), 398  
spos (kivy.input.motionevent MotionEvent attribute), 413  
spring\_constant (kivy.effects.dampedscroll.DampedScrollEffect attribute), 318  
stack (kivy.graphics.context\_instructions.MatrixInstruction attribute), 353  
stack (kivy.graphics.context\_instructions.PopMatrix attribute), 352  
stack (kivy.graphics.context\_instructions.PushMatrix attribute), 352  
stack (kivy.graphics.LoadIdentity attribute), 345  
stack (kivy.graphics.MatrixInstruction attribute), 337  
stack (kivy.graphics.PopMatrix attribute), 339  
stack (kivy.graphics.PushMatrix attribute), 339  
StackLayout (class in kivy.uix.stacklayout), 627  
start (kivy.uix.videoplayer.VideoPlayerAnnotation attribute), 659  
start() (in module kivy.modules.console), 444  
start() (kivy.animation.Animation method), 182  
start() (kivy.base.EventLoopBase method), 238  
start() (kivy.core.camera.CameraBase method), 286  
start() (kivy.effects.kinetic.KineticEffect method), 319  
start() (kivy.input MotionEventProvider method), 399  
start() (kivy.input.provider MotionEventProvider method), 414  
start() (kivy.input.providers.tuio.TuioMotionEventProvider method), 407  
start() (kivy.loader.LoaderBase method), 204  
start() (kivy.uix.screenmanager.CardTransition method), 606  
start() (kivy.uix.screenmanager.TransitionBase method), 604  
state (kivy.core.audio.Sound attribute), 285

state (kivy.core.video.VideoBase attribute), 299  
state (kivy.uix.behaviors.button.ButtonBehavior attribute), 475  
state (kivy.uix.video.Video attribute), 655  
state (kivy.uix.videoplayer.VideoPlayer attribute), 659  
status (kivy.core.audio.Sound attribute), 285  
StencilPop (class in kivy.graphics), 341  
StencilPop (class in kivy.graphics.stencil\_instructions), 373  
StencilPush (class in kivy.graphics), 341  
StencilPush (class in kivy.graphics.stencil\_instructions), 373  
StencilUnUse (class in kivy.graphics), 341  
StencilUnUse (class in kivy.graphics.stencil\_instructions), 373  
StencilUse (class in kivy.graphics), 341  
StencilUse (class in kivy.graphics.stencil\_instructions), 373  
StencilView (class in kivy.uix.stencilview), 629  
step (kivy.uix.slider.Slider attribute), 621  
stop() (in module kivy.modules.console), 444  
stop() (in module kivy.modules.inspector), 447  
stop() (in module kivy.modules.joycursor), 448  
stop() (kivy.animation.Animation method), 183  
stop() (kivy.app.App method), 201  
stop() (kivy.base.EventLoopBase method), 238  
stop() (kivy.core.audio.Sound method), 285  
stop() (kivy.core.camera.CameraBase method), 286  
stop() (kivy.core.video.VideoBase method), 299  
stop() (kivy.effects.kinetic.KineticEffect method), 319  
stop() (kivy.input.MotionEventProvider method), 399  
stop() (kivy.input.provider.MotionEventProvider method), 414  
stop() (kivy.input.providers.tuio.TuioMotionEventProvider method), 407  
stop() (kivy.loader.LoaderBase method), 204  
stop() (kivy.multistroke.ProgressTracker method), 248  
stop() (kivy.uix.screenmanager.TransitionBase method), 604  
stop\_all() (kivy.animation.Animation static method), 183  
stop\_property() (kivy.animation.Animation method), 183  
stopTouchApp() (in module kivy.base), 239  
str\_to\_gesture() (kivy.gesture.GestureDatabase method), 234  
strikethrough (kivy.uix.label.Label attribute), 564  
string\_to\_keycode() (kivy.core.window.Keyboard method), 301  
string\_types (in module kivy.compat), 218  
StringProperty (class in kivy.properties), 258  
strip (kivy.uix.label.Label attribute), 565  
strip\_border (kivy.uix.tabbedpanel.TabbedPanel attribute), 634  
strip\_cls (kivy.uix.splitter.Splitter attribute), 626  
strip\_comments() (kivy.lang.Parser method), 432  
strip\_comments() (kivy.lang.parser.Parser method), 435  
strip\_image (kivy.uix.tabbedpanel.TabbedPanel attribute), 634  
strip\_size (kivy.uix.splitter.Splitter attribute), 626  
StripLayout (class in kivy.uix.tabbedpanel), 633  
stroke\_length() (kivy.gesture.GestureStroke method), 234  
strtotuple() (in module kivy.utils), 266  
style (kivy.uix.codeinput.CodeInput attribute), 528  
style\_name (kivy.uix.codeinput.CodeInput attribute), 528  
success (kivy.graphics.shader.Shader attribute), 371  
suggest() (kivy.core.spelling.SpellingBase method), 291  
suggestion\_text (kivy.uix.textinput.TextInput attribute), 646  
Svg (class in kivy.graphics.svg), 373  
SwapTransition (class in kivy.uix.screenmanager), 605  
swipe\_threshold (kivy.uix.pagelayout.PageLayout attribute), 581  
Switch (class in kivy.uix.switch), 630  
switch\_to() (kivy.uix.screenmanager.ScreenManager method), 602  
switch\_to() (kivy.uix.tabbedpanel.TabbedPanel method), 635  
sx (kivy.input.motionevent.MotionEvent attribute), 413  
sy (kivy.input.motionevent.MotionEvent attribute), 413  
sync() (kivy.lang.builder.BuilderBase method), 433  
sync() (kivy.lang.BuilderBase method), 430  
sync\_height (kivy.uix.spinner.Spinner attribute), 624  
system\_size (kivy.core.window.WindowBase attribute), 312  
sz (kivy.input.motionevent.MotionEvent attribute), 413

T

tab\_height (kivy.uix.tabbedpanel.TabbedPanel attribute), 635  
tab\_list (kivy.uix.tabbedpanel.TabbedPanel attribute), 635

tab\_pos (kivy.uix.tabbedpanel.TabbedPanel attribute), 635  
tab\_width (kivy.uix.tabbedpanel.TabbedPanel attribute), 635  
tab\_width (kivy.uix.textinput.TextInput attribute), 646  
tabbed\_panel (kivy.uix.tabbedpanel.TabbedPanelStrip attribute), 636  
TabbedPanel (class in kivy.uix.tabbedpanel), 633  
TabbedPaneContent (class in kivy.uix.tabbedpanel), 635  
TabbedPaneException (class in kivy.uix.tabbedpanel), 636  
TabbedPaneHeader (class in kivy.uix.tabbedpanel), 635  
TabbedPaneItem (class in kivy.uix.tabbedpanel), 635  
TabbedPaneStrip (class in kivy.uix.tabbedpanel), 636  
target (kivy.core.window.Keyboard attribute), 301  
target (kivy.graphics.texture.Texture attribute), 382  
target (kivy.uix.vkeyboard.VKeyboard attribute), 664  
target\_stack (kivy.graphics.ApplyContextMatrix attribute), 344  
target\_widget (kivy.effects.scroll.ScrollEffect attribute), 320  
template (kivy.adapters.adapter.Adapter attribute), 276  
template() (kivy.lang.builder.BuilderBase method), 433  
template() (kivy.lang.BuilderBase method), 430  
tessellate() (kivy.graphics.tesselator.Tesselator method), 376  
Tesselator (class in kivy.graphics.tesselator), 376  
tex\_coords (kivy.graphics.instructions.VertexInstruction attribute), 346  
tex\_coords (kivy.graphics.texture.Texture attribute), 382  
tex\_coords (kivy.graphics.VertexInstruction attribute), 343  
text (kivy.core.text.LabelBase attribute), 294  
text (kivy.uix.label.Label attribute), 565  
text (kivy.uix.rst.RstDocument attribute), 592  
text (kivy.uix.textinput.TextInput attribute), 646  
text\_autoupdate (kivy.uix.spinner.Spinner attribute), 624  
text\_entry\_timeout (kivy.uix.behaviors.compoundselection.CompoundSelection attribute), 480  
text\_size (kivy.core.text.LabelBase attribute), 294  
text\_size (kivy.uix.label.Label attribute), 565  
text\_validate\_unfocus (kivy.uix.textinput.TextInput attribute), 646  
TextInput (class in kivy.uix.textinput), 638  
textinput (kivy.uix.settings.SettingPath attribute), 616  
textinput (kivy.uix.settings.SettingString attribute), 615  
Texture (class in kivy.graphics.texture), 380  
texture (kivy.core.camera.CameraBase attribute), 286  
texture (kivy.core.image.Image attribute), 289  
texture (kivy.core.video.VideoBase attribute), 299  
texture (kivy.graphics.Fbo attribute), 331  
texture (kivy.graphics.fbo.Fbo attribute), 357  
texture (kivy.graphics.instructions.VertexInstruction attribute), 346  
texture (kivy.graphics.VertexInstruction attribute), 343  
texture (kivy.uix.effectwidget.EffectWidget attribute), 535  
texture (kivy.uix.image.Image attribute), 555  
texture (kivy.uix.label.Label attribute), 565  
texture\_size (kivy.uix.image.Image attribute), 556  
texture\_size (kivy.uix.label.Label attribute), 566  
texture\_update() (kivy.uix.label.Label method), 566  
TextureRegion (class in kivy.graphics.texture), 383  
textures (kivy.atlas.Atlas attribute), 207  
thumbnail (kivy.uix.videoplayer.VideoPlayer attribute), 659  
tick() (kivy.clock.ClockBaseBehavior method), 217  
tick() (kivy.clock.ClockEvent method), 214  
tick\_draw() (kivy.clock.ClockBaseBehavior method), 217  
time (kivy.clock.ClockBaseBehavior attribute), 217  
time\_end (kivy.input.motionevent.MotionEvent attribute), 413  
time\_start (kivy.input.motionevent.MotionEvent attribute), 413  
time\_update (kivy.input.motionevent.MotionEvent attribute), 413  
timeout (kivy.clock.ClockEvent attribute), 214  
title (kivy.app.App attribute), 201  
title (kivy.uix.accordion.AccordionItem attribute), 508  
title (kivy.uix.actionbar.ActionPrevious attribute), 513  
title (kivy.uix.popup.Popup attribute), 583  
title (kivy.uix.rst.RstDocument attribute), 592  
title (kivy.uix.settings.SettingItem attribute), 615  
title (kivy.uix.settings.SettingsPanel attribute), 614  
title\_align (kivy.uix.popup.Popup attribute), 583  
title\_args (kivy.uix.accordion.AccordionItem attribute), 508  
title\_color (kivy.uix.popup.Popup attribute), 583  
title\_font (kivy.uix.popup.Popup attribute), 583  
title\_size (kivy.uix.popup.Popup attribute), 583

**title\_template** (kivy.uix.accordion.AccordionItem attribute), 508  
**to\_local()** (kivy.uix.widget.Widget method), 674  
**to\_parent()** (kivy.uix.widget.Widget method), 674  
**to\_widget()** (kivy.uix.widget.Widget method), 674  
**to\_window()** (kivy.uix.widget.Widget method), 674  
**tocrees** (kivy.uix.rst.RstDocument attribute), 592  
**toggleFullscreen()** (kivy.core.window.WindowBase method), 312  
**toggle\_node()** (kivy.uix.treeview.TreeView method), 651  
**ToggleButton** (class in kivy.uix.togglebutton), 647  
**ToggleButtonBehavior** (class in kivy.uix.behaviors), 469  
**ToggleButtonBehavior** (class in kivy.uix.behaviors.togglebutton), 494  
**tolist()** (kivy.graphics.transformation.Matrix method), 385  
**top** (kivy.core.window.WindowBase attribute), 313  
**top** (kivy.uix.widget.Widget attribute), 674  
**total** (kivy.uix.filechooser.FileChooserProgressBase attribute), 545  
**touch\_control** (kivy.uix.switch.Switch attribute), 630  
**touch\_deselect\_last** (kivy.uix.behaviors.compoundselection.CompoundSelectionBehavior attribute), 480  
**touch\_distance** (kivy.uix.switch.Switch attribute), 630  
**touch\_multiselect** (kivy.uix.behaviors.compoundselection.CompoundSelectionBehavior attribute), 480  
**touches** (kivy.base.EventLoopBase attribute), 238  
**TouchRippleBehavior** (class in kivy.uix.behaviors), 473  
**TouchRippleBehavior** (class in kivy.uix.behaviors.touchripple), 495  
**TouchRippleButtonBehavior** (class in kivy.uix.behaviors), 473  
**TouchRippleButtonBehavior** (class in kivy.uix.behaviors.touchripple), 496  
**transfer\_gesture()** (kivy.multistroke.Recognizer method), 247  
**transform** (kivy.uix.scatter.Scatter attribute), 596  
**transform\_inv** (kivy.uix.scatter.Scatter attribute), 597  
**transition** (kivy.animation.Animation attribute), 183  
**transition** (kivy.uix.screenmanager.ScreenManager attribute), 603  
**transition\_progress** (kivy.uix.screenmanager.Screen attribute), 601  
**transition\_state** (kivy.uix.screenmanager.Screen attribute), 601  
**TransitionBase** (class in kivy.uix.screenmanager), 603  
**Translate** (class in kivy.graphics), 342  
**Translate** (class in kivy.graphics.context\_instructions), 353  
**translate()** (kivy.graphics.transformation.Matrix method), 386  
**translation\_touches** (kivy.uix.scatter.Scatter attribute), 597  
**transpose()** (kivy.graphics.transformation.Matrix method), 386  
**TreeView** (class in kivy.uix.treeview), 649  
**TreeViewException** (class in kivy.uix.treeview), 651  
**TreeViewLabel** (class in kivy.uix.treeview), 652  
**TreeNode** (class in kivy.uix.treeview), 652  
**Triangle** (class in kivy.graphics), 342  
**Triangle** (class in kivy.graphics.vertex\_instructions), 387  
**trigger\_action()** (kivy.uix.behaviors.button.ButtonBehavior method), 475  
**trigger\_action()** (kivy.uix.behaviors.ButtonBehavior method), 469  
**trim\_left\_of\_sel()** (kivy.adapters.dictadapter.DictAdapter method), 276  
**trim\_left\_of\_sel()** (kivy.adapters.listadapter.ListAdapter method), 280  
**trim\_right\_of\_sel()** (kivy.adapters.dictadapter.DictAdapter method), 276  
**trim\_right\_of\_sel()** (kivy.adapters.listadapter.ListAdapter method), 280  
**trim\_to\_sel()** (kivy.adapters.dictadapter.DictAdapter method), 276  
**trim\_to\_sel()** (kivy.adapters.listadapter.ListAdapter method), 280  
**triple\_tap\_time** (kivy.input.motionevent.MotionEvent attribute), 413  
**Tuio2dCurMotionEvent** (class in kivy.input.providers.tuio), 407  
**Tuio2dObjMotionEvent** (class in kivy.input.providers.tuio), 407  
**TuioMotionEventProvider** (class in kivy.input.providers.tuio), 406

U

**ud** (kivy.input.motionevent.MotionEvent attribute), 413  
**uid** (kivy.input.motionevent.MotionEvent attribute), 413  
**unbind()** (kivy.event.EventDispatcher method), 230  
**unbind()** (kivy.properties.Property method), 257  
**unbind\_property()** (kivy.lang.builder.BuilderBase method), 433  
**unbind\_property()** (kivy.lang.BuilderBase

method), 430  
**unbind\_uid()** (kivy.event.EventDispatcher method), 231  
**unbind\_uid()** (kivy.event.Observable method), 232  
**unbind\_uid()** (kivy.lang.builder.Observable method), 432  
**unbind\_uid()** (kivy.lang.Observable method), 429  
**unbind\_uid()** (kivy.properties.Property method), 257  
**unbind\_widget()** (kivy.lang.builder.BuilderBase method), 434  
**unbind\_widget()** (kivy.lang.BuilderBase method), 431  
**unbundler()** (kivy.lib.osc.OSC.CallbackManager method), 438  
**underline** (kivy.uix.label.Label attribute), 566  
**underline\_color** (kivy.uix.rst.RstDocument attribute), 592  
**unfocus\_on\_touch** (kivy.uix.behaviors.focus.FocusBehavior attribute), 488  
**ungrab()** (kivy.input MotionEvent method), 398  
**ungrab()** (kivy.input.motionevent MotionEvent method), 413  
**ungrab\_mouse()** (kivy.core.window.WindowBase method), 313  
**unicode\_errors** (kivy.uix.label.Label attribute), 566  
**uniforms** (kivy.uix.effectwidget.AdvancedEffectBase attribute), 536  
**uninstall\_twisted\_reactor()** (in module kivy.support), 265  
**UnistrokeTemplate** (class in kivy.multistroke), 250  
**unload()** (kivy.core.audio.Sound method), 285  
**unload()** (kivy.core.video.VideoBase method), 299  
**unload()** (kivy.uix.video.Video method), 655  
**unload\_file()** (kivy.lang.builder.BuilderBase method), 434  
**unload\_file()** (kivy.lang.BuilderBase method), 431  
**register()** (kivy.input.providers.tuio.TuioMotionEvent static method), 407  
**unregister\_event\_types()** (kivy.event.EventDispatcher method), 231  
**unschedule()** (kivy.clock.CyClockBase method), 215  
**up\_count** (kivy.uix.behaviors.compoundselection.CompoundSelectionBehavior attribute), 480  
**update()** (kivy.effects.kinetic.KineticEffect method), 319  
**update()** (kivy.input.MotionEventProvider method), 399  
**update()** (kivy.input.provider.MotionEventProvider method), 414  
**update()** (kivy.input.providers.tuio.TuioMotionEvent method), 407  
**update\_bbox()** (kivy.uix.gesturesurface.GestureContainer method), 549  
**update\_config()** (kivy.config.ConfigParser method), 223  
**update\_from\_scroll()** (kivy.uix.scrollview.ScrollView method), 610  
**update\_velocity()** (kivy.effects.kinetic.KineticEffect method), 319  
**UpdateNormalMatrix** (class in kivy.graphics), 344  
**url** (kivy.network.urlrequest.UrlRequest attribute), 456  
**URLRequest** (class in kivy.network.urlrequest), 454  
**use\_bubble** (kivy.uix.textinput.TextInput attribute), 646  
**use\_handles** (kivy.uix.textinput.TextInput attribute), 647  
**use\_kivy\_settings** (kivy.app.App attribute), 202  
**use\_parent\_frag\_modelview** (kivy.graphics.instructions.RenderContext attribute), 348  
**use\_parent\_frag\_modelview** (kivy.graphics.RenderContext attribute), 340  
**use\_parent\_modelview** (kivy.graphics.instructions.RenderContext attribute), 348  
**use\_parent\_modelview** (kivy.graphics.RenderContext attribute), 340  
**use\_parent\_projection** (kivy.graphics.instructions.RenderContext attribute), 348  
**use\_parent\_projection** (kivy.graphics.RenderContext attribute), 340  
**use\_separator** (kivy.uix.actionbar.ActionGroup attribute), 512  
**use\_separator** (kivy.uix.actionbar.ActionView attribute), 512  
**user\_data\_dir** (kivy.app.App attribute), 202  
**usersize** (kivy.core.text.LabelBase attribute), 294  
**usleep()** (kivy.clock.ClockBaseBehavior method), 217  
**uvpos** (kivy.graphics.texture.Texture attribute), 382  
**CompoundSelectionBehavior** (kivy.uix.behaviors.compoundselection.CompoundSelectionBehavior attribute), 382  
**uvsize** (kivy.graphics.texture.Texture attribute), 382  
**V**  
**v** (kivy.graphics.Color attribute), 329  
**v** (kivy.graphics.context\_instructions.Color attribute), 351  
**value** (kivy.effects.kinetic.KineticEffect attribute), 566

value (kivy.uix.progressbar.ProgressBar attribute), 584  
value (kivy.uix.settings.SettingItem attribute), 615  
value (kivy.uix.slider.Slider attribute), 622  
value\_normalized (kivy.uix.progressbar.ProgressBar attribute), 584  
value\_normalized (kivy.uix.slider.Slider attribute), 622  
value\_pos (kivy.uix.slider.Slider attribute), 622  
value\_track (kivy.uix.slider.Slider attribute), 622  
value\_track\_color (kivy.uix.slider.Slider attribute), 622  
value\_track\_width (kivy.uix.slider.Slider attribute), 622  
values (kivy.uix.settings.SettingBoolean attribute), 616  
values (kivy.uix.spinner.Spinner attribute), 624  
VariableListProperty (class in kivy.properties), 262  
vbar (kivy.uix.scrollview.ScrollView attribute), 610  
Vector (class in kivy.vector), 269  
velocity (kivy.effects.kinetic.KineticEffect attribute), 319  
vertex\_count (kivy.graphics.tesselator.Tesselator attribute), 376  
VertexInstruction (class in kivy.graphics), 342  
VertexInstruction (class in kivy.graphics.instructions), 346  
VerticalBlurEffect (class in kivy.uix.effectwidget), 536  
vertices (kivy.graphics.Mesh attribute), 338  
vertices (kivy.graphics.tesselator.Tesselator attribute), 377  
vertices (kivy.graphics.vertex\_instructions.Mesh attribute), 395  
Video (class in kivy.uix.video), 653  
VideoBase (class in kivy.core.video), 298  
VideoPlayer (class in kivy.uix.videoplayer), 657  
VideoPlayerAnnotation (class in kivy.uix.videoplayer), 659  
view\_adapter (kivy.uix.recycleview.RecycleViewBehavior attribute), 500  
view\_clip() (kivy.graphics.transformation.Matrix method), 386  
view\_list (kivy.uix.filechooser.FileChooser attribute), 542  
view\_mode (kivy.uix.filechooser.FileChooser attribute), 542  
viewclass (kivy.uix.recycleview.layout.RecycleLayout attribute), 502  
viewclass (kivy.uix.recycleview.RecycleView attribute), 500  
viewport\_size (kivy.uix.scrollview.ScrollView attribute), 610  
VKeyboard (class in kivy.uix.vkeyboard), 661  
volume (kivy.core.audio.Sound attribute), 285  
volume (kivy.core.video.VideoBase attribute), 299  
volume (kivy.uix.video.Video attribute), 655  
volume (kivy.uix.videoplayer.VideoPlayer attribute), 659  
vs (kivy.graphics.shader.Shader attribute), 371  
vs (kivy.uix.screenmanager.ShaderTransition attribute), 604

**W**

wait() (kivy.network.urlrequest.UrlRequest method), 456  
walk() (kivy.uix.widget.Widget method), 675  
walk\_reverse() (kivy.uix.widget.Widget method), 675  
WeakMethod (class in kivy.weakmethod), 271  
WeakProxy (class in kivy.weakproxy), 272  
wheel (kivy.uix.colorpicker.ColorPicker attribute), 529  
Widget (class in kivy.uix.widget), 667  
widget (kivy.core.window.Keyboard attribute), 301  
widget (kivy.modules.console.Console attribute), 445  
WidgetException (class in kivy.uix.widget), 676  
width (kivy.core.image.Image attribute), 289  
width (kivy.core.image.ImageData attribute), 290  
width (kivy.core.window.WindowBase attribute), 313  
width (kivy.graphics.Line attribute), 336  
width (kivy.graphics.texture.Texture attribute), 383  
width (kivy.graphics.vertex\_instructions.Line attribute), 393  
width (kivy.input.shape.ShapeRect attribute), 414  
width (kivy.uix.widget.Widget attribute), 676  
window (kivy.core.window.Keyboard attribute), 301  
window (kivy.input.recorder.Recorder attribute), 409  
WindowBase (class in kivy.core.window), 301  
WipeTransition (class in kivy.uix.screenmanager), 605  
with\_previous (kivy.uix.actionbar.ActionPrevious attribute), 513  
WM\_MotionEvent (class in kivy.input.providers.wm\_touch), 405  
WM\_Pen (class in kivy.input.providers.wm\_pen), 405  
wrap (kivy.graphics.texture.Texture attribute), 383  
write() (kivy.config.ConfigParser method), 223  
write\_tab (kivy.uix.textinput.TextInput attribute), 647

**X**

x (kivy.graphics.context\_instructions.Scale attribute), 353

- x (kivy.graphics.context\_instructions.Translate attribute), [353](#)
- x (kivy.graphics.Scale attribute), [341](#)
- x (kivy.graphics.Translate attribute), [342](#)
- x (kivy.input.motionevent MotionEvent attribute),  
[413](#)
- x (kivy.uix.widget.Widget attribute), [676](#)
- x (kivy.vector.Vector attribute), [271](#)
- xy (kivy.graphics.context\_instructions.Translate attribute), [353](#)
- xy (kivy.graphics.Translate attribute), [342](#)
- xyz (kivy.graphics.context\_instructions.Scale attribute), [353](#)
- xyz (kivy.graphics.context\_instructions.Translate attribute), [353](#)
- xyz (kivy.graphics.Scale attribute), [341](#)
- xyz (kivy.graphics.Translate attribute), [342](#)

## Y

- y (kivy.graphics.context\_instructions.Scale attribute), [353](#)
- y (kivy.graphics.context\_instructions.Translate attribute), [353](#)
- y (kivy.graphics.Scale attribute), [341](#)
- y (kivy.graphics.Translate attribute), [342](#)
- y (kivy.input.motionevent MotionEvent attribute),  
[413](#)
- y (kivy.uix.widget.Widget attribute), [676](#)
- y (kivy.vector.Vector attribute), [271](#)

## Z

- z (kivy.graphics.context\_instructions.Scale attribute), [353](#)
- z (kivy.graphics.context\_instructions.Translate attribute), [353](#)
- z (kivy.graphics.Scale attribute), [341](#)
- z (kivy.graphics.Translate attribute), [342](#)
- z (kivy.input.motionevent MotionEvent attribute),  
[413](#)